

COLLECTED WORKS OF JOHN STUART MILL

VOLUME XXX

The Collected Edition of the Works of John Stuart Mill has been planned and is being directed by an editorial committee appointed from the Faculty of Arts and Science of the University of Toronto, and from the University of Toronto Press. The primary aim of the edition is to present fully collated texts of those works which exist in a number of versions, both printed and manuscript, and to provide accurate texts of works previously unpublished or which have become relatively inaccessible.

Editorial Committee

JOHN M. ROBSON, *General Editor*

HARALD BOHNE, J.C. CAIRNS, J.B. CONACHER,
D.P. DRYER, MARION FILIPIUK, FRANCES HALPENNY,
SAMUEL HOLLANDER, R.F. MCRAE, IAN MONTAGNES,
ANN P. ROBSON, F.E. SPARSHOTT

Writings on India

by JOHN STUART MILL

Edited by

JOHN M. ROBSON, MARTIN MOIR, and ZAWAHIR MOIR

Introduction by

MARTIN MOIR

Formerly Archivist and Deputy Director,
India Office Library and Records, London

Textual Introduction by

JOHN M. ROBSON

University Professor and Professor of English,
Victoria College, University of Toronto

UNIVERSITY OF TORONTO PRESS
ROUTLEDGE

© *University of Toronto Press 1990*
Toronto and Buffalo
Printed in Canada
ISBN 0-8020-2717-2

London: Routledge
ISBN 0-415-04878-8



Printed on acid-free paper

Canadian Cataloguing in Publication Data

Mill, John Stuart, 1806–1873.

Collected works of John Stuart Mill

Edited by John M. Robson and others.

Includes bibliographical references.

Partial contents: v. 30. Writings on India / edited by
John M. Robson, Martin Moir, and Zawahir Moir.

ISBN 0-8020-2717-2 (v. 30)

1. Philosophy. 2. Political science. 3. Economics.

I. Robson, John M., 1927– . II. Title.

B1602.A2 1963 192 C64-000188-2 rev

British Library Cataloguing in Publication Data

Mill, John Stuart, 1806–1873

Writings on India. – (Collected works of John Stuart Mill; v.30).


I. Title II. Robson, J.M. (John Merce), 1927– 954.03

ISBN 0-415-04878-8

This volume has been published with the assistance of a grant
from the Social Sciences and Humanities Research Council of Canada

Contents

| | |
|---|-----|
| INTRODUCTION, by Martin Moir | vii |
| TEXTUAL INTRODUCTION, by John M. Robson | lv |
| Trade with India (1828) | 1 |
| Minute on the Black Act (1836) | 11 |
| Penal Code for India (1838) | 17 |
| The East India Company's Charter (1852) | 31 |
| The Petition of the East-India Company (1858) | 75 |
| ✓ Memorandum of the Improvements in the Administration of India during the Last Thirty Years (1858) | 91 |
| Report to the General Court of Proprietors (1858) | 161 |
| ✓ A Constitutional View of the India Question (1858) | 173 |
| ✓ Observations on the Proposed Council of India (1858) | 179 |
| ✓ Practical Observations on the First Two of the Proposed Resolutions on the Government of India (1858) | 185 |
| ✓ The Moral of the India Debate (1858) | 193 |
| A President in Council the Best Government for India (1858) | 199 |
| Letter from the East India Company to the President of the Board of Control (1858) | 205 |
| Maine on Village Communities (1871) | 213 |
| APPENDICES | |
| Appendix A. Check List of Mill's Indian Despatches (1823–58) | 239 |
| Appendix B. List of Published Extracts from Mill's Indian Despatches | 297 |
| Appendix C. Editorial Emendations | 309 |
| Appendix D. Index of Persons and Works | 311 |
| INDEX | 333 |
| ILLUSTRATIONS | |
| East India House in Mill's Time | vi |
| Facsimiles | 231 |



East India House in Mill's Time

Introduction

MARTIN MOIR

IN MAY 1823, my professional occupation and status for the next thirty-five years of my life, were decided by my father's obtaining for me an appointment from the East India Company, in the office of the Examiner of India Correspondence, immediately under himself. I was appointed in the usual manner, at the bottom of the list of clerks, to rise, at least in the first instance, by seniority; but with the understanding, that I should be employed from the beginning in preparing drafts of despatches, and be thus trained up as a successor to those who then filled the higher departments of the office. My drafts of course required, for some time, much revision from my immediate superiors, but I soon became well acquainted with the business, and by my father's instructions and the general growth of my own powers, I was in a few years qualified to be, and practically was, the chief conductor of the correspondence with India in one of the leading departments, that of the Native States. This continued to be my official duty until I was appointed Examiner, only two years before the time when the abolition of the East India Company as a political body determined my retirement.¹

Thus in his *Autobiography* John Stuart Mill tersely and modestly sums up his long period of employment in the Examiner's Office of the East India Company. To this factual resumé he later adds a few remarks on the increase in his official responsibilities that took place towards the end of his career.² More tantalizingly, he also includes some brief observations on the benefits and occasional limitations of his employment. For example, as a "theoretical reformer of the opinions and the institutions of his time," he appreciated the useful insight into "the practical conduct of public affairs" which his Company experience brought him. On a more personal level, he noted that the experience also taught him how best to present his own views to "persons unlike" himself, how to compromise on non-essential matters, and—perhaps most significant for his personal happiness—how to accept with equanimity occasional defeats at the hands of his superiors.³

As for the interest and demands of his Company work, and its general place in his life, he concluded that his duties "were sufficiently intellectual not to be a distasteful drudgery, without being such as to cause any strain upon the mental powers of a person used to abstract thought, or to the labour of careful literary

¹*Autobiography* [A], *Collected Works* [CW], I (Toronto: University of Toronto Press, 1981), 83-5. References to material in this volume are given in parentheses in the text.

²*Ibid.*, 247, 249.

³*Ibid.*, 87.

composition.”⁴ And in a passage omitted from the published text of his *Autobiography* at the instance of his wife, Harriet, he pointed more frankly to the real advantages of his official duties: “While they precluded all uneasiness about the means of subsistence, they occupied fewer hours of the day than almost any business or profession, they had nothing in them to produce anxiety, or to keep the mind intent on them at any time but when directly engaged in them.”⁵ No doubt he regretted certain limitations attached to his position—his short period of annual leave (only four weeks) and the fact that he was virtually prevented from playing a part in public life. But these restrictions were acceptable when set against the advantages of an employment which guaranteed his financial security and left him with sufficient time and energy for his “private intellectual pursuits.”⁶

The fact that Mill offers this short and low-key account of his East India Company activities, apparently relegating them to the level of a useful but essentially subordinate part of his intellectual life, has presented his modern interpreters with a whole range of problems. Most immediately, how could someone so deeply committed to the understanding and betterment of human society apparently fail to appreciate the importance and interest of his own central position in the formulation and review of the East India Company’s policies in South Asia? Was he really comparatively detached from his official duties, as his *Autobiography* suggests, or was he more committed than he chose to admit? Alternatively, was his position in the Examiner’s Office perhaps less influential than might at first sight appear, placing him primarily in the position of a servant of the Company charged with the preparation of its despatches? Moreover, any exploration of the problem of Mill’s East India Company role leads imperceptibly to the more basic and, to the post-colonial sensibility, more puzzling issues of how to connect Mill the administrator with Mill the political philosopher. How, for instance, did the author of *On Liberty* and *Representative Government* view the rights and best interests of the Indian subjects of the East India Company?

Though definitive answers to all such enquiries and conundrums are unlikely to be found, one can at least reduce some of the mystery by reviewing and assessing the surviving evidence for Mill’s Company career in considerably more detail than his *Autobiography* provides.

THE HOME GOVERNMENT OF THE EAST INDIA COMPANY⁷

THE EAST INDIA COMPANY that Mill joined in 1823 occupied a central position in the rather elaborate system for the home government of British India. Certain


⁴*Ibid.*, 85.

⁵*Ibid.*, 84n.

⁶*Ibid.*, 85.

⁷For more detailed accounts of the East India Company and the Board of Control, see “Minutes of Evidence Taken before the (House of Commons) Select Committee on the

TABLE 1



features of this system were later much admired and defended by Mill as conducive to the good government of India. But in 1823 it is likely that he was more struck by its administrative complications than by its latent political virtues. The principal features of the Company's organization within the wider administrative framework, as Mill first experienced them, can best be represented by a diagram (Table 1).

The East India Company was immediately responsible for the administration of British territories in India and elsewhere but was itself subject to close government supervision through the Board of Control. The executive part of the Company, the Court of Directors, consisted of twenty-four directors elected by the Company's larger share-holders or proprietors and broadly representative of the main sectional interests in the Company's affairs (e.g., the City of London, "ex-Indian" administrators, etc.). Every year the Company's directors appointed a Chairman and a Deputy Chairman (the "Chairs") as their leading spokesmen; they also assigned themselves to a number of standing committees, each responsible to the Court as a whole for the management of a distinct aspect of the Company's activities. When the young Mill first joined the Company there were thirteen main committees (the most important of which were concerned with correspondence, buying and warehouses, and shipping) apart from the special statutory Secret Committee, discussed below. The Court and its committees were also assisted in their transaction of business by a large number of officials and departments led by the Company's Secretary and the Examiner of Indian Correspondence. Most of the

Affairs of the East India Company; I, Public," *PP*, 1831-32, IX; "Report from the (House of Commons) Select Committee on Indian Territories: Minutes of Evidence," *PP*, 1852, X; C.H. Philips, *The East India Company, 1784-1834* (Manchester: Manchester University Press, 1961); Martin Moir, *A General Guide to the India Office Records* (London: British Library, 1988).

Company's formal decision-making took place at the meetings of the Court of Directors, usually held about twice a week. The Court of Proprietors' policy role was by this period somewhat circumscribed, being largely confined in its expression to the quarterly general meetings and occasional specially convened meetings.

During this period the Company still traded extensively with India and China, etc., but it had already lost its monopoly rights over the Indian trade in 1813 and was soon to be stripped of all its commercial functions through the Charter Act of 1833. However, while the Company's trading operations gradually decreased, the importance of its political and administrative responsibilities for the government of vast territories in South Asia continued to expand and develop. Essentially, the Company's control of these territories was maintained through an immensely detailed and regular correspondence with the leading administrative bodies established in the Indian Sub-continent—the Governor-General and Council at Calcutta and the Governors and Councils at Bombay and Madras.

In the exercise of its growing political responsibilities the East India Company was, as has already been indicated, subject to close government scrutiny and direction through the Board of Commissioners for the Affairs of India, usually known simply as the Board of Control, which had been established under Pitt's India Act of 1784. Though technically still composed of a group of paid and unpaid official commissioners, the Board was in practice dominated by its President—the first named of its commissioners. Supported by a staff of secretaries and departmental clerks, the President upheld the Board's statutory powers of control over the Company by means of a well-established bureaucratic system. According to this system, the Company was obliged to supply the Board with copies of all its incoming Indian letters and to submit all its drafts of outgoing despatches for the Board's approval and possible alteration before issue. The Board was further empowered to prepare and send its own secret instructions to India on matters of war, peace, and diplomacy through the medium of the special Secret Committee of the Court of Directors (consisting of the two Chairs plus a senior director); and also to call upon the Court to prepare and submit for approval despatches on any subjects connected with the civil and military government of the Indian territories.

Within this complex system of dual government it will be evident that the Office of the Examiner of Indian Correspondence, in which so many of the Company's despatches were prepared, necessarily occupied a position of central importance. Not only had the despatches drafted by the Examiner and his Assistants to satisfy the critical scrutiny of the Board of Control; they also had ultimately to constitute authoritative statements of policy and principles for the guidance of the governing bodies in India. Given the exceptional nature of these duties, it is not surprising that the Company's directors began to keep a fairly close watch over the working of the Office during the first quarter of the nineteenth century. Two particular aspects were perceived as requiring attention. In the first place there was the need

to ensure that the department had enough staff to keep pace with the ever-increasing size of the Indian correspondence and also to see that the correspondence itself was clearly and efficiently divided up among the available staff. Secondly, both the Court of Directors and the Board of Control became gradually more aware of the importance of selecting and retaining men of sufficient ability to maintain the quality of the Indian correspondence as its character inevitably became more complex and demanding.⁸

In so far as the staffing aspect was concerned, the directors were initially rather slow in recognizing the manpower needs of the Examiner's Office. In fact until 1804 the Examiner had to cope with virtually the whole of the correspondence single-handedly, drafting despatches in most of the Office's departmental branches, viz., Public, Revenue, Military, Judicial, and Political, besides acting as Clerk to the Company's Secret Committee (see above). Thereafter, during the next five years, a measure of relief was afforded by transferring the Military correspondence to the Auditor (and later to a new Military Secretary) and by appointing two or three Assistants to the Examiner to take charge of drafting the Judicial, Public, and Revenue despatches. Thus in the years immediately preceding Mill's appointment much of the basic structure of the department had gradually been reshaped to include the Examiner, two or three Assistants, plus a staff of about a dozen clerks to perform the more routine duties.

More radical than this modest expansion of the Examiner's immediate staff were the directors' new arrangements for appointing outsiders to the Assistants' posts. These experiments involved official recognition that the traditional Company practice of filling vacancies by promoting clerks in strict order of seniority could not always be counted on to produce a man of the right calibre to perform the intellectual activities required. The more perceptive directors gradually persuaded their colleagues that in such circumstances it was better to disappoint the clerks by looking outside the Company for more suitable candidates, "sooner than submit to so serious an evil as that of having momentous business imperfectly performed."⁹ In this way, from 1809 onwards, several talented outsiders were brought in to fill senior vacancies in the Office, including William McCulloch who, having been recruited in 1809 as an Assistant, was promoted to the position of Examiner in 1817—a post which he continued to hold when John Stuart Mill entered the Office in 1823.¹⁰

However, undoubtedly the most spectacular experiment in this form of

⁸See Martin Moir, "The Examiner's Office: The Emergence of an Administrative Elite in East India House (1804-58)," *India Office Library and Records Report* (1977), 25-42.

⁹Quoted *ibid.*, 32.

¹⁰For William McCulloch, see Martin Moir, "The Examiner's Office and the Drafting of East India Company Despatches," in *East India Company Studies Papers Presented to Professor Sir Cyril Philips*, ed. Kenneth Ballhatchet and John Harrison (Hong Kong: Asian Research Service, 1986), 135.

recruitment—and one that sets the scene for the younger Mill's arrival—took place in May 1819 when, to fill a number of vacancies that had arisen, the Court of Directors selected three outsiders as Assistants to the Examiner: James Mill, Thomas Love Peacock, and Edward Strachey. As to the mode of selection, it appears that the directors were sufficiently impressed by the elder Mill's recently published *History of British India* to waive further scrutiny of his qualifications. Indeed, Mill himself believed that he owed his appointment principally to his book. Somewhat similarly, Edward Strachey, with his considerable experience of judicial administration in India, was deemed well qualified for the work. Peacock, on the other hand, despite his literary reputation, was seen as more of an unknown quantity. He was therefore called upon to furnish evidence of his capacities to understand Indian administration, emerging triumphantly from this trial with a lucid survey of revenue policies entitled "Ryotwar and Zemindarry Settlements."

Once established in the Office, the three distinguished "outside examiners" were each allotted responsibility for the correspondence of a particular department, Strachey being placed first with the Judicial, followed by Mill with the Revenue, and Peacock with more miscellaneous duties—all the Assistants working under the supervision of the Examiner, William McCulloch. The more delicate question of determining their final order of seniority was left open for several years, and it was not until April 1823 that the Court of Directors finally grasped the nettle by appointing James Mill as Assistant Examiner, ranking immediately after McCulloch with an annual salary of £1200, leaving Strachey (with £1000) and Peacock (with £800) still classed as Assistants to the Examiner.¹¹ Clearly the elder Mill was now regarded as the most likely successor to the headship of the office (he eventually succeeded McCulloch in 1830), and his growing ascendancy was further reflected in the appointment of his son as an additional junior clerk in the Examiner's Office on 21 May, 1823.

MILL'S APPOINTMENT AND APPRENTICESHIP WITH THE EAST INDIA COMPANY (1823-28)

BEFORE EXPLORING the wider significance and consequences of the appointment of John Stuart Mill as junior clerk in 1823—for Mill's father, for the East India Company, and for Mill himself—it is necessary to summarize the available documentary evidence concerning the nature and terms of the appointment itself. In the Company archives, the main outlines of the story as given in the Minutes and Reports of the Committee of Correspondence and the Minutes of the Court of Directors are simple enough. On 9 April, 1823, the Correspondence Committee

¹¹India Office Records [IOR]: Court Minutes (9 Apr., 1823), B/175, 1077; Correspondence Committee Minutes (9 Apr., 1823), D/8, 1131-2.

briefly concluded that the business of the Examiner's Office "requires an additional Clerk," and accordingly proposed the appointment of such a clerk with the further recommendation that the right to nominate to the new post should be given to the Chairman, James Pattison.¹² The Court agreed to these proposals on the same day, and it then appears that, with Pattison's support, the younger Mill formally petitioned the Court for the post (following the usual Company practice) and was duly appointed on 21 May, 1823.¹³

As regards the actual terms of his employment, Mill's own account in the *Autobiography*, quoted earlier, is fully borne out by the Company records and other sources. That is to say, his appointment as junior clerk was made subject to the "usual terms and conditions," and he took his place at the lowest level in the clerical establishment of the Examiner's Office, with twelve clerks above him in seniority, above whom in turn stood the small élite group of Assistants to the Examiner now led by his father.¹⁴ Equally, his appointment was subject to the normal Company regulations for junior clerks, which obliged him to serve for three years without salary, though modestly encouraged by a small annual gratuity of £30.¹⁵ More interestingly, the Company records also precisely confirm the classic account given in his *Autobiography* of the unusual nature of his work during his first few years, i.e., that he was employed "from the beginning in preparing drafts of despatches" under the supervision of his father and his immediate superiors, and on the understanding that he would be "thus trained up as a successor to those who then filled the higher departments of the office." Indeed, the Court Minutes for 2 March, 1825, almost exactly foreshadow his own later account of this process, explaining that it had proved possible to employ him "in preparing drafts of Despatches, instead of performing the duties usually assigned to persons of his standing" because of "the great pains bestowed on his education" as well as his own "acquirements which are far in advance of his age" (he was only seventeen—the minimum age for appointment—when he joined).¹⁶ Thus the celebrated educational regime instituted by his father was acknowledged and endorsed by his employers.

For James Mill there was thus the dual satisfaction of securing his son's rather special employment at the same time as his own promotion to the level of Assistant Examiner, over and above Strachey and Peacock. Did he owe these successes solely to the good opinion of his own conspicuous ability, industry, and eloquence which the Company's directors had by then formed? According to a rather strange tradition passed down through the family of Edward Strachey, which surfaced in a

¹²IOR: Correspondence Committee Minutes (9 Apr., 1823), D/8, 1132.

¹³IOR: Court Minutes (21 May, 1823), B/176, 134.

¹⁴IOR: Accountant General's Records: Salary Warrants (Dec. 1823), L/AG/9/4/15.

¹⁵See entries for Mill in Quarterly Salary Warrants in IOR: Accountant General's Records: Salary Warrants (1824), L/AG/9/4/16.

¹⁶IOR: Court Minutes (2 Mar., 1825), B/177, 666.

review of Alexander Bain's life of James Mill published in the *Spectator* in April 1882, there were indeed more sinister influences at work. Faced with the prospect that Edward Strachey would be recognized as his official superior on the completion of the agreed period of probation for the three new Assistants to the Examiner, James Mill, so the Stracheys darkly believed, had deliberately and successfully sought to undermine the position of his rival by insinuating to the Chairman that Strachey was insufficiently conciliatory in his dealings with the Board of Control. The Strachey family further suspected that, having secured by these means his own appointment as Assistant Examiner, the elder Mill went on—this time unsuccessfully—to try to secure Peacock's post for his son, whom he had brought into the Office "with singular adroitness."¹⁷

It is difficult to determine whether there was any factual basis at all for these suspicions. Certainly Mill's sister Harriet firmly denied the story in a letter to the *Spectator* which appeared some two months after the original review of Bain's book, though she admitted that by then it was very hard to find any reliable first-hand evidence about the issue.¹⁸ Alexander Bain also concluded that there was no truth in the Strachey story. It may be added that the Company records have nothing concrete to say on the matter beyond confirming that Edward Strachey did indeed temporarily resign his post in 1823 in protest against what he considered his unfair supersession by Mill.¹⁹

Whatever the truth of the Strachey allegations, there can be no doubt that John Stuart Mill's work in the Examiner's Office soon won the support and approval of the Company directors. By March 1825—some eighteen months after he had taken up his new appointment—the Court not only recorded their special appreciation of his ability to draft despatches, in the terms quoted above, but also awarded him a gratuity of £100 in recognition of his past services, and arranged for his transfer into the newly formed Correspondence Branch of the Examiner's Office (see below).²⁰ In the following March he was again rewarded with another special gratuity, this time of £200,²¹ and soon afterwards, in May 1826, after completing the usual three years' service without salary, he was formally appointed a salaried clerk of the Company with an initial remuneration of £100 per year.²² A further special gratuity of £200 was granted to him in March 1827 for his "zeal and assiduity," in addition to his basic salary.²³ Finally, in February 1828,

¹⁷Review by Sir Edward Strachey of Alexander Bain's *James Mill: A Biography*, *Spectator*, 15 Apr., 1882, 499-500. See also IOR: Sir William Foster's Notebooks, L/R/5/225, 40-1.

¹⁸*Spectator*, 24 June, 1882, 828.

¹⁹IOR: Miscellaneous Letters Received (6 May 1823), E/1/151, 37-45; Court Minutes (23 Apr., 21 May, and 10 June, 1823), B/176, 25, 138, and 192.

²⁰IOR: Court Minutes (2 Mar., 1825), B/177, 666-7.

²¹IOR: Correspondence Committee Reports (19 Feb., 1828), D/77, 294.

²²IOR: Correspondence Committee Reports (31 May, 1826), D/74, 77-8.

²³IOR: Correspondence Committee Reports (3 Mar., 1827), D/75, 362.

after noting that Mill had by then successfully completed nearly five years' experience in drafting despatches in the Political and Public Departments of the correspondence, the Court of Directors decided to bring his period of apprenticeship as a clerk to a conclusion, and with the full support of the Examiner, William McCulloch, promoted him to the position of Fourth Assistant to the Examiner, with the starting salary of £310 per annum, exclusive of any gratuities.²⁴

Apart from its many other points of interest, the story of Mill's apprenticeship at East India House illustrates certain general features in the development of the East India Company's home administration during this period. In particular, it is already evident, from the earlier discussion of the underlying issues involved in the Company's new-found willingness to recruit talented outsiders to perform the more demanding intellectual duties of the Examiner's Office, that the younger Mill was fortunate in arriving at a time when the traditional bureaucratic norms that had previously governed the prospects of the Company's clerks were being modified in favour of more dynamic and meritocratic criteria. Indeed, in the context of these developments, Mill's period of training for higher responsibility between 1823 and 1828 provides a special case-study of the Company's readiness to extend its new, quasi-meritocratic recruitment policy into the internal structure of the Examiner's Office.

This point emerges most clearly in the general reorganization of the Examiner's Office that took place in March 1825. In this fairly radical operation the directors for the first time decided to split the whole department into two divisions, one the Correspondence Branch (immediately consisting of the various Assistant Examiners) and the other that of the ordinary clerks, thus in effect drawing a stronger line between the intellectual duties of the former and the more routine or mechanical functions of the latter. More significantly, the Court declared that in future the higher posts in the Correspondence Branch were to be fully "open to talent," so that although clerks of long standing continued to be eligible for promotion, "mere length of service in the absence of the necessary qualifications gives no claim whatever." In return for losing their automatic claim on the higher posts the ordinary clerks were given a certain compensation in the form of increased allowances for the senior clerical positions, but essentially the Court had come down more firmly in favour of the more flexible meritocratic approach to the choice of Examiners and their assistants. On the same occasion, as if to give immediate expression to the new principles, John Stuart Mill was, as already noted, formally transferred to the new Correspondence Branch. Although he was still classed as clerk, it must by then have become obvious to his clerical colleagues that the young man's promotion over their heads to the Examiner class in the Correspondence Branch was now only a matter of time—three years in the event.

²⁴IOR: Correspondence Committee Reports (19 Feb., 1828), D/77, 293-4; Court Minutes (20 Feb., 1828), B/180.

How far these administrative reforms, which clearly prepared the way for his son's elevation, may have had their origin in the ideas and ambitions of James Mill is impossible to determine; the Court Minutes state only that they were introduced for the future better management of the Examiner's Office, and with the backing of Mill's superior, William McCulloch.²⁵

Finally, in considering the wider significance of his first few years of employment at East India House, it is necessary to enquire, at least briefly and speculatively, what that experience may have meant to Mill himself. Did it, for instance, contribute in any way to that deeply felt sense of his own mental development that increasingly provides a connecting link between his personal psychology and his philosophical and social ideas? In this speculation we may begin by looking again at the passage in his *Autobiography*, quoted earlier. Two contending ideas seem to emerge from these later reflections on his East India House initiation. On the one hand, he is concerned to emphasize his father's decisive role in securing the appointment "immediately under himself," and thereby determining his "professional occupation and status for the next thirty-five years." This strong notion of James Mill's determining influence over the future course of his life is enhanced by the younger Mill's passing reference to the instructions he received from his father while learning to prepare despatches in the Examiner's Office. In fact, viewed from these paternalist perspectives, the first few years of J.S. Mill's East India Company employment look more like prolongation of his father's celebrated tutelage than the first moves towards personal independence. However, Mill's autobiographical account also conveys a contrary and increasingly dominant sense of the eventual significance of his own work. Thus, having acknowledged his debt to his father's instructions, he goes on to show that with "the general growth of [his] own powers," he was able to master the art of drafting despatches to the extent that he was soon officially recognized as competent to take independent charge of "one of the leading departments" of the Indian correspondence.

This idea of Mill's first five years at East India House as involving a progression from youthful dependence to mature self-direction—as a true professional apprenticeship in fact—seems to contribute positively to a wider understanding of his intellectual and emotional development during this crucial period. On this reading, for example, the small group of Political and Public despatches which he prepared between 1824 and 1826 under the eyes of his father and the Examiner may be set alongside the early articles for the *Westminster Review* and newspapers, and the editorial work on Bentham's *Rationale of Judicial Evidence*, which he also prepared during these years. Taken together these writings represent both the culmination of his youthful capacity to absorb and structure new knowledge under his father's guidance, and the beginnings of a special personal ability to synthesize

²⁵IOR: Court Minutes (2 Mar., 1825), B/177, 666-7.

that knowledge and put forward his own original ideas with confidence and fluency. Arguably, of course, it was this latter development that, turned round against itself in the "mental crisis" of 1826-27, eventually propelled Mill forward to break free from the exclusive culture of rational analysis associated with his father's dominance.²⁶ It is perhaps unlikely that his East India House experiences played any direct part in this personal crisis. Nonetheless, as he emerges from it in 1827-28, with a new sense of purpose and his own developing conception of the nature of human culture, it is curiously appropriate that his period of clerical apprenticeship should also have been ended and official maturity recognized in his promotion to the level of Assistant to the Examiner.

MILL AS ASSISTANT TO THE EXAMINER (1828-56) AND THE DRAFTING OF DESPATCHES

MILL'S PROMOTION in 1828 marks the beginning of the very long central part of his official career with the East India Company, which continued until his appointment as Examiner in March 1856. During this period the basic character of his role as an Assistant to the Examiner, responsible mainly for the drafting of Political, Foreign, as well as some Public despatches, seems to have changed very little. But before considering the exact nature of this work, it is important to look more carefully at the question of his general standing within the Examiner's Office during these years. How far is it right to conceive of his position as essentially static? Was there perhaps more movement beneath the surface than may at first appear?

Part of the answer to these questions may be found in the records concerning Mill's financial position, particularly during the 1830s. The years between 1834 and 1836 saw a rapid improvement in his personal fortunes. The process began in April 1834 when the Court of Directors decided to incorporate the annual gratuity of £200—which had been granted to him regularly since 1825—into his annual salary in the form of a special allowance. This, together with the usual small annual increments he had received since his appointment as Assistant in 1828, brought his salary up to £600.²⁷ In February 1836, as the result of the retirement of one of his senior colleagues, Mill moved up to Second Assistant to the Examiner (just below David Hill and Thomas Love Peacock), while his salary was also increased to £800.²⁸ Finally, a few months later, in July 1836—as part of a general reorganization following the death of his father—Mill moved forward once again into the place of First Assistant to the new Examiner, Thomas Love

²⁶A, CW, I, 137-91.

²⁷IOR: Correspondence Committee Reports (27 Mar., 1834), D/90, 200-1; Court Minutes (8 Apr., 1834), B/187, 663-4.

²⁸IOR: Court Minutes (17 Feb., 1836), B/191, 421.

Peacock, ranking next to David Hill (who had succeeded to the position of Assistant Examiner). Along with this move came a further salary increase for Mill, bringing his annual remuneration to £1200.²⁹ However, with Peacock and Hill then firmly established above him, Mill's period of rapid upward mobility came to a halt and he continued in the position of First Assistant for the next twenty years. Only near the end of this long period, in August 1854, did the directors decide to award him a further salary increase, this time of £200 (see xxix below), apparently in connection with his defence of the Company during the Parliamentary investigations leading to the Charter Act of 1853 (16 & 17 Victoria, c. 95).³⁰

The picture of Mill's career emerging from this personal data is of a short initial phase of rapid advancement followed by a long, rather static period and a final upturn; it gains definition, however, when other elements in his professional situation are considered.

Among the more powerful but imponderable influences must be reckoned the effects of his father's death in June 1836. Mill's reaction to that event, and the stress that preceded it, appears to have taken the form of another bout of sickness and depression, for which in July 1836 he obtained over three months' official leave which he spent in travelling abroad with his brothers. It is clear from his private correspondence that this period of personal unhappiness continued into 1837 when he returned to his arrears of work at East India House with the feeling that for the first time he had become "a thorough mechanical drudge."³¹ But in the long run it is reasonable to suppose that the removal of his father's stern and dominating presence gradually had a positive and even a creative effect upon Mill's outlook and attitude to his Company work and the opportunities it afforded, as well as on his more general development as an independent thinker.³²

One particular episode which seems to bring out the growing underlying strengths of his position during the long middle period of his career was his success in obtaining a junior clerkship in the Examiner's Office for his younger brother, George Grote Mill, in April 1844. On this occasion, following the usual Company practice, Mill was required to provide a testimonial on his brother's behalf in which he certified that the latter's education "has been under my exclusive superintendence during the last seven years with the exception of short intervals;

²⁹IOR: Court Minutes (22 July, 1836), B/192, 444.

³⁰IOR: Court Minutes (30 Aug., 1854), B/228, 928-9; Finance and Home Committee Reports, No. 227 (23 Aug., 1854), L/F/1/90.

³¹Mill to Nichol (29 Jan., 1837), in *Earlier Letters, 1812-1848*, ed. Francis E. Mineka, Vols. XII-XIII of CW (Toronto: University of Toronto Press, 1963), XII, 322. See also IOR: Court Minutes (29 June, 1836), B/192, 283; and Mill to Henry Taylor ([1837]), in *Later Letters, 1848-1873*, ed. Francis E. Mineka and Dwight N. Lindley, Vols. XIV-XVII of CW (Toronto: University of Toronto Press, 1972), XVII, 1969-70.

³²For the differences between the Indian "policies" of James and John Stuart Mill, see Eric Stokes, *The English Utilitarians and India* (Oxford: Clarendon Press, 1959), 47-50, 240-2, etc.; Lynn Zastoupil, "J.S. Mill and India," *Victorian Studies*, XXXII (Autumn, 1988), 31-54. See also below, I.

that his conduct and character have always been excellent and his acquirements considerably surpass the average of well educated youths."³³ George Mill was duly installed in the Office, and after a short period of probation was transferred into the Correspondence Branch to gain experience in the drafting of Indian despatches under his brother's tutelage. He there seems to have shown considerable promise, to the extent that it was soon the declared intention of the Examiner, Thomas Love Peacock, to recommend him for one of the specially remunerated posts of "Clerk of Correspondence."³⁴ Unfortunately, further advancement was prevented by his increasing ill health—he had contracted lung disease—and in the autumn of 1848 he was obliged to take a long period of sick leave and eventually to retire altogether in March 1850. He died three years later in Madeira.³⁵

The most striking feature of this episode lies in its close resemblance to J.S. Mill's own early career with the Company and again, as with that more celebrated apprenticeship, George Mill's experience can be interpreted in several different ways. On one level the episode seems to indicate a curiously strong readiness on J.S. Mill's part to assume a paternal position towards his younger brother, even to the extent of employing phrases of recommendation in his testimonial which almost seem to mimic what James Mill had told the Company directors about his own qualities and attainments some twenty years before. There are obvious pitfalls in seeking too specific a psychological explanation for these curious resonances, but the record of the occasion may at least be tentatively added to the other evidence that exists for the ever-intriguing story of Mill's paternal problems.³⁶

On a more mundane level, George Mill's appointment and short career reflect the high status and influence by then enjoyed by J.S. Mill within the Company's home establishment. They also reinforce the picture already formed of the rather special influence which the representatives of the Mill family had directly or indirectly come to exert on the way in which the Examiner's Office had developed and functioned. The point here is not that the Mills' influence was in any way improper or unusual (such dynasties of family employees were quite common in the Company's history) but rather that J.S. Mill's experimental apprenticeship in the 1820s provided the Company with the kind of model it later used in training other potential despatch writers in the Correspondence Branch of the Examiner's Office, including, for a short while at least, George Grote Mill.³⁷

Finally, in trying to identify the less obvious but positive features of Mill's long

³³IOR: Finance and Home Committee Papers, No. 31 (Apr. 1844), L/F/2/82; Court Minutes (9 Apr., 1844), B/207, 653.

³⁴IOR: Finance and Home Committee Papers, No. 22 (Mar. 1850), L/F/2/132; Mill to Sterling (29 May, 1844), CW, XIII, 629; Mill to Chapman (9 Mar., 1847), CW, XIII, 708.

³⁵IOR: Court Minutes (13 Mar., 1850), B/219, 851-2.

³⁶In this connection it is interesting to recall the emotional effect that reading a passage in Marmontel's *Memoirs* had on Mill during his mental crisis of 1826-27 (A, CW, I, 145).

³⁷Moir, "The Examiner's Office: An Administrative Elite," 37-8, 41-2.

middle period of Company employment, we must also recognize the importance of the opportunities for personal friendship and freedom that his official career offered. Rather sadly, there is little to suggest that his personal relations with Peacock, his immediate superior, were at all close.³⁸ On the other hand, there is ample proof that Mill did enjoy close and stimulating friendships with several other Company colleagues during the 1830s and 1840s, most notably with Horace Grant (who held one of the special Correspondence Branch clerkships between 1837 and 1845) and William Thornton (who, after a short spell in the Examiner's Office, worked in the Marine Branch of the Secretary's Office from 1837 to 1856).³⁹ Such contacts grew out of shared intellectual interests, connected, for example, with Grant's educational studies and Thornton's economic and literary works. But the records also clearly show that Mill's friendship warmly extended into acts of personal kindness and support for both Grant and Thornton.⁴⁰

There is also evidence that, in so far as the pressures of his official business allowed, Mill was able to use his room in East India House as a place where he could informally invite various friends and acquaintances.⁴¹ This amenity may have been of considerable value to him during the years when his external social contacts tended to diminish as a result of the delicacy and difficulty of his longstanding relationship with Harriet Taylor. In the same way, as his *Autobiography* suggests, he was able to use whatever free time came to him during his rather gentlemanly official working day (10 a.m. to 4 p.m.) to get on with his personal correspondence and writings. Although Mill himself sometimes complained to his personal correspondents of the extent to which his freedom was restricted by his Company duties,⁴² the hundreds of private letters which he wrote from East India House during the 1830s and 1840s testify to a not inconsiderable degree of official latitude. And both his *System of Logic* and *Principles of Political Economy* were written on East India Company stationery, almost certainly during office hours.

The general opportunities which Mill's position normally gave him are brought out most illuminatingly in a letter which he wrote to Thomas Carlyle from India House on 30 June, 1837, with which he forwarded a copy of his

³⁸William Foster, *The East India House: Its History and Associations* (London: Lane, Bodley Head, 1924), 211; Mill to Harriet Mill (6 Jan., 1854), CW, XIV, 122-3.

³⁹Foster, *East India House*, 224-5, 238-9; Moir, "The Examiner's Office and the Drafting of Despatches," 132, 139.

⁴⁰IOR: Finance and Home Committee Reports (2 July, 1845), L/F/1/22, 429-31; Finance and Home Committee Papers, No. 43 (July 1845), L/F/2/93; see also below, xxxi-xxxii. In Mill's will, Grant and Thornton were named as executors, though in the event they were superseded by Helen Taylor; see CW, Vol. XXXI, App. A.

⁴¹Foster, *East India House*, 215-18; IOR: Sir William Foster's Notebooks, L/R/5/226, 106.

⁴²See, for example, Mill's letter to Carlyle of 22 December, 1833, in which he complains that his position at East India House "hampers [his] freedom of action in a thousand ways" (CW, XII, 200).

review of Carlyle's *History of the French Revolution*. "I have," he writes,

very little to do here at present. I have worked off my arrear of business at this office, and the work does not now come in nearly so fast as I can do it. It is the way of my work to go in that sort of manner—in fits—and I like that well enough, as it gives me intervals of leisure. I am using this interval to get on with my book—a book I have done little to since the review began, and which you will think very little worth doing—a treatise on Logic.⁴³

The extent to which Mill was able during these years to combine his official duties with his other intellectual interests during the "intervals" in his working day naturally raises the whole question of the character and scope of his Company work. How demanding were his duties, and—more interesting perhaps—how far was he in a position to formulate and control the Company's Indian policies through the despatches which he drafted?

Attempts to throw light on these issues may usefully start with the factual, especially the quantitative, aspects of Mill's work, and fortunately it is here possible to construct a kind of base-line for determining the sheer scale of his official activities by using his own list of despatches supplemented by other archival data.⁴⁴ The significance of this evidence was in fact perceived very early on by his friend William Thornton when contributing his account of Mill's Company career for the obituary notices published in the *Examiner* in May 1873.⁴⁵ After describing his former colleague's own list of despatches, "a small quarto volume of between 300 and 400 pages, in their author's handwriting," Thornton went on to recall that at East India House the Court of Directors' despatches used to occupy on average for each year "about ten huge vellum bound volumes, foolscap size, and five or six inches thick, and that of these volumes, two a-year, for more than twenty years running, were exclusively of Mill's composition."⁴⁶ Rather less vividly but more exactly, Table 2 shows the variations in Mill's annual output of despatches for the whole of his Company career (1823-58). In interpreting this data it is also, of course, necessary to have an idea of the average length of these despatches. For this purpose it may suffice to note that in 1837 (when Mill found time during his office hours to write part of his *Logic*) his output of 34 despatches occupy some 1200 pages of the generously spaced copyist's handwriting, giving an average of 35 pages per despatch. These figures may be contrasted with those for 1844 (the year of George Mill's appointment) when Mill's output rose to 88

⁴³CW, XII, 340.

⁴⁴For Mill's list of despatches, see Appendix A.

⁴⁵*Examiner*, 17 May, 1873, 506-8.

⁴⁶*Ibid.*, 506-7. Mill's list of despatches, to which Thornton refers, apparently passed from the custody of the East India Company to that of the India Office in 1858 when the Company was dissolved and Mill himself retired. The volume was subsequently put away in the office and forgotten. It was rediscovered in 1916 among the miscellaneous records of the Political Department, transferred to the India Office Record Department, and added to the Home Miscellaneous Series as Volume 832. It is now included among the European Manuscripts of the India Office Library and Records (MSS Eur B 405). See IOR: Sir William Foster's Notebooks, L/R/5/225, 253; and also Appendix A.

TABLE 2
Despatches drafted by John Stuart Mill (1824-58)⁴⁷

| Year | Political | Foreign | Public | Public Works | Ecclesiastical | Marne | Law | Commercial | Prince of Wales Island | TOTAL |
|------|-----------|---------|--------|--------------|----------------|-------|-----|------------|------------------------|-------|
| 1824 | 3 | | 6 | | | | | 1 | | 10 |
| 1825 | 3 | | 6 | | | | 1 | | | 10 |
| 1826 | 5 | | 11 | | 3 | | | 1 | 2 | 22 |
| 1827 | 4 | 1 | 13 | | 3 | | 1 | | 1 | 23 |
| 1828 | 10 | | 15 | | 1 | 4 | | | 2 | 32 |
| 1829 | 10 | 1 | 2 | | | | | | 2 | 15 |
| 1830 | 20 | 1 | 6 | | | | | | 1 | 28 |
| 1831 | 11 | | 9 | | | | | | | 20 |
| 1832 | 16 | | 5 | | | | | | | 21 |
| 1833 | 14 | | 3 | | | | | | | 17 |
| 1834 | 21 | | 2 | | | | | | | 23 |
| 1835 | 67 | 3 | 3 | | | | | | | 73 |
| 1836 | 20 | | 2 | | | | | | | 22 |
| 1837 | 32 | 2 | | | | | | | | 34 |
| 1838 | 74 | 2 | 1 | | | | | | | 77 |
| 1839 | 29 | 2 | | | | | | | | 31 |
| 1840 | 46 | 2 | | | | | | | | 48 |
| 1841 | 63 | 2 | 1 | | | | | | | 66 |
| 1842 | 57 | 2 | | | | | | | | 59 |
| 1843 | 56 | 1 | | | | | | | | 57 |
| 1844 | 86 | 1 | 1 | | | | | | | 88 |
| 1845 | 56 | 1 | 4 | | 1 | | | | | 62 |
| 1846 | 61 | 2 | 1 | | | | | | | 64 |
| 1847 | 48 | 1 | 1 | | | | | | | 50 |
| 1848 | 57 | | | | | | | | | 57 |
| 1849 | 72 | | | | | | | | | 72 |
| 1850 | 66 | | | | | | | | | 66 |
| 1851 | 65 | | 1 | | | | | | | 66 |
| 1852 | 73 | | | | | | | | | 73 |
| 1853 | 96 | | | | | | | | | 96 |
| 1854 | 83 | | | | | | | | | 83 |
| 1855 | 36 | | | | | | | | | 36 |
| 1856 | 56 | | | | | | | | | 56 |
| 1857 | 51 | | 1 | 26 | | | | | | 78 |
| 1858 | 56 | | | 22 | | | | | | 78 |
| 1523 | 24 | 95 | 48 | 8 | 5 | 1 | 2 | 8 | 1713 | |

despatches, occupying about 2120 pages, giving an average of 24 pages per despatch. Table 2 shows that thereafter his annual quota of despatches averages 66 for the remaining period of his employment.

⁴⁷This table is based on the data contained in Appendix A.

The administrative and subject range of Mill's despatches can to some extent be deduced from the departmental headings shown in the table. Clearly, his principal responsibility throughout his official career was for drafting the Political despatches (amounting to 1522). Broadly speaking, these despatches are concerned with the Company's non-secret relations with independent and protected princely states throughout the Indian Sub-continent, as well as with the frontier regions and territories bordering on British India, such as Afghanistan, Iran and the Gulf, Burma, etc. Very closely connected with the despatches of the Political Department—and eventually absorbed by them—are those of the Foreign Department (1827-47), which mainly deal with the affairs of other European powers in South Asia, notably the French, Dutch, and Portuguese. The remaining 190 or so despatches drafted by Mill may be roughly grouped into four categories: Public Department despatches (1824-57) which range widely over many aspects of the civil government of British India but are particularly concerned with education and the press;⁴⁸ Prince of Wales Island despatches (1826-30) covering the general administration of the Prince of Wales Island (or Penang) Presidency; miscellaneous despatches (1824-45) including Ecclesiastical, Marine, Law, and Commercial despatches; and Public Works Department despatches (1857-58) relating principally to roads and canals in British India.

This extensive information makes it possible to gauge the descriptive and quantitative range of Mill's despatches in considerable detail and with a fair degree of precision. What, however, poses more difficulty is the evaluation of the qualitative aspects of his contribution and, in particular, the assessment of his personal and official influence over the Company's policies in India. To begin to sketch out part of an answer, it is necessary, first, to understand the peculiar function of the Company's Indian despatches, and second, to look more closely at the elaborate procedure by which the despatches were prepared and approved—a procedure in which, as Mill himself admitted, he was "merely one wheel in a machine, the whole of which had to work together."⁴⁹

As regards the essential function of the Company's despatches, Mill provides some enlightening observations in the course of his own evidence to the Parliamentary Select Committee in 1852:

The home Government at this moment exercise an absolute control over the Government in India. Within what limits do you think that control should be exercised? There are very few acts of the Government of India which it is possible for the authorities here to set aside when they are once done. Some very important things they can do: they can put a stop to pecuniary jobbing when they detect it; they can cancel improper appointments, and control salaries and establishments; and they can, and often do, redress the grievances of individuals. But in most of the political measures of a general character, they have very little power of interfering with effect or advantage, after the thing is done. They have, however, a great

⁴⁸It also seems that Mill was responsible for overseeing the Public and Ecclesiastical drafts prepared by his younger brother, George Grote Mill, between 1844 and 1848 (Moir, "The Examiner's Office and the Drafting of Despatches," 136; see also above, xviii-xix).

⁴⁹A, CW, I, 87.

power of making useful comments, which may serve as instructions for subsequent cases of the same kind; and it seems to me the greatest good that the home authorities can do is to comment freely on the proceedings of the local authorities, to criticise them well, and lay down general principles for the guidance of the Government on subsequent occasions. (69-70.)

In other words, Mill is here indicating the reactive and *ex post facto* character of most of the home government's despatches, including, of course, his own. Even with the improvements in the speed of communications between London and India, it was clearly not feasible for the Court of Directors (and behind them the Board of Control) to try to regulate the actions of the "men on the spot" in Calcutta, Madras, or Bombay in detail or in advance.⁵⁰ The most that could usually be aimed for, as Mill shows, was to comment critically on what had already been done in India, to lay down general principles for future guidance, and to correct any specific abuses that had been brought to light in the official letters from India. Thus Company despatch writers were more often critically reviewing Indian policies than actually controlling them. However, as Mill makes clear elsewhere in his evidence before the Select Committee, there were also differences in the amount of prior consultation that was possible between the Government of India and the Company in London, depending on the area of administration concerned. For example, while in the ever-shifting field of political and foreign relations the opportunity for such prior discussions was inevitably limited, it was possible for more substantive policy consultations to take place in the correspondence concerned with the introduction of new policies in "internal government" (e.g., over land revenue, judicial and educational reforms, or public works expenditure) (43-4).

The effects of these general limitations on the scope and character of the Company's Indian correspondence are at once apparent in many of the despatches which Mill himself drafted. Thus, typically, the successive paragraphs of his Political Department despatches add up to a careful critical review of the events and decisions reported earlier in great detail in the Indian government's own letters to London. In many or most instances, the despatch gives the Court of Directors' retrospective approval for particular measures already taken, including here and there a piece of advice and criticism, and occasionally some enunciation of broader principles or policy to be followed more carefully in future when appropriate. In general, in Mill's Political despatches, the more significant broad expressions of policy or principle occur in the context of comments on the degree of intervention

⁵⁰In 1828, when Mill became an Assistant to the Examiner, it usually took about six months for letters from the Bengal Government to reach the Company in London. During the 1830s and 1840s the communication system improved considerably as the Company began to employ steamships and to make more use of the Red Sea route. By 1852, when Mill gave his evidence to the Parliamentary Select Committee, letters from Bengal usually took about two months to reach London. See also Philips, *East India Company*, 264.

that is proper or politic in the internal affairs of particular princely states. For example, the whole question of how far the Company should actively interfere in the internal government of Oudh in the light of its existing treaty relations with that state is a recurrent theme in the twenty or so Political despatches concerning Oudh which Mill drafted between 1828 and 1856. Many less known comments on the advisability or otherwise of British intervention in the internal affairs of other states occur throughout Mill's enormous output of Political despatches. It hardly needs to be added that such general comments on the theme of intervention and internal sovereignty are not included because Mill himself was interested in such subjects, but rather because they were part of the larger, more contentious issues attached to British rule in South Asia during that period—issues that regularly dominated the minds of all officials concerned with the expansion and security of the Company Raj. Why, in such circumstances, Mill himself, from his position in London, decided to take one particular line rather than another, remains of course a distinct and often very difficult area for exploration (see l-liv below).

Another, perhaps less important field in which Mill, as the representative of the Court of Directors, often felt obliged to take a more active critical line in his Political despatches was that concerned with the financial and other personal claims of individual officials in the employ of the Indian Political Department, and in the control of the whole Political Department establishments. Here he is specially concerned with redressing the genuine grievances of individuals and regulating government expenditure, even if doing so meant giving instructions to the British Indian authorities to countermand their earlier decisions.

In the case of the non-Political despatches for which he was responsible—which, it must be stressed, constitute a minority within his total output—Mill's comments to the Select Committee, quoted earlier, are also pertinent. Thus, although his despatches in these departments conform to the general pattern of those issued in the Political Department (i.e., a systematic review of the relevant transactions reported earlier by the governments in India), they also from time to time contain more positive statements of the policy or principle to be followed in particular aspects of "internal government." Among the best known of such statements are those included in a succession of Public Department despatches devoted to educational matters. Between 1825 and 1836 Mill was responsible for about seventeen such despatches, and there is sufficient evidence to show that the central questions thrown up in the course of this correspondence—most notably, how far it was proper to encourage indigenous Indian learning and culture, and what were the best ways of spreading Western knowledge in Indian society—were matters on which he was ready to take a strong personal stand. The nature of that stand, along with his other "personal views" on British Indian policy, will be considered more closely in the last part of this Introduction (xxxix-liv below).

In addition to being somewhat restricted by the generally retrospective character of the Company's despatches, Mill and his colleagues in the Examiner's Office

and elsewhere were of course obliged to submit their drafts for approval and possible alteration by a variety of authorities within the Company and the Board. To this extent, as was earlier noticed, Mill realized that he was "merely one wheel in a machine." To appreciate the force of what he meant it is necessary to describe the main bureaucratic hoops through which his drafts had to pass before they finally emerged from East India House in the form of despatches signed by the necessary quorum of directors. One of the fullest contemporary accounts of how the correspondence system worked is that given by Mill's colleague, James Cosmo Melvill, the Company's Secretary, to the Select Committee in 1852. This account may be taken as a basis for a further clarification of the extent to which Mill's drafts were influenced and altered by others.

Each despatch from India is laid before the Court of Directors. When a despatch comes from India it is accompanied by a collection of papers bearing upon the subject, and of course that collection contains the former correspondence relating to it, and the present proceedings of the Government upon it. This despatch comes to the secretary's office, and from it, is immediately transferred to the department to which it relates. In that department an abstract of the contents of the despatch is made; this is lithographed, and copies of it are sent to the Chairman and Deputy Chairman, and the members of the committee having the superintendence of the department to which the despatch relates. The officer in charge of that department then communicates with the Chairman and Deputy upon the despatch, and, in cases in which the subjects are not mere routine, receives instructions as to the tenor of the reply. A draft answer is then prepared, and submitted with the collections to the Chairman and the Deputy; they confer together, and with the officer, upon the subject: and when the draft conforms to their views, they place their initials upon it as the authority for its being sent to the President of the Board, in what is technically called "P.C."; that is to say, previous communication. In due time the draft is returned either unaltered, or with alterations made in it by the President of the Board. If unaltered, the draft is immediately submitted to the committee of the Court having superintendence of the department in which it is. If altered, the officer communicates with the Chairman and Deputy Chairman, who either allow wholly or partially, or reject entirely, the alterations. The draft is finally arranged by the Chairman and Deputy, and is then in like manner submitted to the committee. Drafts generally lie on the table of the committee for a week, during which time both the draft, and any papers bearing upon the case, are perused by the members of the committee. The committee then discuss the draft, and adopt or alter it as they think fit, after which it is submitted to the Court, who usually take a week for consideration, and then the draft comes on for discussion. Every director has an opportunity of expressing his sentiments, and if he differs from the majority, of recording a dissent. When the draft is approved by the Court, the secretary sends it officially, with all the papers, including the dissents, if any, to the Board of Commissioners, and the Board return it quickly, and always within two months, the period limited by law, approved or altered; and if altered, with a statement of their reasons for making the alteration. The unaltered drafts are immediately transcribed, and fair copies, signed by at least 13 members of the Court, are despatched to India. The altered drafts are referred to the proper committee, upon whose report the Court decide, either that the alterations shall be acquiesced in, in which case the draft is signed and despatched to India, or that a remonstrance shall be addressed to the Board against the alterations, in which case the draft is sent back until the final decision of the Board is communicated, and then the despatch is forwarded. Such is the ordinary course of proceeding, but it frequently happens that important questions are raised by the Government of India requiring prompt attention, and those are, both by the Court and the Board, taken

out of the usual course and quickly disposed of; so that replies to references from India are often, now that the communication is so accelerated, received there within six months from the date of the reference, and in some cases earlier than that.⁵¹

This account of the operation of the procedure, though lengthy and complex, effectively identifies the key stages at which the drafts, initially prepared in the Examiner's Office and other departments, were then subject to approval or alteration by (1) the Chairmen, (2) the President of the Board in "Previous Communication," (3) the Chairmen again, (4) the appropriate committee of the Court of Directors, (5) the Court of Directors, and (6) the Board of Control. In the face of such a complicated system, involving reference to so many different individuals and interests, it may be reasonably conjectured that the chances of the author's original document emerging unaltered were not high, particularly in the case of drafts dealing with controversial subjects.

The archival evidence for the passage of Mill's drafts through the above stages is remarkably detailed and extensive but by no means comprehensive. In particular, there is hardly any surviving documentation for the preliminary stages in the drafting process—no record, for instance, of any instructions received by Mill from the Company Chairmen or of the rough sketches for the Previous Communications which drafting officers such as Mill would appear to have produced prior to the preparation of the formal PC (Previous Communication) documents (i.e., stage 1 of the process outlined above). However, for the remaining stages in the process, the regular archive series in the India Office Records (the Company's E/4 Despatches and the Board's L/P&S/6 Previous Communications and Drafts), provide a very ample picture of any alterations or revisions that were made to Mill's Political and Foreign drafts, from the Board's unofficial scrutiny at the PC stage to the final official approval of the despatch by Court and Board (i.e., stages 2 to 6 inclusive). Unfortunately, in the case of the drafts which he prepared in other departments, there is for the most part no record of the scrutiny and alterations at the PC stage, and it is only the later stages, involving the submission of the official drafts to the Committee, Court, and Board (i.e., stages 3 to 6), that are fully documented.⁵²

It would clearly be necessary to investigate, sift, and assess the surviving archival evidence in detail before hazarding any comprehensive conclusions as to the extent to which Mill's own drafts were subject to alteration by others—the Chairs, the committees, and especially the Board of Control.⁵³ Several spot-

⁵¹*PP*, 1852, X, 16-17.

⁵²Moir, "The Examiner's Office and the Drafting of Despatches," 140-52.

⁵³In the evidence he gave to the Parliamentary Select Committee in 1852, Mill stressed the extent to which the directors who then sat on the three committees of the Court of Directors took an active interest in the drafts submitted to them. However, any alterations made by the committees can usually be clearly identified from the records, whereas the earlier part played by the Chairs in the preparation of the PCs is not normally documented. For the functions of the three committees—Finance and Home, Political and Military, and

checks suggest that the majority of his Political PCs were in fact subject to some, if slight, alteration by the Board. Any more thorough investigations of the Board's reviews, in particular, would also need to distinguish carefully between minor verbal alterations and more drastic changes involving the substitution or insertion of whole new paragraphs designed to convey a different view of the matter from that contained in Mill's original draft. When asked by the Select Committee in 1852 whether it was untrue to say that the real direction of the Government of India resided in the Court of Directors (as distinct from the Board), Mill replied: "It is practically by no means a fiction, since it does not happen once in a hundred times that a despatch, prepared by the Court of Directors, undergoes alteration in principle and substance by the Board of Control" (54). It is perhaps more likely than not that this general estimate would prove to be generally correct in relation to the Board's treatment of his own drafts. After all, he himself evidently thought of his despatches as being sufficiently "his" to prepare a special list of them, as well as including those which were printed for Parliament in the record he kept of his own publications.⁵⁴ At the same time it is important to keep in mind that Mill also qualified his positive reply to the Select Committee about the successful passage of the Court's despatches, by admitting that the Chairs "seldom send up a proposed despatch which they know is contrary to the President's opinion," thus acknowledging those rather shadowy occasions when drafts prepared in the Examiner's Office may have been directly or indirectly moulded by the Chairs so as to pass safely through the Board (54).⁵⁵ No doubt (as Mill told the Select Committee) the readiness of the Chairs to accept the drafts put up for them also depended on their own degree of interest in the Indian correspondence. For instance, writing to his wife on 6 March, 1854, Mill referred to the difficulties he had experienced in getting his drafts accepted by Sir James Weir Hogg, "explaining, defending, and altering so as to spoil it as little as I could," and contrasted Hogg's interrogations with the easier responses of his successors, Russell Ellice and John Oliphant.⁵⁶ On the whole, in the face of the uncertainties,

Revenue, Judicial, and Legislative—which were established in 1834 following the decision to end the Company's commercial activities, see Moir, *General Guide*, 28-9.

⁵⁴In considering the question of how far Mill's despatches were altered by the Board, etc., it is important to note that Mill himself omitted over twenty items from his own list of despatches (MSS Eur B405) apparently on the grounds that, though originally prepared by him, they were then so substantially altered by the Board at the PC stage as to cause him to disown them. See those marked with X in Appendix A.

⁵⁵There is some evidence in the L/P&S/6 series of Previous Communications and Drafts that, when faced with particularly difficult or delicate drafts, the Chairs occasionally decided to sound out the President of the Board privately with a "Pre-PC," i.e., an official draft sent ahead of the more formal PC in order to elicit his first reactions. See, for example, Political PC 9097, concerning Jagirs in the Punjab, sent to the President as a "Pre-PC" in November 1854 (Item 721X in the List of Despatches in Appendix A).

⁵⁶CW, XIV, 178; see also 42-3 below for Mill's comments on the role of the Chairs.

it is perhaps best to reserve judgment on the difficult issue of the survival and integrity of Mill's original drafts, at least until more detailed studies of particularly significant and representative drafts have been carried out.

Mill's long middle years as Assistant to the Examiner thus present many facets and episodes of considerable biographical interest, ranging from his more personal reactions concerning his position to the peculiar demands of his drafting responsibilities. Indeed, the evidence for his official activities during this period leaves the impression of Mill's steadily impressive buildup of knowledge about Indian government and of his growing intellectual authority within the Company. Appropriately enough, this impression of his development finds concrete expression towards the end of this period when in 1852 he was required to appear as a representative of the Examiner's Office before the House of Lords Select Committee on Indian Territories—as a senior Company spokesman in effect (see 31-74 below). On the basis of his wide knowledge and long experience of the Company's Indian affairs and his own unique philosophical training, he was then able to present his critical interlocutors with a clear, balanced, and subtly impressive picture of the overall advantages of Company rule. The directors were evidently well pleased with the effectiveness of his performance in their defence, even though the Company failed to deflect the legislature from effecting fresh inroads into its independence through the Charter Act of 1853.⁵⁷ In August 1854, as noted above, the directors expressed their appreciation in the time-honoured Company fashion by adding another £200 to his salary in recognition of "the high sense which the Court entertained of the admirable manner in which he conducts his duties."⁵⁸

MILL AS EXAMINER (1856-58) AND THE END OF THE EAST INDIA COMPANY

THERE WAS NOTHING unexpected or radical about the Company's appointment of John Stuart Mill as Examiner of Indian Correspondence on 28 March, 1856.⁵⁹ Indeed, given that Thomas Love Peacock, the Examiner, and David Hill, the Assistant Examiner, had both tendered their resignations after lengthy and distinguished service, Mill as First Assistant was next in line to succeed to the headship of the office. At the same time it seems almost more than fortuitous that, with Parliament about to embark on its final legislative attack on the Company's position—and with Peacock past seventy and Hill in his seventieth year—both

⁵⁷The Charter Act of 1853 (16 & 17 Victoria, c. 95) reduced the number of directors from twenty-four to eighteen, six of whom were to be appointed by the Crown. The Act also abolished the Company's patronage over Indian civil and military appointments.

⁵⁸IOR: Court Minutes (30 Aug., 1854), B/228, 928-9.

⁵⁹IOR: Court Minutes (28 Mar., 1856), B/231, 1306-7.

men should have chosen this moment to resign, leaving the way clear for Mill, who had already proved his capacities to defend the Company's interests vigorously during the Parliamentary investigations that preceded the enactment of the Charter Act of 1853. The appointment of Mill thus secured for the directors their preferred candidate for the Examinership at a particularly crucial time, while also being strictly in keeping with traditional bureaucratic norms for promotion.

For Mill himself the promotion brought both a substantial rise in salary—from £1400 to £2000—and a considerably wider range of responsibility. As Examiner, he now technically ranked after the Secretary as the second most important officer in the Company's home establishment, and in real terms, considering his national reputation, he must have appeared to his colleagues as a striking and uniquely distinguished figure in their midst. For the next two or more years it is also clear that the pressure of his new official duties left him with fewer of those "intervals" and opportunities for personal reflection and composition of the sort he had been able to enjoy while working in the office during the 1830s and 1840s.

Mill's overall responsibilities as Examiner may be roughly divided into three main aspects: (1) supervising the work of his Office, especially that of his immediate assistants, and continuing to draft certain despatches himself;⁶⁰ (2) acting as Clerk to the Secret Committee of the Court of Directors;⁶¹ and (3) advising the Chairs on key aspects of the Company's Indian Government, especially in their dealings with the Board of Control and with Parliament.

As regards the first aspect, the scale and nature of his supervisory duties can be broadly gauged from an organization chart (Table 3).

To appreciate Mill's role in more detail, it also needs to be borne in mind that as Examiner his particular responsibilities varied according to the status and autonomy of the principal staff groupings within the Office. For example, the two Assistant Examiners, John Hawkins and Francis Prideaux, stood immediately after Mill himself in the hierarchy, and might be occasionally called on to deputize for him.⁶² They were normally expected to take full responsibility for their own draft despatches, discussing them with the Chairs, and piloting them through the Previous Communication negotiations with the Board (as Mill himself had done in


⁶⁰A, CW, I, 247-9. It should be noted that the Examiner's Office at this time was responsible for the preparation of despatches to India in the Political, Public, Judicial, Legislative, Revenue, Separate Revenue, and Public Works Departments. It was not concerned with Financial or Marine despatches, which were dealt with in the Secretary's Department, or with Military despatches, which were handled by the Military Secretary. See also Moir, *General Guide*, 31-2.

⁶¹M.I. Moir, "A Study of the History and Organization of the Political and Secret Departments of the East India Company, the Board of Control and the India Office, 1784-1919" (thesis for London University Diploma in Archive Administration, 1966), 50-2.

⁶²For the official careers of John Hawkins and Francis Prideaux, see Moir, "The Examiner's Office and the Drafting of Despatches," 133, 138.

TABLE 3

Examiner
J. S. Mill



the earlier stages of his own career). This pattern is confirmed by the fact that Mill's own list of despatches during this period (1856-58) does not include any drafts in the Revenue, Judicial, and Legislative Departments—drafts for which Hawkins and Prideaux were primarily responsible.

The position of the three Assistants to the Examiner, Edmund Bourdillon, John Kaye, and William Thornton, seems in theory at any rate to have been similar to that of Hawkins and Prideaux, in that they too were expected to manage most of their departmental drafts, leaving Mill to exercise only general supervision, and to advise or take on the more difficult or important policy issues raised by the correspondence. In practice, however, it appears that only Bourdillon, the most experienced of his Assistants, was able to operate with this degree of autonomy in his control of Public Department drafts.⁶³ In the case of Kaye, who had only joined the Office in 1856, Mill probably considered that it was necessary to lend more support while the newcomer found his feet among the complex issues of the Political Department. Certainly Mill's list of despatches shows that he personally continued to prepare over fifty Political drafts per year from 1856 to 1858, leaving Kaye to deal with the remainder.⁶⁴ Perhaps also Mill may have been a trifle reluctant to relinquish the reins in the Political Department which he had after all held for so long.

By contrast, William Thornton, who took over the Public Works Department in

⁶³*Ibid.*, 131.

⁶⁴*Ibid.*, 134-5.

March 1856, presented Mill with another kind of problem. Thornton had been recommended for the new Assistant's post by Mill himself, on the basis of his personal knowledge of Thornton's intellectual attainments and commitment to the spread of public works. Unfortunately, some months after his appointment, Thornton succumbed to a form of nervous depression that, he said, "for nearly a year absolutely incapacitated me from mental labour." Faced with this critical situation, which might normally have led to Thornton's retirement, Mill came to his friend's rescue, "quietly taking upon himself and for the space of twelve months discharging the whole of my official duties, in addition to his own." In practical terms this involved Mill in preparing some forty-eight Public Works drafts between May 1857 and April 1858, after which Thornton recovered his health and was gradually able to resume his regular duties.⁶⁵

Detailed documentary evidence is somewhat lacking for Mill's official relationships with the other members of his department, viz. the two clerks in the Correspondence Branch and the sixteen or so established clerks who performed the more routine office duties. There is, however, some slight evidence to suggest that he may have exercised supervision over the early drafts of John Melville, one of the Correspondence clerks, but in general it is likely that Melville and Peacock's work on the Revenue, Judicial, and Public drafts was more closely linked with that of Prideaux, Hawkins, and Bourdillon.⁶⁶ For the remaining established clerks, Mill's position was essentially that of a bureaucratic head of the department responsible for the effectiveness of his overall establishment and for taking up as necessary the periodic pecuniary and other personal claims and cases of individual clerks with the Company's directors.

The role of Clerk to the Secret Committee, which Mill also assumed as part of his general duties as Examiner, was by this time somewhat less significant and onerous than might at first be supposed. The members of the Secret Committee, it will be recalled (see x above), consisted of the two Chairs and one of the senior directors. Together they were primarily responsible for transmitting to India secret instructions prepared at the Board of Control on important matters of war, peace, and foreign relations. When Mill first joined the Company in 1823 the Secret Committee had been a considerably more powerful body, able to put forward its own secret drafts to the Board and to enter into confidential discussions with the President concerning the general affairs of the Secret Department. By 1856, however, much of the earlier authority of the Committee had been lost as a result of the Board's growing insistence on controlling the higher-level aspects of the British Indian foreign policy. Very occasionally the Committee was still able to issue isolated despatches concerning the more routine or fringe aspects of Secret Department business, but by and large it had been reduced to something of a

⁶⁵*Examiner*, 17 May, 1873, 507. See also Appendix A, pp. 293-4.

⁶⁶Despatches to India and Bengal, Judicial No. 47 (12 Nov., 1856), E/4/840, 229.

cypher. To John Kaye, for instance, who joined the office in 1856, it was soon apparent that "The President of the Board was in reality the Secret Committee."⁶⁷

As Clerk to the Committee, Mill's position was accordingly rather more formal and administrative than substantial or executive in character. Apart from having final responsibility for the transmission and despatch of the Secret correspondence and its occasional declassification (i.e., laying it before the Court as a whole), the most significant part of his work was preparing or approving the replies to various Secret Department enquiries sent to the Company by the Board, often at the request of the Foreign Office. For the most part the subjects dealt with were not of major diplomatic or military importance. Typically, they covered issues arising from current diplomatic exchanges, e.g. the status of French possessions in India, postal communications in the Gulf, and the recent history of the Kuria Muria Islands, etc. In such cases Mill was usually expected to provide relevant factual data and to represent the Company's views of its own interests in these issues.⁶⁸

More important than his specific work for the Secret Committee was Mill's general position as one of the principal policy advisers to the Chairmen and the Court of Directors between 1856 and 1858. Much of the normal administrative character of this role was obviously connected with the Examiner's general responsibility for the conduct of correspondence—a responsibility which regularly involved him in dealings with the Chairs, the relevant committees of the Directors, and the Court as a whole. Over and above these normal contacts, however, it is clear that Mill was increasingly called upon to advise the Company on some of the key issues then affecting its relations with the government. Central among these problems was the very future of the Company itself, now that the Parliament had determined, through the Charter Act of 1853 (16 & 17 Victoria, c. 95), that the Company's responsibility for India should be held in trust for the Crown (instead of being renewed for a further term of years as earlier Charter Acts had provided). Much as they may have wished to persuade themselves to the contrary, the directors, as well as Mill himself, must have realized that this enactment represented a very real threat to their future corporate existence—that indeed it amounted to a hanging sword whose descent would almost certainly be precipitated by any false move or perceived failure on their part. Unfortunately for the Company, the Mutiny or Great Indian Revolt of 1857, with its traumatic tales of death, disaster, and apparent political mismanagement, was inevitably viewed by government and opposition as just such a failure, requiring a radical legislative remedy.⁶⁹

⁶⁷Moir, "A Study of the Political and Secret Departments," 106.

⁶⁸*Ibid.*, 101-2. Examples of Mill's correspondence with the Board of Control on Secret Department business (1856-58) are in Secret Miscellany Book L/P&S/3/1, 440-2, 482-5.

⁶⁹The account given here of the successive Government of India bills between January and August 1858 is mainly based on *Hansard's Parliamentary Debates* [PD], 3rd ser., 1857-58, Vols. 148-51; *The Cambridge History of India*, Vol. VI: *The Indian Empire*,

By the end of 1857 the directors knew that Lord Palmerston's ministry was preparing a comprehensive measure to end the Company's responsibility for the government of India, and they had evidently instructed Mill and other advisers to begin to prepare a defence. However, they still had no exact knowledge of the government's proposed new constitutional arrangements. On 31 December the Chairs accordingly sent a brief general defence of their position to Palmerston and asked him for details of the proposed India Bill.⁷⁰ Palmerston replied on 18 January that while his government would certainly accord due attention to their observations, he could not provide any more information concerning the new legislation prior to its formal presentation to Parliament.⁷¹ Though still left in the dark but fully aware that time was running out, the Chairs swung the Company into action, and, in this bold counter-attack, Mill played a vital role. By 20 January, 1858, his draft defence of Company rule had been approved by both the directors and proprietors. Embodied in the form of a Petition from the Company to Parliament, it was then formally presented to the Commons on 9 February and to the Lords on the 11th (75-89).⁷² The Petition was closely followed by a more extensive historical defence of the Company's record, also largely prepared by Mill, and entitled *Memorandum on the Improvements in the Administration of India during the Last Thirty Years* (91-160). A few days later, on 13 February, Palmerston introduced his bill for transferring the government of India from Company to Crown. Under his scheme, the home administration was in future to be entrusted to a President assisted by a Council of eight members, each holding office for eight years, and nominated by the Crown either on the basis of previous experience as directors of the Company or by virtue of service/residence in India. It was not a particularly radical scheme, but of course it meant the end of the Company.

The Company's Petition to Parliament as drafted by Mill had the initial disadvantage of having been prepared before the full details of Palmerston's measure were known. Nonetheless it was to prove a remarkably potent and flexible defence. In a finely structured and eloquent sequence of propositions, the Petition gradually succeeded in casting serious doubts on the government's case for withdrawing the Company's Indian responsibilities. The Company, it argued, had

1858-1919, ed. H.H. Dodwell (Delhi: Chand, 1964), 206-12; Sir Courtenay Ilbert, *The Government of India* (Oxford: Clarendon Press, 1907), 94-7; and Donovan Williams, *The India Office, 1858-1869* (Hoshiarpur: Vishveshvaranand Vedic Research Institute, 1983), 1-19.

⁷⁰"Correspondence between the First Lord of the Treasury and the Directors of the East India Company Respecting Legislative Measures to be Proposed for the Future Government of Her Majesty's Dominions in India," *Sessional Papers of the House of Lords, 1857-58*, XI, 445-7.

⁷¹*Ibid.*, 448.

⁷²*PD*, 3rd ser., Vol. 148, col. 970.

on the whole been notably successful in building up a great empire, progressively administered at little cost to the Exchequer. The government had offered no advance justification for its proposed intervention—soon after the 1853 Parliamentary investigation—beyond implying that the Company was to blame for the “calamitous events which have recently occurred in India” (78). Such a charge was quite untenable given that the government itself, through the Board of Control, had long carried ultimate responsibility for the Company’s Indian policies. If mistakes had been made, the government should accept a major share of the blame. Meanwhile the timing of the proposed measure could hardly have been worse—precipitated by reactive emotion, it was also likely to be interpreted by the Indian people as heralding a wholesale British attack on their traditional beliefs and customs. On the other hand, the Petition reasonably continued, the Company was certainly not opposed to introducing changes in the present form of government, provided these could be shown to be improvements on the existing system. Thus, if the government was still determined to transfer the home administration of India to a minister of the Crown, it would surely be recognized by all that a minister would require a special body of advisers to discharge his immense duties responsibly. To be at all effective, such a council would need to be composed of an adequate number of persons experienced in Indian government and with a majority holding their appointments independent of the minister; they would also need to play a full and independent part in the formation of British Indian policies—to prepare despatches, for instance, even if what they proposed was ultimately subject to the minister’s approval. Finally, the Petition drily pointed out, if a council of this type was deemed essential for the home administration of India, the government did not need to look further than the existing Court of Directors. In fact—and here the Petition grasped the full irony of its logic—if all the basic conditions for the general good government of India were present in the existing pattern of administration represented by the Court and the Board, why bother to change the system?

The Petition, as drafted by Mill, combined with the detailed *Memorandum* on the Company’s Indian administration, were soon recognized in Parliament as something of a *tour de force*. More particularly, while basically denying the need for radical legislation, the Petition had pointed the way towards a possible compromise with the government in which some of the essential features of the old Company regime might be perpetuated, especially through the creation of an active and independent council for the proposed minister. However, in the short time available neither Mill nor the Company’s defenders inside Parliament could prevent the Commons from approving, in the course of February 1858, the basic principles of intervention contained in Palmerston’s India Bill. In fact, the Company escaped further action on the basis of this bill only because Palmerston himself was turned out of office on another issue shortly afterwards.

Palmerston’s departure provided only a brief respite for the Company, as the

new ministry, led by Lord Derby, with Disraeli as Chancellor of the Exchequer and Ellenborough as President of the Board of Control, was equally determined for various reasons to bring an end to the Company's rule. However, while Derby's new India Bill resembled Palmerston's in its basic objectives, including the need for a council to advise the new Secretary of State, it failed to provide a generally acceptable constitution for the proposed council. According to the new scheme, the council was to consist of eighteen members, nine of whom were to be Crown nominees, while the remainder were to be elected, partly by persons who had served in India or held Company stock, and partly by the Parliamentary electors of the leading commercial cities, e.g., London, Manchester, Liverpool, etc. It soon became apparent that such an elaborate system would not gain Parliamentary approval. By April 1858 the government therefore agreed to drop the main provisions of the bill and to proceed more flexibly on the basis of a series of resolutions which could be more easily discussed and amended, and eventually formed into a new measure.⁷³

By April 1858 the debates on the future constitution of the home government of India had reached a crucial stage. That two measures designed to bring about the change to Crown rule had had to be abandoned was not much comfort to the Company, since it was clear that the government still intended to push ahead with its basic plans. At the same time, the Parliamentary debates as a whole had begun to display a more sympathetic attitude to the Company than had previously been the case, and a greater willingness to consider some of the fundamental arguments in favour of a more independent body of councillors for the new Secretary of State, which Mill's Petition had originally articulated back in February. At this critical juncture the Court of Directors felt the necessity of acquainting the Company's proprietors with their views of the legislative threat that hung over them, and of planning their future defensive strategy. To accomplish this important stock-taking with realism and rationality they again turned to Mill. The resultant *Report to the General Court of Proprietors, Drawing Attention to the Two Bills Now before Parliament Relating to the Government of India*, largely drafted by Mill, was approved by the Court on 6 April (161-71). While noting the more favourable view of the Company's government now taken in the Parliamentary debates, the new Report actively criticized the provisions of both bills and concluded that neither had succeeded in putting forward a form of administration better than the existing Company/Board system. Only that system, with its built-in official checks and balances, was properly suited to the general good government of India. However, the Report acknowledged that there was now little prospect of deflecting the government from its intention to bring an end to Company rule. Instead, building realistically on the earlier arguments contained in the Petition, the Report urged that "every exertion should be used in its passage through committee to

⁷³*Ibid.* (12 Apr., 1858), Vol. 149, col. 877; for the Resolutions, see *ibid.*, Appendix.

divest it of the mischievous features by which both Bills are now deformed, and to maintain, as at present, a really independent Council, having the initiative of all business, discharging all the duties, and possessing all the essential powers of the Court of Directors" (171).

Mill's ingenious strategy for maintaining a balanced and informed home government for India through a kind of covert survival of the Court of Directors in the form of the newly envisaged Council for India was effectively pursued by the Company's supporters inside and outside Parliament between April and June 1858. And beyond all earlier expectations they succeeded in putting forward or modifying many of the key proposals that dominated the constitutional debate during the final crucial phases of the legislative process. Mill himself was especially active during the period in writing pamphlets stressing the dangers inherent in the government's policy and the importance of implanting an active and independent council in the proposed new institutional framework (*A Constitutional View of the India Question*, 173-8; *Observations on the Proposed Council of India*, 179-83; *Practical Observations on the First Two of the Proposed Resolutions on the Government of India*, 185-92; *The Moral of the India Debate*, 193-8; and *A President in Council the Best Government for India*, 199-204).

In seeking an audience for their case, Mill and his allies were no doubt considerably helped by the government's growing readiness "to deal tenderly with the Company."⁷⁴ In the series of government resolutions put forward and debated during May and June 1858, which eventually formed the basis of the new India Bill introduced by Lord Stanley on 24 June, there was on the whole more awareness of the importance of giving a measure of independence to the new council, more willingness to recognize the need for some continuity with the Court of Directors, and more appreciation of the need to protect Indian governments and revenues from the negative aspects of British party politics and overt exploitation. These various trends were strikingly illustrated in the final important exchanges that took place between the Chairs and Lord Stanley towards the end of June 1858. These exchanges opened with a letter of 23 June from the Chairs to Stanley, again drafted by Mill (205-12). In this letter the Chairs welcomed those elements in the new bill that gave more independence to the council, but went on to make a last-ditch effort to convince the government of the need to strengthen the council's powers in general policy-making, especially by giving it a right of veto over the Secretary of State's proposals to dispose of the Indian revenues. Somewhat surprisingly, the government then agreed to incorporate new clauses in the bill to give expression to at least those parts of the Chairs' recommendations which related to the security of the Indian revenues.

The "Act for the Better Government of India," which finally emerged from these debates and discussions, was successfully piloted through Parliament by

⁷⁴*Cambridge History of India*, VI, 211.

Stanley and given royal assent on 2 August, 1858.⁷⁵ Although the Act brought no retreat on the central issue of the transfer of the Company's government of India to the Crown, many of its provisions represented a real compromise between the government and the Company. A Secretary of State for India was to take over all the powers of the Company and the Board of Control, but most of his powers were to be exercised in conjunction with a specially constituted Council of India consisting of fifteen members, the majority of whom had to have a substantial Indian qualification. Eight of the members were to be nominated by the Crown and seven elected by the retiring Court of Directors, with subsequent vacancies in each group to be filled by the Crown and the Council respectively. All members were also to hold office for life or during good behaviour. The Secretary of State was directed to submit all proposed orders and despatches to the Council before issue except those of a secret or urgent character. In general, the Secretary of State was empowered to overrule his Council if the need arose, except in cases involving expenditure from Indian revenues or affecting patronage and appointments in India, for which it was necessary to obtain the agreement of a majority of members present at a Council meeting.

The final India Act of 1858 must be reckoned in certain respects to be a rather equivocal measure. It was true that the Company was finally extinguished, but its directors were given at least some prospect of an after-life through the newly created Council of India. Was there really so much structural difference, some may have reflected, between a President of the Board of Control working in conjunction with a Court of Directors, and a Secretary of State assisted by a Council? For Mill, in particular, who had intellectually masterminded so much of the Company's defence, there was at least the considerable satisfaction of seeing many of the essential checks and balances contained in the Company system—which he considered vital for the good government of India—appropriately incorporated into the new dispensation through the Secretary of State's Council. And, in describing the end of the affair to his friend Henry Chapman on 8 July, 1858, he could not resist a note of personal triumph.

The East India Company has fought its last battle, and I have been in the thick of the fight. The Company is to be abolished, but we have succeeded in getting nearly all the principles which we contended for, adopted in constituting the new government, and our original assailants feel themselves much more beaten than we do. The change though not so bad as at first seemed probable, is still, in my opinion, much for the worse.⁷⁶

There is then no doubt that between January and June 1858, when the Company's future hung in the balance, Mill identified himself totally with its defence and with the furtherance of the ideals of government for which he believed it stood. But once the Company's fate was sealed by Stanley's India Act, he was

⁷⁵*PD*, 3rd ser., Vol. 151, col. 2369.

⁷⁶*CW*, XV, 560.

understandably not inclined to join the new Office of the Secretary of State for India, the creation of which he had opposed, even though it also incorporated some of those positive features of Company administration which he had fought so hard to perpetuate.⁷⁷ On 18 August, 1858, the Company directors recorded their last appreciation of “the valuable services” which he had rendered for so many years, “especially of the distinguished ability and unwearied zeal with which he had assisted the Court of Directors during the recent Parliamentary discussions”; and they accordingly awarded him a special gift of five hundred guineas.⁷⁸ At the same time he made clear his intention to resign and was granted an annual pension of £1500.⁷⁹ Finally, on 2 September, 1858, when the Company’s responsibility for India was withdrawn and its home establishment formally wound up, Mill took his leave from East India House. He refused offers of a seat on the new Council of India, almost refused to accept the silver inkstand which his Company colleagues had presented to him, and never again sought or occupied an official position in the home government of British India.⁸⁰

MILL’S INDIAN WRITINGS

MILL’S WRITINGS about India and the East India Company that provide the subject matter of this volume⁸¹ comprise (1) a huge corpus of official or quasi-official material, only a small proportion of which was ever published, and (2) a very small group of non-official published articles which may be judged to reflect his more personal interests.

The bulk of the official corpus is made up of the archival copies of Mill’s draft despatches to India—over 1700 documents surviving in various forms in the India Office Records, only a small minority of which were printed for the use of Parliament—together with some related official correspondence and minuting.⁸² The remaining part of Mill’s official writings consists of eleven items, all of which are included in the present volume. These may be roughly classified as follows:

(a) one manuscript memorandum, the so-called Minute on the Black Act

⁷⁷A, *CW*, I, 249.

⁷⁸IOR: Court Minutes (18 Aug., 1858), B/236, 1345-6.

⁷⁹IOR: Accountant General’s Records: Organization of Home Establishment, Entry for J.S. Mill, L/AG/30/12; Accountant General’s Records: General Establishment Book, L/AG/21/6/23, 541.

⁸⁰Foster, *East India House*, 222-5.

⁸¹There are, of course, also scattered Indian “writings” and references included in other volumes of *CW*, especially in Vols. XII-XIX, and XXII-XXV.

⁸²Mill’s despatches are listed in Appendix A. Other letters and notes written by Mill in the course of his official duties at East India House will be found in several archive series in the India Office Library and Records, most notably in Secret Home Correspondence, 1856-58, L/P&S/3/1, 47-61. These will be found in *Additional Letters*, Vol. XXXII of *CW*.

(1838), which forms part of the Broughton Papers held by the British Library (11-15);

(b) five items officially printed by the East India Company and/or Parliament during the 1852-53 and 1858 Parliamentary enquiries into the future of the Company: "The East India Company's Charter" (1852), 31-74; *The Petition of the East India Company* (1858), 75-89; *Memorandum of the Improvements in the Administration of India during the Last Thirty Years* (1858), 91-160; *Report to the General Court of Proprietors* (1858), 161-71; *Letter from the East India Company to the President of the Board of Control* (1858), 205-12;

(c) five items published as anonymous pamphlets designed to influence public opinion during the crucial Parliamentary debates of 1858: *A Constitutional View of the India Question*, 173-8; *Observations on the Proposed Council of India*, 179-83; *Practical Observations on the First Two of the Proposed Resolutions on the Government of India*, 185-92; *The Moral of the India Debate*, 193-8; and *A President in Council the Best Government for India*, 199-204.

The very small group of non-official Indian writings, also reproduced in this volume, consists of three articles, each dealing with a subject in which Mill seems to have had some personal interest. However, only one of these articles, the review of Maine's work on village communities (213-28), can be reckoned as a fairly solid contribution to the contemporary controversies concerning the historical development of private property rights and common ownership in Europe and Asia. The remaining two items are of minor Indian interest, the first being a youthful and rather technical comment on the application of free trade principles to British imperial commerce, "Trade with India" (1827), 1-9, while the second article, "Penal Code for India" (1838), 17-30, was intended to draw public attention to the significance of what had been recently achieved in the codification of Indian penal law.

The striking contrast between Mill's enormous official corpus of Indian writings and his tiny output of voluntary non-official writings about India raises again the teasing conundrum of what exactly India meant for him personally (see also vii-viii above). Thus, on one reading of this evidence, it is certainly true that he took his East India Company responsibilities very seriously, writing copiously in the course of their discharge, and receiving regular commendations from the Company's directors. The fact that during his thirty-five years of Company employment he chose to write very little in a personal capacity about Indian affairs may be partly accounted for by the constraints and demands of his official position. Yet, as his *Autobiography* and private letters indicate, it is also evident that for much of this time he thought of his Indian duties as essentially belonging to his official employment rather than to the sphere of his more personal interests. He was not, after all, a professional orientalist, and so, once freed from his official position in 1858, it is understandable that he should have decided to write very little about India and henceforward to devote himself almost entirely to his more

consuming interests in philosophy, sociology, and political reform. In the face of these somewhat conflicting lines of interpretation, we may perhaps turn to Mill himself, not so much for a clear-cut answer on one side or the other but, more characteristically, for a clue to their possible reconciliation. In describing in his *Autobiography* the circumstances that led to his decision to retire in 1858, he mentions among other factors the conclusion that he had "given enough" of his life "to India."⁸³ In other words, he appears to have felt that having committed himself wholeheartedly to his Company duties for so long, and especially during the last few years, he now felt justified in bringing that period of his life to a close.

To recognize that Mill's Indian writings resulted primarily from his strong commitment to his official duties rather than reflecting his personal concerns does not either lessen the importance of these writings or suggest that they were written in a special compartment of his mind closed off from his wider speculative thought. On the contrary, what we know of Mill, especially of his intellectual integrity, would presuppose certain connections between what he wrote officially about Indian government and society and his more general philosophical standpoint.⁸⁴ In his essay on Coleridge (1840) Mill explicitly rejected the idea that in the sphere of political and social action it is possible to proceed effectively without specific theoretical presuppositions and first principles: in such activities mere pragmatism or trial and error processes do not provide a sufficient *modus operandi*.

They [Coleridge and Bentham] agreed in recognising that sound theory is the only foundation for sound practice, and that whoever despises theory, let him give himself what airs of wisdom he may, is self-convicted of being a quack. If a book were to be compiled containing all the best things ever said on the rule-of-thumb school of political craftsmanship, and on the insufficiency for practical purposes of what the mere practical man calls experience, it is difficult to say whether the collection would be more indebted to the writings of Bentham or of Coleridge.⁸⁵

At the same time, in view of the range and complexity of Mill's speculative thought, it would be unrealistic to expect all the links between his official and personal writings to be easy or straightforward. Mill's characteristic intellectual posture was that of attempted synthesis—a constant effort to reconcile the conflicting parts of his intellectual heritage. His East India Company role must have placed further strains on his reconciling powers, and one would expect signs of the associated tussles to be apparent in at least some of his official Indian writings.

Mill's principal ideas about Indian government should be approached in the light of the preceding general consideration. And in the following brief resumé of

⁸³A, CW, I, 249.

⁸⁴See Zastoupil, "J.S. Mill and India," 31-54.

⁸⁵"Coleridge," in *Essays on Ethics, Religion, and Society*, CW (Toronto: University of Toronto Press, 1969), X, 121.

these ideas some attempt is made, where relevant, to show the ways in which his Indian writings need to be set within the wider pattern of his thought.

To be more fully intelligible, Mill's mature views on the best form of government for India—a central topic in the majority of his published Indian writings—have to be understood as a part of his general conception of the nature and purpose of government and its role in historical development as described in his non-Indian writings.⁸⁶ In general, Mill held that a system of representative government, based on universal suffrage and the greatest possible freedom of thought and expression, was the best form of government, as most conducive to the furtherance of human happiness and the development of virtues and intelligence in individuals and society as a whole. There was no doubt in his mind that such a system was very well suited to the needs of the more progressive nations of Western Europe. However, influenced by a combination of his father's pessimistic views of Indian culture, together with Comtian and Saint-Simonian notions about the main stages in the progress of human thought, Mill concluded that representative government could not as yet be introduced into the less advanced and traditional societies of Asia, including India.⁸⁷ The people of these societies were, he contended, too passive, and too crushed by centuries of despotism, to take an active stand in defence of their individual legal and political rights. On a broader plane, he conceded that Asian countries such as India and China had in earlier ages achieved high levels of civilization, but he considered they were now too dominated by custom as the "final appeal," and insufficiently alive to the stimulating power of individualism and the claims of contrary opinions, sincerely and rationally held. As a result, in comparison with the advanced states of Europe, eastern societies such as India had become stationary, unable to progress on their own volition.⁸⁸

What then was to be done about the government of such peoples? And how was India in particular to be awakened from its state of "semi-barbarism" and brought up to a higher level of intellectual and social progress? Mill did not believe that there were any simple answers to such questions. There was no "sweeping rule" which could be applied; India was viewed by him as "a peculiar country," its peoples "most difficult to be understood, and still more difficult to be improved" (155).⁸⁹ In general, however, he inclined to think that the best government for

⁸⁶Principally in *Considerations on Representative Government* [CRG], in *Essays on Politics and Society*, Vols. XVIII-XIX of *CW* (Toronto: University of Toronto Press, 1977), XIX, 371-577; and *On Liberty*, *CW*, XVIII, 213-310.

⁸⁷A, *CW*, I, 26-9, 171-3; George D. Bearce, *British Attitudes towards India, 1784-1858* (London: Oxford University Press, 1961), 69-78; Stokes, *The English Utilitarians*, 53-6; Alan Ryan, *The Philosophy of John Stuart Mill* (1970; 2nd ed., London: Macmillan, 1987), 177-81.

⁸⁸*On Liberty*, *CW*, XVIII, 224, 272; *CRG*, *CW*, XIX, 377-8, 393-4, 396-7, 401, 406, 413-14.

⁸⁹Cf. *CRG*, *CW*, XIX, 377-8, 567-8.

India and similar societies was some form of benevolent despotism. In theory such a government might be initiated by an unusually gifted indigenous ruler, such as Akbar, but such figures, Mill thought, were very rare. A more effective way forward would be through the benevolently inspired rule of a "superior people" belonging to "a more advanced state of society." This would have the very positive advantage of conveying the subject people "rapidly through several stages of progress."⁹⁰ On the other hand, Mill had reservations about the capacity of a foreign government to act in the interests of its subjects, especially where—as was the case between Britain and India—the rulers had very little understanding of the ruled and little sympathy for them. In these circumstances, he concluded the best solution was for the rulers to "govern through a delegated body, of a comparatively permanent character," well informed, and able to give priority to the best interests of the subject people.⁹¹ In the context of this kind of reasoning it is hardly surprising that Mill came to regard the English East India Company as almost providentially designed to bring good government to India.⁹²

At this point, Mill's more theoretical reasonings about the government of dependencies like India, as mainly set out in *Representative Government*, begin to merge with the more specific polemical arguments in defence of the Company contained in his various official writings about Indian government between 1852 and 1858. In these latter (cf. xxxiv-xxxix above), Mill is primarily concerned to define and defend the special advantages of Company government in India against those who sought to replace it by direct Crown rule. To some extent, the range and nature of the arguments he uses in these writings vary with the changing political circumstances (i.e., as between the situation facing the Company in 1852 and that which confronted it six years later). But in general he finds two or three main grounds for advocating the maintenance of Company rule. In the first place, he contends that the Company's delegated responsibility for India had enabled it to develop a whole tradition of disinterested and informed Indian administration in which officials were able to serve free from the negative influences of British party politics and other sectional interests.⁹³ Secondly, he argues that under the dual government of the Company and the Board of Control, the Company had become institutionally committed to the needs of Indian government, its success being measured by the extent to which it was able to convince the Board of the soundness of the policies and the views contained in its draft despatches to India. The same

⁹⁰*Ibid.*, 418-19; cf. *ibid.*, 567.

⁹¹*Ibid.*, 573.

⁹²*Ibid.*, 577.

⁹³*CRG, CW, XIX, 573-5; and 36-8, 39, 41, 49-51, 79-80, 84-5, 169-70, and 176 below.* However, although Mill believed that the delegated responsibility exercised by the Company had enabled it to develop a tradition of disinterested administration in India, he was largely in favour of recruiting Company civil servants through competitive examinations (see 60, 73).

system thus ensured that every significant proposal or enactment affecting Indian government was subject to the closest possible scrutiny by the two branches of the home government, as well as in India itself. Short of the benefits of a more open system of representative government—ruled out by Mill’s theoretical reasoning—there could hardly be a better guarantee of good government for India (42, 45, 59, 52-5; 87-8). Conversely, Mill believed that if the dual government were replaced by the single authority of a Secretary of State, all these advantages would be lost and Indian interests made subject to erratic, uninformed, and Anglo-centric policies.

Mill continued to deploy basic arguments of this type until it became clear in the course of the Parliamentary debates of 1858 that there was little hope of saving the Company. The emphasis in his writings then shifted from a direct defence of the Company to trying to make sure the new India Office would at least retain some of the vital checks and balances and informed commitment that characterized the Company system, through the medium of the proposed Council for the Secretary of State (163-9; 181-3; 201-4; 207-12; see also xxxvi-xxxvii above). These last efforts are of special interest for students of Mill’s style and psychology because they illustrate the peculiar way in which he succeeded in waging a skilful “political” campaign on the Company’s behalf without losing his character as a high-minded political thinker.

Although Mill always firmly denied that India was then fitted for any real form of representative government, at least some of his writings show that he also believed that Indians would eventually progress to the stage where they could take over responsibility for their own government. Indeed, in a general sense, he was committed, by his belief that the moral legitimacy of British rule in India ultimately depended on its progressive and benevolent character, to supporting policies designed to bring eventual self-government to the country.⁹⁴ In his evidence to the Select Committee in 1852, it is clear that Mill expected this progress to be directly reflected in a gradual increase in the number of Indians appointed to the more senior positions in the Indian administration. They were, he noted, already taking over as junior judges and deputy collectors in Bengal and the North-Western Provinces, adding that “there is a great and growing desire to admit them to all offices for which they are considered sufficiently qualified in point of trustworthiness” (64). This process would, he envisaged, gradually continue until “the time arises when the natives shall be qualified to carry on the same system of Government without our assistance” (65).

Mill’s evidence here presents a rather sedate and academic picture of the likely road to Indian self-government, in which “trustworthy” Indian bureaucrats gradually prove themselves able to take over the system which their British superiors had in their wisdom installed. There is no sense of the likely effects of

⁹⁴51; *CRG, CW*, XIX, 567-73.

wider Indian political pressures and mass movements, no time-span is even roughly implied, and there is apparently no awareness of the ambiguity of "trustworthiness" as a criterion for Indian advancement. And yet for all its narrowness and vagueness—and we must remember that Mill was on this occasion severely restricted by the need to respond cautiously and closely to the specific enquiries of his interrogators—his general prediction of the way in which the British Indian bureaucracy would adapt itself to a gradual process of "Indianization" and a measure of "responsible government" was not all that far from what eventually happened.⁹⁵

So far only Mill's principal ideas about the historical and philosophical *raison d'être* of British or, rather, Company rule in India, and its likely *dénouement*, have been briefly considered. What may be called the middle ground of his overall conceptions, i. e., the sort of broad policies, social, political, and economic, which he believed should be pursued during the high-tide of British ascendancy, has hardly been entered. It is this middle region that still poses the greatest difficulties for students of Mill's Indian ideas, since his more accessible published writings for the most part provide only general indications of his views, while the vast corpus of his official draft despatches—in some respects the most promising source of fresh insights—still lies largely unexplored.⁹⁶ What follows is thus necessarily scarcely more than a series of introductory comments on the broad character of his ideas on social and political policies in India.

In approaching these issues of policy, it is important to begin by referring back to Mill's broad theoretical guidelines concerning the objectives and methods to be followed by a Western-style government in a colonial and (in his view) "semi-barbarous" society. These guidelines are again set out more clearly in his

⁹⁵Mill's gradualist attitude towards Indian self-government, combining a firm view that Indian society was then insufficiently advanced for representative institutions with a cautiously optimistic estimate of its likely future progress towards that goal, needs to be studied further within the wider context of his own position and the contemporary political scene in Britain and India. Not only was Mill's approach conditioned by his *a priori* views of the backwardness of oriental societies, but he may also have been constrained by the circumstances of his own Company employment. For example, within Britain itself, the minority of politicians who were then prepared to take a more radical view of the possibilities of British withdrawal or a measure of constitutional advance for Indians—e.g., Richard Cobden, John Bright, T. C. Anstey, etc.—were also often highly critical of Mill's East India Company employers. The situation for Mill was further complicated by the somewhat separate issue of how far the remaining independent and protected princely states in the Sub-continent should be preserved. See also l-liv below; Bearce, *British Attitudes towards India*, 231-3, 237; Stokes, *English Utilitarians*, 287, 298-9.

⁹⁶But see the pioneer research of Joseph Hamburger, "The Writings of John Stuart Mill and His Father James Mill in the Archives of the India Office," *American Philosophical Society Yearbook*, 1957, 324-6; Abram L. Harris, "John Stuart Mill: Servant of the East India Company," *Canadian Journal of Economics and Political Science*, XXX (1964), 185-202. See also li and liv below.

general writings on government than in those that specifically deal with India. The following passage from his *Representative Government* offers perhaps the most illuminating starting point:

To determine the form of government most suited to any particular people, we must be able, among the defects and shortcomings which belong to that people, to distinguish those that are the immediate impediment to progress; to discover what it is which (as it were) stops the way. The best government for them is the one which tends most to give them that for want of which they cannot advance, or advance only in a lame and lopsided manner. We must not, however, forget the reservation necessary in all things which have for their object improvement, or Progress; namely, that in seeking the good which is needed, no damage, or as little as possible, be done to that already possessed.⁹⁷

In other words, Mill is here articulating in the context of his examination of good government a characteristically personal synthesis of the conflicting political philosophies of Utilitarianism, organic conservatism, and, it appears, his own form of “administrative realism,” learnt perhaps partly at his desk in East India House. One would therefore expect to see something of the same rather complex balance of differing political criteria in his approaches to more specific aspects of British Indian policy and administration.

Mill’s approach to the particular issue of how far indigenous Indian religions and customs should be interfered with by the British Raj is in some ways the easiest of his “policy views” to identify from his published writings. Here, following the mainstream of Company policy, he strongly opposed “all interference with any of the religious practices of the people of India, except such as are abhorrent to humanity” (81)—by which he appears to have meant practices such as *Sati* and *Thagi*. He was especially hostile to any official attempts to “force English ideas down the throats of the natives; for instance, by measures of proselytism, or acts intentionally or unintentionally offensive to the religious feelings of the people.”⁹⁸ The precise ground for his opinions on these matters is, however, somewhat more difficult to locate. Principally, it would seem that his stand was related to his strong belief in the virtues of toleration and freedom of conscience, to his equally strong aversion to any official support for the prejudices and privileges of British settlers in India, and to his overall idealistic conceptions of the Company’s government as the ultimate guardian and protector of the Indian people, able to respect their deeper feelings. It is clear too that, with the lessons of the 1857 Revolt very much in mind, he believed that any official backing for a policy of proselytism was likely to trigger widespread disaffection and even “a general rising throughout India” (81), thus endangering the successful outcome of the government’s overriding obligation to bring peace and progress to the Sub-continent. On the other hand—as part of the same civilizing duty—Mill, like most contemporary English

⁹⁷*CRG, CW, XIX, 396.*

⁹⁸*Ibid., 570.*

liberals, was strongly in favour of all government measures aimed at eradicating what he regarded as cruel and barbarous practices like infanticide and slavery, as well as discouraging certain retrograde indigenous prejudices, such as that against the remarriage of Hindu widows (122-5).

The development and reform of judicial systems in British India constituted another area of contemporary controversy on which Mill had very decided opinions which to some extent parallel his attitudes towards Indian religions and customs. With the lessons of his early Benthamite education still dominant, he was particularly interested in the progress of legal reform in India, and vigorously supported the efforts and achievements of the Indian Law Commission from the 1830s onwards in preparing a penal code for India and the later codes of civil and criminal procedure. "These codes," he noted, "when enacted, will constitute the most thorough reform probably ever yet made in the judicial administration of a country" (114; see also 19-30, 69). And there is little doubt that he conceived of measures of this type as representing the kind of wholesale improvements that it was the Company's special moral duty to deploy for the benefit of Indian society. At the same time, he was notably sensitive during the 1830s to the importance of ensuring that British settlers in India, especially traders, planters, and fortune seekers, should be made to abide by Indian laws, administered through the Company's courts, in regulating their dealings with Indians outside the Presidency towns. "An Englishman has no right to go up the country and say to the natives, I will regulate my transactions with you by the laws of my own country, and if you think I have injured you, you shall not have the redress your own laws would give you, but shall be satisfied with that given by laws you know nothing about" (i.e., those administered by the Supreme Court at Calcutta) (13). In this whole area of equality before indigenous laws, Mill consistently took the side of Indians against the settlers who "are naturally inclined to despise the natives and to seek to make themselves a privileged caste" (15). But again, as in his defence of religion and custom, there was also what sounds like a prudential and non-moral element in his position. For instance, he argues that Indians needed to be protected against oppression by the English settlers because the future security of the British Empire in India depended on maintaining the British reputation for "superior moral worth and justice" in their dealings, and of "being more just and disinterested than the native rulers" (15). If pressed about the moral dubiety of this particular justification, it is uncertain how Mill would have responded. Perhaps he would have explained his reasoning in Utilitarian terms by invoking the importance of the ultimate good to be brought to India by disinterested and responsible British rule.

Mill's views about educational policy in some ways constituted the most developed and original of his several efforts to postulate and explore the fundamental aims of British social policy in India. Not surprisingly, these ideas have already attracted considerable scholarly interest, even though they find their fullest expression not in his published writings but in a smallish group of his draft

despatches to India.⁹⁹ Mill was responsible for preparing some seventeen drafts on the subject of Indian educational policy between 1825 and 1836. Of these documents, the most detailed exposition of his mature ideas is contained in Public Department PC 1828 of 1836, the contents of which were, somewhat ironically, totally rejected by Sir John Hobhouse, the President of the Board of Control, in December 1836, so that Mill's draft was never actually issued as a despatch.¹⁰⁰

Mill's document was primarily intended as a detailed rebuttal of the new educational policy adopted in March 1835 by the Government of India led by Lord Bentinck and Lord Macaulay. Convinced of the immense superiority of Western scientific knowledge and literature over traditional Indian learning, and faced with a growing need for more Indian government employees with a knowledge of English, Bentinck decided that official funds should in future be entirely "employed in imparting to the native population a knowledge of English literature and science through the medium of the English language."¹⁰¹ Previous government funding for oriental learning (e.g., stipends for professors and students, and grants for translation work) was accordingly to be withdrawn. Mill's critique of this policy took the form of a complex and interlocking argument. He begins in a characteristically prudential vein by warning against the "alarm and disaffection on the part of the people" likely to result from the new policy of withdrawing funds from oriental learning, with its implied rejection of Indian culture and religion.¹⁰² However, more importantly, he then proceeds to take issue with the whole underlying logic of the Bentinck-Macaulay thesis. Essentially, he does this by drawing a clear distinction between (a) the limited plan of funding colleges to teach English to potential government employees, and (b) the more fundamental policy of spreading Western ideas and knowledge through the country, given that "the object of our measures" is "the intellectual and moral improvement of the people of India." Mill is ready to approve expenditure on the new English-language colleges, but argues that in pursuit of the larger project it would be quite "chimerical" to try to diffuse Western ideas to the people at large through the medium of a foreign language, and through the agency of men seeking only

⁹⁹See, for instance, Bearce, *British Attitudes towards India*, 282-6; K.A. Ballhatchet, "The Home Government and Bentinck's Educational Policy," *Cambridge Historical Journal*, X (1951), 224-9; R.J. Moore, "John Stuart Mill at East India House," *Historical Studies*, XX (Oct. 1983), 497-519; Mitsuo Takashima, "John Stuart Mill and Indian Education: A Phase of His Work at East India House," *Economia*, No. 99 (Dec. 1988), 7-24.

¹⁰⁰IOR: Revenue, Judicial, and Legislative Committee Miscellaneous Papers: PC 1828, Recent changes in native education, L/P&J/1/92; Mill to Henry Taylor ([1837]), CW, XVII, 1969-70. See also Appendix A, No. 1578X.

¹⁰¹*Selections from Educational Records*, Pt. I, ed. H. Sharp (Calcutta: Superintendent of Government Printing, 1920), 131.

¹⁰²IOR: Revenue, Judicial, and Legislative Committee Miscellaneous Papers: PC 1828, L/P&J/1/92. The quotations in this paragraph are from this document.

enough knowledge of English to enter government employ. Such an immense project, Mill maintains, could be accomplished only through the medium of the vernacular languages used by the mass of the population. Consequently, the government should try to enlist the active cooperation of the Indian learned classes—pandits, maulvis, and others able to interpret complex Western ideas by adapting “the requisite words and terms of expression” from Arabic and Sanskrit for use in the vernacular languages. Only such scholars could be reasonably expected to prepare the necessary textbooks for use in Indian schools, and themselves act as teachers. Instead of alienating the scholarly class by withdrawing funds from oriental learning, the government should do as much as possible to secure their support and assistance by restoring the funds for their professors and students and the grants for translations, as well as encouraging the more promising of such scholars to pursue their own studies of English language and literature to a high level.

Mill’s vision of a gradual modernization of Indian thought and society achieved through the active involvement of the Indian scholarly class may have struck his opponents as too idealistic, much as their contrary ideas appeared “chimerical” to him. But with the benefit of historical hindsight, it may be reasonably conjectured that at least some of the more negative processes of social alienation and polarization associated with less thoughtful promotions of Westernization might have been lessened had his ideas been accorded a more positive official reception and a more sustained programme of support.

Mill’s general ideas about socio-economic development in India seem in certain respects to be complementary to his views about the best way to achieve intellectual and educational progress in the Sub-continent. They are not, however, as fully developed or sustained as his educational policies and, indeed, they have to be extracted and even partly deduced from several of his brief general accounts of British Indian land-revenue policy, principally those contained in the *Memorandum of the Improvements in the Administration of India* and the *Principles of Political Economy*, plus other less formal writings, such as his review of Maine’s book on village communities.¹⁰³ The lack of a more detailed treatment of these issues is perhaps understandable given that Mill himself had no special or direct responsibility in the Examiner’s Office for the preparation of despatches in the Revenue Department. Incidentally, the reasons why Mill’s ideas about economic and social development occur within his scattered writings about Indian revenue policy have to do with the central importance of the subject—especially of settlement policy—in the economy of nineteenth-century British

¹⁰³*Principles of Political Economy*, Vols. II-III of CW (Toronto: University of Toronto Press, 1965), II, 121-2, 237, 240-1, 319-23; and 93-111 and 213-28 below. For a full account of Mill’s economic ideas in relation to India, and their influence on British Indian administrators, see S. Ambirajan, *Classical Political Economy and British Policy in India* (Cambridge: Cambridge University Press, 1978).

India. Upon this policy much else depended, including the financial resources available to the government, the prosperity of the rural economy, and legal rights of landlords and peasant cultivators.

Essentially Mill believed that India's economic and social progress substantially depended upon government support for the *ryots* (peasant cultivators) and the *panchayats* (village councils). He thus approved both the earlier *ryotwari* settlements in Madras and Bombay and the later settlements with the *panchayats* of the North-Western Provinces and Punjab. He likewise argued for the strengthening of the proprietary rights of the *ryots* in Bengal and Oudh over and against the *zamindars* and *talugdars*, whom he viewed as non-productive landlord classes.

In adopting this general position, Mill was characteristically drawing upon the different strands of his inherited and acquired philosophies. His championing of the *ryots* very much recalls his father's earlier Benthamite stand in their favour. On the other hand, as a liberal individualist, Mill also evidently conceived of the *ryots* as potential agents of agrarian progress to be freed from the oppressions of their landlords and encouraged to improve the value of their lands. At the same time there are also signs of Mill's attachment to historicist values in his approach to these issues. He is, for instance, very pleased to discover historical and other evidence to support the contention that both *ryots* and *panchayats* had originally held a stronger position in Indian society. To that extent they could be seen by him as representing part of the good already possessed within Indian society which it was the government's moral duty to foster and revivify. The *panchayats* in particular he regarded as part of the real framework of Indian society, fascinating for their apparent evocation of an earlier tradition of the common ownership of land—a favourite theme of Mill's—and encouraging for their evidence of constructive cooperation among local Indian communities.

Mill's ideas and writings about the protected Indian states are of a somewhat different character from what he thought and wrote about major social questions affecting British India. Not only was his official involvement in the affairs of Indian states—the most important part of Political Department business—more intensive and prolonged than his concern with social issues such as law, but the states' affairs themselves were of a peculiarly complex legal and historical nature, not easily reducible to broad policy statements for one who understood their intricacies. In fact, to appreciate Mill's views on the states more clearly, it is first necessary to understand something of their overall political position vis-à-vis the British Indian government during the first half of the nineteenth century.

In general, British relations with the Indian states during this period were largely based upon a system of subsidiary alliance-cum-suzerainty, in which the Government of India normally recognized and even guaranteed the internal sovereignty of the states, while assuming responsibility for their external affairs

and power to depute political agents to reside within their borders.¹⁰⁴ However, in practice this system covered a wide variety of political relations based on particular conventions and practices affecting particular states or groups of states. These ranged from the Company's treaties with Oudh, which made British political and military support dependent on the Nawab's achieving some improvement in the state's internal government, to the complex arrangements with the numerous minor rulers of Kathiawar, which gave the Government of India a special residuary power to ensure effective judicial administration within their territories. Moreover, during the later part of Mill's administrative involvement, the overall position of the Indian states was further complicated by the Government of India's tendency to intervene more drastically in their internal affairs, using, for example, the doctrine of lapse (the refusal to allow rulers to adopt heirs when their natural lines had failed) to justify direct annexations. Faced with the need to comment regularly upon particular instances of this complex and evolving system of suzerainty, there was perhaps a natural tendency for someone in Mill's position to limit his views to the particular circumstances of the case, rather than to elaborate grand theories or strategies. Nonetheless, there were also certain fundamental and recurrent issues of policy, such as the pros and cons of the general system of indirect rule and the circumstances under which intervention was deemed to be politically or socially justified, about which Mill was certainly expected to hold views of a general kind.

In so far as his official writings are concerned, there is an embarrassment of riches awaiting the attention of students of Mill's ideas about the states in the form of hundreds of Political Department PCs and Drafts held by the India Office Records in London. So far only a few scholars have ventured to investigate in detail parts of this vast archive, most recently Robin Moore and Lynn Zastoupil.¹⁰⁵ Their first findings are of considerable interest, revealing certain similarities in Mill's working approach to the problems posed in different areas, as well as offering different interpretations of his more general attitudes towards the states. By contrast, there is comparatively little about the Indian states to be found among Mill's published writings, partly perhaps because of a certain official reticence on his part and partly because, as suggested earlier, the piecemeal complexity of the subject did not lend itself to the formation of a satisfactory overall synthesis. Certain brief indications of his attitudes to the civilizing benefits of indirect rule may, however, be gleaned from portions of his 1858 *Memorandum of the Improvements in the Administration of India*. Somewhat similarly, the Indian states did not figure much in his private correspondence, though, as will be

¹⁰⁴*The Imperial Gazetteer of India: The Indian Empire*, new ed., 26 vols. (Oxford: Clarendon Press, 1907-09), IV, 77-82.

¹⁰⁵Moore, "John Stuart Mill at East India House"; Zastoupil, "J.S. Mill and India."

noticed below, a few of his personal letters throw some interesting light on the general principles that lay behind his approach.

With these important reservations, we may now tentatively enquire whether it is possible to discern any general shape for Mill's views about the states. As already mentioned, the recent researches of Moore and Zastoupil have already yielded some important insights on the way Mill approached the thorny question of intervention in states where the Company judged the subsidiary-alliance system was failing to induce the necessary improvements in their internal administration. According to Moore's analysis of Mill's draft despatches concerning relations with Oudh, Mill was converted to an acceptance of the need for direct annexation only during the 1850s, despite the long history of failure in the Company's attempts to bring about some kind of reform and improvement in the Nawab's government. For almost thirty years before the final annexation in 1856 Mill consistently preferred to try every possible intermediate course, ranging from encouragement and cajolery to temporary assumptions of power, to try to secure improvements in the state. On the basis of this and other evidence, Moore concludes that Mill preferred on the whole to work for improvement "by the engraftment of British advice upon princely administration."¹⁰⁶

Zastoupil's findings about Mill's approach to the problem of lawlessness in the territories of the petty rulers of Kathiawar are not inconsistent with Moore's findings about Mill's Oudh policy, although Zastoupil's general interpretation of Mill's approach differs significantly from Moore's. Zastoupil shows that between 1830 and 1856 Mill abandoned his earlier more punitive approach to the Kathiawar rulers in favour of a constructive and conciliatory policy that encouraged the local rulers to play an active role alongside British officials in settling their subjects' internecine disputes peacefully through local tribunals. Whereas in Oudh the Company's longstanding attempts to induce the Nawab to improve local administration— attempts supported by Mill—ultimately ended in failure and British annexation, the more limited operation of reducing lawlessness in Kathiawar through the agency of the rulers and the courts—also strongly backed by Mill—eventually met with some success.

This view of Mill as substantially committed to a policy of seeking gradual improvements in the internal conditions of the Indian states through advice and influence is also partly confirmed by his own account of what he saw as the more significant achievements of the Company in its relations with the states.

In the more considerable native states, our influence is exerted on the side of good, in every mode permitted by positive engagement. Not only have the British representatives incessantly, and to a great degree successfully, incited native princes to prohibit and suppress the barbarous usages which we have ceased to tolerate in our own territories; but defects have been pointed out, and improvements suggested, in their revenue and judicial

¹⁰⁶Moore, "John Stuart Mill," 508.

administrations. Financial disorder and general misgovernment have been the subject of grave remonstrance, followed up by such positive marks of displeasure as were consistent with the respective treaties. (152.)

Ever an optimistic educator, Mill then goes on to describe the benefits that had accrued from the Company's policy of instructing young rulers during their minorities "in European knowledge," and initiating them "into public business under the eye of a British officer" (152).

While there is thus some agreement that Mill generally inclined towards a policy of guiding states towards social and administrative improvements, there is also substantial disagreement about the reasons that led him to follow this policy, and uncertainty about the circumstances in which he was ready to abandon it for more radical schemes of intervention and annexation. For example, Moore finally tends to see Mill as a penetrating, non-doctrinaire political analyst, whose more general theories play little part in his practical approach to the problems of the states and of Indian government generally. In particular, Moore concludes that he lacked "any special regard for existing institutions or traditions, except that they formed the given, the datum line in any particular case."¹⁰⁷ Zastoupil, however, sees a significant growing readiness on Mill's part to work with, and respect, existing Indian agencies and practices and even a willingness to empathize with Indian customs, in the interests of achieving overall social progress. He then interprets this approach in terms of the gradual breakaway from his father's more narrow Benthamite principles which Mill achieved during the 1830s, partly under the influence of romantic conservative writers like Coleridge, but also through exposure to the ideas of British Indian administrators, such as Munro, Elphinstone, and Malcolm, who favoured the more sympathetic and positive use of indigenous Indian structures, social groups, and traditions.¹⁰⁸

Mill himself has provided an interesting retrospective account of the basic grounds upon which he was prepared to abandon indirect rule in favour of direct intervention. In a private letter to John Morley on 26 September, 1866, in which he discusses the justification for the use made by Lord Dalhousie (Governor-General 1848-56) of the doctrine of lapse in annexing different states, he comments:

I approved of all Lord Dalhousie's annexations, except that of Kerouli which never took effect, having been at once disallowed from home & indeed Lord D. himself gave it up before he knew of its having been negated. My principle was this. Wherever there are really native states, with a nationality, & historical traditions & feelings, which is emphatically the case (for example) with the Rajpoot states, there I would on no account take advantage of any failure of heirs to put an end to them. But all the Mahomedan (Rampore excepted which descends from Fyzoola Khan the Rohilla chief) & most of the Mahratta kingdoms are not of home growth, but created by conquest not a century ago & the military chiefs & office holders who carry on the government & form the ruling class are

¹⁰⁷*Ibid.*, 518.

¹⁰⁸Zastoupil, "J.S. Mill and India," 54.

almost as much foreigners to the mass of the people as we ourselves are. The Scindia & Holkar families in Central India are foreign dynasties, & of low caste too, Mahrattas who have usurped provinces from their native dynasties of Jats, Goojars, Boondelas &c. The home of the Mahrattas is in the South, & there is no really native Mahratta kingdom now standing except Kolapore. In these modern states created by conquest I would make the continuance of the dynasty by adoption not a right nor a general rule, but a reward to be earned by good government & as such I would grant it freely.¹⁰⁹

Mill's account offers a number of points of interest, particularly (1) the distinction he tries to draw between "really native states, with a nationality, & historical traditions & feelings," and states more recently created by foreign conquest and usurpation, and (2) his readiness to deploy the threat of annexation by lapse in the case of states belonging to the latter category. In the first place there is something rather unrealistic and subjective about this attempt to draw a clear line between "really native states" and the rest, and to construct a viable policy on the supposed distinction. Indeed, the implied picture of Mill himself weighing the destinies of assorted Indian dynasties from his office in London has a certain cartoon quality about it. One can perhaps see the position he is reaching for as a characteristic blend of utilitarian and historicist values, but the actual formulation given here does not seem easily applicable to the complexities of contemporary Indian polity. It should, of course, also be borne in mind that Mill was writing informally about complex events long after they had happened, and perhaps also wishing to simplify for Morley's benefit.

On another level, Mill's "principle," as described in this letter, is not entirely compatible with either Moore's or Zastoupil's initial conceptions of his fundamental political posture—a little too historicist for the portrait of a non-doctrinaire analyst and a shade too interventionist and utilitarian for the picture of a conciliatory respecter of Indian institutions. Mill, who enjoyed the processes of classification, is not himself easily classified.

These continuing uncertainties and differences of interpretation again underline the importance of carrying out further detailed investigations of Mill's original draft despatches to India in order to arrive at more broadly based conclusions about his policies concerning Indian states. That such an undertaking would also involve making fine judgments on matters of documentary evidence, as well as setting the new data within the wider context of Mill's development as a political philosopher and social theorist, only serves to confirm the substantial challenges that Mill's work still throws out to modern interpreters.

¹⁰⁹CW, XVI, 1202-3.

Textual Introduction

JOHN M. ROBSON

OF MILL'S fourteen published writings on India, eight appeared in anonymous pamphlet form, all in connection with the legislation of 1858 that transferred to the Crown all the affairs of the East India Company. These exist only in the one printed version, except for "The Petition of the East India Company," which also appeared in *Parliamentary Debates*. Two other items, "John Stuart Mill, Esq., Is Called in and Examined" (1852), and "Letter from the Chairman and Deputy Chairman of the Honourable East India Company to the President of the Board of Control" (in connection with the legislation of 1858), were published in *Parliamentary Papers*; the latter also appeared in *Supplement to Votes*, which is the copy-text because a copy of it, corrected by Mill in punctuation, is in his library, Somerville College, Oxford. Three articles appeared in periodicals: "Foreign Dependencies—Trade with India," in the *Parliamentary History and Review* (1828); "Penal Code for India," in the *Westminster Review* (1838); and "Mr. Maine on Village Communities," in the *Fortnightly Review* (1871). The last of these is partly extant in manuscript (Library of Congress) and was republished in the posthumous fourth volume of Mill's *Dissertations and Discussions* (1875). There is one manuscript, the "Minute on the Black Act" (1836) in the British Library, deriving (like the pamphlets) from Mill's employment in the Examiner's Office of the East India Company.

Editors' notes to each item identify the copy-text (and other versions when they exist), indicate whence such titles as are not original have been derived, and supply other specific explanatory material, such as the description of the item in Mill's own list of his published writings, and any corrections found in his own copy. Editorial footnotes (signalled by numeric series within each item) give personal identifications, bibliographic details, and such limited historical comment as seems necessary for comprehension. Notes in the originals are signalled by the series *, †, ‡, etc.; occasionally references within the text have been moved to footnotes for consistency, and some have been corrected.

In the few cases where more than one version of a text is extant, full collations have been made, and substantive variants recorded in footnotes that indicate the origin and nature of the different readings. Obvious typographical errors in versions other than the copy-text are ignored. Sometimes a variant reading is

accepted into the text, as at 81.4, where “changes” is preferred to the copy-text’s “change” because it is found in two other versions and makes sense. An example of deletion is seen at 83.19, where the text reads “respectfullyⁱ and deferentiallyⁱ”; the variant note reads “-D”, indicating that “and deferentially” does not appear in D (*Debates in the East India Company*).

The only editorial interventions in printed texts are made for consistency; special instances are given in Appendix C with, as necessary, explanations for the changes. Usually these are evident in context, though a few trouble the conscience: at 49.34, e.g., the alteration from “provided for it within” to “provided within” is made in the interest of sense (“it” has no evident antecedent; if “good government” is intended, the sense is unaltered). In general, the titles are from the originals; added titles and abbreviations of the originals are evident from the editors’ notes. Headings have been restyled. Other general practices include: “2dly” and similar forms are given as “2ndly”; ordinals attached to rulers’ names are given in the form “Charles I”; “&c.” is given as “etc.”; terms mentioned rather than used are given in italic. The titles of works published separately are given in italic and of parts of works in inverted commas. Foreign words and phrases are normalized in italic type. Long quotations have been set in smaller type, and the quotation marks deleted (in one case doing so involves placing a tag—“says Mr. Maine”—in square brackets; in another, an introductory colon has been added). Square brackets also appear when page references are added to the text to conform to Mill’s own practice in particular items. Volume and page references in the original have been standardized and corrected as necessary.¹

A few items call for particular changes in detail. In the text of “Penal Code for India,” “Code” is normalized to “code”. In “The East India Company’s Charter,” Mill’s parliamentary evidence, the numbers of the questions are not given in the text (the range is supplied in the editors’ note), and the questions are printed in italic type (in other volumes the names of the questioners are given, but in this case they do not appear in *Parliamentary Papers*); “connection” is regularized to “connexion”, the dominant form in this item. In “The Petition” and *Observations*, “minister” is regularized to “Minister” and “council” to “Council” (with the support of the alternate versions). In “The Petition,” “government” is altered in appropriate contexts (i.e., when specific) to “Government”, and “her” when applied to “Majesty’s Government” is changed to “Her”, which is in that item the normal form (as it is in “Letter to the Board of Control,” where no changes are

¹The corrections are:

217.8 61 [61-2]
 219.19 85 [85-7]
 220.26 88 [88-9]
 221.7 88 [87-8]
 227.12 149-51 [166-8]
 227.39 68 [67-8]

needed); however, in *Memorandum* and *Practical Observations*, where the other form is dominant, "Her" is altered to "her". In "Maine on Village Communities," "shown" is altered to "shewn", the dominant form. In the editors' note to *Report to the General Court of Proprietors* (162), the reading in the manuscript list of Mill's published writings—"New Bills Law"—has been corrected to "Two Bills Now".

A location check list of Mill's Indian Despatches makes up Appendix A; its headnote explains the system of reference, and the standardization of Indian names. We very much regret that the enormous extent of the despatches and the vast cost of transcribing and editing them precluded their inclusion in this edition. A selection was of course feasible, but no justifiable principle of exclusion presented itself. A companion list of the published extracts from Mill's despatches comprises Appendix B; it is based on Mill's manuscript list of his published writings. Appendix C lists textual emendations, and Appendix D is an Index of Persons and Works. The analytic Index has been prepared by Dr. Jean O'Grady.

ACKNOWLEDGMENTS

For permission to publish manuscript materials, we are indebted to the National Provincial Bank, residual legatees of Mary Taylor, Mill's step-granddaughter, and (for specific manuscripts) to the India Office and Records and Reference Divisions of the British Library and to the Library of Congress. Published Crown-copyright documents in the India Office Records reproduced/transcribed appear by permission of the Controller of Her Majesty's Stationery Office. We are most grateful to the librarians and staff of the Reference, India Office, and Newspaper branches of the British Library, and of the British Library of Political and Economic Science, the University of Toronto Library, the Institute for Historical Research (University of London), Somerville College Oxford, the University of London Library, the Library of University College London, the Victoria University Library, and the Yale University Library. Of the project staff, Jean O'Grady, the Post-doctoral Fellow, has immensely benefited us by expanding her knowledge of sources concerning India and then sharing it with us; Marion Filipiuk, the multi-talented senior Research Assistant, and Rea Wilmshurst, inputter and economist of time and space, have as usual made the preparation of the volume possible; and Jonathan Cutmore and Jannifer Smith-Rubenzahl have each done all that was asked, and more, and well. Though Harriet Taylor Mill's presence is not clearly evident in John Stuart Mill's writings on India, one cannot but believe that she and he would be particularly delighted at the collaboration between Martin and Zawahir Moir so well demonstrated here, as well as that less evident but equally rewarding between Ann P. Robson and myself—whatever of mine she chooses to claim, is hers.

TRADE WITH INDIA

1828

EDITORS' NOTE

Parliamentary Review, Session of 1826-27 (London: Baldwin and Cradock, 1828), 58-68. Headed and running titles: "Foreign Dependencies—Trade with India." Not signed; not republished. Identified in Mill's bibliography as "An article on trade with India which appeared in the Parliamentary Review for the session of 1827" (MacMinn, 8).

Trade with India

ON THE 15TH MAY,* Mr. Wolryche Whitmore moved for a Committee to inquire into the trade between Great Britain and India. Mr. Whitmore rested his demand for investigation upon a specification of grievances; among which he insisted chiefly upon the inequality of the duties on East India and on West India produce; the impediments which, as he affirmed, the East India Company were accused of throwing in the way of private merchants trading to the East Indies; and lastly, the commercial restrictions, which he seemed to suppose existed at Singapore, and other "emporia in the Eastern Archipelago."¹

On the first of these topics, the discriminating duties on East India produce, our opinion has been already given. The subject was plainly treated, in the course of the debate, by Mr. William Smith; who placed the advocates of these duties in a dilemma from which they cannot possibly escape.² If the duties were equalized, the taxed commodities either could, or could not, be obtained at less cost from the East Indies than from the West. If they could, the discriminating duties are a tax on the people of England, to enable the West Indians to carry on what is, or would otherwise be, a losing business, by means of slave labour. If not, the duties are meant for no purpose except to ward off a danger which does not exist: they ought, therefore, to be repealed, were it for no other reason but because animosities are engendered, and valuable time wasted, by the agitation of the question from year to year.

The complaints of Mr. Whitmore against the East India Company, it is impossible to decide upon without a full inquiry: and if they be persevered in, it is highly proper that they should be subjected to investigation by any committee which may hereafter be appointed to inquire into the East India trade. Judging, however, from what Mr. Whitmore hinted rather than stated concerning the nature

*See *Times*, May 16. [William Wolryche Whitmore (1787-1858), Motion for a Committee to Inquire into the Trade between Great Britain and India, *PD*, 2nd ser., Vol. 17, cols. 814-15, reported on 16 May in *The Times*, p. 2, and in the *Morning Chronicle*, p. 2. The report in *The Times* does not contain the passages Mill cites below; that in the *Morning Chronicle* bears some resemblance to the quotations, but obviously Mill was using another, unidentified source.]

¹Quoted in the report in the *Morning Chronicle*, but not in either *The Times* or *PD*.

²William Smith (1756-1835), Speech on Trade with India (15 May, 1827). *PD*, 2nd ser., Vol. 17, cols. 836-8.

of the imputations, we do not imagine them to be of a very serious character. "The Company secured to itself, in some cases, the right of preemption. Their resident agents advanced money to the growers, and then shut up the produce, so as to answer the demands of the Company."³ This is the sum total of Mr. Whitmore's complaints: but surely if, as would appear from this statement, the Company actually advances to the producers the capital with which they carry on the production, it is entitled to privileges somewhat greater than those of a simple purchaser; and there is nothing unfair in the transaction, unless it can be shewn, that, by an abuse of the powers of government, the Company extorts from the producers more favourable terms than the private merchants could obtain, for the same equivalent, by the competition of the market. This, however, Mr. Whitmore does not affirm.

The debate chiefly turned upon the question of the discriminating duties; on which subject Mr. Huskisson, though he opposed the motion, expressed his entire concurrence in the general principles laid down by Mr. Whitmore, and declared that he had nothing more at heart than to promote them, "so far as they could be fairly and justly brought into operation."⁴ This, we believe, is a profession which few men would have any objection to make on any subject. To attach to it any meaning, it would be necessary that we should have the means of knowing how far the speaker's ideas of fairness and justice extend. Mr. Huskisson, however, took particular care to say nothing which should give the remotest indication of the course he intended to pursue. His speech was according to the old approved parliamentary tactics. Fair words to all parties, pledges to none: impossibility of laying down any principles which could be inflexibly adhered to: necessity of delay; not a short delay, to give time for consideration, but a delay of several years—delay until the House should take into consideration the renewal of the East India Company's charter, which expires, we believe, in 1834.⁵ It was impossible to shew one single point of contact or connexion between the question of the East India Company's charter, and that of the duties on East India produce. If the duties on East India sugar *are* a grievance, they are a grievance whether the King or the Company is to have the government of India, and whether the Company or private merchants are to be, after 1834, the importers of tea from Canton. Yet, so truly parliamentary is the policy of postponing the consideration of whatever appears likely to give trouble or annoyance; so deeply rooted in the hearts of our public men is the desire to put off, till the latest period possible, the evil day when the partial interests of any powerful body are to be interfered with;

³Quoted in the report in the *Morning Chronicle*.

⁴The reports of the Speech on Trade with India (15 May, 1827) by William Huskisson (1770-1830) in *PD*, *The Times*, and the *Morning Chronicle*, do not contain this passage.

⁵53 George III, c. 155 (1813) had (like the other Charter Acts) a twenty-year term.

that almost every member who followed joined with Mr. Huskisson in begging Mr. Whitmore to withdraw his motion, and "leave the matter to Government,"⁶ to be by them postponed until the time comes when attention will be distracted by so many other still more important topics connected with India, that whatever the Government may be pleased to ordain on the subject will pass, comparatively speaking, unchallenged and undiscussed.

The reasons stated for the postponement were far from sufficient to account for the apparent universality of the desire for it. There were "experiments already in progress,"⁷ of which the result was not yet apparent. We are aware of none, the result of which, if known, could have the slightest influence upon the merits of this question. The inquiry would "excite and inflame those anxious alarms," which Mr. Huskisson said it was his "earnest wish to allay."⁸ This argument, though it is perfectly *en règle*, being invariably brought forward as a reason against discussion whenever discussion is inconvenient, is yet such a one as ought never to be heard from the lips of an enlightened statesman. Common sense, if it were listened to, would dictate a directly opposite conclusion. If there are groundless alarms, by what means can they be so effectually dispelled as by laying open promptly and completely the real state of the case? As a general proposition, it will scarcely, we presume, be maintained, that ignorance or misinformation is less likely to produce groundless alarms than correct information; and if it is on the sugar question in particular that correct information is expected to prove so alarming, the reason must be one which it would not answer Mr. Huskisson's purpose to tell; that, if all the facts were known, so gross and glaring would the injustice appear which is done to the public of Great Britain, for the sake of the planters, that public indignation would at once compel a reform of the system. The absurdity of this plea is the more obvious, because the West Indians, and Mr. Huskisson along with them, profess to believe that the East Indies, even if the duties were equalized, could not supply sugar on equally advantageous terms with the West. Surely, if this be true, an inquiry, the result of which would be to establish this fact, would allay apprehensions, not excite them. True it is that the West Indians, by their strenuous opposition to the removal of these unpopular duties, an opposition which would be without a motive if they themselves believed what they say, prove sufficiently their own insincerity. But every one will acquit Mr. Huskisson of such paltry artifices. The true reason, as we suspect, which would render the granting of a committee a source of real alarm to the planters, is one which Mr. Huskisson

⁶See Charles Wentworth-Fitzwilliam (1786-1857), Lord Milton, later 3rd Earl Fitzwilliam, Speech on Trade with India (15 May, 1827), *The Times*, 16 May, p. 2, and cf. Charles Ross (ca. 1800-60), Speech on Trade with India (15 May, 1827), *PD*, 2nd ser., Vol. 17, col. 836.

⁷Huskisson, speech of 15 May, *The Times*, 16 May, p. 2.

⁸*Ibid.*

could not decently state, however strongly he may have felt it. This reason is simple;—it would convince them that Government was in earnest. At present, they may flatter themselves, with some appearance of justice, that it is not.

It well deserves attention, that such flimsy excuses, when they were excuses for delay, should have been so completely satisfactory to the House. But any reason is good enough, when the conclusion accords with our inclinations: any ostensible motive will suffice, when the course which it recommends falls in with the predominant habit of our minds.

In answer to what had been observed by Mr. Whitmore on the subject of Singapore, and the other “emporium in the Eastern Archipelago,”⁹ Mr. Huskisson stated, that “no tonnage, or duty of any description,”¹⁰ was now demanded at those ports: and the fact is, that Singapore has always been a free port, and that the duties which were formerly levied at Penang and Malacca have recently been discontinued. Mr. Huskisson viewed this circumstance “with great satisfaction, because it was the result of those principles of policy which he had recommended.”¹¹ Were we, also, convinced that the measure was borne out by the principles to which Mr. Huskisson alluded, it could not but have our entire approbation. We are afraid, however, that, instead of being a result of those principles, it is in direct opposition to them; and that the ministry, which recommended or sanctioned such a measure, have been misled by names.

The principle, which Mr. Huskisson supposes to have dictated this course, is the principle of free trade; and if we look to the words alone, free trade undoubtedly implies exemption from all taxes or duties whatsoever. But a principle, when it is expressed in two words, is very seldom expressed accurately; some necessary condition or qualification is almost always omitted: and when we are satisfied with adhering to the *terms* of a proposition, and are not careful to keep always in view the *grounds* of it, we are perpetually in danger of acting in contradiction to the very principle which we imagine to be directing our conduct.

The principle of free trade is the principle of leaving undisturbed the natural distribution of capital; and the foundation of it is the observed and well-established fact, that capital, when left to itself, under the guidance of individual interest, always finds out the channels in which, under the existing circumstances, and in the existing state of knowledge, the greatest produce can be obtained at the least expense to the community. When this principle is clearly apprehended, it is evident at once that free trade does not require that the different employments of capital shall be subject to *no* taxation, but only that, if taxed at all, they shall be taxed *equally*, so that one employment may not be encouraged more than another.

If there are two modes of obtaining the same commodity, and both are

⁹Whitmore, motion of 15 May, *Morning Chronicle*, 16 May, p. 2.

¹⁰Huskisson, speech of 15 May, *The Times*, 16 May, p. 2.

¹¹*Ibid.*

taxed,—taxed moreover to an exactly equal amount,—the commodity will naturally be obtained in the cheaper of the modes; but if a minister awkwardly attempts to introduce free trade, by removing the tax from the more expensive mode of obtaining the article, while the cheaper mode remains taxed, as before, the commodity will probably be obtained in the more expensive mode, and a quantity, greater or smaller, of expense and labour, will be uselessly thrown away.

This is precisely what has been done in the Eastern seas. The ports of Continental India, particularly Calcutta and Bombay, have hitherto been the entrepôts of a very extensive and valuable commerce; but at these places the port charges still continue, while they are now abolished in the Straits of Malacca. The unavoidable consequence will be, that many ships, for unloading which the situation of Bombay or Calcutta is more convenient, will resort to Penang or Singapore in order to save the duties, at the cost of a longer, a more hazardous, or a more expensive voyage. The whole of what is thus expended is sheer loss to the nation and to the world; and a loss, too, of that very kind, which it is the particular object of the principle of free trade to prevent; loss, by substituting a less advantageous disposition of capital for a more advantageous one. It is as if all duties and port charges were to be abrogated in London, while they continued to be levied at Bristol and Liverpool. No doubt, this would give to the commerce of London a most flourishing appearance, since a much larger number of ships, from America and the West Indies, would resort to London, in order to avoid the duties; but it is obvious, that the additional expense of the more circuitous voyage would be a clear and uncompensated loss to the community.

But even if the remission of duties, instead of being partial, had been universal, extending to all India, or even to all the world; we should be prepared to maintain, that the measure was a violation of that principle of which the doctrine of free trade is a consequence,—the principle of not disturbing the natural arrangement of capital. That principle, we contend, absolutely requires that all expenses which are incurred for commerce should be defrayed by commerce. The natural distribution of capital is equally disturbed, when any of its employments is charged with factitious expenses, or when it is relieved from its own.

The settlements of Singapore, Penang, and Malacca, were established, and are maintained, solely for the convenience of commerce; and none of them possesses any resources, independently of commerce, at all adequate to the liquidation of its own expense. The question now is, whether this expense, which must be borne by somebody, shall be borne by those who alone benefit by it, and for whose sake it was incurred; or be charged upon the community in general of Great Britain or India. We maintain that the former, both on the principles of justice and on those of political economy, is the advisable arrangement.

Free trade implies freedom not from restrictions only, but from all partial encouragement. Why is it that Government never thinks of erecting, at its own charge, buildings or machinery for any branch of manufacture—the cotton

manufacture, for example? Not because the removal of any source of expense is not in itself advantageous; but because, when it can be removed from one class only by being transferred to another, there is no good reason for giving a bounty to the consumers of cotton, at the expense of the public in general, or any other portion of it.

If, instead of buildings, Government were to supply means of conveyance; if they were to abolish all tolls, and to supply waggons and other vehicles, free of charge, for carrying from place to place all descriptions of goods, could they here plead free trade in their defence? or rather would not such a measure be a direct infringement of the principle on which free trade is founded? The consumers of goods brought from a distance, have no claim to receive a premium at the expense of those who consume goods produced in their immediate vicinity; and as such a system would inevitably cause goods to be brought from a distance, which could be obtained cheaper by being produced at hand, the excess of expense, which would not be taken away, but only be laid upon other shoulders than those of the consumer, would be a clear loss to the community.

To take another illustration still more exactly appropriate to the case in hand: suppose that Government were to purchase the London Docks, and lay them open, with the warehouses adjoining, to all importing merchants, free of charge—would this be a proper application of the public money? Surely not. Let the expense of procuring commodities be borne by the consumers of those commodities: they will then be the more frugal in their consumption; and let not the whole public be taxed to afford, without necessity, a separate advantage to a part.

Such precisely is the case of Singapore, Penang, and Malacca; but with this great aggravation, that as each of those settlements is confessedly only an entrepôt, the parties for whose benefit British money is expended, are, for the most part, not even British subjects. It may be true that the merchants, who resort thither, are generally subjects of Great Britain; but the system which exempts them from all share in the expense incurred specifically for their convenience, is a boon, not to them, but to the consumers of the goods, of which they are only the carriers. They are benefitted indeed, but it is only by that extension of business which proceeds from a diminution of price, and by being freed from the trouble and annoyance attendant on a custom-house. Whatever tax might be imposed upon them, would be ultimately paid by their customers; the people on the east side of the Gulf of Malacca, and those among the people on the west side, who consume goods brought from the east. If the duty were one or two per cent, (or whatever else might be a fair equivalent for the protection given, and the wharfs and warehouses afforded,) one or two per cent would be added to the price of European and Indian goods in the Eastern Archipelago, and one or two per cent to that of the goods carried from thence to Europe and India. The effect, therefore, of this mistaken application of the principle of free trade, is merely to occasion to the purchasers of such goods a saving of that amount. So far as concerns the goods which pass to the

east of the Gulf, being exactly one half of all which touch at the settlements, the saving is purely to the nations of Eastern Asia. On the remaining half, our countrymen merely share the advantage with all other nations trading to the east.

We have entered into a somewhat minute examination of this question, not so much for the importance of the subject immediately before us, but rather because we were anxious to clear up the misunderstanding with respect to the scope and effect of the principle of free trade, by which Mr. Huskisson seems, in this instance, to have been misled. We earnestly deprecate the converting any phrase, however unobjectionable in itself, into a catch-word, because it is sure in that case to find its way into the mouths of many who do not understand, or do not attend to its accurate meaning. "Equality," in a neighbouring nation, and "No Popery" in our own, originally meant nothing but what was innocent and laudable. If the inventors of these expressions had taken for their motto a *principle* instead of an *abbreviation*, the one phrase could never have been made a handle wherewith to exterminate men for being *unequal* to their neighbours, by superiority in riches or talents; nor the other a ground for persecuting the *men*, whose *opinions* only it was originally intended to condemn. Such disastrous effects are not likely to arise from any abuse of the terms "*Free Trade*;" but it is necessary, when that phrase is made use of, always to bear in mind that the real principle of legislation is that of allowing private interest to regulate wholly the disposition of private capital, and avoiding to give any factitious advantage to one employment of it over another. It is by this test alone that every proposition, be its object to free trade from restrictions, or to impose them, must ultimately be tried.

MINUTE ON THE BLACK ACT

1836

EDITORS' NOTE

British Library, Add. MSS 36,468 (Broughton Papers), ff. 401-7. As unpublished, not listed in Mill's bibliography.

This paper is one of the briefs assembled by John Cam Hobhouse, Baron Broughton, President of the Board of Control 1835-41 and 1846-52, as guides in preparing his response (which was negative) to the petition from inhabitants of Calcutta against India Act XI (1836), the so-called Black Act. For the petition, see "Memorial of the Inhabitants of Calcutta and Others, of All Classes of His Majesty's Indian Subjects, to the President and Board of Commissioners for the Affairs of India, and the Court of Directors of the East India Company," *PP*, 1837-38, XLI, 264-6.

Minute on the Black Act

THE PETITIONERS PRAY that cases of marriage, divorce, and inheritance or succession, respecting Englishmen, should be removed altogether from the Company's Courts, and that in all other civil cases (viz. debt, contract or trespass) wherein Englishmen are affected either as plaintiffs or defendants, an appeal should lie to the Sudder Adawlut or to the Supreme Court, at the option of the appellant.

The first of these prayers might without impropriety be complied with if the English inhabitants really wish it; because the marriages and divorces of the English, and the succession to their property, cannot in any way affect the interests or rights of the *natives*. On these matters therefore I, at least, see no reason why the appeal should not lie to the Supreme Court, or even, if the English wish it, why the Supreme Court should not have sole cognizance, until the Indian Code is completed,¹ which is all that the petitioners require.

But on the other question the interests and rights of the natives are most seriously at stake. When an Englishman in India, beyond the bounds of the Presidency, borrows or lends, or enters into contracts of any other kind with natives, he must be understood to do so according to the native laws, the only ones which are known to the parties he contracts with. The same reasoning applies to those cases of civil injury known by the name of trespass. An Englishman has no right to go up the country and say to the natives, I will regulate my transactions with you by the laws of my own country, and if you think I have injured you, you shall not have the redress your own laws would give you, but shall be satisfied with that given by laws you know nothing about. If an Englishman goes there for his own purposes, it is to be expected from him that he will make himself acquainted with the institutions and customs of the country: but it is not to be expected of the natives that they should, previous to dealing with him, make themselves acquainted with *his* laws and institutions: and their passive character and dread of the name of an Englishman make it necessary to give facilities instead of interposing difficulties to their resisting fraud or oppression when attempted to be practised on them by the more powerful race.

But if it be admitted that the English must be governed by the same laws as the natives, it is absurd to say that the Court which adjudicates their causes in the last

¹See "Penal Code for India" below.

resort, shall be the Supreme Court, which administers a totally different system of law, and from which an Englishman might again drag the native he had injured before the Privy Council.

The principal things to be done in meeting these petitioners are, certain misrepresentations to be set right and certain principles to be proclaimed.

First, as to the misrepresentations—

1st. The petition is so framed as to keep out of view the fact that the Act does not affect *Calcutta*. It is only when the *Calcutta* people settle and acquire property in the *Mofussil*, that they are placed under the Company's Courts and the laws which govern the natives.

2dly. The petition talks invidiously of placing Europeans under *native judges*, sinking the fact that native judges have jurisdiction only in small sums, in which the expense of an appeal to the Supreme Court would be so out of proportion that it would never be incurred unless to harass an adversary.

3dly. The petition imputes all sorts of incapacities to the Company's judges, in the teeth of facts, and in a manner grossly libellous to the service, but especially talks of judicial functions confided to inexperienced young men; forgetting that even if their prayer was granted, the same young men would continue to judge in the first instance, and that the question merely is whether the *appeal* from those young men shall lie to the Supreme Court or to the *Sudder Adawlut*: now the *Sudder Adawlut* does not consist of inexperienced young men but of the most able and experienced men who have passed all their lives in the execution of judicial functions, and are far superior on the average in judgment and experience to the young or second rate barristers who go out to be judges of the Supreme Court with all the self conceit and professional prejudice of men who know their own technicalities and little else—though there are some honorable exceptions, as Sir Edw. Ryan.²

Secondly: The principles to be proclaimed—

The first and greatest of these is, that the Natives of India need protection against the English, and that to afford them that protection is one of the first duties of the British government in India. To shew the necessity of this, reference may be had to the many parliamentary papers which shew the oppression and injustice the natives are subject to from the indigo planters, and the extreme difficulty of protecting them from it. The natives may as well have no justice at all, as be told to look for it to the Supreme Court, probably the most expensive tribunal in the world, and placed often a thousand miles from them. Accordingly all parties, the Judges of the Supreme Court included, joined in recommending that the Court should be divested of its jurisdiction over the *Mofussil*, or that that jurisdiction should be very much curtailed.

²Edward Ryan (1793-1875), chief justice of Bengal since 1833.

Secondly; it should be proclaimed that the English who resort to India or any other foreign possession, to make their fortunes, are naturally inclined to despise the natives and to seek to make themselves a privileged caste. That this is a pretension which ought to be resisted; and it is because the Company has always resisted it, that the English public of Calcutta are as a body, always hostile to the Company's government.

Lastly; our empire in India, consisting of a few Europeans holding 100 millions of natives in obedience by an army composed of those very natives, will not exist for a day after we shall lose the character of being more just and disinterested than the native rulers and of being united among ourselves. It is difficult enough for the Govt to watch sufficiently over the acts of its own servants: but when to these come to be added a far greater number of Europeans spread over the whole country, coming into competition and collision with the natives in all walks of life, and over whom the government has no control but through the courts of justice; most of them men contemplating only a temporary residence; many of them needy, and not a few of them profligate; then unless the control of the courts of justice over these men be strict and even rigid, the conduct of a large proportion of them is sure to be such as to destroy the *prestige* of superior moral worth and justice in dealings which now attaches to the British name in India: and unless the government can coerce them with a strong arm, they will form in the eyes of the natives an English public foreign and often hostile to the government, and the overawing influence of our power and capacity which has been derived from our union, will be weakened; and thus our government in India will gradually lose both its moral supports—and physical support, independent of those, it has none.

PENAL CODE FOR INDIA

1838

EDITORS' NOTE

London and Westminster Review, VII & XXIX (Aug. 1838), 393-405. Headed: "Art. VII.—*A Penal Code*; prepared by the Indian Law Commissioners, and published by Command of the Governor-General of India in Council. Calcutta, [Bengal Military Orphan Press,] 1837." (In *PP*, 1837-38, XLI, 463-588. It was not enacted until 1860.) Running titles: "Penal Code for India." Signed "S." Not republished. Identified in Mill's bibliography as "A review of the proposed Penal Code for India in the same number of the same review [as "Milnes's Poems"]" (MacMinn, 51).

Penal Code for India

IT HAS BEEN for some time, we suspect, the opinion of all who have paid much attention to the *vexata quaestio* of codification, that, from a question of Theory, it has now passed into one of Practice. The possibility of making a code (for the possibility only, and not the advantage, was contested) has long since been as well proved as words can prove it, and can only be made more evident by actually trying to *do* that which, until done, the world will never believe *can* be done, at least well enough to be worth doing. And such, in truth, has been the history of most great improvements in human affairs. That civilization should exist without slavery, or a great state without monarchical government, were not generally believed possible, until seen realized. The multitude, justly distrustful of their own capacity to decide upon the evidence of general reasoning, turn a deaf ear to all demonstrations of the practicability of any great thing hitherto undone. And among such things the reduction of the whole laws of any country into a set of written enactments proceeding from the direct authority of the legislature, must as yet be considered. Of the points usually insisted upon by the later opponents of codification, the one perhaps in which they have been the most successful is in showing that the Code Napoleon¹ (though a prodigious improvement upon the old French law) is no code, in the genuine sense of the word: for as it does not define the technical terms it makes use of, but leaves their meaning and extent to be determined by the decisions of the courts of justice, a real knowledge of the law can only be obtained, as in England, by a study of precedents and cases; and it has even been found worth while to reprint large editions of the old law books,² for the light which they throw upon the principles on which the judges proceed in their interpretation of the so-called code. To frame a body of statute law which should need no such adventitious aid; which should contain in itself all the law that is necessary, all that the judge requires to enable him to execute the will of the legislator when he knows the facts of the particular case; this would be to construct a code. But this, so far as

e. 30 p.

¹Code Napoléon, formulated in 1803-04, appears in Bulletin 154 bis., No. 2653 bis (3 Sept., 1807), *Bulletin des lois de l'empire français*, 4th ser., Numéros bis.

²Jean Domat (1625-96), *Les lois civiles* (1689-94) and *Le droit public* (1697), reprinted in *Oeuvres*, 9 vols. (Paris: Kleffer and Tenré, 1821-25); and Robert Joseph Pothier (1699-1772), *Traité des obligations* (1761) and *Contrat de vente* (1762), reprinted in *Oeuvres*, 13 vols. (Paris: Beaucé, 1817-20), and in three other eds. before 1825.

we know, has never been the object aimed at in any of the modern European attempts at codification, anterior to the one now before us.

It is because the present *is* an attempt to attain that object, and (so far as we can yet venture to judge) an eminently successful one, that we are anxious to invite to it the attention and the criticism of jurists, and of persons practically conversant with the interpretation of language. We believe that this proposed Penal Code has solved the problem; that it has actually done, so far as the penal branch of law is concerned, that which was denied to be possible, namely, to frame adequate definitions of offences, expressed in general language: definitions sufficiently accurate, to leave no doubt that complete accuracy is attainable. Doubtless, as there are imperfections in all works, and especially in all *such* works, examination will not fail to detect, or experience disclose, cases needful to be provided for, which the framers of these definitions have overlooked; but the emendations necessary to include such cases, can be made without disarranging the plan or disturbing the symmetry of the code; and that is enough.

The Indian Law Commissioners are a body of five persons, appointed under the authority of the last Charter Act to frame a code of law for the inhabitants of India.³ The propriety of such a measure at the particular juncture, appears to have been suggested by the liberty then first granted to Englishmen, for settling in India without license from the East India Company. The great influx of Europeans which was expected to ensue, impressed upon the framers of the Charter Act a sense of the necessity of so revising the laws and tribunals of India, as on the one hand to leave Englishmen no just ground of complaint against the institutions of the country in which they might come to live, and on the other to afford effectual protection to the natives against their encroachments. The anomaly of exempting Europeans from the laws and tribunals of the country, and giving them separate ones of their own, was utterly indefensible in principle; it had been found productive of the most serious oppression and denial of justice to the natives, in cases affecting Europeans, even under the more limited access to the country which the latter had hitherto enjoyed; and now, when the government was no longer to have either the privilege of prohibiting the immigration of persons objectionable in point of character, or that of supplying the defect of legal control by an arbitrary power of banishment, it became an imperative duty to withdraw all legal immunities from Europeans; to subject them to the only tribunals accessible to the people, and (so far as possible) to the only laws which those tribunals were, or could be made, competent to administer.

³By Clause 53 of 3 & 4 William IV, c. 85 (28 Aug., 1833); the five Commissioners initially appointed were George William Anderson (1791-1857), Charles Hay Cameron (1795-1880), Thomas Babington Macaulay (1800-59), John Macleod (1792-1881), and Frederick Millett (d. 1856), who was Secretary.

Such, therefore, was the more especial and peculiar motive which led to the creation of this Commission of codification. To this inducement, however, we believe may be added, without any undue compliment to the parties concerned, a sense of the importance of the object in itself, and of the value of any experiment which might tend to accelerate its successful accomplishment. We are the more inclined to ascribe this honourable motive to the authors of the measure, inasmuch as Mr. Charles Hay Cameron, the only gentleman who was sent from England specifically as a member of the Commission (and whose remarkable qualifications for such a post, are well known to all who have any knowledge of him and of the subject) was recommended to the choice of the Court of Directors and of the ministry, by the complete reform which he, as a Commissioner of Inquiry, had advised, and her Majesty's Government effected, in the courts of justice and judicial procedure of Ceylon.⁴ Alone of all known countries, that British colony now actually enjoys a judicial system constructed on the best conceptions of philosophic jurists—a system in which, without any servile deference for the authority of Bentham, the principal improvements made in the theory of the subject by that great man have been, with due consideration of local circumstances, adopted and carried into practice.⁵ The system is understood to have worked admirably during the few years it has been in operation; and the introduction of it does honour to the Colonial Office. The operations of the Indian Law Commission are adding a second instance in support of a prediction once made, that the foreign dependencies of the empire will enjoy the benefits of many reforms, long before the much more compact masses of private interest which oppose themselves to such changes at home, will permit the mother country to share in them.

It was judiciously considered fitting that, of the five Commissioners who were appointed to give laws to India, three should be Company's servants, of tried abilities and the requisite local knowledge; while the remaining two should be persons sent from England, and conversant with the general principles of law-making. Of these two Mr. Cameron was one; the other was Mr. Macaulay, who, having been appointed a member of the Legislative Council of India, assumed, in addition to his rather scanty functions as such, that of President of the Law Commission. Mr. Cameron's health having prevented him from taking part in the later proceedings of the Commission, the letter to the Governor-General in

⁴"Report of Charles H. Cameron, Esq., One of His Majesty's Commissioners of Inquiry, upon the Judicial Establishments and Procedure in Ceylon" (31 Jan., 1832), *PP*, 1832, XXXII, 119-52.

⁵Of the relevant works by Jeremy Bentham (1748-1832), the one best known to Mill was the one he had edited, *The Rationale of Judicial Evidence*, 5 vols. (London: Hunt and Clarke, 1827). The fascicles of Bentham's *Works*, ed. John Bowring, had just begun to appear.

Council, which accompanies the project of a penal code, is signed only by the other four members;⁶ and a greater share of the labour of completion than was at first anticipated has devolved upon the accomplished President of the Commission, whose style, pruned of whatever would be unsuitable to the character of the work in hand, is distinctly visible in every part of the volume before us, in which it was possible that style should be discernible.

It is not in its particular application to the circumstances of India, but as a specimen of codification in general, that this proposed body of penal law has claims on the attention of the English reader. We shall therefore omit all consideration of the appropriateness of the punishments, whether as to quality or quantity, and shall confine our notice to the definitions of offences, and the nomenclature and expression of the code at large.

The first four chapters are of a general kind, comprising all those explanations and directions which may be given once for all;⁷ and which, in an unsystematic mass of enactments like the English statute book, are either said over again in every statute (sometimes even in every clause of every statute) or left unsaid altogether. Such, for instance, are these—"The pronoun *he* is used of any person, whether male or female." "The word *man* denotes a male human being of any age; the word *woman* denotes a female human being of any age." "The words *to do a thing* denote omissions as well as acts." "The word *act* denotes as well a series of acts as a single act; the word *omission* denotes as well a series of omissions as a single omission."⁸ These simple instances, with many of a more complicated character, compose the first chapter, entitled "General Explanations." The remainder of the generalities are comprised in the three succeeding chapters—"Of Punishments;" "General Exceptions;" and "Of Abetment." In these chapters some, though not many terms, which require definition, are left undefined, the definition in those instances properly belonging not to the penal, but to the civil code, which has not yet been commenced; and in general it may be remarked, that since all offences are such by virtue of their being violations of rights, the attempt to define offences until rights have been defined (which is the business of the civil code), must be attended with peculiar difficulties; but this code has demonstrated the possibility of surmounting these difficulties in a far greater degree than could have been anticipated. Under the chapter of "General Exceptions" we fear that offences by culpable negligence would in many cases escape punishment; but culpable negligence, when productive of actual mischief, is itself, in the more serious cases, made a distinct offence by the subsequent chapters of the code; and

⁶The letter is printed in *PP*, 1837-38, XLI, 465-72. The Governor-General of India 1836-42 was George Eden (1784-1849), Earl of Auckland.

⁷"General Explanations" (pp. 473-6), "Of Punishments" (pp. 476-8), "General Exceptions" (pp. 479-82), and "Of Abetment" (pp. 483-6).

⁸*Ibid.*, pp. 473-5.

in minor cases it may be presumed to be the opinion of the Commissioners that liability to a civil action for damages is the appropriate remedy.

The remaining chapters (chaps. v to xxvi) are those which treat of the separate classes of offences; and the best mode of exhibiting the peculiarities and the general execution of the code will be to extract at length the first section of one of the most important of its chapters—the section “Of Offences affecting Life.”

294. Whoever does any act, or omits what he is legally bound to do, with the intention of thereby causing, or with the knowledge that he is likely thereby to cause, the death of any person, and does by such act or omission cause the death of any person, is said to commit the offence of “Voluntary culpable homicide.”

ILLUSTRATIONS.

(a). A lays sticks and turf over a pit, with the intention of thereby causing death, or with the knowledge that death is likely to be thereby caused. Z, believing the ground to be firm, treads on it, falls in, and is killed. A has committed the offence of voluntary culpable homicide.

(b). A, with the intention or knowledge aforesaid, relates agitating tidings to Z, who is in a critical stage of a dangerous illness. Z dies in consequence. A has committed the offence of voluntary culpable homicide.

(c). A, with the intention or knowledge aforesaid, gives Z his choice whether Z will kill himself, or suffer lingering torture. Z kills himself in consequence. A has committed the offence of voluntary culpable homicide.

(d). A, with the intention or knowledge aforesaid, falsely deposes before a court of justice that he saw Z commit a capital crime. Z is convicted and executed in consequence. A has committed the offence of voluntary culpable homicide.

(e). A is hired to guide Z through a jungle. In the midst of the jungle, A, no circumstance having occurred to release him from his legal obligation to guide Z through the jungle, with such intention or knowledge as aforesaid, leaves Z. Z dies in consequence. A has committed the offence of voluntary culpable homicide.

(f). A being legally bound to furnish food to Z, who is the mother of a sucking child, omits to furnish her with food, intending or knowing it to be likely that Z's death may be the consequence of the omission. Z survives, but the child is starved to death in consequence of the failure of milk, which is caused by A's omission. Here, even if A did not know of the existence of the child, he has committed the offence of voluntary culpable homicide.

(g). A keeps Z in wrongful confinement, and is, therefore, legally bound (see clause 338) to furnish Z with what he knows to be necessary to prevent Z from being in danger of death. A knowing that Z is likely to die if medical advice be not procured, illegally omits to procure such advice. Z dies in consequence. A has committed the offence of voluntary culpable homicide.

(h). A knows Z to be behind a bush. B does not know it. A, intending to cause, or knowing himself to be likely to cause, Z's death, induces B to fire at the bush. B fires and kills Z. Here, B may be guilty of no offence, or if his firing was, under the circumstances, a rash act, he may be guilty of the offence defined in clause 304. But A has committed the offence of voluntary culpable homicide.*

*The cases of *justifiable* homicide are not defined in this chapter, having been provided for in the chapter of *General Exceptions* [Clauses 74-6, p. 481].

295. Voluntary culpable homicide is "murder," unless it be of one of the three mitigated descriptions hereinafter enumerated; that is to say,

First, Manslaughter;

Secondly, Voluntary culpable homicide by consent;

Thirdly, Voluntary culpable homicide in defence.

296. If a person, by doing anything which he intends or knows to be likely to cause death, commits voluntary culpable homicide on a person whose death he neither intends nor knows himself to be likely to cause, the voluntary culpable homicide committed by the offender is of the same description of which it would have been if he had caused the death which he intended or knew himself to be likely to cause.

297. Voluntary culpable homicide is "manslaughter," when it is committed on grave and sudden provocation, by causing the death of the person who gave that provocation.

Explanation.—Provocation is designated as "grave" when it is such as would be likely to move a person of ordinary temper to violent passion, and is not given by anything done in obedience to the law, or by anything authorised by the law of civil or criminal procedure, or by anything done by a public servant* in the exercise of the lawful powers of such public servant, or by anything done by any person in the exercise of the right of private defence,[†] against the offender.

ILLUSTRATIONS.

(a). A, under the influence of passion excited by a provocation given by Z, intentionally kills Y, Z's child. This is not manslaughter, but murder.

(b). A is lawfully arrested by Z, a bailiff. A is excited to sudden and violent passion by the arrest, and voluntarily kills Z. This is not manslaughter, but murder.

(c). A appears as a witness before Z, a magistrate. Z says that he does not believe a word of A's deposition, and that A has perjured himself. A is moved to sudden passion by these words, and kills Z. This is not manslaughter, but murder.

(d). A attempts to pull Z's nose. Z, in the exercise of the right of private defence, strikes A. A is moved to sudden and violent passion by the blow, and kills Z. This is not manslaughter, but murder.

(e). Z strikes B. B is by this provocation excited to violent rage. A, a bystander, intending to take advantage of B's rage in order to cause Z's death, puts a knife into B's hand. B kills Z with the knife. Here, B may have committed only manslaughter, but A has committed murder.

(f). Y gives grave and sudden provocation to A. A, on this provocation, fires a pistol at Y, neither intending nor knowing himself to be likely to kill Z, who is near him but out of sight. A kills Z. Here, A has committed manslaughter.

298. Voluntary culpable homicide is "voluntary culpable homicide by consent," when the person whose death is caused, being above twelve years of age, suffers death, or takes the risk of death, by his own choice:

*Who are to be considered *public servants* has been stated in the chapter *General Explanations* [Clause 14, p. 474].

†The *right of private defence* has been defined, and the necessary provisions made for it, in the chapter *General Exceptions* [Clauses 74-84, pp. 481-2].

Provided,

First, That the offender does not induce the person whose death is caused to make that choice, by directly or indirectly putting that person in fear of any injury;*

Secondly, That the person whose death has been caused is not, from youth, mental imbecility, derangement, intoxication, or passion, unable to understand the nature and consequences of his choice;

Thirdly, That the offender does not know that the person whose death is caused was induced to make the choice by any deception, or concealment;

Fourthly, That the offender does not conceal from the person whose death is caused anything which the offender knew to be likely to cause that person to change his mind.

Explanation.—Voluntary culpable homicide committed by inducing a person voluntarily to put himself to death is voluntary culpable homicide by consent, except when it is murder.

ILLUSTRATIONS.

(a). Z, a Hindoo widow, consents to be burned with the corpse of her husband. A kindles the pile. Here A has committed voluntary culpable homicide by consent.

(b). A, by instigation, voluntarily causes Z, a child under twelve years of age, to commit suicide. Here, on account of Z's youth, the offence cannot be voluntary culpable homicide by consent. A has therefore committed murder.

(c). A, by deceiving Z into a belief that Z's family have perished at sea, voluntarily causes Z to commit suicide. Here, on account of the deception practised by A, the offence cannot be voluntary culpable homicide by consent. A has therefore committed murder.

299. Voluntary culpable homicide is "voluntary culpable homicide in defence," when it is committed by causing death under such circumstances that such causing of death would be no offence if the right of private defence extended to the voluntary causing of death in cases of assault not falling under any of the descriptions enumerated in clause 76, or in cases of theft, mischief, or criminal trespass, not falling under any of the descriptions enumerated in clause 79.

ILLUSTRATIONS.

(a). Z attempts to horsewhip A, not in such a manner as to cause grievous hurt[†] to A. A draws out a pistol. Z persists in the assault. A, believing in good faith that he can by no other means prevent himself from being horsewhipped, shoots Z dead. A has committed voluntary culpable homicide in defence.

(b). Z commits simple theft on A's horse, and rides away with it. Here A has a right of private defence which lasts till either Z can effect his retreat with the property, or till A can recover his horse, but which does not extend to the infliction of death, inasmuch as A is in no danger of death or hurt. A pursues Z, and, not being able to overtake him, shoots him dead. A has committed voluntary culpable homicide in defence.

(c). Z commits an assault, not of a dangerous description, on A. A, knowing that he can

**Injury*, defined in the chapter *General Explanations* [Clause 29, p. 477].

[†]*Grievous hurt*, defined in a subsequent section of the Code. The right of private defence extends to the voluntary causing of death in cases in which there is danger of "grievous hurt" [Clause 315, p. 509].

defend himself from the assault without killing Z, kills Z. Here, as A's act would be an offence even if the right of private defence in cases of assault of the descriptions not enumerated in clause 76 extended to the voluntary infliction of death, A has committed voluntary culpable homicide, which is not voluntary culpable homicide in defence, but which, according to the circumstances, will be manslaughter or murder.

300. Whoever commits murder shall be punished with death, or transportation for life, or rigorous imprisonment for life, and shall also be liable to fine.*

301. Whoever commits manslaughter shall be punished with imprisonment of either description,[†] for a term which may extend to fourteen years, or fine, or both.

302. Whoever commits voluntary culpable homicide by consent shall be punished with imprisonment of either description, for a term which may extend to fourteen years and must not be less than two years, and shall also be liable to fine.

303. Whoever commits voluntary culpable homicide in defence shall be punished with imprisonment of either description for a term which may extend to fourteen years, or fine, or both.

304. Whoever causes the death of any person by any act or any illegal omission, which act or omission was so rash or negligent as to indicate a want of due regard for human life, shall be punished with imprisonment of either description for a term which may extend to two years, or fine, or both.

305. If the act or illegal omission whereby death is caused in the manner described in the last preceding clause, be, apart from the circumstance of its having caused death, an offence other than the offence defined in clause 327, or an attempt to commit an offence, the offender shall be liable to the punishment of the offence so committed or attempted, in addition to the punishment provided by the last preceding clause.

Explanation.—In cases in which the doing of a certain thing and the attempting to do that thing are distinct offences, if the offence defined in the last preceding clause be committed in the attempting to do that thing, the additional punishment to which the offender is liable is the punishment not of attempting to do that thing, but of doing that thing.

ILLUSTRATION.

A uses force to Z, a woman, intending to ravish her. He does not ravish her, but commits the offence defined in clause 304. Here the term of imprisonment to which A has made himself liable is to be regulated not by the term of imprisonment assigned to the offence of attempting to ravish, but by the term of imprisonment assigned to actual rape, that is to say, A is liable to rigorous imprisonment for a term of not more than sixteen nor less than two years.

306. If any child under twelve years of age, any insane person, any delirious person, any idiot, or any person in a state of intoxication, commits suicide, whoever previously abets by

*See Clause 50 [p. 477], "Where no sum is expressed to which a fine may extend, the amount of fine to which the offender is liable is unlimited." The reasons for not fixing (in general) a *maximum* of fine are excellently stated in one of the Commission's notes [Note A, pp. 536-7].

[†]The two descriptions of imprisonment, *simple* and *rigorous*, are defined in the chapter *Of Punishments* [Clause 40; see also Note A, p. 535].

aid* the commission of such suicide shall be punished with death or transportation for life, or rigorous imprisonment for life, and shall also be liable to fine.

307. If any person commits suicide, whoever previously abets by aid the commission of such suicide shall be punished with imprisonment of either description for a term which may extend to fourteen years, and must not be less than two years, and shall also be liable to fine.

308. Whoever does any act, or omits what he is legally bound to do, with such intention or knowledge and under such circumstances that if he by that act or omission caused death, he would be guilty of murder, and carries that act or omission to such a length as at the time of carrying it to that length he contemplates as sufficient to cause death, shall be punished with transportation for life, or with rigorous imprisonment for a term which may extend to life, and must not be less than seven years, and shall also be liable to fine.

ILLUSTRATIONS.

(a). A, intending to murder Z by means of a spring gun, purchases such a gun. A has not yet committed the offence defined in this clause. A sets the gun loaded in Z's path, and leaves it there. A has committed the offence defined in this clause.

(b). A, intending to murder Z by poison, purchases poison, and mixes the same with food which remains in A's keeping. A has not yet committed the offence defined in this clause. A places the food on Z's table, or delivers it to Z's servants to place it on Z's table. A has committed the offence defined in this clause.

309. Whoever does any act, or omits what he is legally bound to do, with such intention or knowledge and under such circumstances that if he, by that act or omission, caused death, he would be guilty of voluntary culpable homicide, and carries that act or omission to such a length as at the time of carrying it to that length he contemplates as sufficient to cause death, shall be punished with imprisonment of either description, for a term which may extend to three years, or fine, or both.

ILLUSTRATIONS.

(a). A, on grave and sudden provocation, fires a pistol at Z, under such circumstances that if he thereby caused death he would be guilty of manslaughter. A has committed the offence defined in this clause.

(b). A lights a pile prepared for a Suttee, under such circumstances that if he thereby caused death he would be guilty of voluntary culpable homicide by consent. A has committed the offence defined in this clause.

(c). A pursues a thief, and fires at him, under such circumstances that if he killed the thief he would commit voluntary culpable homicide in defence. A has committed the offence defined in this clause.

310. Whoever belongs or has at any time belonged to any gang of persons associated for the purpose of gaining a livelihood by inveigling and murdering travellers in order to take the property of such travellers, is designated as a "Thug."

311. Whoever is a Thug shall be punished with transportation for life, or imprisonment of either description for life, and shall also be liable to fine.⁹

*Previously abets by aid: for the definition, see the chapter *Of Abetment* [Clauses 86-8, p. 483].

⁹Pp. 506-9.

What first strikes the eye in this long extract, is the happy invention of appending authoritative examples by way of Illustration, to all those enactments of the code which require them: an idea by which the advantages of general language, and those which English statutes vainly seek to attain by an enumeration of particulars, are happily blended; and which, besides the greater certainty and distinctness given to the legislator's meaning, solves the difficult problem of making the body of the laws a popular book, at once intelligible and interesting to the general reader. Simple as this contrivance is, it escaped the sagacity of Bentham, so fertile in ingenious combinations of detail. As the Commissioners say, in their introductory letter to the Government—

The definitions and enacting clauses contain the whole law. The illustrations make nothing law which would not be law without them. They only exhibit the law in full action, and show what its effects will be on the events of common life. . . . The illustrations will lead the mind of the student through the same steps by which the minds of those who framed the law proceeded, and may sometimes show him that a phrase which may have struck him as uncouth, or a distinction which he may have thought idle, was deliberately adopted for the purpose of including or excluding a large class of important cases. . . . Thus the code will be at once a statute book and a collection of decided cases. The decided cases in the code will differ from the decided cases in the English law books in two most important points. In the first place, our illustrations are never intended to supply any omission in the written law, nor do they ever, in our opinion, put a strain on the written law. They are merely instances of the practical application of the written law to the affairs of mankind. Secondly, they are cases decided, not by the judges, but by the legislature, by those who make the law, and who must know more certainly than any judge can know, what the law is which they mean to make.¹⁰

With what degree of perfection the definitions contained in the section which we have cited, or in any other part of the code, fulfil the intentions of the framers, we now leave it to competent judges to decide. We are sure that all such persons will find, even in the little we have quoted, enough to satisfy them that their labour will not be uselessly employed in perfecting a work which is already so considerable an advance on all which has preceded in its kind. The Indian Government has caused the code to be printed and widely circulated throughout India, and has publicly invited criticisms and suggestions from all parties competent to give them. But in this country also, there is a Commission for the reform of the criminal law;¹¹ which certainly has not yet effected anything upon a par with the expectations held out at the time of its appointment. A direction from the Home Secretary¹² to these

¹⁰Pp. 469-70.

¹¹For the Commission, see "First Report from His Majesty's Commissioners on Criminal Law" (24 June, 1834), *PP*, 1834, XXVI, 117-77. It issued a "Second Report" in 1836 (*ibid.*, 1836, XXV, 183ff.), and continued with reports almost annually.

¹²Then Lord John Russell (1792-1878).

Commissioners, to report upon the present code, would give India the benefit of their criticisms, would put into their hands a most valuable aid for the performance of their own work, and would be no inconsiderable test of their fitness to perform it. Moreover, both Mr. Macaulay, and the ablest of the Indian members of the Commission, Mr. Macleod (who, we have the best authority for stating, took a most active part and rendered signal service in the concoction of the code,) are now in England. A government which should make any new appointments, either to the Criminal Law Commission, or to any other body constituted for Law Reform, without ascertaining whether these gentlemen, or either of them, were willing to serve on it, would do little honour to its own discernment. Their services, if attainable (of which we ourselves know nothing), would be secured without delay, by any government really in earnest about the Reform of the Law.

The notes to the code, containing the reasons for such of its provisions as seemed to require explanation or defence, are nearly as voluminous as the text.¹³ They are very able and valuable essays, and, we think, rarely fail successfully to vindicate everything in the code, the propriety of which might otherwise have appeared doubtful. In one case, we think the defence eminently unsuccessful; and probably other such cases might be found. By the proposed code, nothing which is true is a libel; or rather (for the Commissioners do not adopt that most ill-chosen word from English law) is defamation: no action can be maintained or penalty inflicted for attacks on reputation, unless the court, having entered into the evidence of truth or falsehood, pronounces the imputation to be false.¹⁴ And the Commissioners defend this provision at some length in their notes;¹⁵ but in a manner which fails to convince us. Nothing can be more proper than that the truth of a charge should be its justification, in all cases in which either a court of justice or the public are competent judges of the subject. But in matters which relate to private life, how can either the one or the other be made cognizant of the circumstances on which the morality or immorality of the act principally depend? Take the case of a family quarrel, for example;—who is to blame, and in what degree, are questions depending upon the previous character and relations of the parties—upon states of feeling produced perhaps by long trains of circumstances, not one of which can be given in evidence, or if it were, could be duly estimated by any one not intimately acquainted with the parties. Let any candid person ask himself, how far advanced he would be, in any such case that he is well acquainted with, towards forming a just estimation of the conduct of the parties, if he knew only such naked facts as would have admitted of being proved in a court of justice? And this in fact is the principal reason for leaving any immoralities whatever exempt from legal punishment. If any sort of act is really blamable, and if the

¹³Pp. 534-88.

¹⁴Clause 470, p. 531.

¹⁵Note R, pp. 581-6.

circumstances which make it such can be so clearly discriminated and made apparent to third parties, as to be susceptible of judicial investigation and proof, it would be difficult to find any sufficient reason for not making that kind of act an offence under the penal code. But to do justice to this subject would require a much longer discussion than can properly find a place here.

That many other defects must necessarily be found in this code, its framers would, we are convinced, be the last persons to deny; and the first to hail any, even hostile, criticism, which might furnish valuable suggestions for its amendment. Unfortunately, few of the attacks of which it has yet been the subject, either from the Calcutta or the London press, bear, so far as they have come to our knowledge, marks of any but the worst motives and spirit.¹⁶ They mostly appear to proceed directly or indirectly from that party of English in India, to protect the natives against whose rapacity and tyranny, is one of the most difficult but most bounden duties of the Indian Government; and who are now venting, against what they consider as mainly the work of Mr. Macaulay, the spleen excited by the part he took in framing what they call the "Black Act;"¹⁷ itself but one, and not a very considerable, step towards executing the declared intention of Parliament for placing Europeans and natives under one equal law.¹⁸ It gave us much regret that so upright and able a supporter of the popular cause as Mr. Ward,¹⁹ should have made himself, on this subject, the organ in Parliament of a handful of foreigners attempting to make themselves a privileged oligarchy in a country of a hundred millions of inhabitants, and who, if the existence and regulations of the East India Company were not a perpetual barrier against them, would be in danger, under a conniving or passive ministry, of establishing a domination as much more tyrannical than that of the English party in Canada in the worst of former days, as the Hindoos are a more ignorant and more passive people than the French Canadians.

¹⁶See, e.g., "Mr. T.B. Macaulay," *Calcutta Englishman*, 13 Jan., 1838, reprinted in *The Times*, 6 Apr., 1838, p. 3; a leading article on the Penal Code, *The Times*, 2 Apr., 1838, p. 4; and a letter to the editor, signed "Buz Hum," *The Times*, 4 Apr., 1838, p. 5.

¹⁷"Act No. XI of 1836 of the Governor and Council of India" (9 May, 1836), *PP*, 1840, XXXVII, 31. See pp. 11-15 above.

¹⁸I.e., by 3 & 4 William IV, c. 85, Sect. 53.

¹⁹Henry George Ward (1797-1860) had on 26 January, 1838, presented to Parliament a petition against the Black Act (*PD*, 3rd ser., Vol. 40, col. 543), and spoke against it on 22 March, 1838 (*ibid.*, Vol. 41, cols. 1134-45).

THE EAST INDIA COMPANY'S CHARTER

1852

EDITORS' NOTE

“Report from the Select Committee of the House of Lords Appointed to Inquire into the Operation of the Act 3 & 4 William IV, c. 85, for the Better Government of Her Majesty’s Indian Territories; with Minutes of Evidence, Appendix, and Index Thereto” (29 June, 1852), *PP*, 1852-53, XXX, 304-36. Headed: “John Stuart Mill, Esquire, is called in, and examined as follows” (p. 304) and “John Stuart Mill, Esquire, is called in and further examined as follows” (p. 313). Mill gave his evidence on 21 and 22 June, 1852, in answer to questions 2912-3019 and (2nd day) 3020-3176. Not republished. Identified in Mill’s bibliography as “Evidence before the Select Committee of the House of Lords on India affairs, printed with their Report, (No. 88. of the sessional papers for 1852) ordered to be printed 29th June 1852” (MacMinn, 77). In the text below, the questions by the Committee members are in italic type. The questioners are not identified in *PP* or in the *Sessional Papers of the House of Lords*, 1852, XIX, where the same Blue Book is presented. The Committee was chaired by the Lord Privy Seal, James Brownlow William Gascoigne-Cecil (1791-1868), Marquis of Salisbury.

The East India Company's Charter

WHAT CONNEXION *have you had with the Government of India?* I am one of the assistants to the Examiner of Indian Correspondence, in whose office the greater part of the correspondence with India relating to the Government is conducted.

For what length of time have you been in that office? Since the year 1823, and nearly the whole of that time in the Correspondence Department; in fact, I may say the whole of it.

Have you been exclusively in that department, or in others also? Exclusively in that department.

Have we reason, do you think, on the whole, to feel satisfied with the general working of the Home Government of India? The present constitution of the Indian Government, considering the great difficulties of the case, seems to me to have worked very satisfactorily.

Will you state more specifically the causes to which you attribute the satisfactory working of the Government? I conceive that there are several causes; probably the most important is, that the whole Government of India is carried on in writing. All the orders given, and all the acts of the executive officers, are reported in writing, and the whole of the original correspondence is sent to the Home Government; so that there is no single act done in India, the whole of the reasons for which are not placed on record. This appears to me a greater security for good government than exists in almost any other government in the world, because no other probably has a system of recordation so complete.

In those records do you find the records of opinions? To a very great extent. If the local officer and the Government differ in opinion, or if the opinions of the different members of the Government differ from one another, the reasons on both sides, and the discussions that take place, are put in writing, and reported to the Home Government, who are thus in possession of all the materials of knowledge that the local authorities can supply.

What do you think would be the consequence of Parliament interfering more frequently and more extensively in the government of India? I think that many bad, and few good consequences would result. The public opinion of one country is scarcely any security for the good government of another. The people of one country, whether represented by the public authorities of this country, or by the nation itself, cannot have the same acquaintance with the circumstances and interests of the other country as they may have with their own. The great security

for the good government of any country is an enlightened public opinion; but an unenlightened public opinion is no security for good government. The people of England are unacquainted, or very ill acquainted, with the people and the circumstances of India, and feel so little interest in them, that I apprehend the influence of public opinion in this country on the Government of India is of very little value, because there are very few cases in which public opinion is called into exercise; and when it is so, it is usually from impulses derived from the interests of Europeans connected with India, rather than from the interests of the people of India itself.

Supposing that appeals were permitted freely to the English Parliament from the decisions of the Governor-general of India, in cases of resumption, such as have taken place at different times, do you think that that would tend greatly to impair the power of the Government of India? I think that anything which causes the people of India to look beyond the Government of India to any authority here, of which they have no knowledge, and concerning which they have most indefinite ideas, would tend to weaken the local Government. Of course that inconvenience must be submitted to in so far as it has any tendency to increase the security for good government; but the real security for the good government of India depends, as it seems to me, upon a careful review of the Acts of the local Government, grounded on the transmission of all the recorded proceedings to this country. The proceedings are subjected to a very rigid examination, not, of course, as to all their details, but as to their general principles, and the spirit in which those general principles are applied to particular cases; this seems to me the only kind of appeal that is of any considerable value in regard to the government of a country at such a distance, and in the peculiar circumstances of India.

*Will you state the successive checks which operated upon the occasion of the deposition of the Rajah of Sattara?*¹ There was first the decision of the Bombay Government; and then that decision could not take effect without the concurrence of the Government of India, which was, therefore, the first check or appeal, as it may be called. In the next place, that decision was subject to reversal by the joint action of the Court of Directors and the Board of Control; and, finally, it was open to any Member of either House of Parliament to bring forward a Motion, which, if it had been effectual, might have led to a Parliamentary inquiry, or eventually to a reversal of the Act.

¹Pratap Singh (d. 1847) had been made head of state by the British in 1819, and was deposed in 1839. For the official account, see "Copies or Extracts of Correspondence and Papers Relating to, and Explanatory of, the Deposition of the Raja of Sattara, and the Appointment of His Brother as His Successor," *PP*, 1843, XXXVIII, Pt. 1, 109-Pt. 2, 675. The resident (referred to below) was Charles Ovans (ca. 1793-1858), who was instrumental in dethroning the Raja, and then was impeached before the Court of Directors. The Governor of Bombay 1838-41 was James Rivett Carnac (1745-1846); members of Council who expressed opinions included William Wilberforce Bird (d. 1857) and Thomas Campbell Robertson (1789-1863).

And to a certain extent there might have been the interposition of the Court of Proprietors? The Court of Proprietors would have had no power of reversing what had been done. They have the power of holding a public discussion, which, as a means of publicity, is not without value.

In regard to the action on that occasion of the Government of Bombay, was there not a minute recorded of the Governor, and were there not also minutes recorded of each member of Council? There were. In the first place, there was the report of the local officer, the Resident at Sattara; this report was then the subject of discussion in the Council, and the Governor and each member of Council recorded their opinion. When they, either unanimously or by a majority, had formed their opinion, they communicated it in a despatch to the Governor-general in Council, who issued the final orders—final as far as India was concerned.

When this despatch, accompanied by the recorded minutes, was forwarded to the Government of India, were there not further minutes written by the Governor-general and the members of Council, each giving his opinion separately upon the subject? Whether that was so in that particular case, I am not certain, but I believe so. In cases of importance it almost invariably happens that the opinion of each member of Council is recorded separately.

With his reasons? With his reasons.

All those reports were then forwarded to the Court of Directors? Yes.

And the subject was discussed by the Court of Directors? Yes.

Were there further minutes entered upon the journals of the Court of Directors upon the same subject? It is not usual to enter on the records of the Court any minutes of opinions, except dissents.² After a resolution is passed, any member of the Court who dissents from the resolution, if he thinks the matter of sufficient importance, records his dissent, accompanied with reasons, and those are, as a matter of course, communicated to the Board of Control.

Are those dissents communicated to the general Court, or to the Committee? The dissents are recorded on the minutes of the Court, and have nothing to do with any Committee.

The expression of all those opinions was submitted to the Board of Control before the ultimate decision was taken upon the subject? Yes; it does occasionally, but seldom, happen, that the ultimate decision is taken before the dissent has been sent to the Board.

It is only in cases where the question has been so repeatedly discussed, that it is thought hardly necessary to send up the dissents; but in the first instance, all the dissents are sent up? The dissents are sent to the Board as soon as they are copied; but cases have happened, though not, I believe, in matters of importance, when the despatch has been sent back approved by the Board before the dissent reached

²For dissents in this case, by Directors John Cotton (1784-1860), John Forbes (1801-40), John Shepherd (d. 1859), and Henry St. George Tucker (1771-1851), see *ibid.*, pp. 604-19.

them: it is only in those cases that the Board has not had the advantage of the dissents before its final decision.

Any member of the Court of Proprietors moreover may, if he thinks fit, raise a question for public discussion, and appeal to the public in England upon the subject? Any nine members may sign a requisition for a special meeting of the Court of Proprietors, or any one proprietor may, at a quarterly meeting, after notice, make a motion on any matter connected with Indian affairs.

You think that those successive checks operate more beneficially for the protection of the natives of India than any constant interference of Parliament on their behalf? No one will deny that it is necessary that Parliament should be open to appeals on all subjects connected with the government of any part of the British Empire; but, so far as my experience goes, I should say that the security for the good government of India derived from discussions in Parliament is far short of that derived from the habitual examination of all papers of any importance by persons specially devoted to that object.

Persons who have no sinister interest? It is next to impossible to form in one country an organ of government for another which shall have a strong interest in good government; but if that cannot be done, the next best thing is, to form a body with the least possible interest in bad government; and I conceive that the present governing bodies in this country for the affairs of India have as little sinister interest of any kind as any government in the world.

Have the natives of India shown a disposition to employ agents in this country for the prosecutions of appeals against the decisions of the Governor-general? Yes; and I think with increasing frequency.

If the opinion became prevalent in India that changes of decision on matters of individual and immediate interest might be readily produced by such appeals to Parliament, do you think that they would become very frequent? Those best acquainted with India say, that the natives are exceedingly averse to giving up any pretension whatever, until they have tried every resource within their reach for getting a hostile decision reversed. I think if it were the habit of the people of India to look to a revision of their cases in England, as a thing which could be procured by sending vakeels, or delegates, here, they would very frequently do so, incurring much useless expense, and often ultimate disappointment. But the proper remedy is, that the Home Government should so act as to convince the natives of India that if their case is just, they will have full justice done to them, on a review of the papers, without sending any one here to represent them; and that if their case is unjust, however many people they may send, it will do them no good.

Would money be wanting on their part to prosecute such appeals? There are many natives who have ample means for the purpose.

Can you suggest any improvements in the present Home Government of India? It is difficult to suggest alterations in a system of Government, of which the good working, so far as it has worked well, could not have been predicted beforehand. The present constitution of the Government of India has been very much the

growth of accident, and has worked well, in consequence of things which were not foreseen, and were not in the contemplation of those who established it in a great measure, from causes not provided for in the received theories of government. So much of the good working of the present Government being the result of accident, accident would probably have a great share in determining the operation of any new system which might be substituted for it; but it would be necessary to keep in view in any alteration the circumstances, so far as they can be assigned, which have been the causes of the beneficial working hitherto. Among the first of those seems to me to be, that those who are sent to administer the affairs of India, are not sent to any particular appointment; they go out merely as candidates; they go out when young, and go through the necessary course of preparation in subordinate functions before they can arrive at the higher ones. That seems to me the first essential requisite for the good government of India. A second great advantage of the present system is, that those who are sent out as candidates to rise by degrees to the higher offices, are generally unconnected with the influential classes in this country, and out of the range of Parliamentary influence. The consequence is, that those who have the disposal of offices in India have little or no motive to put unfit persons into important situations, or to permit unjustifiable acts to be done by them. Any change in the government of India which would bring the appointment to Indian offices into the ordinary channels of political or Parliamentary influence would, I think, take away one of the chief causes of whatever is beneficial in the present working of the Government of India.

Would the sale of such appointments, in your opinion, operate injuriously? It would probably bring a much greater proportion of them than at present into the channels in which political influence flows in this country, and in so far as it did so I think it would deteriorate the Indian Government. At present, the civil servants, appointed very young, and by individual members of the Court, do not usually become eligible for any very high appointment during the time that the Directors who appointed them can be supposed to have any influence over their promotion. Partly from this circumstance, and partly because the person who gives the appointment is only one of 24, it is my belief there is hardly any government existing in which there is so little personal jobbing as in the Government of India.

Is there not a tendency, from the patronage being administered from private and personal motives, to the service of India becoming a sort of caste of particular families and particular connexions? I should say not more than is in the nature of the case, and not to such an extent as to be an evil. It will happen under any system that persons who have served in India will look by preference to Indian appointments for their sons; and they would under any system be likely to have readier access to Indian than to any other appointments. In whatever manner the Home Government might be constituted, it would doubtless be partly composed of persons who have served in India, and, if so, the patronage in their gift would flow in the same channels as at present.

Is it not generally supposed that the patronage in the hands of the Directors is

made use of to obtain elections to the Court? I have heard of such things; I do not know how far that is the case. I have no doubt the directors bestow their patronage on those who have served them in that, or any other way. But the main point appears to me to be, that neither a Director, nor any one else connected with the Home Government, has it in his power to appoint an unfit person to any situation in India: the only thing he can do is, to send out a candidate, who will ultimately obtain an important situation if he is considered fit for it by the local Government; but since the appointment here is only the appointment of a candidate, who is to go to India, and make himself fit for an important situation before he can receive it, the bestowing of this patronage from private motives is not attended with the evils which would arise from making appointments to office on private grounds.

Has not the influence of the proprietors, in the bestowal of the patronage, the effect of distributing the patronage more largely and more widely among the community? No doubt it has; the general course in which the patronage flows is among the middle classes.

What do you mean by the middle classes? I mean, in the present case, by the middle classes, the classes unconnected with politics, or with the two Houses of Parliament.

It has been frequently observed that a very large proportion of the servants of the East India Company have been selected from that part of the kingdom north of the Tweed; is it your opinion that such is the case, or not? It was the case at one time, from accidental circumstances. One of the causes was said to be, that the first Lord Melville was so long President of the Board of Control;³ at present I am not aware that there is a larger proportion of Scotch in the Indian service than in other departments of the public service.

It is your opinion that there are not a greater number of Scotchmen in the East India Company's service than Englishmen or Irishmen? I do not think there are.

Do you consider a tradesman to belong to the middle class, or not? I do.

Are there not a great many sons of tradesmen sent to India? I am not aware what the proportion is; but I have no doubt that there are some.

What circumstance, in your opinion, leads to the appointment of sons of tradesmen to writerships, or cadetships? I cannot answer that question; I have no knowledge of the motives which operate on Directors in disposing of their patronage.

Is it not a curious circumstance that the son of a horse-dealer should be sent to India as a cadet? The son of a horse-dealer is as likely to qualify himself in the subordinate situations for succeeding to the higher as the son of any one else.

But that is not exactly the class from which you would select persons to be the companions of gentlemen who are to fill honourable professions? It is not the class

³Henry Dundas (1742-1811), 1st Viscount Melville, was a member of the Board of Control from 1784 and, although not President until 1793, had effective control of Indian affairs until 1801.

from whom cadets or writers are generally selected; but I see no reason why such persons should be excluded.

Do you see any reason why the aristocracy should be excluded? I see no reason for excluding any one; but it does seem to me undesirable that those who are appointed to situations in India should be persons permanently connected with political parties, or with Parliamentary influence at home.

Do not you think that the higher the class of men who are appointed to fill our civil situations in India, the greater the security for the connection between India and England? I think that the permanence of the connection between India and England depends upon our being able to give good government to India, and to persuade the people of India that we do so.

Is it your opinion that those persons ought to be excluded from the Indian service who have any connection with the great political parties in this country? I would exclude no one; but I think it is a recommendation of the present system that those appointed under it are mostly unconnected with the possessors of Parliamentary influence.

You think that that is advantageous to the Government of India? It is the greatest protection that can be obtained against improper appointments.

Hitherto there has not been even a suspicion against the manner in which the Governor-general has exercised his power of selection? The Governor-general can seldom have any motive to appoint unfit persons to situations in India, because while the service is taken from one class, the Governor-general belongs to another, and none of his personal or political connexions are in the class from which the service is taken. He has thus no personal interest in appointing persons to situations for which they are unfit, and I believe it is very seldom that such appointments take place, except by mistake, or negligence.

Should you think it an extraordinary circumstance if you heard that a gentleman, on being appointed Governor-general, had, in the course of ten days, before he could get out to India, no less than 400 letters asking him for appointments? I should not be surprised to hear of any number of applications for appointments.

What is the second circumstance to which you alluded as a recommendation of the existing constitution of the Government of India? The two circumstances which I mentioned were, in the first place, that those who are sent out are merely candidates; they are never, or very rarely, appointed from England to any situation in India. The second circumstance was, that by the time those candidates come to be eligible for high situations, it generally happens that the Director from whom they received their nomination is no longer a Director.

Those circumstances that you have stated have reference solely to the appointment and promotion of civil servants. Do you see any other circumstance in the working of the Government at home which would recommend it to Parliament for renewal? The great reason, as it seems to me, recommending it for

renewal, is the difficulty, if not impossibility, of forming a system of government which would be likely to work better.

*The late Sir Charles Forbes was not a Director? He was not; but he had a son a Director at one time.*⁴

He took a great deal of interest in the election of Directors? He had great influence in the elections.

Was he not connected with a party which hung together with the view of influencing the election of Directors? I am not aware that he was.

Should you be surprised to hear that Sir Charles Forbes, in the course of his life, had obtained 40 different appointments, and that he had the curiosity to have the likeness taken of every young man for whom he obtained an appointment, and those likenesses were hung round his room? From his long connexion with the Court of Directors, I should not be surprised at his having obtained that number of appointments. Those who were appointed on his recommendation have been as good servants as any others. If it were only from having a son a Director, he might obtain in a number of years almost that number of appointments.

*Have you ever looked at the list of voters for the election of Directors for the purpose of seeing how many gentlemen can obtain a majority of votes?*⁵ I have never examined the list with that particular view.

*Should you be surprised if you found, on looking into it, that 413 gentlemen had 910 votes?*⁶ I should not. That might be the result under any system which gives a plurality of votes on account of the property held.

*Have you looked into the list which has been presented from the India House of the number of persons having more than one vote, and the number of voters and the number of votes? I know that there is a considerable number who have two, three, or four stars opposite to their names. If I am asked whether I think it would be better to give only one vote to each elector, I am inclined to think that it would make no practical difference of any importance. The proprietors are not a body which any one would have selected *à priori* for the election of Directors. Any other body whatever of respectable men would be as likely to elect proper persons as this, and this as likely as any other. As you cannot constitute an elective body in this country identified with the interests of the people of India, it does not appear to me to matter much what the body is.*

⁴Charles Forbes (1774-1849), an active member of the Court of Proprietors of the East India Company, had been head of Forbes and Co. in Bombay, and Tory M.P. 1812-32; his son (who died in 1840) was John Forbes (see n2 above).

⁵The relevant figures are given in "Return (in Part) to an Order of the House of Lords, dated 29th April 1852, Relative to the Affairs of the East India Company," *Sessional Papers of the House of Lords*, 1852, XI, 264.

⁶Of the 413, 311 had two votes, 60 had three, and 42 had four, for a total of 970, rather than 910 (*ibid.*).

Need the present body be identified with the interests of India, looking to what the qualification of the elector is beyond this, that it is their interest to see that the interest of the debt is paid? That is the only interest they have in India.

Do you think that the existence of the proprietors as an elective body has the effect of distributing more widely the patronage of the Court of Directors who now distribute it, than if such proprietary body did not exist, and had no claim upon the distribution? I cannot answer that question; I am ignorant what proportion of the patronage of India goes to the proprietors; and whatever the proportion may be, some considerable part of it would go into the same channels if no such body as the proprietors existed.

The more limited the number of persons who distribute the patronage, and the more limited the claims upon them, the more likely that patronage would be to pass in narrow channels connected with the individuals who gave it? It seems to me the primary and essential object that appointments in India should not be held by persons who have Parliamentary and political influence at home, that being the source from which inducements to make bad appointments, or to sanction bad measures, are most likely to come.

What is there in the constitution of the present Court of Proprietors which prevents any political party in this country from becoming proprietors, and, therefore, electors of the Court of Directors? There is nothing to prevent it; but it has not been the fact, and it is not likely to be the fact.

Is there any necessary connexion between the possession of a certain amount of stock, which gives a vote to the party holding it, and interest in the good government of India; and do you think that it would be desirable to introduce some more direct connexion with India on the part of the electors? I think there is a good deal to be said both for and against any such proposition.

Will you have the goodness to state what the arguments are for and against it? If the question were put with reference to some particular proposition, I might be able to answer more satisfactorily.

Is it your opinion that it would be desirable to allow the holders of the debt in India to vote for the Directors, or to give a right of voting to the Company's servants? I think the constitution of the body of proprietors is of less importance than almost any other question connected with the Government of India; but the main fault of the present system is the long and troublesome canvass which is necessary to enable any person to be appointed a Director; and if there were an increase of the constituency, it is a question whether it would tend to make this canvass a greater or a less burden; it might do either the one or the other.

What objection should you have to Mr. Wynne's proposal,⁷ that the Crown

⁷Charles Watkin Williams Wynn (1775-1850), M.P. 1797-1850, long-time Member of the Board of Control, and its President 1822-28, Speech on the East-India Company's Charter (13 June, 1833), *PD*, 3rd ser., Vol. XVIII, cols. 741-51, esp. 744.

should have the power of appointing Indian servants as Directors on their return from India to this country? I think the fact that all Indian proceedings are reviewed by two separate bodies, independent of one another, is a much greater security for good government than would exist under any system by which those two bodies were merged into one. The double revision by persons of a different class, in a different position, and probably with different prepossessions, tends greatly to promote a close and rigid examination.

Do you suppose that the present system operates as a sufficient check upon the President of the Board of Control? To judge of the present system, it must be compared with some other. If we compare it with the system of an Indian Minister, who should have both the initiation and the final decision, he would act under a much less check than he now does. The Court of Directors, who are the initiating body, not being the body which finally decides; not being able to act but by the concurrence of a second authority, and having no means of causing their opinion to be adopted by that authority, except the strength of their reasons, there is much greater probability that a body so situated will examine and weigh carefully the grounds of all proceedings, than if the same body which had the initiative gave the final order.

On the whole, you conceive that the Court of Directors are the best administrative body that could be found under the peculiar circumstances of the Government of India? I would not pretend to say that no better could be found; but it seems to me they are as good a body as there is any probability of obtaining. Not having the final power, all the power which they exercise depends upon the care which they bestow upon the examination and consideration of the matters committed to them.

Are you acquainted yourself with the details of the correspondence between the Court of Directors and the Board of Control; can you trace a letter from the moment when it originates, to its final arrival before the Board of Control, or does your position enable you to know anything about it? In most cases it does.

With whom does the letter originate? With the Chairman.

Nominally and officially it originates with the Chairman; but does the Chairman, in fact, give instructions for writing the letter? That depends upon circumstances. There is a vast mass of ordinary business respecting which the Chairman neither feels called upon to give previous instructions, nor do those who have the care of the department think it necessary to ask for them.

In point of fact, does it not frequently happen that the correspondence is examined by the clerk, or the secretary, and he suggests what the reply shall be? Sometimes so, and sometimes not. In the course of business, the papers come first into the hands of the secretary or clerk, or the person who is in charge of the correspondence; it is his duty, in bringing those papers to the notice of the Chairman, to be able to answer all questions concerning them, and it is expected of him that he shall have formed an opinion upon the subject.

It is expected that he shall suggest what the answer shall be? It is not expected; but he is always at liberty to do so.

Is it not the practice? It is not the practice universally; it is the practice in ordinary matters.

Is it the general practice? There is no general practice. It is usual for the person in charge of the correspondence to ask the previous instructions of the Chairman, when he thinks there is any doubt of what the opinions of the Chairman would be.

Does he not write a memorandum first of all of the facts? That is sometimes done in complicated and important cases.

Is it not done universally; is not the substance of the papers in the collection stated in a memorandum, for the convenience of the Chairman; how can he possibly read all the papers himself? It is sometimes stated in the form of a memorandum, and sometimes in that of a proposed letter.

But in all cases the substance, at least, is stated in some manner to the Chairman? Yes.

Together with the opinion of the clerk who makes the statement? With an opinion, or without an opinion. Sometimes the officer who makes the statement thinks it desirable to ask the Chairman's instructions first on the facts merely, without giving any opinion. In some cases again the Chairman does not wait till he has the facts brought before him, but sends for the officer, interrogates him on the facts, and gives instructions for preparing the reply, after calling for whatever papers he thinks necessary to understand it. The modes of proceeding vary according to the degree of importance ascribed to the matter, and according to the degree of interest the Chairman takes in the subject.

Do not they vary according to the business-like habits of the Chairman? They do; but since the last Charter,⁸ it has very seldom happened that the Chairman has not been a man of business.

Is it not a rare circumstance that the view of the Chairman is disregarded? By no means. On subjects on which a difference of opinion can fairly exist, it very often happens.

What is the character of the opinion expressed by the clerk; does it consist in remarks upon the correspondence in the way of censure or approval? Yes.

Do you know any one measure which has originated at home? It is scarcely possible to say where measures really originate. In cases of emergency, such as war, anything done must necessarily depend upon the Governor-general on the spot; and all that can be done by the home authorities is to express an opinion upon it after it is done, which may have an influence on the Government in future cases. But with reference to internal government, I am not aware of any great measures which have been adopted until after there has been a great deal of discussion between the Local Government and the Home Government on the subject; and

⁸I.e., 3 & 4 William IV, c. 85 (1833).

though the measure may have originated nominally with the Government of India, the suggestions may often be traced to instructions which had been given, or principles laid down in despatches sent from the home authorities.

At the distance of many years? The despatches from the India House have in many cases tended greatly to form the opinions of Indian politicians in India.

In the case of the abolition of the 160 duties in the North-western frontier in the year 1843,⁹ did that measure originate here? I am not conversant with the details of the Revenue department, though I am, of course, acquainted with its general principles.

Should you not say that the general government of India proceeds on all great occasions without receiving special instructions from home? I think a case can hardly happen in which the Government of India is not tolerably well aware, from previous despatches, whether the course which is about to be adopted is likely to have the approval of the home authorities. There is hardly any measure adopted of which the general principle might not be found discussed in the previous correspondence.

Do not you know whether the abolition of 160 duties upon the North-western frontier was approved or not? I am not aware whether it was approved at the time, but it was sanctioned.

You spoke of the working of the Government being, considering the difficulties, very satisfactory. Can you point out any of the difficulties to which you allude which would be removable by Parliament? It is difficult to foresee in what way alterations would work. But any alteration which placed the control of the Government in some one authority, instead of leaving it divided between two, would, I think, be for the worse.

Would you carry the same principle into effect in every case; instead of having a single Government, do you think it would be convenient to have a double Government? My opinion, if I were able to form any, would depend upon the nature of the case. I am inclined to think that such a double Government would be useful, wherever it was necessary to have a body of a permanent character specially conversant with a subject not generally studied by politicians in this country, while, at the same time, the general Government of the country must also have a voice.

Would you introduce the system of double Government with reference to the 52 colonies of the Crown? I am not sufficiently acquainted with the Colonial department to be able to express a positive opinion; but I should conceive that there might be great advantage from having some body analogous to the Court of Directors as a Council to assist the Colonial Minister.

⁹Act 14 of 1843, "An Act for Regulating the Levy of Customs Duties, and the Manufacture of Salt in the North-western Provinces of the Presidency of Bengal" (5 Aug., 1843), *PP*, 1845, XXXIV, 111-13.

A Council to represent each colony? It does not follow that there should be a separate body for each colony, any more than that there should be a separate body for each Presidency, or each Zillah, in India.¹⁰

Between Australia and Canada there is no connexion; one permanent body would not be able to advise the Minister of the Crown on Australian and Canadian matters? In Canada and Australia there are local representative bodies perfectly competent to exercise that antagonistic discussion, which seems to me an essential element of good government everywhere; but for India you cannot have any local body which shall produce that result.

Is there not a good deal of antagonistic discussion between the Government of India and the authorities at home; are not the Government of India capable of taking their own part, and giving their reasons for their measures? Certainly; but the discussion between the Government here and the Government there, I apprehend, is not sufficient security where there is nothing else to trust to; where there is no body representing the people of the country, and no body of persons *ex officio* conversant with their interests.

Should you say that the Court of Directors represent the people of India? Certainly not.

Is not their position directly antagonistic to that of the people of India? The antagonism which I contemplated was a discussion between persons who could not be supposed beforehand to be likely to be of the same opinion; discussion, by persons all of one mind, is of no use; where you have not the advantages given by a representative Government of discussion by persons of all partialities, prepossessions and interests, to secure that the subject shall be looked at in many different lights, though you cannot have a perfect substitute for this, still some substitute is better than none. If you can have a body unconnected with the general Government of the country, and containing many persons who have made that department of public affairs the business of their lives, as is the case with the Court of Directors, there is much better discussion and much better sifting of the matters committed to their charge, by having such a body in addition to the Minister of the Crown, than by having the Minister of the Crown without such a body, or the Minister of the Crown acting as Chairman of the body.

¹⁰The three Presidencies of Fort William in Bengal (Calcutta), Madras, and Bombay then formed the leading provincial governments in British India. Established by the end of the seventeenth century, each Presidency government originally consisted of a Governor and Council, with the Governor of Fort William, designated as Governor-General under the Regulating Act of 1773, exercising supervisory powers over the other two Presidencies. Under the Charter Act of 1833 the Governor-General was appointed Governor-General of India with increased powers, while continuing for the time being to act as Governor of the Presidency of the Lower Provinces of Bengal (the Upper Provinces being formed into a separate administration later known as the North-Western Provinces). Within each Presidency the most important unit of administration was the Zillah (Zila) or District, usually headed by an official known as the Collector and Magistrate.

Do you think that if the Court of Directors, in its present form, is to be maintained, advantage would be derived from giving a quasi representative character to the Court of Proprietors, so that their representatives might be more identified in feeling with the people of India? I am not aware how the Court of Proprietors could be so constituted as to be identified with the people of India.

*Could you not give to the Court of Proprietors more knowledge of the affairs of India: it appears, by a Return which has been presented to the Committee, that out of 1,760 persons who vote in the election of Directors, there are but 253 persons who have ever been in the service of the Government?*¹¹ I cannot foresee what would be the effect of making the circumstance of having served a certain time in India a qualification for the Court of Proprietors; but I should think it could not have a bad effect, unless by multiplying the body, and rendering the canvass more onerous than at present; the difficulty of the canvass has prevented some of the most eminent servants of the Company from seeking a place in the Court of Directors.

Might not the Court of Proprietors be so extended in number, as to render a canvass impossible; and might it not be so improved in its composition, as to give the means of knowing the respective qualifications and claims of the several candidates who desired to belong to the Direction, having served in India? It is difficult to say; there is no popular election at present, however public in its character, in which there is not a canvass; and in this case it is probable that the canvass would always continue onerous.

For instance, do you think that the 899 ladies who have votes, exercise a sound discretion in the selection of the individuals, knowing their qualifications and claims? I do not believe any portion of the Court of Proprietors exercise much discretion of that kind; I do not believe that to any great degree the election by the proprietors is determined by public grounds. I believe, however, that those who are influential among the proprietors are sufficiently before the public, and are themselves sufficiently interested in Indian affairs, not to use their influence on behalf of persons who would be considered discreditable. That is the extent to which there is now a security, and I doubt whether more would be obtained under any system, because I do not think there are the means of forming an electoral body sufficiently identified with the interests of India to afford much security for a good choice.

Do you think the English and foreign Jews, who hold a large amount of stock, exercise a sound discretion in the election of Directors, with reference to the good government of India? I have already said that I do not think the elections of the Court of Directors are made on public grounds; they are mainly the result of private influence; but those who possess the influence, exercise it under a sufficiently

¹¹*Sessional Papers of the House of Lords*, 1852, XI, 264, gives the number of voters as 1,765; of these 93 had seen civil and 160 military service in India, for a total of 253.

strong sense of responsibility to the public to prevent them from selecting any person very objectionable. The security at present depends rather on the kind of persons who are candidates, than on the kind who are electors. The candidates being, as a general rule, persons of Indian experience, who wish to keep up their connexion with Indian affairs, that is in itself some evidence of their not being wholly unfit for the station, inasmuch as persons who have gone through the Indian service, and retired from it, are not likely to retain a taste for Indian employment, unless they retain in some degree their fitness for it.

Has the tendency of the elections in the last 20 years of the Court of Proprietors, as at present constituted, been to strengthen the connexion of the Court of Directors with India, or otherwise? Nearly all the Directors chosen since the last renewal of the Charter have been persons who have served in India; but that I attribute not to the constitution of the Court of Proprietors, but to the fact, that since the Company has ceased to be commercial, there are not the same inducements as formerly to the merchants and bankers of London either to hold stock, or to become Directors, and in consequence few such have been elected.

Has not the circumstance of the Company having ceased to trade, and having ceased to transact all the business which was connected with that trade, increased the number of the Directors who take part in the consideration of the general Government of India? Very much so; it has rendered the personal participation of the whole of the 24 Directors in the general business of India much more complete than it was before. Under the former constitution of the Company, the administration of India rested, with the exception of the Chairs, entirely with the Committee of Correspondence, composed of the nine senior Directors, the remainder of the Directors having no voice in that portion of the business of the Court; of course they had a voice in the deliberations of the Court itself; but not having been previously prepared, by examination of papers and discussion in Committee, they had not so much influence, and were, besides, occupied with other things. The Committee of Correspondence, composed of the senior Directors, and, therefore, necessarily including any members of the Court who might be superannuated, were extremely overladen with business, and made a much more cursory examination of the papers than the Committees do now. At present the Government of India being the only business of the Court, it is divided among three Committees, to all of which every Director is eligible, and the consequence is, that every Director takes a more active part than formerly in the consideration of the draft despatches that are laid before them by the Chairs.

Has not one effect of that been that the Chairs have much less authority than they used to have in the Court? I think it has.

Has it not produced, whether for good or evil, a great practical revolution in the system of government; formerly the business having been conducted through the Chairs by a small body of persons who had the cognizance and general transaction of political cases; and now the 24 Directors take part in the discussions? There is

generally a great indisposition to oppose the Chairs; and they are never opposed, except where there is fair ground for a difference of opinion.

Is it not the fact, that in former times, before the commencement of the present Charter Act, when the President of the Board of Control had settled any matter with the Chairs, it was practically a final settlement, and the view taken by the Court was not in fact different from theirs; but now a settlement between the Chairs and the President, by no means brings after it, as a matter of course, the acquiescence of the Court? I am not aware whether or not there is so great a difference as the question seems to contemplate: there is certainly some difference, and there is a much more active part taken by individual Directors than formerly.

Is not that, again, a great practical alteration in the system of Government? I do not think it is a great practical alteration; it is some practical alteration.

So that we have now to consider whether it is expedient to retain a Government very different from that which existed in 1834? I should not say very different; in some degree it is different.

Does not the addition of three-fourths to a cabinet, which is the change that has been made, produce a very great change in the mode in which cases are judged of and discussed; are not cases now judged of and discussed as they would be in a popular assembly? On great questions which are likely to lead to a difference of opinion between the Court of Directors and the Board of Control, I doubt whether there is any difference; because on questions which were interesting to the collective body of the Court, all the Directors would at any time have given their minds to the subject, and the opinion expressed would have been the opinion of the collective body; I think the difference which has been produced is in the details; it happens much more frequently now that the draft despatches submitted by the Chairs undergo alterations of details in Committees, or the Court; but these are seldom of a kind that materially alter the Government of India.

Does not the influence of the Chair depend very much upon the individual Chairman? Yes.

This change goes, to a certain extent, to diminish the value of the previous communications? There still is very great advantage in the previous communications.

*With regard to the active participation taken by the whole body of Directors in the transaction of the business, what is your opinion of that part of the law which requires one-fifth of the Court to go out annually?*¹² I think it makes very little difference for either good or harm; I have no decided opinion about it.

With this active part taken by those 24 gentlemen, might it not happen that, merely on account of rotation, a member connected with a department of public business, for which he was peculiarly qualified, might be obliged to go out, and the Court might be deprived of his aid in the transaction of that business? Yes; but that happens much more seldom than might be supposed, because it is always

¹²The practice was instituted by Sect. 1 of 13 George III, c. 63 (1773).

endeavoured to conclude the business of the year within the year. Subjects are begun at such times that they shall not be under discussion at the time of the renewal of the Directors, as in the case of the Session of Parliament, except that there is no interval, as in that case.

Whatever inconvenience exists in that case, your opinion is that care is taken to diminish that inconvenience? I think so.¹³

* * * * *

Are there any circumstances in the relations between England and India which require that the machinery for the government of India should be differently constituted from that of the other dependencies of Great Britain? I think there are very important differences; principally two. In the first place, India is a peculiar country; the state of society and civilization, the character and habits of the people, and the private and public rights established among them, are totally different from those which are known or recognised in this country; in fact the study of India must be as much a profession in itself as law or medicine. In the other dependencies of Great Britain the people are for the most part English, and whoever is fit to deal with English people here, is fit to deal with them there. But in the case of India, even if a person of the greatest knowledge of the world and the most cultivated mind were sent to be Governor-general, he would still have an apprenticeship to serve. This makes it essential that the administration of India should be carried on by men who have been trained in the subordinate offices, and have studied India as it were professionally. A second consideration, not less important is, that the public of India afford no assistance in their own government. They are not ripe for doing so by means of representative government; they are not even in a condition to make effectual appeals to the people of this country; they cannot even make their circumstances and interests and grievances known and intelligible to people so different and so unacquainted with India as the people, and even the Parliament, of this country. The discussion here of Indian subjects, when there is any, is carried on not by persons representing the people of India, but chiefly by Englishmen who have personal interests or connexions in India, generally almost as ignorant of the people and the interests of India as the English public, and having mostly other objects than the interest of the people of India in view. Since, therefore, the great security for good government—public discussion—does not exist for India, as it exists for this country and for its other dependencies, the only means of ensuring the necessary discussion and collision of opinions is provided within the governing body itself. The British colonies, of which the people are mostly English, and in most of which there are representative bodies composed of English people, have ample means of discussion, and ample means by which, if they think themselves aggrieved by any act of the Government, they can appeal home; and when such an appeal is made, the people of this country, although often extremely ill informed as

¹³The Committee adjourned, to resume at 1 p.m. on the next day.

to colonial matters, are much more capable of judging of them than they are of Indian affairs.

What do you think would be the probable effect of carrying on the government of India like that of the colonies, by means of a Secretary of State for India? I should think it would be the most complete despotism that could possibly exist in a country like this; because there would be no provision for any discussion or deliberation, except that which might take place between the Secretary of State and his subordinates in office, whose advice and opinion he would not be bound to listen to; and who, even if he were, would not be responsible for the advice or opinion that they might give.

How could it be a despotism when Parliament would have the control of the conduct of the Secretary of State? Undoubtedly Parliament would have the control; but Parliament not having sufficient knowledge of India and its people, would exercise its control with very imperfect information; and it seems to me of the utmost importance to make provision in the constitution of the Government itself, for compelling those who have the governing power, to listen to, and take into consideration, the opinions of persons who, from their position and their previous life, have made a study of Indian subjects, and acquired experience in them.

But though Parliament might be imperfectly informed, Parliament would not think it was imperfectly informed? That would be one of the evils I should apprehend.

Would it be possible for Parliament to have sufficient cognizance of the facts connected with the administration of the Secretary of State for India, to enable them to act as a check upon his administration? It cannot be said that Parliament and publicity are no check; but I think they are a very insufficient one.

Would it be possible to give such publicity as would enable them to act as a check? It would be possible to give any degree of publicity; but it would not be possible to secure the requisite interest in the subject, or the requisite instruction.

Do you think that, under such a system of Government, the continual change of policy, which would be likely to take place, arising from the change of parties, would be fatal to the Government of India? It would be a great evil if it really happened; possibly, however, it might not happen, and the Government of India might continue to be carried on in much the same way under all parties; but there would not be the same security for this which there is at present. I conceive that there would be two great inconveniences: in ordinary cases there would be apathy and indifference on the part of Parliament and the public; the Secretary of State for India would be able to do exactly as he liked, and to omit any part of his duty if he were too indolent or too ignorant to perform it; but whenever it did happen that interest was excited in Indian questions, they would become party questions; and India would be made (which I should regard as a great calamity) a subject for discussions, of which the real object would be to effect a change in the administration of the Government of England.

Why do you think that greater apathy would exist upon questions relative to the interests of India, than upon questions relating to the interests of the colonies? Because the colonies have the means of making their grievances heard; the colonies are much more closely connected with England; there are many more English people who have interests there; and there are also in the colonies local popular bodies, which is of itself a very great check, independently of any check afforded by Parliament. If there were a possibility at present of establishing a similar check in India, by any form of local representative government, I should think the constitution of the organ of Government in England much less important; but at present the only security for the good government of India is in constituting the Government here with as little imperfection as possible.

Do you think it would be possible to recognise any body in India which should be competent to express an opinion upon measures relating to that country? I do not think that India has yet attained such a degree of civilization and improvement as to be ripe for anything like a representative system. It would certainly be possible for the Government to take natives into its counsels much more than at present; but this I think would be better done by cultivating a greater degree of intercourse between intelligent natives and the members of the Government, or the holders of public offices, rather than by forming a body of persons selected by the Government and considering them as the representatives of the people of India, who, probably for the very reason of their being selected by the Government, would not be inclined to recognise them as their representatives.

It has been stated by some witnesses, that great advantage has resulted in India from the preliminary promulgation of proposed laws, which has had the effect of eliciting opinions from the natives, so as to enable the Government to form an opinion whether the law might be advantageously carried into effect or not;¹⁴ do you think that is a useful practice? I have no doubt that it has been a very useful and indeed a necessary practice. The Court of Directors, in the instructions issued after the last renewal of the charter, pointed out that, in the absence of the security against precipitate legislation derived from public discussion by a numerous body like the Legislature of this country, it was necessary to make some other provision for deliberation and previous information; and therefore to interpose a certain delay between the first proposing and the passing of any Act, and to invite, in every way in which it could conveniently be done, suggestions and information in the meanwhile.¹⁵

¹⁴See the evidence of William Wilberforce Bird and of James Cosmo Melvill (1792-1861), Secretary to the East India Company 1836-58, *PP*, 1852-53, XXX, 95-124 (esp. 98), and 7-72 (esp. 68).

¹⁵See "Dispatch Accompanying the Government of India Act, 1833 (3 & 4 William IV, c. 85), No. 44 (10 Dec., 1834)," printed in Courtenay Peregrine Ilbert, *The Government of India* (Oxford: Clarendon Press, 1898), pp. 492-532, esp. 493-4 (Sects. 4-5) and 497-8 (Sects. 15-16). Attributed to James Mill by tradition in the East India House.

What are the advantages of the division of the home Government of India into two distinct bodies, the Court of Directors and the Board of Control? It affords, I think, a great additional security for discussion and consideration. By rendering the consent of two distinct authorities necessary, you, in the first place, secure discussion between those two. The initiative being given to one body and a veto to the other, and the body over which the veto can be exercised, having in reality no substantial power, except that which it derives from the force of its reasons, it is under very strong inducements to put reason on its side if it can. If the despatches which originate with the Court of Directors are not well grounded in reason, they carry no weight with the Board. The Court of Directors does not and cannot exercise any effective share in the government except in so far as it takes care to have reason on its side. Having this instrument of power and no other, it has the strongest motive to use that instrument to the utmost; and in doing so, it is a most efficient check upon the body which has the ultimate power, because that body being sure to have all subjects brought before it, with the result of the full consideration and concentrated judgment of a body which, from its constitution, has commonly that special knowledge and information which the President of the Board of Control in general has not, the President is under great inducement not to set aside the judgment of this comparatively well-informed body, unless he can give as strong or stronger reasons on the contrary side.

Is it not the case, that even in addition to the ordinary forms of conference and communication between the Chairs, as they are called, and the President of the Board, if there should be any difference between them, the President has the power of consulting the other members of the Court, and frequently does so through the Chairs, and in fact has recourse to any documents which the Chairs may have in their power to lay before him, so as to strengthen the view which they have put before the President? The President can call upon the Chairs to produce any papers upon the subject which they may have omitted to bring before him.

Is it not the case, that independently of the legal power of the President, where different communications have taken place between the President and the Chairs, they are in the habit of laying before him any additional documents which they think will strengthen the views which they have put before the President? Yes, and of discussing all subjects on which there is any difference of opinion.

Is not the Court of Directors specially interested in appointing the very ablest officials? They are; and they exert themselves to obtain the ablest persons they can to conduct the correspondence under them. Their position gives them a very strong interest in doing this, since they can only expect that their draft despatches will be adopted by the Board of Control, if they are such as to carry the weight of reason and knowledge with them.

Would the same benefits be realized, in your opinion, if India were to be governed by the two bodies merged into one, and by endeavouring to form a single body which should unite the advantages of both, such as a Council of India, pre-

sided over by a Minister of the Crown? I think that such a system would be far preferable to a Government merely by a Secretary of State; but that the advantages now derived from the division of the governing body into two parts, the one having the initiative and the other the ultimate control, would not be obtained under the system of a Minister and Council. In the first place, there is now not only an examination by two authorities, but successive examinations by two sets of competent subordinates. If the body were but one, there would be only one set of subordinates; and that is not a trifling consideration, but in practice a very important one. In the next place, if the Minister of the Crown were President of the co-ordinate body, whether it were called the Court of Directors or Council of India, he would have, not as at present substantially a mere veto, but substantially the initiative, as the Chairman now has; and in that case the Council would not be under anything like the same responsibility, and would not exercise anything like the same power that the Court of Directors do. When the Council are obliged to consider the subject first, and to make up their minds upon it, and to write, or cause to be written, the strongest justification they can make of their opinion, the mind of this body is much more effectually applied to the subject, and a much more painstaking and conscientious decision is likely to be arrived at by them, than if they were only considered as the advisers of, or as a check upon another initiating authority. Of course, under the system suggested in the question, it cannot be meant that the power of decision should rest in the Minister and his Council jointly. The ultimate decision would rest with the Minister only, and his Council would be merely a Council. Now, when the Minister had thus both the ultimate power of decision and the initiative, it seems to me that the functions of the Council would be reduced to comparative insignificance, and there would be great danger of their becoming nominal.

If the plan suggested in the last question were adopted, would not the Government of necessity cease to be a double Government, and be a single Government, consisting of combined parts, which from their nature and their functions would be liable to constant collision? They are now liable to collision; but any prolonged conflict is provided against by giving to one of the two authorities—the Minister of the Crown—the ultimate deciding power: and I imagine that in any new system that could be proposed, this provision would be adhered to.

Although there is a liability at present to come into collision, is not that collision, and are not the consequences of such collision, better guarded against by the present system than they would be by that proposed? I conceive that under the alteration proposed, the specially instructed body would not have power enough; in the first place, because the initiative would fall habitually into the hands of the President, and consequently the members of the Council would not be under nearly such strong inducements as the Court of Directors are to form a careful opinion, and to stand up for it. In the next place, they would not be nearly so much

in the public eye. The Court of Directors are at present the ostensible Government of India; they reap a very large proportion of the credit of good government, and of the discredit of bad; and it seems to me of great importance that they should still do so; because that is what places them, with no instrument in their hands but reason, under such strong inducements to employ that instrument to the utmost.

In fact you consider that the present system is a very convenient fiction? I do not think it is fairly described as a fiction, since it is acknowledged, that not only the Board of Control but the Cabinet, when of a different opinion, sometimes think it right to defer to the opinion of the Court of Directors: no doubt because they feel that the Directors are more competent to form an opinion than themselves. As the Court of Directors can have no power but what they derive from that belief, it is greatly for their interest that the belief should be justified.

Is it a fiction to say that the Government of India resides in the Court of Directors? It is practically by no means a fiction, since it does not happen once in a hundred times that a despatch, prepared by the Court of Directors, undergoes alteration in principle and substance by the Board of Control. It is true that this is in a great measure to be accounted for by the constant communication kept up between the Chairs and the President; so that, unless the Chairs are anxious to have a contest with the Board, in order to place on record an important difference of opinion, they seldom send up a proposed despatch which they know is contrary to the President's opinion, and therefore will not pass. Still, however, in practice, the preparation of despatches rests substantially with the Court of Directors, and not with the Board of Control.

You think it is not fairly to be called a fiction; but do you not think that the general notion which people have of their power attributes to them much greater power than they really have? Undoubtedly the habit of speaking of the Court of Directors as the Government of India, causes the controlling power exercised over them to be very much lost sight of, and causes much less of the moral responsibility of the Government of India to rest upon the Minister of the Crown than is really his fair share. But even this has its advantages, because it brings the feeling of responsibility to bear more strongly upon those who possess the requisite knowledge, and whose examination is much more effectual than any examination that can be exercised by persons less acquainted with the subject. It therefore seems to me important that the Court should not be led to consider themselves, or be considered by the public and by the people of India, as a subordinate, but as a co-ordinate authority.

Do they not, under the power they have of initiating all despatches, virtually exercise a principal part in the general administration of the Government of India? In as far as that can be said of the home Government at all, I think they do. I think that those who deliberately consider all subjects in the first instance, recording their opinion, and who do this in such a manner, that in a great majority of cases

their opinion is adopted by the controlling power, have a full share, and virtually the largest share in the administration.

Do not they practically furnish the knowledge by which the Government of India is conducted? They furnish much more than the Board of Control.

Is it not the fact that the Board of Control furnish none? The Board of Control furnish none but the knowledge which their officers have acquired by experience in the office.

What means of resistance, on the part of the Court of Directors, have the Legislature provided, for preventing the Board of Control from usurping the entire power, and reducing the Court of Directors to a nullity? The main security is, that the Board of Control cannot themselves initiate any instructions to India (except in the Secret Department, which is limited by law to matters of war and negotiation) unless by calling upon the Court to do so; it is only if the Court fail to do so within a certain time, that the Board of Control can initiate a despatch, and compel the Court to send it out; and this shows that it was the intention of the Legislature, that the Board should be a controlling rather than an originating power.

Have not the Court of Directors a further power, by having a virtual veto upon the nomination of the Governor-general by the Crown? They have; and I may say, on that subject, that I think the present mode of appointing the Governor-general, namely, by the Court of Directors ostensibly, but with the approbation of the Crown, is the only means by which the Court of Directors could obtain so much as a veto; everybody is aware that the Crown really appoints the Governor-general; but if the Crown were ostensibly to do so, if the nomination were to vest in the Crown, then, even if a veto were nominally given to the Court of Directors, they would not have a real veto. To refuse their sanction to an appointment once made, would appear to them so strong a measure, that it must be a very bad appointment indeed, much worse than is likely to happen, which they would feel called upon so to resist; whereas, by making it in legal form necessary that they should initiate the appointment, you do not secure to them, what I think it is not desirable that they should have, the real appointment, but you give them a real veto; you prevent the Crown from being able to force upon them any Governor-general to whom they have a decided objection. I think that a very important power.

Do you think it is as important, for the maintenance of their authority, that they should have the power of recall? I think it is proper and necessary.

Are there not circumstances under which the nomination of the Governor-general will fall to the Crown? If the Court of Directors make no appointment within two months.

Would it be desirable to place modifications of the same nature upon the power of recall; that is to say, by requiring certain notice of the intention of the Court to exercise the power? I see no particular advantage in that; because it is not to be supposed that the Directors would seriously contemplate a recall, unless they

intended to persevere in it; it is not probable that they would raise the question unless their opinion was thoroughly made up.

*Have you ever referred to what took place between the Government and the Court of Directors in the time of Lord Wellesley?*¹⁶ I have no particular recollection of the history of those transactions.

Have you ever referred to it? I have.

Are you under the impression that the Court of Directors never wished to recall Lord Wellesley? I am under the impression that they did wish, but not so strongly as to take a measure which they knew would be extremely disagreeable to the Government of the time.

*It was rather a strong Government, that of Mr. Pitt, at that time, was it not?*¹⁷ It was.

Is not there a further power of resistance on the part of the Court of Directors, by refusing to send out a certain despatch, and compelling the Board of Control to appeal to public opinion in open court, and forcing them by means of a mandamus in the Court of Queen's Bench? That is only the power which anybody possesses of compelling discussion by resisting a legal authority. The Court would no doubt never think themselves justified in resorting to such an extremity, unless they had such strong conscientious objections to the thing proposed, as to outweigh the objection to refusing obedience to a lawful order.

Do you recollect any instance in which that remedy has been resorted to by the Court? I remember one instance,¹⁸ and I think there have been two within my recollection.

In which it was successfully exercised? In one of the cases it was successfully exercised; I am not certain about the second.

Does the Court of Directors ever resist by avoiding to form a sufficient quorum to sign a despatch? The Court have no occasion to avoid forming a quorum; because no individual can be forced to sign, even if there is quorum, unless by process of law. In one of the cases mentioned, several of the Directors were fully prepared to go to prison, rather than sign an order which they thought grossly unjust.

Was that resistance successful? It was.

¹⁶Richard Colley Wellesley (1760-1842), Marquess Wellesley, was Governor-General 1798-1805. His advocacy of freer trade between India and Britain and his educational projects brought him into repeated conflict with the Court of Directors.

¹⁷William Pitt (1759-1806) was Prime Minister 1783-1801 and 1804-06; his government was especially strong during the wars with France following the French Revolution.

¹⁸When in 1832 the King of Oudh was pressed by money-lenders, the Board of Control obtained a *mandamus* from the Court of King's Bench to compel the Court of Directors to send a despatch insisting that the debts be repaid, but in the face of the Directors' continued opposition, the Board did not persist. Mill refers to the matter in his "India Bill, I" (July 1853), *CW*, Vol. XXIV, p. 1191.

Have not the Directors the power of appealing to the Court of Proprietors, and producing such documents as they may think necessary for instructing the public mind, and thus communicating a knowledge of those measures of which they disapprove, without at the same time appealing to party prejudices, as would be the case were that appeal made to the House of Commons? No doubt the Court of Proprietors afford means of publicity, but not greater than would be obtained by a motion for papers in the House of Commons.

Would not there be this disadvantage in a motion for papers in the House of Commons, that they must act through some party, and the question would at once assume a party character? There are usually members of the Court of Directors in the House of Commons, any one of whom can move for papers.

Would it not be a great disadvantage if Indian matters were made the subject of party conflict? It is necessary that the last resort of an appeal to Parliament should be open; but I have already remarked, that I think the security which that affords for good government is not great, because there is generally no interest in the subject, unless it can be made a party subject; and if it be made a party subject, it is in danger of being decided by party interests.

Then do you consider it to be just advantageous for the Directors to appeal to the House of Commons, as to appeal to the Court of Proprietors? I do not think the appeal to the Court of Proprietors is of any value except as an instrument of publicity. It is plain that they might have a perfect power of publicity given to them, without appealing either to the Court of Proprietors or to Parliament.

How? They might have the liberty of printing and producing papers, and it might be in their power to lay papers before Parliament.

Have they not that power at present? Only if they are moved for.

If papers were moved for in Parliament, would not a conflict most probably arise upon the subject of those papers? It might, certainly, although papers are very often moved for with no such intention, and with no such effect.

Is it in your opinion desirable that the Court of Proprietors should have the power of calling for papers under the present constitution of the Government of India? I think anything which leads to the production of papers or to the discussion of any questionable matter, is always useful, although I do not think the discussions in the Court of Proprietors afford much advantage in the way of good government. They occur rarely, and when they do occur the matter is commonly discussed without much knowledge of the subject, and commonly from other interests than those of the people of India.

Have the Court of Proprietors at the present moment any interest in the prosperity of the people of India further than as it may be connected with their dividends? None whatever.

Is not it desirable that they should have the power to call in question the actions of the Court of Directors and of the Government of India? The Court of Proprietors is a mere public meeting, at which persons of a particular class are admitted to

speak and vote, and I think any public discussion on a public subject has the chance of doing more good than harm.

Would it, in your opinion, be desirable that the papers and correspondence of the Secret Committee should be laid before the Court of Proprietors? There are many transactions of Government, and particularly those of war and diplomacy (the peculiar functions of the Secret Committee), which until the transactions are completed never are, and generally cannot be, consistently with the public interest, laid before the public.

That is an exception to the general benefit which you propose to be derived from public discussion? Yes; but in European matters it is usual to give publicity even to this class of transactions after the emergency has ceased; and this is equally advantageous in Indian affairs. In fact it is usually done; for it hardly ever happens that the papers relating to Indian wars and treaties are not published almost as soon as they conveniently can be.

That is, through the medium of Parliament? Yes, generally.

When those secret papers are ultimately laid before the Court of Directors, are they not laid in extenso? Sometimes.

Not always? Not always.

Sometimes important papers relating to a transaction are withheld altogether, are they not? Sometimes.

What advantage is derived from the power of the Court of Proprietors to call for any papers? It sometimes causes papers to be made public sooner than they otherwise would be, or which, perhaps, might not have been made public at all; but the papers might have been called for by Parliament, if they had not been called for by the Court of Proprietors.

Does not it give to the Court of Directors the power of giving to the world any papers that they may wish to be circulated? No doubt it does.

In that way is it not very useful to the Court of Directors, whenever they wish to make an appeal to public opinion? I think it might be useful. It certainly affords them the means of doing so without the imputation of wishing to make a party opposition to the Government.

In point of fact, is not it their great object in general to avoid the production of such papers? I think there is no unwillingness whatever on their part to produce papers.

Do not the Court of Directors generally try to check such a motion on the part of the Court of Proprietors? Not at all, as far as I have observed, unless the papers relate to transactions still under consideration. In that case, as in similar cases in Parliament, it is often thought desirable that the papers should not be produced till the final decision of the public authorities has been come to.

That is in all pending negotiations? There is often an indisposition to give papers as long as the subject is under consideration; but when a decision has been passed, and the transaction completed, I am not aware that there is ever any

objection made to lay the papers before the Proprietors, if the Proprietors desire to have them.

What is the usual number of persons attending a Court of Proprietors? The quarterly courts are commonly not very numerously attended, being mostly for routine business, unless notice has been given of some motion which excites general interest; but special courts I have known very numerously attended.

When you say "very numerously," what number of persons do you mean? I do not know that I ever counted the number, but I think I must have seen as many as 200 or more.

But usually it is a very small number? Perhaps at quarterly courts there may not be more than 50 or 60; and sometimes a discussion has been kept up when there were (exclusive of the Directors) not more than eight or ten Proprietors in the room.

Are those discussions generally conducted by persons who have an Indian reputation, and who have been connected with the service in India, or by gentlemen who appear to have bought their qualification for the purpose of giving them an opportunity of making speeches and having them reported? There are marked instances of both.

Is not the latter the more common case? I should say, I think, that when motions have been brought forward hostile to the proceedings of the Government of India, they have been oftener by persons who had been previously connected with India, than by persons whose connexion with India Stock may be supposed to have been formed for that purpose.

Assuming that two such bodies as the Court of Directors and the Board of Control ought to exist, is it, in your opinion, desirable that the patronage of India should reside in the body which is inferior in authority? As between the two, it is in the Court of Directors, the weaker body, that I think the patronage should reside, for the reasons which I have already given. It seems to me very important, and at the same time difficult, that a body, every act of whom connected with the Government of India may be overruled, should nevertheless feel themselves, and be felt by others, to have a very important part in the Government, and a very important share of the responsibility of good or bad government. I do not see how they could keep their position, or be considered as the Government of India at all, if the patronage of India, such as it is, that is, the appointment of youths to rise through the lower to the higher offices, were taken away from them to be given to the other authority. If the authority which had the patronage were that which gives the final orders, the Board of Control would be considered as the Government, and the Court of Directors would have no influence at all.

Would there not also be a danger in that case that the appointments would have a political character, which you consider it so extremely desirable to avoid? That is also a very strong objection to vesting the patronage in the Minister of the Crown.

If the patronage were withdrawn from the Court, in what way should it be disposed of, in your opinion? I think in that case the only proper system, and one which I should myself consider as intrinsically the best, would be to bestow it by public competition; by *concours*, as some offices are given in France; to give it to the best qualified among all persons of requisite age and education who might compete for it.

By public examination? By public examination.

By the sale of commissions, or without sale? Certainly not by sale.

If you had such competition as that, you could not have only one Board of Examiners for so many different classes of offices, amounting sometimes to 400 or 500 to be given in one year; but it would be necessary that you should have different Boards of Examiners; and in that way persons rejected by one Board might be admitted by another. Would there not be great danger of not getting the best men by that process? No doubt such a Board might make mistakes; but probably not more than are made, for instance, in the classification of candidates for honours at the Universities, which is generally supposed to be conducted very fairly.

But there it is done by a single Board; but you could not bring 400 or 500 gentlemen before the same Board, and bring them all into one place? Not at one time; but I see no impossibility in even a larger number being examined by the same Board in the course of a year.

This is not a change which you suggest, but you think it would be the best system if any change were made? If there were a change I think that would be the best change, and I think it desirable in itself if it could be done without interfering with the position of the Court of Directors, or of some body similar to them, as a substantive part of the Indian Government.

Do you think it would be desirable to give any portion of the existing patronage to be competed for in the way you have described? I think the more the better.

Supposing it to be considered best to keep the patronage in the hands of the Court of Directors, do you think it would be desirable to set off any portion of that patronage to be competed for in the way you have described? I am not prepared to give a decided opinion. There would be advantages, perhaps preponderating ones, in such an arrangement, provided the Court of Directors retained sufficient patronage to make them be still considered substantially the Government of India.

When you speak of competition, do you mean a bonâ fide public competition open to all the world, or would you require any particular qualifications or previous course of education on the part of the candidates? I would admit persons to compete in whatever manner they had been educated, and at whatever place.

And in whatever condition of life they might be? And in whatever condition of life.

By whom and in what manner is it desirable, in your opinion, that the Governor-general should be appointed? I think the present mode unobjection-

able. I think that the Governor-general should be nominated, as he is, by the Crown, and not by the Court of Directors, but subject to a substantial negative voice on their part. It is a great security against jobbing in India, that appointments to office are not made by the same persons who appoint the candidates. They are made by a great officer who has no previous connexion, or a very slight one, with the service, and is scarcely under any private motive to favour individuals; and I believe that in consequence the appointments are generally made with a remarkable degree of integrity and purity.

Would you think it inexpedient to appoint the Lieutenant-governors of Bombay and Madras from the civil service; and would you consider it more expedient that they should continue to be appointed by the Crown in the same manner in which you think it desirable that the Governor-general should be appointed? That is part of the question what should be the constitution of the subordinate governments. There are at present two systems of subordinate government on trial in India: the old system of a Governor in Council at each Presidency, and the system now on trial at Agra of a Lieutenant-governor.¹⁹ There is hardly experience yet to judge which of those systems ought to be finally adopted.

But as long as you continued to leave a considerable amount of patronage at the disposal of those Governments at the different Presidencies, do you think it would be expedient to select the Governors out of the civil service of the Company? I think they should be selected by the Crown as long as the present Governments of Bombay and Madras are continued. It does not follow that civil or military servants of the Company may not be appointed; in fact, a large proportion of the governors of Madras and Bombay have been servants of the Company, though appointed by the Crown, and they have been some of the very best.

Are there any special reasons for maintaining an exclusive body, such as the civil service of India, from whom all the higher offices in the administration of the Government, except the heads of the different Governments must be selected? What is to be said in favour of an exclusive service, is the necessity of special professional training: the necessity that those appointed to higher situations should have served in the lower, and should have risen by degrees. In fact, there is no other mode of training properly qualified officers. To take a person fresh from Europe, and appoint him to one of the higher situations, would be as objectionable as taking a person from the army, or from a merchant's counting-house, and making him at once a Judge of the Court of Queen's Bench.

Do you think that civil offices should be thrown open to Europeans not in the regular service; that is, to uncovenanted servants? As a general rule, I think not; Europeans not in the regular service can hardly be competently qualified. The maintenance of a sort of professional body called the Civil Service, is

¹⁹By 5 & 6 William IV, c. 52 (1835) the North-West Provinces were established as a Sub-Presidency, at Agra, under a Lieutenant-Governor, subordinate to the Governor-General at Bengal.

recommended by the necessity of a training in the subordinate offices, and if persons are often appointed who have not gone through that training, the object is sacrificed. In fact, the appointment of Europeans not in the regular service, unless quite exceptional, would be tantamount to giving up the principle of sending out young men as candidates, instead of sending persons out to fill particular offices.

*Do you happen to be acquainted with the services of the late Mr. Greenlaw, who was an uncovenanted servant, and who died in the year 1844?*²⁰ I know his name, but I am not particularly acquainted with his services. He held an office to which uncovenanted servants have not usually been appointed.

Are you aware that he was a man of very great ability, and of very eminent public service? I believe he was.

To what grade in the service can uncovenanted servants rise? I am not aware how much of the restriction upon their employment is the effect of law, and how much only of practice, nor am I aware how far the exclusion in practice extends, especially as it has of late been in many instances relaxed; but generally speaking, the European uncovenanted servants are not eligible to anything beyond what would be here considered as clerkships, not to offices of importance and authority.

Not to judgeships? Certainly not; the natives are very largely eligible to judicial offices.

Do you think that the indiscriminate admission of uncovenanted Europeans to civil appointments would interfere very much with the employment of the natives? Very much.

Would it not be liable to this further objection, that the Governor-general would have the selection, as well as the promotion of Europeans in office? I presume that if uncovenanted servants were appointed at first to inferior situations, they would usually be in the first instance selected by heads of offices, rather than by the Governor-general.

Have you ever considered the expediency of filling the subordinate offices in the Foreign Department, with trustworthy Europeans? I presume clerkships are meant; undoubtedly it is of very great importance that the officers so employed should be trustworthy. I believe there is no restriction on the employment either of Europeans, half-caste, or natives to those offices; their qualifications depend upon the care taken by heads of offices in selecting them.

Was it not necessary on one occasion to make almost a clearance of the persons employed? I have no such instance in my recollection, but I cannot say that it was not so.

Are high civil offices thrown open to Europeans in the military service? Many high offices are so; I think the distinction which is made is a very just one; the offices to which military servants are not, except in very rare cases, appointed, are

²⁰Charles Beckett Greenlaw (1784-1844), Secretary to the Bengal Marine Board at Calcutta from 1829 to 1844, and a well-known advocate of steam navigation.

those connected with the administration of the existing somewhat elaborate system of Regulations, for which a person is incompetent, unless he has in the subordinate offices acquired a technical and precise knowledge of the system. But in all offices which do not require this, military men are now largely employed; they are very much employed in the Political, that is, the Diplomatic Department, and also in the civil administration of countries which have not been brought regularly under our laws; and when a territory is newly acquired, and it is necessary rather to ascertain the existing state of the country, and improvise rules for its temporary management, or to frame a system for the future administration of such countries, than to administer a previously existing system; then military men of known ability are very commonly selected, as is the case at present in the Punjab, where the President of the Board of Administration, Sir Henry Lawrence, is a military man, and as was the case with Sir Thomas Munro, and many others.²¹ Very large use is thus made of military men with talents for civil administration; I have known instances of their being even made Collectors in the Regulation provinces; but those cases are rare, and I believe the motive to them was, that there were not at the time a sufficient number of civil servants in the Bombay Presidency. At that time Sir Henry Pottinger, Major Barnewall, and Colonel Robertson were made Collectors.²² Generally speaking, the situations to which military men are not appointed, are those which require a previously acquired special knowledge of the existing Regulations, and the existing modes of administration.

Would you admit the natives of India to the covenanted civil service? I think it of the greatest importance to admit the natives to all situations for which they are fit; and as they are constantly becoming fit for higher situations, I think that they should be admitted to them; but it would probably be better to do this without appointing them to the regular service. The covenanted service, from its constitution, is a service of gradual rise. A member of that service is not appointed to a particular situation to remain in it during his whole period of service, but looks for promotion after a certain time, and hopes to rise to the highest appointments; therefore, as long as the natives are not considered fit for the highest appointments, it would be hardly desirable to admit them to the regular covenanted service,

²¹Henry Montgomery Lawrence (1806-57), who had served with distinction in the Kabul campaign and the Sikh wars, was the President of the Board of Administration in the Punjab 1849-53. Thomas Munro (1761-1827), after service in the first Mahratta war, spent some years in civil administration, and after further military and civil service, was Governor of Madras 1820-27.

²²Henry Pottinger (1789-1856), who served during the Mahratta wars, became Collector at Ahmadnagar (and eventually Governor of Madras); Robert Barnewall (d. 1848), who rose to the rank of Lieutenant-Colonel in the Bombay Army in 1831, was Assistant Collector of the Eastern Zillah north of Mahi in 1819, and Political Agent in Kathiawar from 1821 to 1832; Archibald Robertson (d. 1847), after an Indian military career beginning in 1800, became Collector of the Eastern Zillah north of Mahi in 1817, Collector of Khandesh 1823-26, and, after his return to England, a Director of the East India Company from 1840.

because, if their promotion stopped short while that of others went on, it would be more invidious than keeping them out altogether. It seems preferable that the covenanted service should not be considered as having an exclusive right to appointments. If a native, being qualified in point of integrity, and having, as many of them have, a previous knowledge of that which a European has to learn, is fit for one of the higher appointments, let him have it without going through the covenanted service.

*Is not a native rendered eligible for any appointment under the last Charter Act?*²³ The last Charter Act took away all legal disabilities; but there is a practical exclusion, and so there must be, until the natives are very much improved in character.

But legally a native of India is eligible for any appointment? He is.

*He is not excluded because he is a native of India, but he is excluded because he has not passed through Haileybury?*²⁴ That would exclude him from the covenanted civil service.

Do you think that the natives of India are admitted to as large a share in the civil government of the country as they ought in their present state of education and knowledge to possess? There is a great and growing desire to admit them to all offices for which they are considered sufficiently qualified in point of trustworthiness. Hitherto they have not been admitted to any situations in which there is not a controlling European authority over them; but there is hardly any situation, admitting of that control, to which they are not now eligible; or if there be any such, there is a constant tendency to open such situations to them. They have now, especially in the Bengal and Agra provinces, almost the whole of the administration of justice in the first instance, subject to appeal to Europeans. They are also largely employed as deputy collectors, that is, in the branch of the Government, on which the prosperity of the country depends more than on any other; and those situations are sought for by natives of the highest rank and connexions. There was a remarkable proof of this some years ago in the North West Provinces. When the Nawab of Rampoor died, who was the descendant of Fyzoolla Khan, the chief who ruled over the portion left in existence of the Rohilla power, which was crushed by Warren Hastings, when this Nawab died, leaving no direct heirs, the collateral, who was next in succession, was a deputy collector in our provinces,²⁵ and two other near relations of the deceased Nawab happened to be deputy collectors also.

²³By Sect. 87 of 3 & 4 William IV, c. 85.

²⁴Haileybury College, Hertford, was founded in 1805 to train the nominees for the Indian Civil Service, who were required to spend two years there studying mathematics, natural history, classical and general literature, law and jurisprudence, history, political economy, and one Indian language and its literature.

²⁵Warren Hastings (1732-1818), the first Governor-General of Bengal 1774-85, had defeated the Rohillas in 1773. After Fyzoolla (Faizulla) Khan, the Rohilla chief, died in 1794, there was a struggle between his sons for the succession; eventually his grandson, Ahmad Ali, succeeded with British aid. He died childless, and was succeeded in 1840 by his cousin, Muhammad Saiyid Khan (d. 1855).

The new Nawab went from being a deputy collector under our Government, to succeed to his own principality, and he immediately commenced introducing the improvements which he had learned under our system.

Have those native officers of the Government Europeans placed under them? As deputy collectors they have no Europeans under them as subordinate officers, but only natives.

If the natives of India were to occupy a very large portion of the higher civil and military appointments of the country, do you suppose that we should continue to maintain the dependence of India upon this country? If the natives were allowed to wield the military force of India, I think it would be impossible to maintain British ascendancy there; but I think it would be perfectly possible to open to them a very large share of the civil government without its having any such effect.

Without having any European supervision? I do not think you could make a native Governor-general, but I think natives might in time be appointed to many of the higher administrative offices.

Do you think they might be members of Council? Not, I should think, at present; but in proportion as the natives become trustworthy and qualified for high office, it seems to me not only allowable, but a duty to appoint them to it.

Do you think that in those circumstances the dependence of India upon this country could be maintained? I think it might, by judicious management, be made to continue till the time arises when the natives shall be qualified to carry on the same system of Government without our assistance.

Would you make any change in the functions of the Governor-general, with a view of relieving him from any portion of his duties? I would relieve him from all details; certainly from the government of Bengal. It appears to me that the proper function of the Governor-general is rather to superintend the Government of India in all its departments than to carry on any portion of it in detail. I would give him only the external relations of India, and the business of legislation, along with a general power of receiving appeals from the subordinate Governments, and of interfering, whenever necessary, in the higher departments of their administration, with such portion of the higher patronage as it may be desirable for him to possess.

Would you establish a separate government for Bengal, or would you put it on the same footing as that of the North West Provinces, leaving the Lieutenant-governor in the nomination of the Governor-general? It is difficult to give a positive opinion at present. If I were to recommend either plan, it would be the Agra system, which works extremely well.

*Is not there this reason for the Agra system having worked very well, that during the portion of it which we had immediately under our eye, namely, the latter portion since the year 1844, it has been administered by a man of acknowledged superior ability and activity, Mr. Thomason?*²⁶ It is more particularly during the time of Mr. Thomason that it has been administered with such eminent success;

²⁶James Thomason (1804-53), Lieutenant-Governor of the North-Western Provinces (of which Agra was capital) 1843-53.

and the expediency of continuing the system depends upon the possibility, as may be shown by experience, of providing a succession of such men. Unless this can be provided, I think it would be desirable that all the subordinate Governments should have Councils.

If the Lieutenant-governor of Agra were selected on the same grounds on which the members of Council are selected, would there not be very great danger of the Government not being equally well conducted? The members of Council are selected from the same class of persons as the Lieutenant-governors.

When Mr. Thomason was appointed Governor, was not he taken quite out of his turn, and was he not a much younger man than those who would be named members of Council? He was; no doubt, because there was nobody senior to him who was thought so well qualified.

No one would have been named a member of Council so young as Mr. Thomason? Probably not.

Do you think it expedient to assimilate the Governments of Bombay and Madras to that of Agra? Either that, or to assimilate the Government of Agra to them.

Do you think it desirable that the Governor-general should be attended by his Council when he removes from Calcutta? If the practice which has existed for some years were to continue, that the Governor-general should be a much larger portion of time absent from Calcutta than present there, I think decidedly the Council ought to go with him; and in that case it would become a serious question whether the seat of Government should not be transferred to the interior. If the absence of the Governor-general from Calcutta were only to be occasional, I see no reason why the present system should not continue.

Do not you think there would be great advantage in sending out Governors-general very much younger than they have usually been—men who might be expected to remain 15 or 20 years in the country? It is to my mind doubtful. One of the advantages of the present mode of appointing the Governor-general is that he takes out with him the latest English ideas and sentiments. He is under the influence of the most recent, which in politics are generally the best opinions.

Would he not have the same, if he went out at thirty instead of at fifty? He would; but if he remained a longer time, he would perhaps not retain the advantage.

If he remained a longer time, would he not have the advantage probably of acquiring the language, and the means of communicating personally with individual natives; and would he not, if he were successful in his administration, acquire very great weight and influence throughout India, particularly with the native states? I think he has all the influence now with the native states that he thinks fit to exercise; I think he can do anything he pleases with them.

Might he not possibly obtain more influence than would be desirable? His permanent interests would always be in this country; I am not contemplating the case of his being able to usurp an independent Government there, certainly; but I do not think that danger much to be apprehended.

Not if he were to remain there a great number of years, and thereby very much to increase his influence? I should think the danger not great of a European, who might at any time be recalled, acquiring a degree of influence over the army and the natives, which would enable him to set up an independent government.

Is not that, to a certain degree, the case in all countries similarly situated? I am not aware of any parallel instance.

Does not his influence, in point of fact, mainly depend upon the great power of the country which he is known to represent? He is considered the representative of the irresistible English power.

Would you still maintain the Legislative Member of Council, and if you maintained him, would you assign to him the same duties? It seems to me very important to maintain that office, that there may be at least one person to devote himself specially to so important a part of the business of government as Legislation.

Do you think there would be any advantage in having for administrative purposes, a fifth member of Council sent from England, holding such a position as an Under Secretary of State, and who should remain there for about as long as the Governor-general himself remains? I see no necessity for such an officer, in addition to the Governor-general; the appointment of the Governor-general is intended to contribute European ideas to the Government, and the ordinary members of Council contribute Indian ideas; if the Governor-general is properly appointed, I do not see any use in sending out another officer for administrative purposes.

Is it not the practice for the new Governor-general, when he goes out, to take out with him a private secretary, who may be of very great assistance to the Governor-general in the mere details of his office? Sometime it is; sometimes the private secretary is elected in India.

Would you think it desirable to add to the Council of India civil servants from Madras and Bombay? That would depend upon the nature of the functions assigned to the Supreme Government; if the Governor-general in Council were to exercise a general superintendence over all the Presidencies, without conducting the administration of any; if he were regarded as a supreme authority, to be referred to in cases of difficulty who should have the power of interfering in the affairs of the subordinate Governments, and should receive general reports of their proceedings, but should not be necessarily a part of the ordinary government of India, except as to legislation and great political transactions; in that case I think it would be important that all the Presidencies should be represented in the Supreme Council; that there should be a member from Madras, and another from Bombay, as well as from Bengal and Agra. For the purposes merely of legislation, I am not sure that there is any necessity for this addition to the number of the Council. On any enactments which relate particularly to Madras and Bombay, it is usual for a reference first to be made to the Madras and Bombay Governments; if indeed the

whole proposition does not originate with them, by a draft Act being sent up by them, as it often is, for the approval of the Council.

Is it necessary that the Government of India should have some local knowledge in the decision of questions of pecuniary outlay relating to the subordinate Presidencies? It is necessary, no doubt, that they should have local knowledge; but that knowledge should be supplied to them by the Report sent by the local Governments, or elicited by the inquiries which the Supreme Government has power to make. All that is necessary as a qualification for the members of Council, is the habit of considering questions of a similar kind.

Would not it be desirable that the Council itself should be inspired by some local interest, to enable it to give full weight to the several reasons and arguments sent up from the subordinate Presidencies? That depends upon the degree to which the interference of the general Council at Calcutta extends. If Bombay and Madras continue to have local Governments which exercise a considerable amount of power, and the members of which deliberate in common, recording their opinions on the administration of their respective Presidencies, it does not seem to me necessary that there should be members from Madras and Bombay to advise the Supreme Council; but if there were merely lieutenant-governors at Madras or Bombay, it would be necessary.

Are you aware that no sum beyond 5,000 rupees can be expended by the local Governments without the consent of the Government of India, and that, moreover, not even a shifting and a change in the salaries of a Board can take place which involves an increase of salary to any one of the members, though the sum upon the whole should not exceed for the Board the sum which was before paid? I am not prepared to say, not having considered the subject, whether those restrictions are carried too far. Their object is partly to preserve uniformity of system as to salaries and establishments throughout India, in order that one portion of the service may not have reason to complain that others are treated better than themselves; and partly for the sake of the general finances of India; since the duty of keeping the expenses within the means rests with the authority which controls the affairs of all India, and not with any sectional department.

Do you think it would be conducive to the general public service, if the Court of Directors were to make this alteration (which they might do of their own authority) as regards the composition of the Council, namely, always to have in the Council a military member, and another member who had been engaged in the Judicial Department, and another who had been engaged in the Revenue Department; and in making provisional appointments, to make the succession provisional dependent upon the coming away, or upon the death of the member whom they particularly wished to replace by the person to whom the provisional appointment was given; so that a revenue member would succeed a revenue member, and a military member would succeed a military member; and the Council would always represent those three great departments? The point would be well worth

consideration; but it must be remembered that many members of the service had both revenue and judicial experience. In fact, as a general rule, almost all persons who rise to be members of Council have in some degree combined both those functions.

Must not considerable public inconvenience be caused by this state of things which once happened, that the military member of the Council died, and he was succeeded by a gentleman taken from the judicial department who had a provisional appointment, and the Council was left without a military member, while it had two who were acquainted with law? I think the suggestion involved in the question has much to recommend it; but I am not prepared to give a positive opinion.

Must it not have been so originally, because formerly the members of Council consisted of the heads of departments? That was according to the first constitution of the Council, when it was much more numerous.²⁷

Was not it at that time a Council consisting of the heads of departments, and were not they in the Council only because they were the heads of departments? I believe it was so, but only under a very ancient constitution of the Council; certainly not since the time of Warren Hastings.

*Would you think it desirable to re-establish the Law Commission?*²⁸ I would. I think it of great importance, not only to have an officer forming part of the Government whose business it should be to attend to legislation *pro hâc vice*, but also that what the Legislature certainly intended in the last Charter Act should not be left uncompleted. The intention of the Legislature in appointing the Law Commission was, that the whole law of India and the constitution of the courts of justice should be deliberately considered, and, as far as necessary, remodelled; that great improvements should be made in the procedure of the courts, and that the substantive laws should be consolidated and reduced to a code. This has been in a very small degree performed as yet, because there has not, I think, been sufficient importance attached to it by any of the authorities. I think it very desirable that the subject should be revived.

The home Government at this moment exercise an absolute control over the Government in India. Within what limits do you think that control should be exercised? There are very few acts of the Government of India which it is possible for the authorities here to set aside when they are once done. Some very important things they can do: they can put a stop to pecuniary jobbing when they detect it; they can cancel improper appointments, and control salaries and establishments; and they can, and often do, redress the grievances of individuals. But in most of the political measures of a general character, they have very little power of interfering with effect or advantage, after the thing is done. They have, however, a great

²⁷By Sect. 7 of 13 George III, c. 63 (1773).

²⁸For the Commission and the Commissioners, see "Penal Code for India," above; the code they proposed had still not been enacted.

power of making useful comments, which may serve as instructions for subsequent cases of the same kind; and it seems to me the greatest good that the home authorities can do is to comment freely on the proceedings of the local authorities, to criticise them well, and lay down general principles for the guidance of the Government on subsequent occasions.

Do they exercise that function at present as frequently and as successfully as they have done heretofore? I think the defect, perhaps a natural one in a Government constituted like that of India (and it is a defect of most Governments), is that there is an aversion to lay down any principle that goes beyond the particular occasion. Governments are almost always disinclined to commit themselves to opinions, except on a specific point, and as narrow a one as possible; but when an opinion is given, even confined to a specific point, and reasons are assigned for it, they necessarily involve some principle, and that principle, whether expressly stated or involved by implication in the decision, must serve as some guidance for future occasions.

Do you think that the home Government are more disinclined to laying down general principles than they used to be? I think, perhaps, they are; I think there is less disposition to lay down general principles than there was formerly, perhaps in consequence of the greater interest now taken by individual members of the Court in the proceedings, and the greater application of their minds to them than formerly; for that very reason, there is a greater number of objections, and it is more difficult to frame any statement of principles that shall command a majority.

Are there any further improvements in the constitution of the legislative and administrative body at Calcutta which you can suggest? I am not prepared to make any other suggestions.

Do you see any difficulties likely to accrue from the unlicensed liberty of the press? I think both the dangers and the advantages of the free press in India have been very much overrated: that the dangers were overrated is proved by the fact; it was anticipated by many people, that if full license were allowed to the press, it would drive us out of India altogether.

Do not you believe that there is this difference in the character of the Indian press, as compared with the press of this country, that whereas in this country the tone of the press is decidedly superior to that of ordinary conversation on the subjects of which it treats, in India it is the exact reverse of that; and that if any one were to form an opinion of the general state and tone of European society from the comments made by the Indian press, he would form a very unfair estimate of the general character of European society in the country? I cannot speak from much actual knowledge of the Indian press; my impression certainly is, that the English newspapers in India are of very little use to good government, except in promoting inquiry, and drawing the attention of the Government to facts which they might have overlooked. From the little knowledge I have of the Indian newspaper press, I should say that its comments are seldom of any value.

Is not the style such as does not prevail in good society; would not it give to those who read habitually the leading articles in those papers an impression that the tone of society is very inferior to what it is? I am not sufficiently acquainted with the Indian press to be able to answer the question.

Are you aware that in point of fact, the tone of society in India is as good as it is in this country? I know nothing to the contrary.

You said that not only were the dangers that were expected to accrue from the establishment of a free press in India exaggerated, but also that the expected advantages were exaggerated. Is that your opinion? It is. As long as the great mass of the people of India have very little access to the press, it is in danger of being an organ exclusively of individual interests. The English newspaper press in India is the organ only of the English society, and chiefly of the part of it unconnected with the Government. It has little to do with the natives, or with the great interests of India.

Does not the Government of India labour under this particular disadvantage, that they have no means of defence against unworthy imputations which the press throws out; not being represented in the press? Certainly. It is the practice of the Indian authorities both in India and in England to look on while their proceedings are the subject of unmeasured obloquy by the newspapers and in public discussions, without taking any means of getting a correct statement made of their measures, and of the grounds upon which they have been adopted.

Is there not this difference in India as compared with England, that whereas in England, if an attack is made upon the Government, there is a Government paper that undertakes to rebut it; in India there is no such opportunity of stating the truth? I think the same observation applies to attacks upon the Indian administration in this country; it is very seldom that any portion of the press takes up the cause of the Indian Government.

Do you not think, with reference to the Court of Proprietors, that it might be some advantage if it was necessary that a quorum should be present previously to allowing any public discussion to go on, namely, that there should be, say 40 persons present, instead of having only five, as is the case sometimes now; would it not put some restriction upon their meetings? I have not much considered what would be the effect of such a regulation; but I apprehend that when it is important that a discussion should take place, it would seldom be difficult to obtain as many as 40, or some rather smaller number to be present.

In the course of your examination yesterday you spoke of it as a merit of the Government of India, that it was very much a Government of record, and that everything that was done was to be found upon paper.²⁹ Have you ever heard it objected that that system of record and putting everything upon paper at length, is carried to an extent that is practically inconvenient and cumbersome? It is only

²⁹See p. 33 above.

cumbersome in the sense of making a very great mass of records; but the system of indexing is so perfect that it is easy to refer to everything.

Is it not the fact that it does not necessarily increase the quantity of writing; but it causes all that is written to be sent home? Indian functionaries are obliged to write so quick, that they generally write at great length.

Does not it entail a very large staff of clerks and manual assistants? No doubt it must cause a considerable increase in the establishments, but the expense is amply compensated by the advantage.

Are you acquainted with the manner in which the business is conducted at the Government offices in this country? I have no practical acquaintance with it.

Do you believe that the number of hands compared with the amount of business transacted, and consequently the expense of conducting the business, is much greater in proportion, in the Indian offices, than it is in the offices of the Crown? I am unable to judge. But as the natives in India are paid at a much lower rate than Europeans in England, the number of hands may be much greater without causing greater expense.

Must there not of necessity be a great deal more writing, in consequence of the double Government, and the necessity of keeping a reserved copy in case of any accident happening to the other? Certainly.

Has not the direction given about the year 1829 or 1830, that every gentleman who wrote a letter should write an abstract of it in a book, failed of producing any effect in diminishing the size of the letters? It has made very little, if any, difference.

Is not the present system very nearly identical with that of the Foreign Office in this country, or, at least, ought it not to be so, according to the order given? I am not acquainted with the system of the Foreign Office.

Is it not the practice in the Indian correspondence to collect discussions upon a number of subjects into one letter? The system of separate letters has been much more resorted to in the last 20 years, in consequence of orders sent out when Lord Ellenborough was President of the Board;³⁰ it has, however, been prescribed to the Governments of India, that they should, in addition to separate letters on subjects of sufficient importance to require them, also write quarterly letters, reporting miscellaneous subjects on which there have been no separate reports, because it was found that previous to that time, many subjects went unreported altogether; and the only way to insure a report of them was, by requiring that there should be letters written which should embrace everything not separately reported.

Has the effect of that rule been that letters which deal with multifarious business

³⁰Edward Law (1790-1871), Earl of Ellenborough, was President of the Board of Control 1828-30 (and 1834-35, 1841, and 1858; he was Governor-General 1842-44); the instruction is in "Letter from the Board of Control to the Court of Directors" (13 Oct., 1829), India Office Library and Records, *Letters from the Board of Control to the Company*, E/2/35, pp. 370-9.

are the exceptions, and that letters on separate business are the rule? There is a much greater number of letters on separate subjects, than of miscellaneous letters; but the miscellaneous letters often extend to a greater number of paragraphs.

Is it your opinion that the education adopted in this country, for the civil servants of the Indian Government, is the best that could be adopted? I have great doubts of the necessity or expediency of an exclusive system of education for the civil service. I should be much more inclined to fix a standard of qualification, and admit all persons to receive appointments, if upon examination they are found to come up to that standard, placing the standard high, but allowing them to acquire the knowledge in any way and at any place.

You are not inclined to think that it should be a necessary preliminary that the candidates should have been educated at Haileybury? I am inclined to think the contrary.

Would there be the same facilities of acquiring the requisite knowledge at other places, which there are at Haileybury? If qualifications were required which could be obtained best at Haileybury, there would still be sufficient inducements to seek them there; but I would not make it compulsory. I am not aware of anything necessary for the candidates that can be learned nowhere except at Haileybury.

Does not Haileybury afford particular facilities for obtaining the necessary qualifications? It affords facilities, but they are so costly that it would be possible to obtain them at less expense elsewhere. I speak with deference to the opinions of persons who know more of Haileybury than I do; but my opinion is decidedly against, in any case, requiring as a qualification for employment that the person should have acquired his knowledge at some particular place or in some particular way. I would raise the standard of acquirements as high as possible; but having done that, I would admit a person who possessed the knowledge, in whatever manner he had acquired it.

Would your observation equally apply to the necessity of military education at Addiscombe,³¹ or would you think that, in the case of military officers, it would be desirable still to continue that system? As it is necessary to have a special professional education for military purposes, it has been thought necessary everywhere to have institutions for the purpose; and some of the necessary professional qualifications perhaps cannot be acquired except by something like a college. But I would allow a person to acquire it at any institution at which it can be acquired; for instance, at Sandhurst, and at Woolwich.

All that you would require is, that there should be a certain degree of excellence to which they should come up, leaving the parties examined to have had their preliminary education where they may deem it expedient? Certainly.

³¹Addiscombe, the military equivalent of Haileybury, was founded in Surrey in 1809; the two-year course, initially for artillery and engineering cadets (and after 1816, infantry cadets as well), who were nominated by the East India Company's Directors, included mathematics, fortifications, military and civil drawing, and surveying.

Are you of opinion that the education acquired at Addiscombe is of a very superior kind? I have every reason to think so.

Do you consider that the acquaintances formed in consequence of persons educated for India belonging to the same college are advantageous, by affording facilities of communication in carrying on their duties in after life? It does not at all follow that they are placed in contact with one another afterwards; if they are, it is accidental, and there is the counterbalancing disadvantage that they begin too soon to associate exclusively with one another.

THE PETITION OF THE EAST-INDIA COMPANY

1858

EDITORS' NOTE

In *Memorandum of the Improvements in the Administration of India during the Last Thirty Years, and the Petition of the East-India Company to Parliament* (London: Cox and Wyman, 1858), 111-29. Appeared also in *Debates at the East-India House, Relative to the Proposed Change in the Government of India* (London: Cox and Wyman, 1858), 6-8; and in *PD*, 3rd ser., Vol. 148 (1858), in an unpaginated Appendix. The petition was presented to the House of Commons by Thomas George Baring (1826-1904) on 9 February, 1858, and to the House of Lords by Henry George Grey (1802-94), 3rd Earl Grey, on 11 February (*PD*, 3rd ser., Vol. 148, cols. 970-5 and 1121-37). Headed as title. Unsigned. Not republished by Mill. Identified in his bibliography as "The Petition of the East India Company to the two Houses of Parliament against the intended measure for depriving them of the Administration of India; printed by the company and presented in the Session of 1858" (MacMinn, 90). In the footnoted variant readings, "D" signifies *Debates at the East-India House*, "PD" signifies *Parliamentary Debates*. The square brackets around "Lordships" in the copy-text signal the deletion of the word when the petition was presented to the House of Commons.

The Petition of the East-India Company

To the Right Honourable the Lords Spiritual and Temporal, and the Honourable the Commons of the United Kingdom of Great Britain and Ireland, in Parliament assembled,

“HUMBLY SHEWETH,

That^a your Petitioners, at their own expense, and by the agency of their own civil and military servants, originally acquired for this country its magnificent empire in the East.

That the foundations of this empire were laid by your Petitioners, at that time neither aided nor controlled by Parliament, at the same period at which a succession of administrations under the control of Parliament were losing to the Crown of Great Britain another great empire on the opposite side of the Atlantic.

That during the period of about a century which has since elapsed, the Indian possessions of this country have been governed and defended from the resources of those possessions, without the smallest cost to the British Exchequer, which, to the best of your Petitioners' knowledge and belief, cannot be said of any other of the numerous foreign dependencies of the Crown.

That it being manifestly improper that the administration of any British possession should be independent of the general Government of the empire, Parliament provided, in 1783, that a department of the Imperial Government should have full cognizance of, and power of control over, the acts of your Petitioners in the administration of India;¹ since which time the home branch of the Indian Government has been conducted by the joint counsels, and on the joint responsibility of your Petitioners and of a Minister of the Crown.

That this arrangement has at subsequent periods undergone reconsideration from the Legislature, and various comprehensive and careful Parliamentary inquiries have been made into its practical operation; the result of which has been, on each occasion, a renewed grant to your Petitioners of the powers exercised by them in the administration of India.²

¹By Sects. 1-5 of 24 George III, c. 25 (1784).

²Following on 33 George III, c. 52 (1793), which lasted until 1813, a parliamentary committee was set up which reported five times (see the “Reports of the Select Committee

^a—D Showeth,—that

That the last of these occasions was so recent as 1853, in which year the arrangements which had existed for nearly three-quarters of a century, were, with certain modifications, re-enacted, and still subsist.³

That, notwithstanding, your Petitioners have received an intimation from Her Majesty's Ministers of their intention to propose to Parliament a Bill for the purpose of placing the government of Her Majesty's East-Indian dominions under the direct authority of the Crown,⁴—a change necessarily involving the abolition of the East-India Company as an instrument of government.

That your Petitioners have not been informed of the reasons which have induced Her Majesty's Ministers, without any previous inquiry, to come to the resolution of putting an end to a system of administration, which Parliament, after inquiry, deliberately confirmed and sanctioned less than five years ago, and which, in its modified form, has not been in operation quite four years, and cannot be considered to have undergone a sufficient trial during that short period.

That your Petitioners do not understand that Her Majesty's Ministers impute any failure to those arrangements, or bring any charge, either great or small, against your Petitioners. But the time at which the proposal is made, compels your Petitioners to regard it as arising from the calamitous events which have recently occurred in India.

That your Petitioners challenge the most searching investigation into the mutiny of the Bengal army, and the causes, whether remote or immediate, which produced that mutiny. They have instructed the Government of India to appoint a commission for conducting such an inquiry on the ^bspot.⁵ And^b it is their most anxious wish that a similar inquiry may be instituted in this country by your [Lordships] Honourable House;⁶ in order that it may be ascertained whether

on the Affairs of the East India Company," *PP*, 1808, III; 1810, V; 1810-11, VII; 1812, VI.1; and 1812, VII.1). The result was the Charter Act of 1813, 53 George III, c. 155. Committee reports were also made as the period of that Act came to an end (see *PP*, 1830, V; and 1831-32, VIII-XIV), resulting in the Charter Act of 1833 (3 & 4 William IV, c. 85).

³For the Reports of the Committee before which Mill gave evidence (see "The East India Company's Charter," above) see *PP*, 1852-53, XXX-XXXIII; the result was the Charter Act of 1853, 16 & 17 Victoria, c. 95.

⁴For the "intimation," see "Correspondence between the First Lord of the Treasury and the Directors of the East India Company Respecting Legislative Measures to be Proposed for the Future Government of Her Majesty's Dominions in India," *Sessional Papers of the House of Lords*, 1857-58, XI, 445-8. The measure was "A Bill for the Better Government of India," 21 Victoria (12 Feb., 1858), *PP*, 1857-58, II, 267-86.

⁵See "Letter from the Court of Directors to the Governor-General of India in Council, Military Department," 25 Nov. (No. 236), 1857, *PP*, 1857-58, XLIV, Pt. 1, 48-9.

⁶Though the subject was often debated in both Lords and Commons, there was no Select Committee on the Mutiny. See, however, "Papers Relative to the Mutinies in the East Indies," *PP*, 1857 (Sess. 2), XXX; and 1857-58, XLVI, Pts. 1-4.

^{b-b}D spot; and

anything either in the constitution of the Home Government of India, or in the conduct of those by whom it has been administered, has had any share in producing the mutiny, or has in any way impeded the measures for its suppression; and whether the mutiny itself, or any circumstance connected with it, affords any evidence of the failure of the arrangements under which India is at present administered.

That, were it even true that these arrangements had failed, the failure could constitute no reason for divesting the East-India Company of its functions, and transferring them to Her Majesty's ^cGovernment. For, ^cunder the existing system, Her Majesty's Government have the deciding voice. The duty imposed upon the Court of Directors is to originate measures and frame drafts of instructions. Even had they been remiss in this duty, their remissness, however discreditable to themselves, could in no way absolve the responsibility of Her Majesty's Government, since the Minister for India possesses, and has frequently exercised, the power of requiring that the Court of Directors should take any subject into consideration, and prepare a draft despatch for his approval. Her Majesty's Government are thus in the fullest sense accountable for all that has been done, and for all that has been forborne or omitted to be done. Your Petitioners, on the other hand, are accountable only in so far as the act or omission has been promoted by themselves.

That, under these circumstances, if the administration of India had been a failure, it would, your Petitioners submit, have been somewhat unreasonable to expect that a remedy would be found in annihilating the branch of the ruling authority which could not be the one principally in fault, and might be altogether blameless, in order to concentrate all powers in the branch which had necessarily the decisive share in every error, real or supposed. To believe that the administration of India would have been more free from error had it been conducted by a Minister of the Crown without the aid of the Court of Directors, would be to believe that the Minister, with full power to govern India as he pleased, has governed ill because he has had the assistance of experienced and responsible advisers.

That your Petitioners, however, do not seek to vindicate themselves at the expense of any other ^dauthority. They ^dclaim their full share of the responsibility of the manner in which India has practically been governed. That responsibility is to them not a subject of humiliation, but of pride. They are conscious that their advice and initiative have been, and have deserved to be, a great and potent element in the conduct of affairs in India. And they feel complete assurance that the more attention is bestowed and the more light thrown upon India and its administration, the more evident it will become that the government in which they have borne a part has been not only one of the purest in intention, but one of the

^{c-c}D Government; for

^{d-d}D authority: they

most beneficent in act, ever known among mankind; that, during the last and present generation in particular, it has been, in all departments, one of the most rapidly improving governments in the world; and that, at the time when this change is proposed, a greater number of important improvements are in a state of more rapid progress than at any former period. And they are satisfied that whatever further improvements may be hereafter effected in India can only consist in the development of germs already planted, and in building on foundations already laid, under their authority, and in a great measure by their express instructions.

That such, however, is not the impression likely to be made on the public mind, either in England or in India, by the ejection of your Petitioners from the place they fill in the Indian administration. It is not usual with statesmen to propose the complete abolition of a system of government, of which the practical operation is not condemned, and it might be generally inferred from the proposed measures, if carried into effect at the present time, that the East-India Company, having been intrusted with an important portion of the administration of India, have so abused their trust as to have produced a sanguinary insurrection, and nearly lost India to the British empire; and that having thus crowned a long career of misgovernment, they have, in deference to public indignation, been deservedly cashiered for their misconduct.

That if the character of the East-India Company were alone concerned, your Petitioners might be willing to await the verdict of history. They are satisfied that posterity will do them justice. And they are confident that even now justice is done to them in the minds, not only of Her Majesty's Ministers, but of all who have any claim to be competent judges of the subject. But though your Petitioners could afford to wait for the reversal of the verdict of condemnation which will be believed throughout the world to have been passed on them and their government by the British nation, your Petitioners cannot look without the deepest uneasiness at the effect likely to be produced on the minds of the people of India. To them, however incorrectly the name may express the fact, the British Government in India is the Government of the East-India Company. To their minds the abolition of the Company will, for some time to come, mean the abolition of the whole system of administration with which the Company is identified. The measure, introduced simultaneously with the influx of an overwhelming British force, will be coincident with a general outcry, in itself most alarming to their fears, from most of the organs of opinion in this country as well as of English opinion in India, denouncing the past policy of the Government on the express ground that it has been too forbearing and too considerate towards the natives. The people of India will at first feel no certainty that the new Government, or the Government under a new name, which it is proposed to introduce, will hold itself bound by the pledges of its predecessors. They will be slow to believe that a Government has been destroyed only to be followed by another which will act on the same principles and adhere to the same measures. They cannot suppose that the existing organ of

administration would be swept away without the intention of reversing any part of its policy. They will see the authorities, both at home and in India, surrounded by persons vehemently urging radical changes in many parts of that ‘policy. And^e interpreting, as they must do, the change in the instrument of government, as a concession to these opinions and feelings, they can hardly fail to believe that, whatever else may be intended, the Government will no longer be permitted to observe that strict impartiality between those who profess its own creed and those who hold the creeds of its native subjects which hitherto characterized it; that their strongest and most deeply-rooted feelings will henceforth be treated with much less regard than heretofore; and that a directly aggressive policy towards everything in their habits, or in their usages and customs, which Englishmen deem objectionable, will be no longer confined to individuals and private associations, but will be backed by all the power of Government.

And here your Petitioners think it important to observe, that in abstaining as they have done from all interference with any of the religious practices of the people of India, except such as are abhorrent to humanity, they have acted not only from their own conviction of what is just and expedient, but in accordance with the avowed intentions and express enactments of the Legislature, framed “in order that regard should be had to the civil and religious usages of the natives,” and also “that suits, civil or criminal, against the natives,” should be conducted according to such rules “as may accommodate the same to the religion and manners of the natives.”⁷ That their policy in this respect has been successful, is evidenced by the fact, that during a military mutiny, said to have been caused by unfounded apprehensions of danger to religion, the heads of the native states, and the masses of the population, have remained faithful to the British Government. Your Petitioners need hardly observe how very different would probably have been the issue of the late events, if the native princes, instead of aiding in the suppression of the rebellion, had put themselves at its head, or if the general population had joined in the revolt; and how probable it is that both these contingencies would have occurred, if any real ground had been given for the persuasion that the British Government intended to identify itself with ^fproselytism. And^f it is the honest conviction of your Petitioners that any serious apprehension of a change of policy in this respect would be likely to be followed, at no distant period, by a general rising throughout India.

That your Petitioners have seen with the greatest pain the demonstrations of indiscriminate animosity towards the natives of India, on the part of our countrymen in India and at home, which have grown up since the late unhappy

⁷Provisions in Sects. 18 and 19 of 21 George III, c. 70 (1781), which amended 13 George III, c. 63.

^e—D policy; and

^f—D proselytism; and

events. They believe these sentiments to be fundamentally unjust; they know them to be fatal to the possibility of good government in India. They feel that if such demonstrations should continue, and especially if weight be added to them by legislating under their supposed influence, no amount of wisdom and forbearance on the part of the Government will avail to restore that confidence of the governed in the intentions of their rulers without which it is vain even to attempt the improvement of the people.

That your Petitioners cannot contemplate without dismay the doctrine now widely promulgated that India should be administered with an especial view to the benefit of the English who reside there; or that in its administration any ^sadvantage^s should be sought for Her Majesty's subjects of European birth, except that which they will necessarily derive from their superiority of intelligence, and from the increased prosperity of the people, the improvement of the productive resources of the country, and the extension of commercial intercourse. Your Petitioners regard it as the most honourable characteristic of the government of India by England, that it has acknowledged no such distinction as that of a dominant and a subject race; but has held that its first duty was to the people of India. Your Petitioners feel that a great portion of the hostility with which they are assailed, is caused by the belief that they are peculiarly the guardians of this principle, and that so long as they have any voice in the administration of India, it cannot easily be ^hinfringed. And ^hyour Petitioners will not conceal their belief that their exclusion from any part in the Government is likely at the present time to be regarded in India as a first successful attack on that principle.

That your Petitioners, therefore, most earnestly represent to your [Lordships] Honourable House, that even if the contemplated change could be proved to be in itself advisable, the present is a most unsuitable time for entertaining it; and they most strongly and respectfully urge on your [Lordships] Honourable House the expediency of at least deferring any such change until it can be effected at a period when it would not be, in the minds of the people of India, directly connected with the recent calamitous events, and with the feelings to which those events have either given rise or have afforded an opportunity of manifestation. Such postponement, your Petitioners submit, would allow time for a more mature consideration than has yet been given, or can be given in the present excited state of the public mind, to the various questions connected with the organization of a government for India; and would enable the most competent minds in the nation calmly to examine whether any new arrangement can be devised for the Home Government of India uniting a greater number of the conditions of good administration than the present; and, if so, which among the numerous schemes

^{s-s}D advantages

^{h-h}D infringed; and

which have been, or may be, proposed, possesses those requisites in the greatest degree.⁸

That your Petitioners have always willingly acquiesced in any changes which, after discussion by Parliament, were deemed conducive to the general welfare, although such changes may have involved important sacrifices to themselves. They would refer to their partial relinquishment of trade in 1813;⁹ to its total abandonment, and the placing of their Commercial Charter in abeyance, in 1833;¹⁰ to the transfer to India of their commercial assets, amounting to £15,858,000, a sum greatly exceeding that ultimately repayable to them in respect of their capital, independent of territorial rights and claims;¹¹ and to their concurrence, in 1853, in the measure by which the Court of Directors was reconstructed, and reduced to its present number.¹² In the same spirit, your Petitioners would most gladly co-operate with Her Majesty's Government in correcting any defects which may be considered to exist in the details of the present system; and they would be prepared, without a murmur, to relinquish their trust altogether, if a better system for the control of the Government of India can be devised. But, as they believe that in the construction of such a system there are conditions which cannot, without the most dangerous consequences be departed from, your Petitioners respectfully 'and deferentially' submit to the judgment of your [Lordships] Honourable House their view of those conditions; in the hope that if your [Lordships] Honourable House should see reason to agree in that view, you will withhold your legislative sanction from any arrangement for the Government of India which does not fulfil the conditions in question in at least an equal degree with the present.

That your Petitioners may venture to assume that it will not be proposed to vest the home portion of the administration of India in a Minister of the Crown, without the adjunct of a Council composed of statesmen experienced in Indian affairs. Her Majesty's Ministers cannot but be aware that the knowledge necessary for governing a foreign country, and in particular a country like India, requires as much

⁸For varied proposals that illustrate the public agitation on the subject, see, e.g., Richard Congreve, *India* (London: Chapman, 1857); Francis William Newman, "English Policy in India," *The Times*, 3 Dec., 1857, p. 5; "Hadjee," "Indian Home Government," *ibid.*, 31 Dec., 1857, p. 9; "Indophilus," "The Government of India," *ibid.*, 21 Jan., 1858, p. 10; and Harriet Martineau, *Suggestions towards the Future Government of India* (London: Smith, Elder, 1858).

⁹By Sects. 11 and 24 of 53 George III, c. 155.

¹⁰By Sects. 3 and 4 of 3 & 4 William IV, c. 85.

¹¹Sect. 4 of 3 & 4 William IV, c. 85, required the Company to sell its commercial assets after 22 April, 1834.

¹²By Sect. 2 of 16 & 17 Victoria, c. 95.

special study as any other profession, and cannot possibly be possessed by any one who has not devoted a considerable portion of his life to the acquisition of it.

That in constituting a body of experienced advisers to be associated with the Indian Minister, your Petitioners consider it indispensable to bear in mind that this body should not only be qualified to advise the Minister, but also, by its advice, to exercise, to a certain degree, a moral check. It cannot be expected that the Minister, as a general rule, should himself know India; while he will be exposed to perpetual solicitations from individuals and bodies, either entirely ignorant of that country, or knowing only enough of it to impose on those who know still less than themselves, and having very frequently objects in view other than the interests or good government of India. The influences likely to be brought to bear on him through the organs of popular opinion will, in the majority of cases, be equally misleading. The public opinion of England, itself necessarily unacquainted with Indian affairs, can only follow the promptings of those who take most pains to influence it, and these will generally be such as have some private interest to serve. It is, therefore, your Petitioners submit, of the utmost importance that any council which may form a part of the Home Government of India should derive sufficient weight from its constitution, and from the relation it occupies to the Minister, to be a substantial barrier against those inroads of self-interest and ignorance in this country from which the Government of India has hitherto been comparatively free, but against which it would be too much to expect that Parliament should of itself afford a sufficient protection.

That your Petitioners cannot well conceive a worse form of government for India than a Minister with a Council whom he should be at liberty to consult or not at his pleasure, or whose advice he should be able to disregard, without giving his reasons in writing, and in a manner likely to carry conviction. Such an arrangement, your Petitioners submit, would be really liable to the objections, in their opinion, erroneously urged against the present system.¹³ Your Petitioners respectfully represent that any body of persons associated with the Minister, which is not a check, will be a screen.¹⁴ Unless the Council is so constituted as to be personally independent of the Minister, unless it feels itself responsible for recording an opinion on every Indian subject, and pressing that opinion on the Minister, whether it is agreeable to him or not; and unless the Minister, when he overrules their opinion, is bound to record his reasons, their existence will only serve to weaken his responsibility, and to give the colourable sanction of prudence

¹³The objection to "double government" was raised by Henry John Temple (1784-1865), Lord Palmerston, in his speech asking leave to introduce the Bill on the government of India (12 Feb., 1858), *PD*, 3rd ser., Vol. 148, col. 1279.

¹⁴The image (one of Mill's favourites) comes from Jeremy Bentham, *Letter to Lord Granville on the Proposed Reform in the Administration of Civil Justice in Scotland* (1807), in *The Works of Jeremy Bentham*, ed. John Bowring, 11 vols. (Edinburgh: Tait, 1843), Vol. V, p. 17.

and experience to measures in the framing of which those qualities have had no share.

That it would be vain to expect that a new Council could have as much moral influence, and power of asserting its opinion with effect, as the Court of Directors. A new body can no more succeed to the feelings and authority which their antiquity and their historical antecedents give to the East-India Company, than a legislature under a new name, sitting in Westminster, would have the moral ascendancy of the Houses of Lords and Commons. One of the most important elements of usefulness will thus be necessarily wanting in any newly constituted Indian Council, as compared with the present.

That your Petitioners find it difficult to conceive that the same independence in judgment and act, which characterizes the Court of Directors, will be found in any Council all of whose members are nominated by the Crown. Owing their nomination to the same authority, many of them probably to the same individual Minister, whom they are appointed to check, and looking to him alone for their re-appointment, their desire of recommending themselves to him, and their unwillingness to risk his displeasure by any serious resistance to his wishes, will be motives too strong not to be in danger of exercising a powerful and injurious influence over their conduct. Nor are your Petitioners aware of any mode in which that injurious influence could be guarded against, except by conferring the appointments, like those of the Judges, during good behaviour; which, by rendering it impossible to correct an error once committed, would be seriously objectionable.

That your Petitioners are equally unable to perceive how, if the controlling body is entirely nominated by the Minister, that happy independence of Parliamentary and party influence, which has hitherto distinguished the administration of India and the appointment to situations of trust and importance in that country, can be expected to continue. Your Petitioners believe that in no government known to history have appointments to offices, and especially to high offices, been so rarely bestowed on any other considerations than those of personal fitness. This characteristic, but for which in all probability India would long since have been lost to this country, is, your Petitioners conceive, entirely owing to the circumstance that the dispensers of patronage have been persons unconnected with party, and under no necessity of conciliating parliamentary support; that, consequently, the appointments to offices in India have been, as a rule, left to the unbiassed judgment of the local authorities; while the nominations to the civil and military services have been generally bestowed on the middle classes, irrespective of political considerations, and, in a large proportion, on the relatives of persons who had distinguished themselves by their services in India.

That your Petitioners, therefore, think it essential that at least a majority of the Council which assists the Minister for India with its advice, should hold their seats independently of his appointment.

That it is, in the opinion of your Petitioners, no less necessary that the order of the transaction of business should be such as to make the participation of the Council in the administration of India a substantial one. That to this end, it is, in the opinion of your Petitioners, indispensable that the despatches to India should not be prepared by the Minister and laid before the Council, but should be prepared by the Council and submitted to the Minister. This would be in accordance with the natural and obvious principle that persons chosen for their knowledge of a subject should suggest the mode of dealing with it, instead of merely giving their opinion on suggestions coming from elsewhere. This is also the only mode in which the members of the Council can feel themselves sufficiently important or sufficiently responsible to secure their applying their minds to the subjects before them. It is almost unnecessary for your Petitioners to observe, that the mind is called into far more vigorous action by being required to propose than by merely being called on to assent. The Minister has necessarily the ultimate decision. If he has also the initiative, he has all the powers which are of any practical moment. A body whose only recognized function was to find fault, would speedily let that function fall into desuetude. They would feel that their co-operation in conducting the Government of India was not really desired; that they were only felt as a clog on the wheels of business. Their criticism on what had been decided without their being collectively consulted would be felt as importunate, as a mere delay and impediment; and their office would probably be seldom sought but by those who were willing to allow its most important duties to become nominal.

That with the duty of preparing the despatches to India, would naturally be combined the nomination and control of the home establishments. This your Petitioners consider absolutely essential to the utility of the Council. If the officers through whom they work are in direct dependence upon an authority higher than theirs, all matters of importance will in reality be settled between the Minister and the subordinates, passing over the Council altogether.

That a third consideration, to which your Petitioners attach great importance, is, that the number of the Council should not be too restricted. India is so wide a field, that a practical acquaintance with every part of its affairs cannot be found combined in any small number of individuals. The Council ought to contain men of general experience and knowledge of the world; also men specially qualified by financial and revenue experience, by judicial experience, diplomatic experience, military ^jexperience. It ought to contain persons conversant with the varied social relations and varied institutions of Bengal, Madras, Bombay, the North-Western Provinces, the Punjab, and the native states. Even the present Court of Directors, reduced as it is in numbers by the Act of 1853, does not contain all the varieties of knowledge and experience desirable in such a ^hbody. Neither, ^k your Petitioners

^j-D experience; it

^k-D body; neither

submit, would it be safe to limit the number to that which would be strictly sufficient, supposing all the appointments to be the best possible. A certain margin should be allowed for failures, which, even with the most conscientious selection, will sometimes occur. Your Petitioners, moreover, cannot overlook the possibility that, if the nomination takes place by Ministers at the head of a political party, it will not always be made with exclusive reference to personal qualifications; and it is indispensable to provide that such errors or faults in the nominating authority, so long as they are only occasional, shall not seriously impair the efficiency of the body.

That while these considerations plead strongly for a body not less numerous than the present, even if only regarded as advisers of the Minister, their other office, as a check on the Minister, forms, your Petitioners submit, a no less forcible objection to any considerable reduction of the present number. A body of six or eight will not be equal to one of eighteen, in that feeling of independent self-reliance which is necessary to induce a public body to press its opinion on a Minister to whom that opinion is unacceptable. However unobjectionably in other respects so small a body may be constituted, reluctance to give offence will be likely, unless in extreme cases, to be a stronger habitual inducement in their minds than the desire to stand up for their convictions.

That if, in the opinion of your [Lordships] Honourable House, a body can be constituted which unites the above enumerated requisites of good government in a greater degree than the Court of Directors, your Petitioners have only to express their humble hope that your endeavours for that purpose may be successful. But if, in enumerating the conditions of a good system of Home Government for India, your Petitioners have in fact enumerated the qualities possessed by the present system, then your Petitioners pray that your [Lordships] Honourable House will continue the existing powers of the Court of Directors.

That your Petitioners are aware that the present Home Government of India is reproached with being a double Government; and that any arrangement by which an independent check is provided to the discretion of the Minister will be liable to a similar reproach. But they conceive that this accusation originates in an entire misconception of the functions devolving on the Home Government of India, and in the application to it of the principles applicable to purely executive departments. The Executive Government of India is, and must be, seated in India itself. The Court of Directors is not so much an executive, as a deliberative body. Its principal function, and that of the Home Government generally, is not to direct the details of administration, but to scrutinize and revise the past acts of the Indian 'Governments'¹; to lay down principles, and issue general instructions for their future guidance, and to give or refuse sanction to great political measures, which are referred home for approval. These duties are more analogous to the functions of

¹-D, PD Government .

Parliament, than to those of an Executive Board: and it might almost as well be said that Parliament, as that the Government of India, should be constituted on the principles applicable to Executive Boards. It is considered an excellence, not a defect, in the constitution of Parliament, to be not merely a double but a triple Government. An executive authority, your Petitioners submit, may often with advantage be single, because promptitude is its first requisite. But the function of passing a deliberate opinion on past measures, and laying down principles of future policy, is a business which, in the estimation of your Petitioners, admits of, and requires the concurrence of more judgments than one. It is no defect in such a body to be double, and no excellence to be single; especially when it can only be made so by cutting off that branch of it which by previous training is always the best prepared, and often the only one which is prepared at all, for its peculiar duty.

That your Petitioners have heard it asserted that, in consequence of what is called the double Government, the Indian authorities are less responsible to Parliament and the nation, than other departments of the Government of the Empire, since it is impossible to know on which of the two branches of Home Government the responsibility ought to rest. Your Petitioners fearlessly affirm, that this impression is not only groundless, but the very reverse of the truth. The Home Government of India is not less, but more responsible, than any other branch of the administration of the State; inasmuch as the President of the Board of Commissioners,¹⁵ who is the minister for India, is as completely responsible as any other of Her Majesty's Ministers, and in addition, his advisers also are responsible. It is always certain, in the case of India, that the President of the Board of Commissioners must have either commanded or sanctioned all that has been done. No more than this, your Petitioners submit, can be known in the case of the head of any department of Her Majesty's Government. For it is not, nor can it rationally be supposed, that any Minister of the Crown is without trusted advisers; and the Minister for India must, for obvious reasons, be more dependent than any other of Her Majesty's Ministers, upon the advice of persons whose lives have been devoted to the subject on which their advice has been given. But in the case of India, such ^madvisers^m are assigned to him by the constitution of the Government, and they are as much responsible for what they advise as he for what he ordains: while in other departments the Minister's only official advisers are the subordinates in his office—men often of great skill and experience, but not in the public eye; often unknown to the public even by name; official reserve precludes the possibility of ascertaining what advice they give, and they are responsible only to the Minister himself. By what application of terms this can be called responsible government, and the joint government of your Petitioners and the India Board an irresponsible government, your Petitioners think it unnecessary to ask.

¹⁵I.e., the Board of Control.

^{m-m}D advices [*printer's error?*]

That without knowing the plan on which Her Majesty's Ministers contemplate the transfer to the Crown of the servants of the Company, your Petitioners find themselves unable to approach the delicate question of the Indian Army, further than to point out that the high military qualities of the officers of that army have unquestionably sprung in a great degree from its being a principal and substantive army, holding Her Majesty's commissions and enjoying equal rank with Her Majesty's officers, and your Petitioners would earnestly deprecate any change in that position.

That your Petitioners, having regard to all these considerations, humbly pray your [Lordships] Honourable House, that you will not give your sanction to any change in the constitution of the Indian Government during the continuance of the present unhappy disturbances, nor without a full previous inquiry into the operation of the present system. And your Petitioners further pray that this inquiry may extend to every department of Indian administration. Such an inquiry your Petitioners respectfully claim, not only as a matter of justice to themselves, but because, when, for the first time in this century, the thoughts of every public man in the country are fixed on India, an inquiry would be more thorough, and its results would carry much more instruction to the mind of Parliament, and of the country, than at any preceding period.

**MEMORANDUM OF THE IMPROVEMENTS
IN THE ADMINISTRATION OF INDIA
DURING THE LAST THIRTY YEARS**

1858

MEMORANDUM OF THE IMPROVEMENTS
IN THE ADMINISTRATION OF INDIA
DURING THE LAST THIRTY YEARS

1858

EDITORS' NOTE

In *Memorandum of the Improvements in the Administration of India during the Last Thirty Years, and the Petition of the East-India Company to Parliament* (London: Cox and Wyman, 1858), 1-101. On a contents page appear the sections here indicated by sub-titles, plus "Correspondence" and "Petition" (for the latter see the previous item). Appeared also in *PP*, 1857-58, XLIII, 1-38. Unsigned. Not republished by Mill. Identified in Mill's bibliography as "A small Volume, entitled 'Memorandum of the Improvements in the Administration of India during the last Thirty years;' printed by the E.I. Company and also laid before the House of Commons: of this I was partly the author and partly the Editor, the facts being furnished by the departments of the India House" (MacMinn, 90). There are no corrections in the Somerville College copy. On the title-page of the copy in the Chadwick Tracts, British Library CT 277 (1), Chadwick has written: "Copy of the Minute written by John S. Mill at the suggestion of E. Chadwick" (there seem more likely explanations).

Memorandum of the Improvements in the Administration of India during the Last Thirty Years

AT THIS TIME, when a calamity unexampled in the history of British India has excited an unusual amount of interest in Indian affairs, while the statements publicly made, and the opinions expressed, concerning the administration of the Indian Government, strikingly manifest the deficiency of correct information on the subject; a brief survey of the principal measures which have been of late adopted for improving the internal government of the country, and the physical and mental condition of its inhabitants, may be serviceable in removing false impressions, and in supplying materials for a deliberate judgment.

It may be thought that this survey would most fitly commence from the last renewal of the powers of the East-India Company, with some modifications, in 1853;¹ and it must be said that the years which have since elapsed have been marked by a degree of activity in every description of public improvement, not only greater than that exhibited previously, but unsurpassed, it is believed, in any country and in any age. An interval, however, of only four years is evidently too short to afford an intelligible view of a course of progressive improvement. The foundation of all the great measures which were in active progress during that interval, was laid at an earlier period; and the new measures which have been initiated during that brief term have not yet had time to exhibit tangible results. It is therefore necessary to trace the stream of Indian improvement from a point much higher up in its course; beginning at the origin of the measures which have contributed most, in each department, to give to the administration of India its present enlightened character.

REVENUE ADMINISTRATION, AND RIGHTS OF THE RURAL POPULATION

Connection of the Revenue System with the Rights and Condition of the People

In a country like India, the departments of public business on which the good government of the country, and the security and contentment of the people,

¹By 16 & 17 Victoria, c. 95.

principally depend, are the revenue administration and the judicial administration. The importance of a good and easily accessible administration of justice is the same in India as elsewhere; but the manner in which the entire economical condition of nearly the whole population is determined by the management of the revenue department, cannot, by persons unacquainted with India, be understood without special explanations.

Everywhere, indeed, it is of first-rate importance to a people that the taxes should be of moderate amount; that they should be certain, not arbitrary; and that they should be so assessed and levied as neither to favour one person or class at the expense of another, nor to interfere injuriously with industry. These requisites, too, are obviously of more than their ordinary importance, where the bulk of the tax-paying population consists of persons depending for subsistence on their own exertions in tilling the soil. But these general considerations afford only an imperfect conception of the relation of the tax-paying cultivator in India to the revenue system. Throughout the greater part of India, there is no intermediate landlord between the immediate cultivator and the State. The cultivator does not pay rent to one person and taxes to another: his taxes *are* his rent (or a part of his rent); and his condition is affected by the good or bad quality of the fiscal administration, in every way in which the condition of a European tenantry can be affected by a good or a bad landlord. And there is an additional fact, of greater importance than all the rest. The titles to land, and to all rights issuing out of land, (that is, to all the property of the country, except a small percentage), are in India a branch of the revenue administration. The revenue records, which show who were the persons held responsible for the revenue by the officers of former governments, are the general register of title. They always constitute the principal, and in many cases the sole, reliable evidence of right to the land. While the British Government confined itself, as it necessarily did on the first acquisition of any district, to annual or short settlements, it had no need to look beyond the fact of actual possession; but when it began to grant leases or settlements for long terms of years, it was bound to ascertain that the persons whom it admitted to these engagements were those really entitled to the land. This could only be done by minute local inquiries; and justice required that these should be judicially made, and a full hearing given to all parties on the spot. The revenue officers of Government being thus under the necessity, for revenue purposes, of investigating and ascertaining all titles to land, it has been deemed proper that the adjudication so performed should have the force of a judicial decision; though, if any of the persons interested considers himself aggrieved by the decision, he can seek redress by a suit in the regular courts. It is hence apparent, that in India every revenue officer is also, in the most important sense of the word, a judicial officer. The security of the most important and extensive class of proprietary rights throughout the country, depends upon the manner in which the revenue branch of the Government performs its judicial functions; and the history of the revenue

administration of India is the history of its landed property, and of the economical condition of the whole agricultural population.

Permanent Settlement of the Lower Provinces of Bengal

An important mistake, committed with the most generous intentions by the administration of Lord Cornwallis towards the end of the last century,² has divested the Government, in the oldest and most fertile of its Indian possessions, of this great power of influencing beneficially the condition of the cultivators of the soil. In the provinces of Bengal and Behar, to which were subsequently added Benares, and some districts of the Madras Presidency, the Government gave away its rights over the soil to private landlords, reserving only from each estate an annual payment, which it solemnly bound itself never to increase. It is not necessary here to enter into the disputed questions respecting the original character and rights of these landlords or zemindars. There is no doubt that many of them were persons of hereditary influence and station in the country, and that their connection with the lands, of which they were now recognized as the proprietors, had in general been of a permanent character. But their position was nevertheless essentially that of middlemen; collecting the revenue, not for themselves, but for the Mogul Government; accounting to that Government for their receipts, and remunerated by a percentage (generally ten per cent) of the collections. It is now universally admitted that they never had the power of disposing arbitrarily of the land. There were, everywhere, at least large classes of tenants, whom they could not lawfully eject, except for non-payment of revenue, and from whom they could not lawfully exact more than the customary payments.

These rights of the occupying tenants it was the full intention of Lord Cornwallis to preserve. But the Government demand being now fixed in perpetuity, and claimable from the landlord only, the revenue officers had no longer any power of interposing in favour of the tenantry; and their rights were henceforth left for protection solely to the courts of justice. But the courts of justice could proceed only by regular suit, on the complaint of the injured party. The poverty of the people, their passive character, and the extreme difficulty of proving by legal evidence, before a distant tribunal, what were the customary rates, have rendered this protection illusory; the rights of the Bengal ryots have (as has been said) passed away *sub silentio*,³ and they have become, to all intents and purposes,

²Charles Cornwallis (1738-1805), Earl and then Marquis Cornwallis, was Governor-General 1786-93.

³See Francis Rawdon-Hastings (1754-1826), Marquis of Hastings, previously Earl of Moira, "Minute by the Right Hon. the Governor-General on the Revenue Administration of the Presidency of Fort William, dated the 21st September 1815." App. 9 in *Minutes of Evidence Taken before the Select Committee of the House of Commons on the Affairs of the East India Company, III: Revenue, PP, 1831-32, XI, 450.*

tenants at will. These facts are not adverted to for the purpose of casting blame on a generation long gone by, whose mistakes are sufficiently explained and excused by the short experience they had then had of India, and the extreme difficulty which persons nurtured only in English ideas and institutions, have in correctly apprehending a state of facts so entirely unlike anything which ever existed in England, as the whole framework of Indian society presents. But justice to the subsequent Governments of India requires it to be understood, that in the most fertile and valuable portion of the Indian territory, they inherited from their predecessors an agrarian system, consisting of great landlords and cottier tenants, forming as close a parallel as the difference between Europe and Asia will admit, to the condition of Munster and Connaught; and that the Government has had, during the last sixty years, no more power of correcting the evils of this system, than the Government of the mother country had, during the same period, of remedying the evils of a similar system in Ireland. The tenacity, however, of old impressions, which characterizes the Hindoos, has kept alive the idea of a right still existing in the actual cultivator to hold his land at a rent fixed by custom, not by arbitrary will; and this traditionary feeling, from which the landlords themselves are not exempt, must form the basis of anything that can be hereafter done to improve the tenure of the Bengal ryot.

Present Improvements in Bengal

What the Government had it in its power to do, for alleviating the operation of the existing system, it has done. It takes systematic measures for the education of zemindars who are wards of Government. It has made imperative on the landlords to give to every tenant a written engagement, specifying the amount of rent and the conditions of tenure; and it has made these engagements legally binding.⁴ It has done more. Owing to the hasty and careless mode in which the permanent settlement was in the first instance conducted, the boundaries both of estates and of villages or townships were undefined, and not only the litigation but the affrays, occasioned by boundary disputes, had grown into a public evil. The revenue officers were so ill informed on the subject, that in some cases estates advertised for sale on account of arrears of revenue, were purchased, and possession was demanded, when it was found that the estate existed only in the collector's books, having been swept away by the changes in the bed of the river, or absorbed by the encroachments of the neighbouring landholders. To remedy these evils, a survey was determined on, and has been for several years in progress, for the purpose of ascertaining what estates are in existence, and determining their boundaries. This survey has already produced very appreciable benefit, and holds out the promise of much more.*

⁴By Regulation VIII (1 May) of 1793, in *Regulations of the Government of the Presidency of Fort William in Bengal, 1793-1834*.

*See Appendix A [pp. 155-6 below].

The Governments which have administered Indian affairs in the present generation, have abstained from imitating elsewhere the errors which were committed in the permanent settlement of Bengal. Their object has been, as new provinces were successively brought under British rule, to ascertain accurately the persons, and classes of persons, who by law or usage had a beneficial interest in the land, and the nature and extent of the beneficial interest of each; and having thus determined who were the persons with whom the settlement of the revenue should be concluded, to define the demand of Government on each, and limit it to the smallest amount consistent with the public necessities.

The subsequent revenue administration of India is a succession of conscientious endeavours to fulfil these duties; endeavours which, in a large portion of India, have been rewarded by signal success, and in the remainder are in rapid progress towards it.

Ryotwar System in Madras

Nearly the whole territory of the Madras Presidency became part of the British possessions at a period subsequent to Lord Cornwallis's permanent settlement; and its revenue system was principally founded by two of the ablest men who have ever taken part in the government of India—Colonel Reade⁵ and Sir Thomas Munro. Under this system, the land is not made over to great landlords, but the actual cultivator, the peasant himself, is regarded as the proprietor of the soil, subject to the payment of the Government demand. He has the option annually of increasing or diminishing his holding; and, in the words of the Madras Government in their last general report, "has all the benefits of a perpetual lease, without its responsibilities, inasmuch as he can, at any time, throw up his lands, but cannot be ejected as long as he pays his dues."⁶ He also receives assistance, by remission of assessment in unfavourable seasons. The practical operation of this, which is known as the ryotwar system, evidently depends on the certainty and moderation of the Government demand. For many years these two conditions were very insufficiently realized. The extreme difficulty, to a European revenue officer, of ascertaining the real capabilities of each petty holding, and his unavoidable dependence, for much of his information, upon native subordinates, made it inevitable that great errors should be committed in the first assessments. Some were unnecessarily low, but a much greater number were too high; and if not so at first, many afterwards became so, when the security which our rule had given from the ravages of war and internal depredation, had produced its natural effect in the

⁵Alexander Read (d. 1804) served in the Madras Army, rising to the rank of Colonel in 1804. He won repeated commendations for his revenue settlement work as Collector of Baramahal and Salem between 1792 and 1799

⁶"Report on the Administration of Public Affairs in the Madras Presidency," *General Report on the Administration of the Several Presidencies and Provinces of British India during the Year, 1855-56*, Pt. I (Calcutta: Calcutta Gazette Office, 1857), p. 11.

extension of cultivation, and consequent lowering of the price of agricultural produce; whereby, notwithstanding the increased well-being of the ryots, the same money rent became a burthensome exaction, which was comparatively little felt when the produce bore a higher price. These circumstances were, as justice required, allowed for, and reductions made, but not always sufficiently early, nor to a sufficient amount. And so long as the Government demand was too heavy, it was also uncertain, owing to the necessity of an annual inquiry to test the justice of claims to remission.

Up to this time, it could not be said that the British Government in India had anywhere succeeded in establishing the revenue administration on a sound basis. But inquiries and discussions of the utmost importance were going on, and knowledge was being acquired, the want of which at former periods had led to all the mistakes. It was in the settlement of the North-western Provinces that the fruits of this increased knowledge were first gathered in.

Settlement of the North-western Provinces

The greater part of what are called the North-western Provinces became part of the British dominions through the consequences of Lord Wellesley's Mahratta wars, in the first years of the present century.⁷ For a considerable number of years after the conquest, the revenue arrangements were of necessity provisional. Such serious consequences having been experienced in Bengal from hastening to establish a permanent system, when the knowledge acquired was not sufficient for framing it rightly, there need be no wonder if, in a new field, considerable time was in the first instance devoted to becoming acquainted with the capabilities of the country, and the prescriptive rights of the different classes of its inhabitants. The delay was amply justified by its results. The settlement of the North-western Provinces, commenced and completed between 1834 and 1844, by some of the most distinguished of the Company's servants, among whom the most conspicuous in merit was Mr. Robert Mertens Bird, is the first great monument which the British rule in India has exhibited, of wise, deliberate, but thorough reform, grounded on complete knowledge of the subject, and equally efficacious in removing present evils and in providing for future improvement.⁸

It is now known that in the greater part of India, and without doubt originally throughout the whole, the property in the land (so far as that term is applicable at all in India) resides neither in the individual ryot, nor in the great officers who collected revenue for the former native governments, but in the village

⁷Wellesley's great talents were displayed in the second Mahratta war of 1803-05.

⁸Robert Mertins Bird (1788-1853), an expert on land tenure, was appointed to the Board of Revenue (Allahabad) in 1832, and then was in charge of the revision of settlement in the North-western Provinces 1834-41.

communities. The village community is not co-extensive with the cultivating inhabitants of the village: it consists of the descendants or representatives of those by whom the village was, at some remote period, conquered, or reclaimed from waste. In most cases these proprietors are a part, and in some the whole, of the agricultural population of the village. When they are only a part, the remainder consists of persons, or the descendants of persons, who have taken up their residence in the village at later periods, and had no other original right than the permission of the proprietors; but some of whom have, by grant or prescription, acquired a fixity of tenure, while others have remained tenants at will. The village proprietors formed prescriptively the municipal government of the village; a fact of great importance, village government being the only institution, properly so called, which the Hindoos possessed.

It was with the village communities, as thus defined, that the settlement of the North-western Provinces was made; with a reservation and definition of all rights which had been acquired by any of the ryots under them. The time occupied in the operation was about ten years, and the expense incurred in it was upwards of £500,000. It comprehended a detailed survey of a country about 72,000 square miles in extent, containing a population of more than twenty-three millions. The difficulty and complication of the process will appear from the appended note.*

The proprietary rights, as ascertained and recorded at the survey, were confirmed in perpetuity; but the Government assessment was fixed, in some cases for twenty, generally for thirty, years. In a few of the districts, the term of settlement has expired, or is on the point of expiring. On resettlement, the assessment is liable to revision, and may be increased if the net produce of the land has augmented, but not proportionally to the increase of the net produce; and a pledge has besides been given, that a liberal consideration will be allowed for "improvements attributable only to the efforts of the tenant himself, and especially with regard to such as are of a comparatively recent date."⁹

The effect of the settlement upon the general pressure of the Government demand was to remove irregularities, and in general to lighten the aggregate burthen; the only exceptions being Goruckpore and Azimgurh, in which districts, though they are known to be still lightly taxed, a considerable increase was effected. The beneficial results may be traced in the improved condition of the population, and the ease and punctuality with which a revenue of more than £4,000,000 is collected, as evidenced by the small amount of outstanding balances, and the great diminution in the number of coercive processes for the enforcement of payment.

*See Appendix B [pp. 156-7 below].

⁹"Despatch of the Court of Directors, 13 August, 1851, on the Settlement of the North-western Provinces," in "Selection of Papers Relating to the Revenue Survey and Assessment (India)," *PP*, 1852-53, LXXV, 304.

Settlement of the Punjab

After this great economical and social reform had been for some years in operation, the important territory of the Punjab became, by the event of the Sikh war, a part of British India. This took place in 1849. And now was seen the full value of the superior knowledge of native rights and institutions, which had been acquired since the period of Lord Cornwallis's settlement. The task of bringing the Punjab under British rule was confided to men wisely selected from the body of public servants who had effected and administered the settlement of the North-western Provinces. The principles of the settlement, being grounded on a correct knowledge of the prescriptive rights of all classes, were found equally applicable to the adjacent territory of the Punjab. In India, as in other countries, great reforms have usually been of slow introduction. Our revenue improvements, so long as they were merely tentative, were necessarily slow. But their authors were now able to proceed with the ease and decision of men who thoroughly understood their work. There is something striking in the rapidity with which the latest and best principles of Indian policy, both in revenue and judicial administration, were at once applied to the Punjab by the consummate administrators to whom the discernment of the Marquis of Dalhousie had committed the government of the province.¹⁰ Before a year had elapsed from the first acquisition of the country, great progress had already been made in the introduction of the system of the North-western Provinces, with its most recent improvements. The greater part of the Punjab in extent, and by far the greatest in point of importance, has since been settled for terms of years. The leases were usually shorter than in the North-western Provinces; but the assessment was lowered, as compared with that of the native Government, by Rs. 72,37,244, or £723,724; being not less than twenty-five per cent. It has been ascertained that the Government demand does not exceed one-fifth of the gross value of the produce in rich tracts, and one-sixth, or one-eighth, or even less, in poor tracts. The result has been a peace and security never before known in the province; a rapid increase of cultivation and production; and a contentment with our rule, which has enabled this newly-conquered territory, inhabited by the most warlike population of India, to become the base of our operations for the recovery of our older territories, and has made the Sikhs, so lately in arms against us, an important part of our strength for subduing the general revolt of the Bengal army.

Bombay Ryotwar Reform

While these great improvements were taking place in the north of India, a reform of equal magnitude was being inaugurated in the west and south. The

¹⁰James Andrew Broun Ramsay (1812-60), Marquis of Dalhousie, was Governor-General of India 1848-56.

reformed revenue administration of those territories is not grounded on the village, but on the ryotwar principle. The ryotwar system, or that which recognizes the actual cultivator of the soil as its proprietor, and collects the Government revenue directly from him, is the general system of the South of India. Circumstances already mentioned had, during many years, prevented this system, even under the able management of Sir Thomas Munro, from operating beneficially on the prosperity of the people. As, in Northern India, the territories latest acquired were those which first had the benefit of our improved knowledge and experience; so, the earliest example of a successful ryotwar system was in the districts (forming the greater part of the Bombay territories) which came under British government at the close of Lord Hastings's Mahratta war, in 1818.

The village communities still existed in those territories; and if the village system had been as well understood in 1818 as it was in 1838, the settlement of the Deccan would probably have been made on the same principles as that of the North-western Provinces. Such, however, was not the case: Sir Thomas Munro's principles were then in the ascendant; the settlement was, for the most part, ryotwar; and until about twenty years ago, little had been done to improve the fiscal administration of these territories, beyond the removal occasionally, as they were brought to notice, of vexatious and oppressive taxes, which had been added to, or incorporated with, the land revenue, during the declining period of the Mahratta power. The assessments which we found in force were generally, even after these reductions, excessive; and large remissions were annually required, which necessitated every year an inquisitorial investigation into the affairs of each ryot who claimed a share in the remissions. The agricultural population, being always liable to be called on for an amount of rent which could only be paid in the most prosperous seasons, were constantly in arrear, and were therefore without any incentive to improve their condition.

To remedy these evils, a survey of the country and general revision of the assessment, were undertaken.¹¹ The operation commenced in the Deccan and Southern Mahratta country, where it is now nearly, if not quite, completed; and it is gradually being extended to the northern districts of the Presidency, as the experienced officers, European and native, who have been trained to this difficult duty, can be spared for the purpose. In the northern districts, however, the progress of the survey has been retarded by the greater complication of the landed tenures there prevalent, and by the existence of various classes of middlemen, who, like the talookdars of Oude, are hostile to our improvements, because, though preserving to them their pecuniary rights, they interfere with their power.

¹¹See "Official Correspondence on the System of Revenue Survey and Assessment Best Adapted for, and More or Less Completely Carried into Effect in the Collectorates of Poona, Sholapoor, Ahmednuggur, Belgaon and Dharwar, in the Bombay Presidency," in "Selection of Papers Relating to the Revenue Survey and Assessment (India)," *PP*, 1852-53, LXXV, 312-402.

Where any ancient proprietors, either middlemen or village communities, were found in existence, and in possession of their proprietary rights, at the time of the survey, those rights have been respected; but in general, the principle of the reformed Bombay system is ryotwar. The land, cultivated and waste together, is divided into portions called fields, the extent of a field being for the most part fixed at the quantity of land which can be cultivated with one yoke of bullocks. On each field the Government demand is fixed, for a period of thirty years, at a very moderate rate. While the contract is binding on the Government, the ryot, on his side, can throw up the land at pleasure; and he is not required to pay the assessment for any year, on any field which he has not cultivated, or undertaken to cultivate, in that year. The appended note explains the details of the process.*

The fixation of the Government demand for thirty years would have been of little service to the ryot, if the demand had remained so high as to require, almost every year, remissions of uncertain amount. But it has been fixed on a very low scale, the reduction of the assessment generally exceeding considerably the average amount of remissions and balances under the former system. The effect of this reform is visible in the large increase of cultivation which has always taken place after the completion of the survey of a district; in the realization of the revenue, with scarcely any balance remaining in arrear (in some years with absolutely none); and in the fact, that in all the surveyed districts lands are frequently underlet. These important results have been purchased by an immediate sacrifice of revenue; but the encouragement which a fixed and moderate assessment gives to the occupation of waste land, is gradually making up to Government for the loss; and in some of the surveyed districts, the revenue under the new settlement already exceeds that under the old.

The eminent success of the reformed ryotwar system of Bombay has established the fact, which many Indian authorities trained in a different system had doubted, that the ryotwar, or peasant-proprietary system, may be so organized, and so worked, as to be neither oppressive nor arbitrary; and that, when so organized and worked, it brings the motives to exertion, and to the exercise of intelligence, which property gives, to bear upon those on whom the prosperity of agriculture most depends—the actual cultivators of the soil. In all those parts of India, therefore, in which the village communities have been broken up by the distracted state of the country for generations, or in which the exclusive title of the representatives of the old proprietors has been superseded by the prescriptive rights acquired by the actual cultivators, ryotwar is now the recognized system of revenue management.

Madras Improvements

In the Madras Presidency, considerable improvements in the detail of the revenue system preceded the steps recently taken for a general revision. The most important of these are the two following. In 1837, it was adopted as an universal

*See Appendix C [pp. 157-9 below].

rule, that no land should be more heavily taxed, in consequence of its being applied to the cultivation of a more valuable description of produce.¹² The demand was thenceforth fixed on a general estimate of the productive power of the land, with reference to the staple productions of the country; and the ryot was left perfectly free to cultivate whatever he pleased, without being in any case liable, on that account, to an increased demand. From this time, therefore, there has not been even the semblance of foundation for the statement often made, that the land assessment is a discouragement to the growth of the more valuable products, and, in particular, of cotton. To go any further would be to demand a lower rent from lands on which cotton is grown, than from land devoted to other cultivation: which would be to give a bounty on the production of cotton.

The other great improvement was the establishment of the rule, that no ryot should be required to pay an additional tax (or rent) for his land, in consideration of increased value derived from improvements made by himself.¹³ If, therefore, a proprietor, by labour or outlay of his own, sinks wells, constructs tanks, or plants valuable trees, he enjoys, not for the duration of any settlement, but in perpetuity, the full benefit of the increased value which he has given to the land; an assurance which no private tenant in any country, even of Europe, has obtained.*

Large reductions of the assessment have also been made in the most heavily-taxed districts, which have in general produced so great an extension of cultivation, that the revenue has scarcely suffered.

Ryotwar Reform in Progress at Madras

In 1855, the present enlightened Governor of Madras submitted a plan for a survey and revised assessment of the whole of the Madras territory, on the Bombay principle, to the consideration of the Governor-General in Council.¹⁴ Having obtained the approval of that authority, it was laid before the Court of Directors, and received their formal sanction in a despatch dated the 17th of December, 1856; in which also several improvements were indicated, of which the scheme appeared to be susceptible.¹⁵ A commencement has thus been made in removing the last remaining blot in the administration of the land revenue of British India; for the

¹²"Circular Order of 13 Nov., 1837," in John Maskell, *The Circular Orders of the Board of Revenue from A.D. 1820 to 1850* (Madras: Christian Knowledge Society's Press, 1851), pp. 243-6.

¹³"Circular Order of 25 Nov., 1852," in John Maskell, *The Circular Orders of the Board of Revenue Issued during the Years 1851-1852-1853* (Madras: Christian Knowledge Society's Press, 1854), pp. 110-19.

*See Appendix D [p. 159 below].

¹⁴George Francis Harris (1810-72), Lord Harris, Governor of Madras 1854-59, "Minute of the Right Honourable Lord Harris, on the Proposed General Survey and Assessment" (26 Oct., 1854), in "Papers Relating to the Revised Survey and Assessment of the Madras Presidency, and on the Godavery and Kistna Annicuts," *PP*, 1857, Sess. 2, XXIX, 173-85.

¹⁵"Letter from Court of Directors to Government of Fort St. George," *ibid.*, pp. 186-93.

social and economical condition of the Lower Provinces of Bengal is, for reasons already explained, no longer dependent upon the revenue system.

Under both the reformed modes of revenue administration, the village system of the North-west Provinces and the Punjab (the introduction of which into the more recent acquisitions of Nagpore and Oude has been sanctioned) and the ryotwar system of the Bombay and Madras presidencies, the agricultural population either have, or will shortly have, the benefits of tenures and rights perfectly defined and secured, and moderate rents fixed for a sufficient term to afford, in full strength, the natural incentives to improvement. It should be remembered also, that on the expiration of the thirty years settlements, the holders will not be liable to be ejected. They will only be liable to a revision of the amount of the rent paid to Government; and it is the declared intention of the authorities, that not merely the same; but a still greater degree of moderation, shall be observed in the future, than in the past, settlements.

A further exemplification of the manner in which the Indian authorities now take advantage of the latest experience for purposes of improvement, is afforded by recent proceedings in two limited portions of the territory of India. Cuttack is a portion of the Lower Bengal Provinces, to which the permanent settlements of Lord Cornwallis were never extended. The revenue system of Cuttack is ryotwar; but the attempt has latterly been made to combine the advantages of the ryotwar principle, with a portion of those of the system of the North-west Provinces. The assessment is made on each holding, and the payment to be made by each ryot is fixed, by the Government officers; but the collection of it from the individual ryots by native revenue officers, with the opportunities it affords for vexation and corruption, is done away with: the ryots elect a few of their number to represent the rest; these become responsible to Government for the whole revenue of the village, and take on themselves the recovery from the other ryots of their portion of the payment, according to the terms of the settlement; having recourse to the tribunals, if (which is not a common occurrence) such aid is required. This mixed system of ryotwar and village management, having been successful in Cuttack, is in course of introduction into one of our latest acquisitions, the districts made over to our permanent administration by the Nizam; and the plan has been recommended by the home authorities to the attention of the Madras Government, with a view to eventual application to that presidency.

Fiscal System of India

After this review of the present revenue administration of India in its bearing on the social relations, proprietary rights, and economical condition of the mass of the people, it remains to speak of it as a merely fiscal system.

Land Revenue

Nearly two-thirds of the revenue of India consist of the rent of land. So far as this

resource extends in any country, the public necessities of the country may be said to be provided for, at no expense to the people at large. Where the original right of the State to the land of the country has been reserved, and its natural, but no more than its natural, rents made available to meet the public expenditure, the people may be said to be so far untaxed; because the Government only takes from them as a tax, what they would otherwise have paid as rent to a private landlord. This proposition undoubtedly requires modification in the case of a ryot or peasant cultivating his own land; but even in his case, if the Government demand does not exceed the amount which the land could pay as rent if let to a solvent tenant (that is, the price of its peculiar advantages of fertility or situation), the Government only reserves to itself, instead of conceding to the cultivator, the profit of a kind of natural monopoly, leaving to him the same reward of his labour and capital which is obtained by the remainder of the industrious population.

Any amount whatever of revenue, therefore, derived from the rent of land, cannot be regarded, generally speaking, as a burthen on the tax-paying community. But to this it is of course essential that the demand of revenue should be kept within the limits of a fair rent. Under the native Governments, and in the earlier periods of our own, this limit was often exceeded. But under the British rule, in every instance in which the fact of excessive assessment was proved by large outstanding balances and increased difficulty of realization, the Government has, when the fact was ascertained, taken measures for reducing the assessment. The history of our government in India has been a continued series of reductions of taxation; and in all the improved systems of revenue administration, of which an account has been given in the preceding part of this paper, the object has been not merely to keep the Government demand within the limits of a fair rent, but to leave a large portion of the rent to the proprietors. In the settlement of the North-west Provinces, the demand was limited to two-thirds of the amount which it appeared, from the best attainable information, that the land could afford to pay as rent. The principle which has been laid down for the next settlement, and acted on wherever resettlement has commenced, is still more liberal: the Government demand is fixed at one-half, instead of two-thirds, of the average net produce; that is, of a fair rent. The same general standard has been adopted for guidance in the new assessment of the Madras territory. In Bombay no fixed proportion has been kept in view; but the object has been, that land should possess a saleable value. That this object has been attained throughout the surveyed districts of Bombay, there is full evidence: and as the ryots have been secured from increase of revenue for the space of thirty years, the value of land may be expected, from the progress of improvement, to be constantly on the increase.

Opium

It has been shown above, that by far the largest item in the public revenue of India is obtained virtually without taxation, because obtained by the mere interception of a payment, which, if not made to the State for public uses, would

generally be made to individuals for their private use. A similar remark though for a different reason, is applicable to the second in amount of the sources of Indian revenue,—that of opium. The opium revenue is not derived from the taxation of any class of her Majesty's subjects, but is (as far as this can be truly said of any impost) paid wholly by foreigners. It cannot reasonably be contended that this is an improper source of revenue, or that the burthening of an article considered to be noxious, with an amount of taxation which has sometimes caused it to be sold for its weight in silver, can be liable to objection as encouraging the consumption of the article. Whether this revenue, of between four and five millions sterling, should be levied as it is at present in Bengal (though not in Bombay) by a Government monopoly, or in the more usual form of an excise duty, is a question of detail on which opinions differ, and which is open to consideration. The former mode has hitherto been retained, under the belief that the unrestricted production and sale of the article would give such facilities to smuggling, as would render the realization of anything like the present amount of revenue impossible. It might, however, be practicable—though this is doubtful—to maintain the price in the foreign market by restrictions on exportation; but it is matter for serious consideration whether any system involving the free cultivation of the poppy, would not expose India itself, which has hitherto been comparatively free from this kind of hurtful indulgence, to be flooded with the article at a low price.

Salt

The third item, in point of amount, of the revenue of India, is that from salt. This is the only considerable tax existing in India which can be regarded as objectionable in principle, and the entire abandonment of which, if financially practicable, would be a benefit to the people at large. It is impossible, however, to look upon this impost in the same light in which it would deserve to be considered if it were levied in addition to other heavy burthens. We must bear in mind, in extenuation of the objections to a tax on salt, that it is, speaking generally, the only tax which the labouring ryot of India pays.

The revenue from salt is commonly said to be obtained by means of a monopoly. This, however (as will be seen by the appended note,* is strictly true only of the Madras Presidency; and even there the monopoly is of a very qualified description, since the importation of the commodity is free, subject to a duty considered equivalent to the profit charged by Government on the salt produced by it. In the Bombay territory there never has been a monopoly, or even a Government manufacture. There is an excise duty, imposed to compensate for other more objectionable taxes, yielding a far greater amount of revenue, which have been abolished. The Government of India, in 1844, fixed this excise duty at one rupee per maund of 82 $\frac{2}{7}$ lbs.; but before this rate had come into operation, it was

*See Appendix E [p. 160 below].

reduced by the Court of Directors to twelve annas (three-fourths of a rupee).¹⁶ In the same year, and for a similar reason—namely, to compensate for other taxes then abolished—the Government of India fixed the selling price of the monopoly salt in the Madras Presidency, at one and a half rupees per maund; but the Court of Directors immediately reduced it to one rupee.¹⁷

In Bengal, up to 1836, there was a real monopoly. In that year, in anticipation of the subsequent recommendation of a Committee of the House of Commons, the Bengal system was fundamentally modified.¹⁸ The present system is, to ascertain the actual cost to Government of all descriptions of salt manufactured at the Government works, and to issue it to dealers in any quantity applied for, at a price equal to the cost with the addition of a fixed duty. Importation is free, subject to the payment of the same duty. The duty has been gradually lowered from three sicca rupees per maund (equivalent to 3 1/4 Company's rupees) to 2 1/2 Company's rupees (about three farthings per pound); while the Madras duty is only 7/8 of a rupee, and the Bombay only 3/4 (less than a farthing per pound). The reduction in Bengal, not having been attended with the hoped-for increase of consumption, has not been carried further. Even if the revenue derived from salt were not required for the necessary purposes of government, it is still conceived that more good would be done to the people by retaining the tax, and expending its proceeds in roads and works of irrigation, than could possibly be done by its remission.

Within the last three years, the manufacture of salt in the districts round Calcutta has been laid open to all who are willing to engage in it, subject to excise regulations. Very little use, however, has been made of this liberty, the quantity of salt manufactured under license having only amounted to from 20,000 to 25,000 maunds. It is hoped that the quantity will increase, and that private enterprise may in time supersede Government agency. But the small amount of response made to the encouragement held out, is a presumption that the Government arrangements for the manufacture and sale afford as marketable an article, at as low a cost, as could be produced by private manufacturers.

Tobacco Monopoly abolished

The tobacco monopoly which formerly existed in the Malabar provinces of the Madras Presidency, and which yielded an annual revenue of about six lacs of

¹⁶The duty was fixed by Act XVI of 1844 (27 July), *PP*, 1845, XXXIV, 67. The reduction was ordered on 3 July; see "Extract of a Despatch in the Separate Revenue Department, from the Court of Directors to the Governor-General in Council," *ibid.*, p. 79 (Sect. 14).

¹⁷The price was fixed in Act VI of 1844 (16 Mar.), *PP*, 1846, XXXI, 36-48. The reduction was ordered on 3 July in the despatch cited in the previous note, pp. 78-9 (Sect. 10).

¹⁸Act XIV of 1836 (30 May), *PP*, 1840, VII, 414-20, in anticipation of "Report from the Select Committee on Salt, British India" (2 Aug., 1836), *PP*, 1836, XVII, 1-371, esp. p. 3.

rupees (£60,000), was abolished in 1852, without equivalent:¹⁹ and this article is now wholly untaxed.

Customs

The customs, in India, are not a very productive source of revenue, the classes who consume any considerable amount of foreign productions being comparatively limited. There is no branch of taxation in which the burthens of the people have been more conspicuously lightened by the British Government. The most important taxes levied on commodities by the native Governments of India, were the inland customs, or transit duties. Every petty chief whose territory was situated on any of the great lines of commerce, made use of his position to extort from traders the largest sums which they could be induced to pay. In the British territories, these duties have been entirely abolished: in the Lower Bengal Provinces as early as the administration of Lord Cornwallis (reimposed in a modified form in 1801, and finally abolished in 1836);²⁰ in the North-western Provinces from 1834 to 1836;²¹ in the Bombay Presidency in 1837;²² in Madras in 1844;²³ and in our other possessions immediately after their acquisition. This was not a small sacrifice of revenue. The transit duties in Madras alone yielded a net revenue of about thirty-one lacs of rupees, or £310,000 sterling. Several of the native princes have, with praiseworthy liberality, followed the example of the British Government, by abolishing, or greatly lowering, their transit duties;²⁴ and the diplomatic influence of our Government is freely used to encourage this policy. In cases in which the duties levied by some particular chief have been an obstruction to important lines of mercantile communication, and in which it was not probable that the chief would be indemnified for their loss by the increase of his other sources of revenue, our Government has even purchased his assent by pecuniary compensation.

Besides these duties, the sale of goods was, under the native Governments, hampered by innumerable exactions, laid on under various pretences, most of which we have, on every occasion of coming into possession of a new territory, abolished or commuted. But some taxes on internal trade still remained even in the British territories. The last of these has been swept away less than two years ago,

¹⁹Court of Directors' Revenue Despatch to Madras, No. 14 of 22 Sept., 1852, India Office Records [IOR]: E/4/977, pp. 517-37.

²⁰Initially on 20 June, 1788, confirmed by Bengal Regulation XLII of 1793 (1 May). The duties were reimposed in principal towns by Bengal Regulation XI of 1801 (6 Aug.), and abolished by Sect. 1 of Act XIV of 1836.

²¹The transit duties were formally abolished by India Act XIV of 1836 (30 May), although administrative orders directed against them began in 1833.

²²By Act XVII of 1837 (24 July), *PP*, 1840, XXXVI, 65-9.

²³By Act VI of 1844.

²⁴See, e.g., "Engagements within the Raja of Biccaneer and the Nawab of Bahawalpore, Respecting Transit Duties," *PP*, 1845, XXIV, 70-1.

by an order from the home authorities, bearing date the 5th November 1856, for the abolition of the Mohturfa, or tax on houses, trades, and professions, in the Madras Presidency.²⁵ There are now no internal customs in British India, except, in some cases, town duties; and these, not for general, but for local purposes, and as far as possible under local management; though the exertions of the Indian Governments to foster a municipal spirit, and induce the inhabitants of towns to take an active part in the management of town affairs, are only beginning, and very slowly, to be successful.

There has been similar activity in reducing the duties on the external commerce of India, and extending the principles of free trade. In the recent acquisitions of Sind and the Punjab, the frontier duties have been entirely abolished, and those territories are outside our customs line. On the frontier line between the Punjab and the North-western Provinces, customs are paid on salt and sugar only. In Southern India the land tariff is the same as that on imports by sea. The discriminating duties on goods carried in foreign vessels were abolished in 1848; and in 1850 the coasting trade was thrown open to the ships of all nations.²⁶ In thus abolishing the navigation laws, the Government of India preceded the Imperial Government.²⁷ The three presidencies were formerly, in regard to commerce, treated as distinct settlements, and the trade between them subjected to the same duties as that between India and Great Britain. In 1848 this trade was completely thrown open,²⁸ and the whole of British India treated, for customs purposes, as one empire; and great success has attended the efforts of the Company to obtain for the produce of native states in dependent alliance with us, the privilege of admission into the ports of the United Kingdom at the rates of duty chargeable on goods of British origin. The duty levied on British goods imported into India is five per cent *ad valorem*. There is still a distinctive double duty on many articles imported from foreign countries; and a general export duty of three per cent (from which however cotton is exempt) on the produce and manufactures of India. These are admitted defects; and the export duties were marked out by the home authorities, in a despatch of 1846, to be dispensed with at the earliest period which financial considerations may permit.²⁹

²⁵See "Letter from the Court of Directors to the Governor-General of India in Council, Revenue Department, 5 Nov. (No. 17), 1856," in "Correspondence Relating to East India Affairs," *PP*, 1857, Sess. 2, XXIX, 412-14.

²⁶By, respectively, Act VI of 1848, *PP*, 1851, XLV, 115, and Act V of 1850, *PP*, 1852, XXXVI, 39.

²⁷The parallel Imperial enactment was 12 & 13 Victoria, c. 29 (1849), which, in Sect. 6, threw open the Indian coasting trade to all nations starting in 1850.

²⁸Again by Act VI of 1848.

²⁹See "Letter from the Court of Directors to the Governor-General of India in Council, Separate Revenue Department, 22 Apr. (No. 3), 1846," *Sessional Papers of the House of Lords*, 1847-48, XXX, 462.

Post-office

The post-office in India, as in England, is maintained more for public convenience than as a source of revenue. Its improvement in India has fully kept pace with that in England. Reductions of postage, and the removal of practical impediments and imperfections, may be said to have been constantly in progress; and the great change recently made in the post-office system of this country has been imitated, with equal success, in India.³⁰ The principle of uniform postage, without reference to distance, has been adopted, and letters and newspapers are conveyed from Cape Comorin to Peshawur at the same charge as for the shortest distance. The lowest rate is half an anna, or three farthings, for a letter a quarter of a tola in weight (equivalent to about one-tenth of an ounce); it having been found by experiment that the average weight of native letters is considerably below this limit. There is an ascending scale of charges up to twelve tolas, above which weight letters are not conveyed by the ordinary post; but a parcel post is also maintained by Government, which they are prepared to abandon whenever the duty shall be undertaken by private enterprise. Newspapers are conveyed at a charge of one anna, or three halfpence each. The postage on letters and newspapers must be prepaid by stamps, under penalty of double postage on delivery. There is also a book post, at a minimum rate of one anna per twenty tolas (about half a pound), and an ascending scale up to 120 tolas, or three pounds. Arrangements have been made with her Majesty's Government for the conveyance of letters, newspapers, and books, from any part of England to any part of India, at low rates of postage, payable in one sum, either on despatch or receipt. The Post-office department for all India is under the control of a Director-General at Calcutta, immediately under the Government of India. The progress of improvements in every branch of the details has been very striking, and it is believed that the department will not suffer by a comparison with that of any other country.

The pecuniary results of the change to a low uniform postage have been as satisfactory as in England. It had been doubted whether such a population as that of India would take advantage of the facilities afforded for correspondence, to the extent necessary to make up, in any considerable degree, to the revenue, for the diminution of the rate. At the close, however, of 1855-56 (the first complete year of the new system), the number of chargeable letters had increased 101 per cent as compared with the preceding year, and 142 per cent as compared with 1849-50. The loss of revenue, which, if there had been no increase of correspondence, would have been Rs. 9,12,000, is only Rs. 3,01,869, and may be expected yearly to diminish.

General Prosperity

The general result of all these improvements in administration, combined with the security which our rule has for the first time given to property against the

³⁰In England, by 2 & 3 Victoria, c. 52 (1839); in India, by Act XVII of 1854 (not in *PP*).

ravages of war and fiscal rapacity, has been a great and rapid growth of general prosperity. Besides the remarkable increase of cultivation and population, the cheapening of agricultural produce, and the recovery of the revenue after great reductions, which have been already commemorated, there has been an enormous increase in the external commerce of India. The exports have risen from £7,993,420 in 1834-5, to £23,039,268 in 1855-6, being 188 per cent. The export of cotton amounted in the former year to 98,320,050 lbs., and in the latter to 237,179,949 lbs., being an increase of 141 per cent; but the quantity exported to England has increased in a much greater ratio, namely from 38,268,402 lbs. to 170,771,510 lbs., or 346 per cent. The export of rice, chiefly from the east coast of the Bay of Bengal, has so vastly increased that labour can scarcely be found to transport it to the coast; the wages of labourers have risen to an unexampled height, and the agricultural population of large districts are, for the first time in memory, out of debt to money-lenders and to their landlords. During the same period of twenty-one years, the imports into India have risen from £4,261,106 to £13,447,027, or upwards of 227 per cent; the great excess of exports above imports being regularly liquidated in silver.

JUDICATURE AND LEGISLATION

Judicial arrangements of Lord Cornwallis

The history of the judicial administration of British India bears a striking analogy to that of the revenue administration. It began with well-intended, but premature and ill-considered measures, which produced many evils, and but a small part of the good which their authors expected from them. When experience had disclosed the faults of the system at first adopted, similar errors were avoided, and a better system introduced into our later acquisitions; while palliatives of great value, though falling short of the full exigencies of the case, were adopted in the older provinces. Last came the plans, now in an advanced stage of their progress, for effecting a complete reform.

At the period at which the judicial arrangements of Lord Cornwallis were made, the ideas of civil judicature entertained in England still partook of an almost barbarous character. The English courts of law were still encumbered with all the technicalities, and disgraced by all the delay and expense, which had descended from the middle ages, or grown up in the attempt to make the institutions of the middle ages suffice for the wants of modern society; and unfortunately these courts, far from being considered defective, were looked upon as the models to be imitated in every other place, departure from which was regarded as an imperfection, in all cases to be regretted, though not always to be avoided. The Legislature, however, had recognized that forms of procedure more simple and expeditious might possibly be necessary in India; and power had been given to the

judges of her Majesty's Supreme Court to modify the procedure of that court, so as to meet the exigency:³¹ but the power was never acted on. It is, therefore, not surprising that Lord Cornwallis's courts were greatly infected (though in a far less degree than the courts in England then were) with technicalities of procedure, calculated both to defeat justice, and to obstruct the access to it by needless delay and expense. But the arrangements had a still more fatal defect: the judicial establishment was totally inadequate to the wants of the country. The attempt to administer justice (except in the most trifling cases) wholly by European agency, made it impossible to defray the expense of the number of courts necessary to render justice accessible: and if the benefits of judicature were to be afforded at all to the mass of the people, the intrusting, under proper securities, of the greatest portion of it to native functionaries, was not a question of expediency, but of necessity.

Subsequent Improvements

The creation of native courts of justice, and (as the experiment succeeded) the progressive extension of their powers, has been the greatest practical improvement made in the administration of justice in our older provinces during the last and present generation. The foundation for the present extensive employment of uncovenanted and native agency in the judicial department, was laid by the administration of Lord William Bentinck in 1831.³² At present, in the Bengal and Bombay Presidencies, the entire original jurisdiction in civil suits is in the hands of the native judges, the covenanted Europeans being only judges of appeal; and the same thing is true of the Madras Presidency, in regard to all suits below the value of 10,000 rupees. The employment of uncovenanted agency has also been greatly extended in the administration of criminal justice, and in the revenue department. Deputy magistrates (in some instances exercising judicial powers equal to those of the district magistrate) and deputy collectors, discharge important functions, and afford material assistance to the head authorities of the district. Most of these are natives, and some of them natives of high rank and influence.

The movement towards reform in legal affairs generally, also dates from the administration of Lord William Bentinck. At Bombay, indeed, the Regulations of Government, comprising the penal law and the law of procedure actually in force, and as much of the civil law as had been introduced by our own Government, had already, under Mr. Elphinstone's administration, been consolidated into what is

³¹By 21 George III, c. 70 (1781).

³²William Cavendish Bentinck (1774-1839), Lord Bentinck, was Governor-General 1828-35; the provision is seen in "Extract Public Letter to Bengal, 18 Feb., 1829," in "Correspondence Relative to the Employment of the Natives in the Civil Department of the Service, 1821-32," *PP*, 1831-32, IX, Appendix, 374-5.

called the Bombay Code.³³ But it was on the recommendation of Lord William Bentinck's Government that, by the Act of 1833, the present ample legislative powers for all India were conferred on the Governor-General in Council; a barrister appointed from England being added to the Council, for the express purpose of aiding the Government in its legislative functions.³⁴ By the Act of 1853, the Legislative Council was further enlarged by the addition of the Chief Justice and one puisne judge of her Majesty's Supreme Court, two members representing Madras and Bombay, and selected by those Governments, and two representing Bengal and the North-western Provinces, and appointed by the Lieutenant-Governors; to whom the Governor-General has the power of adding two other civil servants of Government, selected at his discretion.³⁵ The Legislative Council now holds its sittings in public, and its debates are regularly reported and published.

Since the first institution of the Legislative Council, few years have passed in which there have not been one or two legislative measures for the improvement of the procedure of the civil courts. The object of some has been to facilitate the progress of suits through their various stages; of others, to secure the correct recording of the judgment, by prescribing that it shall be made by the judge himself; of others, to insure a more speedy and certain execution of judgments; of others, to render more efficient the systems of regular and special appeals. Legislative measures have also been taken for reforming the law of evidence; for the abolition of Persian as the language of record; and for putting the office of native pleader on a more efficient and respectable footing. The defects of the criminal courts have likewise largely engaged the attention of the Legislature, and much has been done for their improvement. But notwithstanding these partial amendments, it cannot be said that the courts, in what are called the Regulation Provinces, have yet been freed from their radical defects. The principal impediments to a good administration of justice, are the complicated and technical system of pleading in the civil courts, and in the criminal courts the character of the police.

The New Codes

By the Act of 1833, a Law Commission was appointed to sit in Calcutta, and inquire into the jurisdiction and procedure of the courts of justice and police establishments, and into the operation of the laws, civil and criminal.³⁶ The

³³Mountstuart Elphinstone (1779-1859) was Governor at Bombay 1819-27; for the Bombay Code (also known as Elphinstone's Code), see Regulation I of 1827 (1 Jan.), *PP*, 1829, XXIII, 251-4.

³⁴By Sects. 43 and 40, respectively, of 3 & 4 William IV, c. 85.

³⁵By Sect. 22 of 16 & 17 Victoria, c. 95.

³⁶By Sect. 53 of 3 & 4 William IV, c. 85.

declared purpose of Parliament in creating the Law Commission, as well as in the new constitution given at the same time to the Legislative Council, was to facilitate measures for bringing Europeans and natives under the same courts of justice, civil and criminal.³⁷ The machinery constructed for this purpose has been employed to lay the foundation for correcting all the principal defects of the laws and of the tribunals. The Commission prepared a penal code of great merit, and made many reports full of valuable suggestions on other branches of legal administration, some of which have been acted on. But it was important that any new system, before being brought into practical effect, should be well understood by those who would have to apply it, and should be approved by those whose authority would carry the greatest weight. Opinion could not be expected to ripen all at once on so great a subject as the reconstruction of the legal and judicial system of a vast country; and the suggestions of the Law Commissioners, being referred to various authorities, elicited great varieties of judgment. By the Act of 1853, a Commission was appointed to sit in London, for considering and reporting on the recommendations of the Indian Law Commissioners.³⁸ The wants of India as to codes, both of substantive law and of procedure, civil and criminal, have been fully considered by the Commissioners so appointed. They have recorded a strong recommendation in favour of the preparation of a code of civil law for India; and they have prepared complete codes of civil and criminal procedure, grounded on a rare combination of appropriate local knowledge with the matured views of enlightened jurists.³⁹ These codes, together with the penal code passed by the earlier commission,⁴⁰ are in progress through the Legislative Council of India, and would probably by this time have been law, but for the calamitous events by which the attention of all Indian authorities has of late been engrossed.

These codes, when enacted, will constitute the most thorough reform probably ever yet made in the judicial administration of a country. The code of civil procedure entirely sweeps away the present cumbersome and complicated system of pleading, and substitutes the *vivâ voce* examination of the parties;⁴¹ and in all other respects, as compared with the previous practice, it is of great simplicity, and eminently free from delay and expense. As Mr. Colvin, the Lieutenant-Governor of the North-western Provinces, observed in his last general report,

³⁷Also in Sect. 53. For the Commission and its proposals, see "Penal Code for India," above.

³⁸By Sect. 28 of 16 & 17 Victoria, c. 95.

³⁹See "Reports of Her Majesty's Commissioners Appointed to Consider the Reform of the Judicial Establishments, Judicial Procedure, and Laws of India," *PP*, 1856, XXV, esp., for the Code of Civil Law, "Second Report," p. 269; for Civil Procedures, "First Report," pp. 21-88, "Third Report," pp. 291-346, and "Fourth Report," pp. 451-506; and for Criminal Procedures, "First Report," pp. 94-184, "Third Report," pp. 350-428, and "Fourth Report," pp. 510-89.

⁴⁰Finally enacted by Act XLV of 1860 (6 Oct.).

⁴¹See "Reports," *PP*, 1856, XXV, 43 (Clause 87 in "First Report").

It is not alone, as the Lieutenant-Governor apprehends, that by the new code of procedure, the practice of the courts will be made more simple and rapid, and the costs of a suit be diminished; it is because, as he hopes, the judges will be brought much more frequently into direct communication with the parties in suits and their witnesses, without any intervention of agents or pleaders, that he looks to the public becoming satisfied that the courts are to be trusted as a means for obtaining substantial justice, and not dreaded as an engine capable of being readily perverted to the working of fraud and wrong under the forms of law. It is not, he fears, to be denied that low classes of practitioners and unscrupulous habits of chicane have grown up about our courts, with their old complex and artificial pleadings and rules: and this being the case, it cannot be matter of surprise that among a population so generally ignorant and helpless, discredit and dislike should have extensively attached to our judicial institutions.⁴²

Under the new code, if not materially altered by the Legislative Council, India is likely to possess, so far as judicial institutions can secure that blessing, as good and as accessible an administration of civil justice, as the lights of the age are capable of conferring on it.

Judicial System of the Non-Regulation Provinces

It was only the Regulation Provinces which stood in need of such a reform; for the Non-Regulation Provinces have had (generally from their first acquisition) the benefit of a cheap, accessible, and expeditious administration of justice, free from all such formalities and technicalities as either defeat justice, or add needlessly to the difficulty and expense of obtaining it. The following are the terms in which the eminent Sir John Lawrence, in his last general report, describes the judicial system of the Punjab, which has been the model of those introduced into all the other recently-acquired territories, as well as into our older possessions of Saugor and Bundelcund:

In former reports it has been shown how the system of civil judicature in the Punjab has been founded and erected; how that no effort has been spared to render justice cheap, quick, sure, simple, and substantial; how every other consideration has been rendered subordinate to these cardinal points. We are, indeed, without elaborate laws, but we have brief rules, explaining, in an accessible form, the main provisions of the several systems of native law on such matters as inheritance, marriage, adoption, testamentary or other disposition of property; and setting forth the chief principles to be observed in other branches of law; such as contracts, sale, mortgage, debt, commercial usage. We have the most open and liberal provisions for the admission of evidence. We have complete arrangements for reference to arbitration, and for the ascertainment of local custom. We have a procedure, without any pretension to technical exactitude; but a procedure which provides for the litigants and their respective witnesses being confronted in open court, for a decision being arrived at

⁴²John Russell Colvin (1807-57), Lieutenant-Governor of the North-western Provinces 1853-57, "Report on the Administration of Public Affairs in the North-Western Provinces," *General Report on the Administration of the Several Presidencies and Provinces of British India during the Year 1855-56*, 2 pts. (Calcutta: Calcutta Gazette Office, 1857), Pt. I, pp. 12-13.

immediately after this brief forensic controversy, and for judgment being delivered to the parties then and there. We have a method of executing decrees, which, while it allows no door to be opened for evasion or delay on the part of defendant, and thus renders a decree really valuable to plaintiff, as being capable of ready enforcement, and gives him his right free from lien, encumbrance, or doubt; yet, on the other hand, prevents the defendant from being hastily dealt with, or from being placed at the mercy of his creditor. We have Small-cause Courts scattered all over the country, and several regular courts at every central station; so that everywhere justice is near. Our civil system may appear rough and ready; whether it would be suited to other provinces, in a different stage of civilization and with a different machinery at command, may be a question; but in the Punjab it attains the broad and plain object aimed at, and without doubt gives satisfaction to the people.

But in order to regulate the administration of justice, a complete system of reporting has been established. Month by month, the reports of every court are transmitted to the judicial department at head-quarters, and are there criticised. At the close of each year, these reports, and the figures embodied in them, are collated, averages are struck, division is compared with division, and district with district, and the general result, with a brief critique by superior authority, indicating the defects to be avoided and the reforms to be emulated, is published for the information of all officers concerned. It is believed that many improvements in the working of the courts are traceable to this system. Every court works under a constant sense of supervision, and with the great objects to be aimed at perpetually in view, and standing out in strong relief.

In respect of speed, the average duration of a suit in 1854 was twenty-eight days, and in 1855 twenty-three days. This average has been becoming laudably lower year after year; it is now nearly as low as it can be, consistently with due inquiry and deliberation; and as the above average includes all those cases which for any special cause may be protracted, it is evident that the trial of most suits can only extend over a very few days. In respect to cheapness, the cost averaged only 5r. 0a. 1p. per cent on value of suits during 1854, and 4r. 13a. 3p. per cent during 1855. As a proof of the entire absence of technicalities, it is to be observed that only 5.19 per cent of the suits were nonsuited during 1854, and 5.42 per cent during 1855. The small number of nonsuits which are ordered are probably real and honest ones.⁴³

Prison Discipline

In the course of the last few years the system of prison discipline in India has undergone a complete and most salutary revolution. The origin of this reform may be dated from the report of a committee appointed in Calcutta in 1838, composed chiefly of the principal members and secretary of the Indian Law Commission.⁴⁴

Up to this time, those inmates of jails who were under sentence of labour, were employed almost exclusively (in fetters) on the roads: which rendered prison discipline almost impossible, as the prisoners could nearly always, by the connivance of their guards, command intercourse with friends and relations; and the engineer officers, in their anxiety to obtain efficient work, fed them highly, and

⁴³John Laird Mair Lawrence (1811-79), Baron Lawrence, Chief Commissioner for the Punjab from February 1853, "Report on the Administration of Public Affairs in the Punjab Territories," *ibid.*, Pt. II, pp. 3-5.

⁴⁴*Report of the Committee on Prison-Discipline to the Governor General of India in Council, 8 January, 1838* (Calcutta: Baptist Mission Press, 1838).

treated them in other respects with an indulgence entirely inconsistent with the purposes of punishment. At the same time, the mortality from exposure and unhealthy localities was great. The committee showed that the State were absolute losers by employing convict labour on the roads; that it would be a positive saving to keep them in idleness in the jails, as the cost of extra superintendence and guards considerably exceeded the expense at which the work they did could be executed by hired labour. Since this time out-door convict labour has been abandoned, and the prisoners are employed within the jails in various manufactures; and this employment, which commenced in 1843, has every year become more profitable, until, in 1855-56, the profit in the fifty-five jails of the Lower Provinces of Bengal reached the large sum of Rs. 1,11,582 (£11,000). This profit now forms a fund for the execution of the public works formerly performed by the convicts themselves. The jail manufactures, too, are of such improved quality, that some of them have acquired a high character in foreign markets; and public exhibitions of them are now held in the Town Hall of Calcutta.

Prisoners sentenced for long terms of years are now removed to large central jails; and the change has been attended with great improvement in general management and discipline. There is an inspector of jails for each presidency and sub-presidency. These officers are most active in discovering and correcting defects, and increasing the effectiveness of the jails, both as reformatories and as places of punishment.

The reform of the police of India is not yet in so advanced a state; but the present disturbances found the authorities in the very crisis of their deliberations on the subject. The police has hitherto remained the most faulty part of our system in India, and it is the part which it is by far the most difficult to reform effectually. The peculiar difficulty of administering criminal justice in India arises from the character and habits of the people. In most countries, the voluntary and active co-operation of the people may be looked for in bringing criminals to justice. In India, rather than incur the trouble and annoyance of appearing as a prosecutor or as a witness, a man will even forswear himself to screen the man who has robbed him. The injury he has suffered is looked upon as the decree of destiny, and he has no disposition to add to the inconvenience by incurring exertion and expense, and perhaps exposing himself to the further vengeance of the criminal. Among such a people there is only the police who can be looked to for bringing criminals to justice. The great powers which must be intrusted to the police of such a country, and that police necessarily composed principally of natives, give rise, when combined with the passive and slavish character of the people of many parts of India (especially of Bengal), to evils with which the Government has hitherto struggled with very imperfect success.

Police

The police of India, up to a very recent date, consisted of native establishments,

under the control and orders of the European magistrate. Each zillah, or judicial district, is formed into subdivisions (more or fewer, according to the size of the district) each of which is under the charge of a local stipendiary police, consisting of a head native officer and his subordinate clerks, sergeants, and constables. The native police in the Bengal Presidency is (with the partial exception of the tehsildars in the North-western Provinces) separate from the body of revenue officers. In the Presidency of Madras, the same officers discharge both revenue and police functions; and, until recently, this was also the case at Bombay.

The recognized defects of the system are, the low rate of pay, and the consequent inferiority of the class of men who enter the police, and also the disproportion of the strength of the force to the density of the population, and to the extent of country committed to their charge. With a view to the correction of these evils in Bengal, higher grades of subdivisional police officers have of late years been created, and their pay has been increased. Deputy magistrates have also been appointed, and invested with the judicial and police charge of subdivisions. The former measure has been productive of some good, by inducing a more trustworthy class to enter the service; the latter has not yet been carried to a sufficient extent to effect any practical improvement of a general character.

The state of the police of the North-western Provinces had deeply engaged the attention of the late Lieutenant-Governor, the lamented Mr. Colvin. That distinguished functionary conducted, through the district commissioners, a general revision of the local police establishments; reducing the number of officers in some of the districts, but increasing the salaries, and holding out the sure prospect of promotion as the reward of good conduct and efficient service. These measures were the best that could be adopted with the then available materials; but they did not at all touch the essential constitution of the police. With regard to the village police, the ancient and indigenous police of the country; in the North-western Provinces, its proper maintenance by the villages themselves is provided for by the conditions of the settlement. In the Lower Provinces, the terms of the permanent settlement have unfortunately deprived the Government of the power of enforcing this obligation. An Act has, however, been passed for the maintenance of an improved city police, by an assessment on the occupiers of houses;⁴⁵ and this plan has been introduced into several large cities and towns.

It is in the Bombay Presidency that the greatest improvements have been actually effected in police administration. The measures for this purpose were commenced under Sir George Clerk's administration, in 1848.⁴⁶ Under the new

⁴⁵Act XX of 1856 (14 Nov.).

⁴⁶The criticisms and proposals of George Russell Clerk (1800-89), Governor of Bombay 1847-48 and 1860-62, are in "Minute by the Honourable Sir George Clerk (28 Apr., 1848)," *Sessional Papers of the House of Lords*, 1852-53, XIII, 176-90. They led in part to the reforms in appointment and punishment laid out in Acts XXVII and XXVIII of 1852 (2 July).

system, revenue and police functions have ceased to be combined in the same native officers. The powers of punishment previously exercised by police officers have been taken away. To each district has been appointed a European superintendent of police (either a military or an uncovenanted officer), under whose command the police force of the district, both village and stipendiary, is placed, and who exercises the functions of an assistant to the magistrate in his police duties. This functionary, again, has the aid, in each subdivision under his orders, of an officer called joint police amildar, who has the more immediate charge of the preservation of the public peace, and the preliminary investigation into crimes of a serious nature. Active measures have been set on foot for reorganizing the village police, by ascertaining the assignments formerly made in lands and money for the purpose, and requiring that the duties for which these assignments were the remuneration, be really performed. The general control and direction of the police of the whole presidency, except the island of Bombay, is concentrated in one chief officer, under the title of Commissioner of Police. These measures are believed to be already effecting a great improvement in the police of the presidency.

In the Punjab, a police system had to be, not reformed, but created; and this task has been fulfilled with the same efficiency with which every other part of the administration of that territory has been organized. As the Punjab police may not improbably form a model for other parts of India, it is well to note the general features of its constitution.

The police establishments consist of two parts; the preventive police with a military organization, and the detective with a civil organization.

The preventive police consists of foot and horse; each regiment has its own native commandant, and the whole force is superintended by four European officers. Both arms of the service are regularly armed and equipped, and are ready at a moment's notice to reinforce the civil police.

The civil police consists, first, of a regular establishment, paid by the State; secondly, of the city watchmen, paid from a fund raised by the levy of town duties; and, thirdly, of the village police, nominated by the landholders, confirmed in their offices by the magistrate, and paid by the villagers.

The infantry of the military preventive police furnish guards for jails, treasuries, frontier posts, and city gates, and escorts for treasure. The cavalry are posted in detachments at the civil stations; and smaller parties, stationed at convenient intervals along the grand lines of road, serve as mounted patrols. The general duties of the civil police consist in reporting crimes, tracking and arresting criminals, and procuring evidence against them.

The police of the Punjab have been eminently successful in repressing crimes of a violent nature, in breaking up gangs of murderers and robbers, and in bringing criminals to justice; and in no part of India is the authority of the Government more thoroughly respected than in the Punjab.

In 1856, the Court of Directors, in a despatch which has been laid before Parliament, discussed at some length the defects of the police of India, and the means available for their correction, and proposed for the consideration of the Government of India a plan of thorough reform, grounded on the three principles, of European command, unity of action throughout the country, and complete separation between revenue and police duties.⁴⁷

This plan has undergone careful deliberation from the Government of India. The various members of that Government, and the Lieutenant-Governor of Bengal, have individually recorded their sentiments, in minutes characterized by a frank recognition of existing defects, an earnest desire of improvement, a remarkable amount of knowledge and understanding of the subject, and great ability in the statement and discussion of the merits and defects of the various plans advocated.⁴⁸ For the present, so far as regards the Bengal Presidency (including the North-western Provinces), the recommendations of the Government of India are limited to a better choice and ampler remuneration of the native police, and to the aiding and strengthening them, in certain localities, by police corps of a semi-military character.⁴⁹ These measures have been sanctioned; and until their effect has been tried, the Court of Directors have consented to put in abeyance the more fundamental changes which they had recommended. But authority has at the same time been given to the Government of India, should the present state of the country in their opinion render it expedient, to organize the police of Bengal on the model of that of the Punjab.⁵⁰

In the Madras Presidency, the opinion of the local Government was favourable to the Court's original views; and in September last authority was finally given to that Government for the thorough reorganization of the police system. The leading features of the scheme which has been sanctioned are as follows:

The appointment of a chief commissioner of police for the whole presidency, in whom will be vested, in direct communication with the Chief Secretary to Government, the direction, discipline, and internal economy of the police force;

⁴⁷"Despatch from the Court of Directors to the Governor-General of India in Council, Judicial Department, 24 Sept. (No. 41), 1856," *PP*, 1857, Sess. 1, XI, 127-32.

⁴⁸See, e.g., Charles John Canning, "Minute by the Right Honourable the Governor-General (18 Feb., 1857)," in "Papers Relating to the System of Police in the Bengal Presidency," *PP*, 1857, Sess. 2, XXIX, 363-73; John Peter Grant (1807-93), a Member of Council, "Minute by the Hon. J.P. Grant (9 Apr., 1857)," *ibid.*, pp. 374-87; and Frederick James Halliday (1806-91), appointed first Lieutenant-Governor of Bengal in 1854, "Minute by the Hon. the Lieutenant-Governor of Bengal (30 Apr., 1856)," *ibid.*, pp. 327-53.

⁴⁹See "Letter from the Government of India to the Hon. Court of Directors, Home Department, Judicial, 14 May (No. 18) of 1857," *ibid.*, pp. 287-8.

⁵⁰The sanctions and authority are given in "Despatch from the Court of Directors to the Governor-General of India in Council, Judicial Department, 4 Nov. (No. 61), 1857," in "Despatches Relating to Police (East India)," *PP*, 1857-58, XLIII, 413-15.

The appointment in each district of a European deputy commissioner of police, with a sufficient number of subordinate officers and peons or constables;

The entire separation of the police from all connection with the revenue branch of administration, and of the magistrate (who will now be a purely judicial officer) from the properly police duty of the prevention and detection of crime:

And, finally, measures for reorganizing, and, it may almost be said, reviving, the village police, which, from its close connection with the localities, must necessarily constitute the last (and a most important) link in any police system really efficient, or willingly supported by the people.⁵¹

Thuggee and Dacoitee Suppression

The imperfections of the general police of India have not prevented some results from being attained in the way of suppression of crime, sufficiently remarkable to have attracted an amount of European notice seldom accorded to Indian affairs. The most memorable of these is the suppression of the Thugs. This singular association, which, though recruited from all castes, and even from Mussulmans, was held together by a religious tie, and a common worship of the Hindoo goddess of destruction, infested all the roads in India; and from their universal practice of murdering all they robbed, it was not only almost impossible to obtain evidence for their conviction, but the extent of their crimes was greatly underrated, and their very existence in many parts of India, disbelieved in. A separate police was organized specially against them. The gangs were broken up in the only manner in which this could possibly have been effected—by encouraging some of them to denounce the rest. From the narratives of these approvers, taken separately from one another and with the utmost precautions against the possibility of concert, lists of all the Thugs in India were obtained, and the particulars of the crimes committed by each. These were then traced to their haunts, identified, tried, and convicted, on the evidence of their accomplices, confirmed by the finding of bodies, the identification of property, or other corroborative evidence. Many suffered death, a much greater number transportation for life, and, in a few years from the commencement of the operations, all India was cleared of these criminals. The pardoned accomplices remain under surveillance at Jubbulpore, in Central India, where they and the children of the captured Thugs have been taught several useful branches of manufacture. The Jubbulpore School of Industry now supplies to Government and the public many valuable carpets and linen cloths, and a great proportion of all the tents used in India.

When the work of the Thuggee Suppression Department was nearly completed as far as regarded the Thugs, its operations were extended to the still more prevalent crime of dacoity, or robbery and burglary on a large scale by organized gangs of professional banditti. The mode of breaking up the gangs by means of

⁵¹“Despatch from the Court of Directors to the Governor at Madras, Judicial Department, 30 Sept. (No. 13), 1857,” *ibid.*, pp. 415-16.

approvers, which had been so successful against the Thugs, has been put in practice with equal success against dacoits; and this crime, so far as it was perpetrated by large associations ranging over a wide extent of country, has now been almost as completely rooted out as Thuggee. Dacoitee had been almost entirely suppressed in the North-western Provinces and in Bombay, before the occurrence of the recent disasters. In the Lower Provinces of Bengal the crime has been greatly reduced within the last three or four years. In seven large districts surrounding Calcutta, where it was lamentably prevalent, the number of dacoitees has been progressively reduced from 524 in 1851, to 111 in 1855. In some of the districts of the Madras Presidency, dacoitees of a local character, by small gangs, to which the approver system is not equally applicable, are still frequent; but the improvement in the police, and other measures in contemplation, will, it is hoped, speedily reduce their number.

Suppression of Piracy

The piracies which formerly made the navigation of the Arabian seas unsafe for commerce, have been so effectually suppressed by the East-India Company's cruisers, that there is now hardly any part of the world in which trading vessels are more secure against depredation. The formerly piratical tribes have been bound by engagements to abstain not only from piracy, but from maritime war, which affords opportunities and pretexts for piracy: and, for the first time probably in history, a perpetual peace, guaranteed by treaties and enforced by superior naval strength, reigns in the Persian Gulf.

Infanticide

Equal vigour has been displayed against many barbarous usages of the natives. Special measures have been carried on during a long series of years for the suppression of female infanticide, a crime which had become a positive custom among several of the higher castes in various parts of India, from motives, not of religion, but of family pride. The co-operation of the native princes has been urgently invited, and to a great extent obtained, for the suppression of this practice. In the places, and among the castes, in which the practice was ascertained to exist, means were taken to obtain an annual census of female children. A report of all births, of all deaths of infants, and of the causes of deaths, was required, under stringent regulations and penalties. Engagements were taken from the influential persons of the castes to preserve their own children, and to aid in enforcing the same conduct on others. Honorary rewards and marks of distinction have been conferred on chiefs and others who have exerted themselves for the promotion of the object. By great efforts of persuasion and address, the heads of castes and tribes have been prevailed on to agree to a limitation of that favourite subject of vanity,

marriage expenses; and grants of money are regularly made to poor persons of the castes, in aid of the marriages of their daughters. These efforts have been rewarded by a continual diminution of the number of infanticides, evidenced by a constant increase in the number of females in existence, of the formerly delinquent castes.

Suttee

Suttee, or the voluntary burning of widows on the funeral piles of their husbands, after having been long discouraged by every means short of positive prohibition, was finally made a criminal offence in all who abetted it, by a legislative Act of Lord W. Bentinck's administration,⁵² and has now entirely ceased in the provinces subject to British administration. Unremitting efforts have been used to induce the native princes to follow the example, and have been at last successful with all of them except one, the Maharana of Odeypore,⁵³ the representative of the oldest and proudest dynasty in India: and this prince professes himself willing to abolish the rite, when the cessation of existing differences between himself and his feudatory chiefs shall enable him to obtain their concurrence in the measure. Various other modes of self-immolation practised in India,—by drowning, burying alive, or starvation,—have been, with equal success, prohibited and suppressed.

Witchcraft

The pretence of supernatural powers was a source of great evil in India, not only as a means of extortion and intimidation, but also by the numerous murders perpetrated on persons suspected of practising on the lives or health of others by magical arts. These acts of fancied retaliation have been, with a gentle but powerful hand, repressed, and great progress has been made towards their extinction. The fraudulent pretence is now punished as a substantive crime.

Tragga

The insecurity of rights, and the imperfection of the tribunals, under the native Governments, had introduced, on the part of those who were, or believed themselves to be, injured, a singular mode of extorting redress. They hired a person of one of the religious classes to threaten that unless the demand, whatever it might be, was complied with, he would kill or wound himself or some one else; thereby, it was supposed, entailing the guilt of murder or of wounding on the person whose alleged injustice was the original cause of the act. If the threat

⁵²By Regulation XVII of 1829 (4 Dec.).

⁵³Maharana Sarup Singh (d. 1861), ruler 1842-61.

proved ineffectual, the honour of the threatener was engaged to carry it into practical effect; and many suicides or murders were committed from this cause. This barbarous practice, known by the name of *Tragga*, has been almost entirely suppressed, partly by penal laws, and partly by affording more legitimate means of enforcing just claims.

Meriah Sacrifices

Among the barbarous tribes who occupy the hill tracts of Orissa, on the south-west frontier of Bengal, human sacrifices prevailed until a very recent period. By a well-devised and judicious series of conciliatory measures, worthy of a more lengthened record than can be given to them in this place, the extinction of this enormity has been effected.

Abolition of Slavery

After a full consideration of the subject of slavery in India, by the Indian Law Commissioners and by the Government of India, an Act was passed in 1843, which entirely abolished slavery as a legal status.⁵⁴ The courts of justice are forbidden to recognize it; no fugitive, claimed as a slave, can be forcibly restored; and every act which would be an offence if done to a free person, is now equally an offence when done to the persons formerly considered slaves.

Wet Begaree, or Forced Labour

One of the most oppressive of the burthens on the agricultural and labouring classes under the native Governments, was compulsory labour, not only for the repair of roads where any existed, but for the purpose of carrying the abundant baggage of Government officers or powerful individuals when journeying from one place to another. This practice has been abolished. The last vestige of it, in a licensed form, is believed to have been in the construction of the Thibet road through the Himalaya Mountains, and orders have recently been issued for its discontinuance there.

Civil Rights of Religious Converts

By an Act passed in 1850, the principle already laid down in a Bengal Regulation of 1832, that change of religion should not involve loss of property or

⁵⁴See "Report of the Indian Law Commissioners on Slavery" (15 Jan., 1841), *PP*, 1841, Sess. 1, XXVIII, 279-873; and "A Copy of the Letter from the Governor-General of India in Council, in the Legislative Department, 10 May (No. 8), 1841, and of the Minute of the Governor-General Enclosed therein, on the Subject of Slavery in the East Indies," *PP*, 1841, Sess. 2, III, 109-14; both leading to Act V of 1843 (7 Apr.).

civil rights, was extended to the whole of the territories subject to the British Government of India.⁵⁵ The religious and civil laws of the Hindoos have in this point been completely set aside; and converts to Christianity have been shielded, as far as law can shield them, against temporal ill consequences from their change of faith.

Re-marriage of Widows

By an Act passed in 1856, another great inroad has been made on Hindoo prejudices, by legalizing the re-marriage of widows.⁵⁶

Discontinuance of Connection with the Religious Ceremonies of the Natives

An Act passed in 1840 gave effect to instructions issued by the home authorities in 1833, on the subject of pilgrim taxes, and the superintendence of native festivals.⁵⁷ The instructions directed that the interference of British functionaries in the interior management of native temples, in the customs, habits, and religious proceedings of their priests and attendants, in the arrangement of their ceremonies, rites, and festivals, and generally in the conduct of their interior economy, should cease; that the pilgrim tax should everywhere be abolished; and that in all matters relating to their temples, their worship, their festivals, their religious practices, and their ceremonial observances, our native subjects be left entirely to themselves. Property held in trust for religious uses of course cannot be diverted from them by any act of the Government; but if such trusts are infringed, redress must be sought, as in all other cases, from the tribunals. In 1841 the home authorities sent out further instructions, that no troops or military bands of music be called out, and no salutes fired, in honour of native festivals; and all such acts have since been regarded as strictly prohibited. When any case of infringement of these principles is found to have been overlooked, it is, on being brought to notice, immediately corrected.

IMPROVEMENT OF THE COUNTRY BY PUBLIC WORKS

The measures which have now been briefly described, for fixing and moderating the demands of Government on the tax-paying population, and securing to every

⁵⁵By Act XXI of 1850 (11 Apr.), *PP*, 1852, XXXVI, 65-6, Sect. 9 of Regulation VII of 1832 (10 Oct.) was extended to the whole of the British territories in India.

⁵⁶By Act XV of 1856 (13 June).

⁵⁷"Revenue Department Despatch No. 3, 20 Feb., 1833, to Our Governor-General in Council at Fort William, Bengal," *PP*, 1837, XLIII, 190-9, given legislative effect by Act X of 1840 (20 Apr.).

one the full enjoyment of the fruits of his industry, are in themselves the most effectual means which could have been adopted for improving the productive resources of the country. In a country like India, however, the direct aid of Government to industry is required, for a variety of purposes which, in more advanced countries, are sufficiently, and even better, provided for by private enterprise. The principal of these are, irrigation, and the means of communication by roads and canals.

Irrigation Works

The British Government in India has frequently been charged with niggardliness in incurring expense for these purposes. There was some, at least apparent, ground for the charge, in former generations; though even then, the truth fell far short of the current representations. It is often asserted that the country is covered with the remains of tanks and other works of irrigation, which the native rulers constructed, and which the British Government has allowed to decay. The fact is overlooked, that most of these were already in a state of decay before the country came into our possession; long periods of disorder and military devastation having destroyed the funds which should have repaired them, and the security which would have admitted of their repair. Many works which are supposed to have fallen into decay, never were completed: many were allowed to decay by the native sovereigns; for it was only occasionally that a prince, of unusual talents and vigilant economy, had funds to spare for such purposes; and the same prince who would commence new works with which his own name was to be connected, would often neglect to keep up those of his predecessors. Whether it is a just subject of censure, that the restoration of these old works was not commenced earlier, is a question depending on many and various considerations; but the activity in this department for many years past has been exemplary.

Jumna Canals

The Western and Eastern Jumna canals were of ancient construction, but had fallen into disrepair and become useless to the country, until again brought into activity by the labours of the Company's officers at a sufficiently early date to admit of a full estimation of the benefits which the country has reaped from their restoration. The main line of the Western Jumna Canal is in length 445 miles. In the famine year, 1837-38, the gross value of the crops saved by the water of this canal was estimated at £1,462,800; of which about one-tenth was paid to Government as land and water rent; while the remainder supported, during a year of devastating famine in other districts, the inhabitants of nearly 500 villages.

The works originally projected for the restoration of the Eastern Jumna Canal were completed in 1830; but considerable improvements have been effected since that date at a large expense. In 1853, the Court of Directors sanctioned an

expenditure of £15,276 for improving this canal, so as to economize the water, facilitate its distribution, and correct the malarious state of the country on its banks. It is stated, that on the 1st of May, 1852, the clear profit to Government on this canal had been £9,759.

Up to 1847-48, the expenditure incurred on these and some minor works in the North-western Provinces had amounted to about £557,000, while the amount received in direct canal revenue was in all £546,000. The quantity of land brought under the influence of irrigation was 1,300,000 acres, yielding produce of the annual value of £2,500,000, and supporting a population of 600,000 souls.

Ganges Canal

The history of the Ganges Canal, the greatest work of irrigation ever constructed, belongs to a more recent period. The employment of the water of the Ganges for irrigation purposes appears to have been first contemplated by Colonel Colvin, who, on delivering charge of his office of superintendent of canals to his successor, the present Sir Proby Cautley, recommended the project to his consideration.⁵⁸ Colonel Cautley carefully examined the country through which the canal would pass, and the scheme was, in 1841, brought under the consideration of the home authorities, who gave it their cordial support,⁵⁹ subject to a further examination of the project by a committee of engineer officers. The committee's report was favourable,⁶⁰ but various difficulties intervened, and the work cannot be said to have been fairly commenced, on a scale commensurate with its importance, till the year 1848.

The total length of the Ganges Canal and its branches, when completed, will be 998 1/2 miles, and it will furnish abundant irrigation for an area of 4,500,000 acres. The canal, in the words of the Lieutenant-Governor of the North-western Provinces, "presents a system of irrigation unequalled in vastness throughout the world; while the dimensions of the main channel, and the stupendous works of masonry which occur in its course, more particularly in the section between Roorkee and Hurdwar, render the work eminently one of national distinction and honour."⁶¹ The amount expended on it up to the 1st of May 1856, had reached the sum of £1,560,000; and when completed, the total cost will fall little short of £2,000,000. The canal has but just begun to be brought into operation; but it is

⁵⁸John Colvin (1794-1871), who held the position of Superintendent of Canals in the Delhi Territory and adjoining districts for most of the period from September 1825 to December 1836, was succeeded by Proby Thomas Cautley (1802-71).

⁵⁹See "Letter from the Court of Directors to the Governor-General of India in Council, Revenue Department, 1 Sept. (No. 12), 1841," in "Copies of the Correspondence Respecting Works of Irrigation, &c., in India," *Sessional Papers of the House of Lords*, 1851, XVI, 66-7.

⁶⁰The engineers included William Erskine Baker (1808-81) and Henry Yule (1820-89).

⁶¹John Russell Colvin, "Report on the Administration of Public Affairs," pp. 83-4.

estimated by Colonel Baird Smith, the director, that the annual produce of the land already watered by it is of the value of from £150,000 to £200,000; and that when the canal is in full operation, the value will ultimately reach the enormous sum of £7,000,000.⁶²

On the 30th April, 1856, the canal had been carried so far that the water flowed continuously through 449 1/2 miles of the main trunk and terminal branches. The extent of main channels of distribution (rajbuhas) completed, was 435 1/2 miles, and 817 miles more were in active progress.

The canal is fitted also for purposes of navigation, but it has not yet been made available to the public for this purpose, although extensively used by the Government for the transport of materials. Colonel Baird Smith states that the canal closes its first year of work (1855-56) with an aggregate revenue, from all sources, of rather more than Rs. 60,000, having watered during the year about 55,000 acres of land, and having placed beyond the risk of serious damage from drought, an area of cultivation extending over about 166,000 acres, distributed among 1,134 villages.

Punjab Canals

In the Punjab, the canals are of two kinds, inundation canals and permanent canals. The inundation canals are cuts from the rivers, which are empty during the winter, because the water is not then high enough to enter them; but as the water rises in the spring, from the melting of the snows, these channels fill, and remain full until late in autumn. The fertility of the South-western Punjab mainly depends on these canals, and in a former age they appear to have been conducted from all the rivers; their course being traceable by the ruins not only of villages but of cities and public buildings, which depended for existence on their fertilizing influence. Such of these canals as were found in working order at the annexation, have been maintained, improved, and enlarged; and plans and estimates have been formed for the restoration of others. As yet, however, the greater part of the funds which could be spared for the purpose, have been devoted to the construction and improvement of permanent canals. In 1849, the enlargement and extension of the Huslee Canal, stated to be capable of irrigating 70,000 begahs of land, was sanctioned, and it is now in good working order.⁶³ But this will ultimately be superseded by the Baree Doab Canal for irrigation and navigation.⁶⁴ The length of

⁶²Richard Baird Smith (1818-61) was in charge of the Jumna Canal 1843-50; he became superintendent of canals in the North-Western Provinces 1854-59. The figures cited here and two paragraphs below are in *Revenue Reports of the Ganges Canal for the Year 1855-56* (Rorkee: Thomason College Press, 1856), p. 43.

⁶³See "Letter from the Court of Directors to the Governor-General of India in Council. Revenue Department, 5 Dec. (No. 11), 1849," *PP*, 1851, XLI, 723-4.

⁶⁴See "Letter from the Court of Directors to the Governor-General of India in Council, Revenue Department, 25 Apr. (No. 5), 1851," *ibid.*, pp. 724-5.

this new work is about 450 miles; the original estimate of the cost was £530,000; but more extensive works than were at first expected having been found necessary, and the rates of labour having proved much dearer than those calculated, the ultimate cost will fall little short of a million sterling. In May 1856, more than 325 miles had been excavated; and it was hoped that the canal would be opened in 1859. The expected return is 12 lacs of rupees, or £120,000 per annum.

Sind Canals

The cultivation of the province of Sind is dependent on the rise of the river Indus, whose waters are distributed over the face of the country by a network of canals of greater or smaller dimensions. About two and a half lacs (£25,000) are annually expended in clearing these canals from the deposits of silt left in them by the receding waters. The principal works which have received special sanction, are the widening and deepening of the Begaree Canal in Upper Sind, at a cost of £13,000 (expected return £11,900 per annum), and the improvement and extension of the Foolalie Canal, at a cost of £15,083.

In the Madras Presidency, the means of artificial irrigation are chiefly obtained by the construction of tanks or reservoirs for preserving the monsoon rains, and storing them up for use in the dry season, and of "anicutts," or dams across the beds of rivers, by which the waters are maintained at a level higher than that of the country, in order to be from thence conducted over its surface. Of the latter class of works, the most worthy of notice are those which have been constructed on the Coleroon, the Godavery, and the Kistna.

Coleroon Works

The commencement of the Coleroon works is said to be traceable to the second century of our era. Imperfectly executed in the first instance, they were found, when the country came into our possession in 1801, to be very defective; and notwithstanding the remedial measures adopted, the bed of the river continued to rise, from the deposit of silt; the extent of land which the means of irrigation could reach, diminished; the revenue fell off, and the condition of the people was gradually deteriorating. This state of things appears to have reached its acme about 1829-30. Plans and estimates were then framed, and from 1836 the work was regularly and vigorously prosecuted.⁶⁵ The total expenditure on the Upper and Lower Coleroon anicutts, up to their completion, amounted, as far as can be ascertained, to upwards of £80,000. In addition to this sum, subsidiary works for conveying irrigation over the districts of Tanjore, and portions of Trichinopoly and South Arcot, were constructed, at a cost of about £100,000.

⁶⁵Some account of the plans and estimates for the Coleroon works is given in "First Report of the Commissioners Appointed to Inquire into and Report upon the System of Superintending and Executing Public Works in the Madras Presidency, 23 Dec., 1852," *PP*, 1852-53, LXXIV, 40-460.

The average quantity of land watered annually from the Coleroon and Cauvery prior to 1836, is given at 630,613 acres. Since the improvements, the average (up to 1850) was 716,524 acres; being an increase of 85,911. The annual increase of revenue has been about £44,000; and it may be assumed that the agricultural community have benefited to the extent of at least £66,000 per annum, from the extension of the area of irrigation. It is further calculated that at least an equal amount is added to the value of the annual produce, by the better irrigation of the lands which the waters already reached.

Godavery Anicut

An expenditure of £47,575 for the construction of the Godavery anicut was sanctioned in 1846. It was then anticipated that the total cost, with compound interest at 5 per cent, would be recovered in ten years, and that thenceforward a clear profit would be returned of at least £9,000 per annum.⁶⁶ The work has, however, proved much more costly than was expected. Up to 1852, the amount expended was £130,000, and a further outlay of £110,000 was expected to be required, which, with £24,000 allowed for annual repairs during its completion, would raise the total expenditure on the works (including a system of roads and an important line of inland navigation) to £264,000. The amount expended has, it is stated, been already repaid by the increased receipts; and the Madras Public Works Commissioners of 1852 (to one of whom, Colonel Cotton, the merit of this important work is in a great measure due) estimate that when the works shall be in full operation, the total increase of revenue will not be less than £300,000 per annum, while the gain to the people, by enabling them to cultivate the more valuable products, such as sugar-cane, rice, etc., instead of the ordinary dry crops, will exceed £3,000,000 per annum.⁶⁷

Kistna Anicut

The anicut across the Kistna river was commenced in 1853. The original estimate of the cost was £155,000;⁶⁸ but it is probable that this amount will be to some extent exceeded. It is intended, by 290 miles of irrigation channels distributed on both sides of the river, to supply water sufficient for 280,000 acres of rice cultivation, or 350,000 of rice, sugar, and possibly cotton, combined. The

⁶⁶Arthur Thomas Cotton (1803-99), then Captain of Engineers, "Extracts from the Report on the Godavery Anicut (17 Apr., 1845)," *PP*, 1852-53, LXIX, 234-40.

⁶⁷See "Report of the Commissioners of Public Works in the Madras Presidency (23 Dec., 1852)," *Sessional Papers of the House of Lords*, 1852-53, LXV, 160. Mill here mistakes Major Frederic Conyers Cotton (1807-1901), the Madras Public Works Commissioner, for Colonel A.T. Cotton, the engineer (see n66).

⁶⁸See "Letter from the Court of Directors to the Governor in Council in Fort St. George, Revenue Department, 8 Jan. (No. 1), 1851," *PP*, 1851, XLI, 726-7.

results anticipated are, an increase of £60,000 in the revenue of Government, and a gain of £90,000 per annum to the agricultural community.

Palar Anicut

In 1854, sanction was given to an expenditure of £86,611 for the construction of an anicut across the Palar river, in North Arcot, and of the works subsidiary to it. The expected increase of revenue was stated at £18,470 per annum, or, deducting ten per cent for repairs, £16,623.

Very large sums have in the aggregate been spent in the construction of new, and still more in the repair and restoration of old, tanks and wells, both in the Madras Presidency and in the other parts of India which depend on works of that description for water supply. In some hill districts, ravines have been dammed up, and a head of water obtained for the irrigation of the adjacent valleys or plains. This was the plan of Colonel Dixon's irrigation works in Mhairwarra;⁶⁹ and a system of such works had begun to be executed in Bundelcund, when the disturbances broke out.

A disposition has been of late shown to form companies for the execution of profitable works of irrigation, on certain conditions to be granted by the State. In September last, the Indian Governments were directed to take this subject into deliberate consideration, and to frame rules under which the aid of private companies in the construction of such works might most beneficially be employed; and readiness was expressed to give to such companies a guarantee of interest, on the same footing as railway companies.⁷⁰

Roads and Navigable Canals

Next in importance to irrigation works, are the means of internal communication. Whatever may have been the degree of care bestowed by the Hindoo and Mahomedan Governments on the former object, it has not been pretended that they did anything for the latter. It was never their practice to lay out money in the construction of permanent roads, or in the formation of canals for navigation. The plains of India are traversable by carts, and even by armies, without made roads, throughout the dry season; and neither (in general) military movements, nor commercial transport, were carried on during the rains. Roads, therefore, in India, were not, as in some countries, a matter of absolute necessity; and in this respect, whatever has been done at all, has been done by the British Government.

⁶⁹Charles George Dixon (1795-1857), a Colonel in the East India Company's army, author of *Sketch of Mairwara: Giving a Brief Account of the Origin and Habits of the Mairs* (London: Smith, Elder, 1850), which includes descriptions of the irrigation works in Ajmeer-Merwara.

⁷⁰See "Despatch in the Public Works Department of the Court of Directors to the Governor-General of India in Council, 9 Sept. (No. 13), 1857," summarized in "Papers Relating to Irrigation Works, India," *PP*, 1861, XLIII, 308.

Grand Trunk Road

The most important line of road in India is the Grand Trunk Road from Calcutta to Delhi, through Hooghly, Burdwan, and Benares, and including either in the main line, or by means of branches, all the principal cities of the North-west Provinces. This road, 837 miles in extent, has been gradually brought to its present state of a thoroughly well-formed road, metalled and bridged, except a few of the larger rivers, which are still crossed by ferries; but over all these (it is believed), except the Ganges and the Soane, bridges are in course of construction. This road, with its continuation to Kurnal (and now to Lahore, which is in course of completion), has been divided into different portions, each under the charge of a separate engineer officer, with an establishment for the purposes of construction, or of maintenance and protection, as the case may be. The cost of the Grand Trunk Road as far as Delhi had been, up to the year 1848, £489,100, and the annual expense of maintaining it was then estimated at £35,000.

Since the annexation of the Punjab, a continuation of the Grand Trunk Road from Lahore to Peshawur, a distance of 275 miles, has been in progress. This road also is to be completely metalled and bridged throughout. The cost was estimated, when the work was sanctioned in 1852, at £154,848. By means of this road a direct line of communication will have been established between Calcutta and the extreme boundary of the British territory to the north-west, a distance of 1,500 miles. Besides this, many other roads in the Punjab, and among them roads from Jullundur to Lahore, and from Lahore to Mooltan, have been undertaken.

The sea has been mainly relied on for communication with Madras; but roads are now in course of formation, which will provide a line of continuous communication by land.

Great Deccan Road

The land communication with Western India is carried on by way of the Grand Trunk Road to Benares, onward by Mirzapore and Jubbulpore to Nagpore, and thence to Bombay. The road beyond Mirzapore, under the name of the Great Deccan Road, was commenced thirty years ago, but was kept up only as a fair-weather road till within the last few years, when arrangements were made for its being thoroughly raised, metalled, and bridged. The distance from Mirzapore to Nagpore or Kamptee, is nearly four hundred miles. Estimates amounting to £11,659 were sanctioned by the Court of Directors in 1856, for bridging the portion of road between Mirzapore and Jubbulpore, which had been already metalled; £25,084 were also sanctioned for raising and metalling the portion between Jubbulpore and Kamptee, and measures were further authorized to bridge this portion of the road.

Agra and Bombay Road

Another great and important line, the Agra and Bombay road, 735 miles in

length, was commenced in 1840. In 1854, the Court sanctioned an annual expenditure of £9,880 for the maintenance and improvement of the portion of this road between Agra and the frontier of the Bombay Presidency.

Dacca and Chittagong Road

After the annexation of Pegu, roads were projected by way of Dacca to Arracan, from which province a road was to be carried over the mountains to Prome. Great difficulty was experienced in laying out a road from Calcutta to Dacca, and it is probable that this part of the project will not be carried into effect; the traffic of this district, so intersected by tidal channels, being left to be carried on by water, unless it shall be found practicable to form a railway. A road to Jessore (the line of communication with Assam and Burmah) was however sanctioned, at a cost of £41,720 on a rough estimate. From Dacca to Chittagong, considerable progress has been made in the formation of a road, or rather in the completion, as a first-class road, of the road which, though in a most inefficient state, previously existed. From Arracan into Pegu, the task of forming a road across the mountains by the Toungoo Pass has been most successfully accomplished by Lieutenant Forlong.⁷¹

Pegu Roads

In Pegu itself, no time was lost after the acquisition of the province, in commencing improved means of communication. The sanction of the home authorities was sought and given to roads from Rangoon to Prome, a distance of nearly two hundred miles, at an estimated cost of £160,000, and from Martaban to Toungoo *via* Sitang.

Miscellaneous Roads

Besides the great lines of communication above enumerated, a multitude of shorter lines have been constructed, at the entire cost of Government, in Bengal, the North-western Provinces, and the Punjab, while considerable sums have annually been expended in the two former divisions of territory from local funds. Among the roads either completed or under construction at the expense of Government, is one from a point on the East-India Railway to Darjeeling (roughly estimated at about £200,000); another from Doobee, on the Grand Trunk Road, to Patna (cost £115,000); numerous roads in the Saugor and Nerbudda territories; and a road from the plains to Simla and the other hill stations, continued through the mountains to Chini in Thibet. The district roads were, until within the last few years, maintained from the profits of the ferries kept up by Government; but there are now also appropriated to this purpose, in Bengal, the surplus tolls on the

⁷¹James George Rorke Forlong (1824-1904) was head of the Public Works Department at Pegu.

Nudea rivers and the Calcutta canals, amounting altogether to £50,000, and the surplus proceeds of various local funds established for other purposes. In the North-western Provinces, one per cent on the land revenue is contributed in equal portions by the Government and by the landowners, for the purpose of district roads; the landowners being thus freed from the obligation which previously lay on them, of keeping in repair the public roads which passed through their lands. In these provinces, as in Bengal, the ferry funds are appropriated to district roads, and they amount to about £20,000.

Madras Roads

The first step to the systematic prosecution of road-making in the Madras Presidency was taken in 1845, by the appointment of an officer to the charge of the main or trunk lines of road, and the appropriation to the maintenance and improvement of the roads, of the annual sum of £40,000. The roads under the charge of the superintendent were, the Western Road, to the Mysore frontier towards Bangalore (200 miles); the Southern Road, to Trichinopoly (205 miles); the Northern Road, to the Bengal frontier, with a branch to Cuddapah (785 miles); and the Sumpajee Ghaut Road, from the western frontier of Mysore to Mangalore (105 miles). Up to May 1851, £37,121 had been expended on the Western Road, exclusive of the cost of superintendence; and the road had been made passable for travelling-carriages at the rate of six miles an hour. Besides the road department under the charge of the superintendent, the Civil Engineers of districts were charged with the improvement of the district roads, under the orders of the Collectors; and the care of roads in some districts was under the officers of the Military Board. The expenditure on roads, bridges, and ghauts, under the Madras Presidency, increased in the five years from 1846 to 1850, from an average of £16,179 to one of £42,076. The expenditure in 1849, 1850, and 1851, was respectively £45,149, £58,197, and £59,680. In the succeeding year the department came under an improved organization; and the outlay in 1855-56, the last year for which it can be ascertained, was £193,930; to which may be added £30,957 for navigable canals,—in all, £224,887.

Among the works in progress in the Madras Presidency for the improvement of the means of communication, is the formation of the East Coast Canal, to be effected by the junction of the various back-waters, and of the local canals which in several places already exist, completed by entirely new channels to be excavated. The expenditure on this work, up to 1855-56, amounted to £14,171.

Bombay Roads

The made roads in the Bombay Presidency, twenty-five years ago, were almost entirely limited to the presidency town and its immediate neighbourhood; the road from Bombay (or rather Panwell, on the other side of the harbour) to Poonah, being the only road to a distant place on which any considerable expenditure had

taken place. This road has since been greatly improved, and supplied with bridges. The Bhore Ghaut, or pass, on this road, formerly accessible only to bullocks, and coolies (or porters), had in 1830, at an expense of about £13,000, been made easy for carriages: the Thull Ghaut, on the Bombay and Agra road, has since been similarly improved; and roads over the Khoonda Ghaut, the Tulkut Ghaut, and the Koomtudee Ghaut, to the southward, have since been put under construction, to facilitate the communications between the coast and the interior of the country.

The portion of the Agra and Bombay road within the jurisdiction of the Bombay Government is 270 miles in length: the expenditure on it had amounted, in 1848, to £75,390; and since that time a considerable outlay has taken place, especially on the improvement of the Thull Ghaut and the road below it.

Sind Roads

A system of roads for Sind, at an estimated cost of from £20,000 to £30,000, received the sanction of the home authorities in 1854, and is in progress.

New Organization of Public Works

From the preceding details it will be seen that very considerable sums had been expended on the construction and improvement of roads in India at a much earlier period than is frequently represented. But the extraordinary activity with which these operations have been carried on dates from 1850. In January of that year, the home authorities, being dissatisfied with the progress made in the prosecution of public works throughout India, deliberately reviewed, in a despatch to the Government of India, the system under which such works had, up to that time, been carried on, and found, in the division of responsibility and the absence of unity of action, ground for the opinion that a great change was required.⁷² In consequence of the orders contained in that despatch, a Commission was appointed in each presidency, to consider and report on the subject. Their investigations have led to the formation of a separate department of Public Works in each presidency, based on one uniform plan, and to the addition of a secretary in the department of Public Works to the secretariat of the Government of India. From this period to the commencement of the present unhappy disturbances, the activity of the department has been incessant; the engineer officers of the three Indian armies supplying the higher order of professional skill, and the subordinate European superintendence being afforded by numerous non-commissioned officers possessing the requisite qualifications, and latterly by a considerable number of civil engineers, engaged in England, who have proved in many cases of the greatest value to the department.

⁷²See "Letter from the Court of Directors to the Government of India, Public Department, 30 Jan. (No. 2), 1850," in "Papers Relating to Public Works, India," *PP*, 1852-53, LXXV, 1-10.

Colleges of Civil Engineering

As a means of supplying well-qualified subordinates for the purpose of public works, a college for instruction in civil engineering was established in 1847. It was fixed at Roorkee, near the head of the Ganges Canal, the works and establishments at that place affording peculiar facilities for combining practical with theoretical instruction. The plan of the college was greatly enlarged in 1852; and its annual charge is about £7,000. The establishment of colleges of civil engineering at Calcutta, Madras, and Bombay, has subsequently been sanctioned.⁷³

Railways

The preceding statements relate only to works constructed by public money. The construction of railways is carried on by private capital, with a guarantee of interest by the Government. It is proper to give a brief summary of the railway-works which have been sanctioned and commenced.

Four thousand one hundred and fifty-eight miles of railway have been sanctioned, and measures are being taken for their construction under a guarantee of interest, viz.:

By the *East-Indian Railway Company*, from Calcutta to Delhi, with branches from Burdwan to Raneegunge, and from Mirzapore to Jubbulpore, 1,400 miles.

By the *Eastern Bengal Railway Company*, from Calcutta to the Ganges at Koostree, near Pubnah (130 miles), being the first section of a line to Dacca, with a branch to Jessore; which, when completed, will form the basis of a system of railways for Eastern Bengal.

By the *Madras Company*, from Madras to the western coast at Beypore, 430 miles; and

From Madras, *viâ* Cuddapah and Bellary, to meet a line from Bombay at or near the river Kistna, 310 miles.

By the *Great Indian Peninsula Company*, from Bombay to Callian, thirty-three miles, with extensions,

North-east to Jubbulpore, to meet the line from Mirzapore, with a branch to Oomrawuttee and Nagpore, 818 miles; and south-east, *viâ* Poonah and Sholapore, to the Kistna river, to meet the line from Madras, 357 miles.

By the *Sind and Punjab Company*, from Kurrachee to a point on the Indus, at or near to Kotree, 120 miles; and from Moulton to Lahore and Amritsir in the Punjab, 230 miles.

By the *Bombay, Baroda, and Central India Company*, from Bombay to Surat, Baroda, and Ahmedabad, 330 miles.

⁷³See "Despatch from the Court of Directors of the East India Company to the Governor-General in Council, 19 July (No. 49), 1854," *PP*, 1854, XLVII, 160.

The following statement shows the amount of capital which, it is estimated, will be required for the above extent of lines, and the amount of capital already issued:

| RAILWAY COMPANY | Estimated outlay required to complete the several Lines sanctioned | Total amount of Capital at present issued with the sanction of the East-India Company |
|-----------------------------------|--|---|
| East Indian | £12,731,000 | £8,731,000 |
| Eastern Bengal | 1,000,000 | 1,000,000 |
| Madras | 6,000,000 | 4,000,000 |
| Great Indian Peninsula | 10,000,000 | 6,333,300 |
| Sind and Punjab | 2,500,000 | 1,000,000 |
| Bombay, Baroda, and Central India | 2,000,000 | 1,750,000 |
| | £34,231,000 | £22,814,000 |

In addition to this assistance by way of guarantee, the land for the railways (including compensation for all buildings thereon), and for their termini, has been given by Government. The value of this may be estimated at more than £1,000,000 for the above extent of line.

The lines in course of construction have been chosen for commercial, quite as much as for military and political, objects. In every case the existing channels of trade have been followed. The chief cotton-producing districts are provided with railway accommodation; and in one or two instances, such as the railway which connects the great cotton-field of Berar with Bombay, and the railway through Surat and Guzerat, the principal object is to develop the agricultural resources of those districts, and to bring their produce into communication with the sea.

At present only a small section is open in each Presidency, making about 400 miles in all; but 3,600 more are being constructed almost simultaneously. The following statement will show the sections now open, the periods at which other sections are to be opened, and at which the whole will be completed: [See pp. 138-9.]

The works for the trunk lines above described have been made suitable for locomotive engines, and are of a solid and permanent character, so that an uninterrupted communication will be maintained throughout the year.

The mileage cost of the lines which have been completed has been:

East Indian.—Calcutta to Raneegunge, 121 miles (including double line to Burdwan, and terminal stations), about £12,000 per mile.

Madras.—Madras to Arcot, sixty-five miles, about £5,500 per mile.

The data in respect to the line now open in the Bombay Presidency, constructed by the Great Indian Peninsula Railway Company, are not sufficiently complete to enable the actual mileage cost to be ascertained.

It is, perhaps, premature to judge of the success of Indian railways as commercial undertakings; but the line from Calcutta to Raneegunge is already

| RAILWAY COMPANY | Total length of Lines | Experimental Line | Periods at which it is estimated that the remaining Works on the Lines will be completed |
|---|-----------------------|--|--|
| EAST INDIAN:— | | | |
| Calcutta to Delhi . . . say | 1,100 | Calcutta to Burdwan, and branch to Raneegunge, 121 miles; commenced 1850, completed 1855 | Burdwan to Rajmahal (130 miles), 210 from Calcutta; December, 1860 |
| Mirzapore to Jubbulpore (a) | 300 | | Between Allahabad and Cawnpore (1st section N. W. P. division), 126 miles; nearly ready for opening† |
| (a) Note—No period yet specified for the completion of the line | 1,400 | | Cawnpore to Delhi, 260 miles; October, 1858 (excepting the bridge over the Jumna) |
| GREAT INDIAN PENINSULA:— | | | |
| Bombay to Callian | 33 | Bombay to Callian, 33 miles; commenced 1850, completed 1854 | Callian to Bhosawal, 241 miles; October, 1859 |
| Callian to Jubbulpore, with branch to Nagpore, via Oomramuttee | 818 | Sections N.E. to Wassind (16 miles) and S.E. to Campoolie (38 miles) have subsequently been opened. Now open, 87 miles | Bhosawal to Oomrawuttee to Nagpore, 138 miles; March, 1861 |
| Callian to the Krishtna, via Poonah and Sholapore | 357 | | |
| | | | N. E. LINE |
| | | | Bhosawal to Sholapore to Krishtna; not estimated, probably the end of 1861 |
| | | | S. E. LINE |
| | | | Poonah to Sholapore 165 miles; 1860 |
| | | | Callian to Poonah, 91 miles; February, 1858 |
| | 1,208 | | |

MADRAS:—

| | | | |
|--|-----------------------------|---|--|
| Madras to Beypore Madras, <i>via</i> Cuddapah and Bellary, to the Krishtna, about | 430 310 <hr/> 740 | Madras to Vellore, 81 miles, commenced 1853, completed to Arcot 1856, and to Vellore in 1857 Vellore to Vaniembaddy, 125 miles from Madras, January, 1858. To Beypore on the Western coast, March, 1859 | The line to the Krishtna not yet estimated, probably to Bellary in 1861, and to the Krishtna in 1862 |
|--|-----------------------------|---|--|

SIND:—

| | | |
|---|-----|--|
| Kurrachee to the Indus, at or near to Kotree | 120 | Estimated to be completed by October, 1859 |
|---|-----|--|

BOMBAY, BARODA, AND CENTRAL

INDIA:—

| | | |
|---|-----|---|
| Bombay to Surat, Baroda, and Ahmedabad | 330 | Estimated to be completed from Surat to Baroda in 1858, and to Ahmedabad in 1859. The section between Bombay and Surat not yet estimated |
|---|-----|---|

*Delays have occurred in this district, in consequence of the Sonthal insurrection and the subsequent disturbances in Bengal

†Would have been opened by December, 1857, but for delays occasioned by the mutiny.

earning a profit of nearly seven per cent, being two per cent beyond the guaranteed rate of interest. The following table will show the extent of traffic on the East-Indian Railway for the year ending 31st December, 1856:

| PERIOD | Number of Passengers conveyed | | | |
|--|-------------------------------|-----------|-----------|---------|
| | 1st Class | 2nd Class | 3rd Class | Total |
| Six Months ending 30th June, 1856 | 6,466 | 23,256 | 402,599 | 432,321 |
| Six Months ending 31st December, 1856 | 6,639 | 25,877 | 432,605 | 463,121 |
| | 13,105 | 49,133 | 835,204 | 895,442 |

| PERIOD | Goods Tons | Receipts | | |
|--|---------------|----------|----|----|
| | | £. | s. | d. |
| Six Months ending 30th June, 1856 | 33,010 | 95,188 | 16 | 4 |
| Six Months ending 31st December, 1856 | 44,675 | | | |
| | 77,685 | 95,188 | 16 | 4 |

It may be observed that these are the results of the traffic on a line where the amount of merchandise conveyed is very small, compared with what it will become when the railway is continued to the Ganges at Rajmahal.

The numbers stated under the head of "Third Class," in the above table, will in some degree indicate the extent to which the natives use the railway. The receipts from this class are nearly four times as great as from the two higher classes combined; the receipts from passenger traffic in the half-year ending 30th June 1856, having been:

| | | |
|-----------|-----|----------|
| 1st Class | Rs. | 27,986 |
| 2nd " | | 29,589 |
| 3rd " | | 1,99,883 |

In addition to the lines specified above, the Court have sanctioned the construction of one by the Calcutta and South-eastern Railway Company, from Calcutta to the Mutlah river, upon the same terms as to the provision of land, but without any guarantee of interest.

Electric Telegraph

Even more important as a means of communication than railways, is the electric telegraph; the use of which, at the commencement of the late disturbances, may be

said with scarcely any exaggeration to have saved our empire. Having already, in a wonderfully short space of time, connected the seats of the different Governments by lines of telegraph upwards of three thousand miles in length, the Government of India is now engaged in establishing additional lines of about the same extent, through which the most important places will be brought into communication with each other by alternative routes.

The lines established, and in course of construction, are:

1st. From Calcutta, *viâ* Benares, Cawnpore, Agra, Meerut, Delhi, Umritsir, and Lahore, to Peschawur; with a branch to Lucknow.

2nd. From Bombay to Agra, *viâ* Indore and Gwalior.

3rd. From Bombay to Madras, *viâ* Sattara, Bellary, and Bangalore.

4th. From Bombay along the coast, by Vingorla and Mangalore, to Cananore.

5th. From Bangalore to Ootacamund and Mahableshwar.

6th. From Benares, through the centre of the Peninsula, by Mirzapore, Jubulpore, Nagpore, and Hyderabad, to Bellary.

7th. From Bombay, by Surat and Baroda, to Kurrachee.

8th. From Kurrachee, by Hyderabad (Sind) and Moulton, to Lahore.

9th. From Calcutta, by Dacca, Akyab, and Prome, to Pegu and Rangoon.

10th. From Calcutta to Madras, by the coast; and—

11th. From Madras, along the coast, by Pondicherry, Tranquebar, and Ramnad, to Ceylon.

The lines already established have cost, upon an average, about £50 per mile. Besides their inappreciable value to the Government for political and military purposes, they are freely used by the mercantile community. Though the charges are very moderate, the revenue, in the first year of working the lines, exceeded the expenses, and since then the receipts have been steadily increasing.

EDUCATION

Early Educational Proceedings

The first measures of the English Government for aiding education in India were directed to the preservation of Oriental learning from decay; and several institutions, supported or endowed by Government, were maintained for that special purpose. A secondary object was the training for the service of Government, of men acquainted with the systems of law followed by the various religious communities, and constituting on certain subjects the rule binding on our tribunals.

The views of the Government, however, gradually underwent a great change; and, partly from the spontaneous action of the Government and its officers, partly by directions from home, the basis of the Government measures for promoting

education was greatly widened, on the one hand by introducing the study of English into all the higher places of instruction under Government influence, and on the other by giving a much wider range and greater practical utility to the studies carried on in the vernacular or other Oriental languages.

Government Colleges

All the Government educational institutions in Bengal have been either gradually brought within the scope of these principles, or were originally founded on them. Those institutions consisted, previously to 1854, of the Hooghly, Dacca, and Kishnaghur provincial colleges, with the schools attached to them: to these has since been added a college at Berhampore. At Calcutta itself, the Government contributed to the funds for the support of the Hindoo College and of the Mahomedan Madrissa, but there was no institution at the Presidency town open to all classes and creeds, at which an education of a high order was imparted. This deficiency was supplied in 1854, an arrangement being made by which the Hindoo College, as an exclusive institution, was abolished, and a Presidency College established, calculated to afford an education of the highest order, and open without restriction to all sections of the community.⁷⁴ The cost of this institution will amount to above £10,000, when all the arrangements shall be complete. It amounted in 1855-56 to between £7,000 and £8,000. In addition to general education, provision is made in this institution for instruction in law and jurisprudence: medicine and civil engineering are otherwise provided for.

The Government colleges in the North-western Provinces consisted, in 1854, of those at Benares, Agra, Delhi, and Bareilly. In these, as at the Bengal colleges, education was imparted through the medium both of English and of the vernacular. The education given was of a very efficient character, and the students generally obtained employment in the service of Government, in which many of them fill situations of responsibility.

Village Schools

For a considerable period, the direct aid of Government to education, both in Bengal and in the North-western Provinces, was principally confined to the Government colleges, and to the schools which were attached or affiliated to them for the purpose of supplying them with students. In 1846, however, Mr. Thomason, the Lieutenant-Governor of the North-western Provinces, proposed a plan for the establishment throughout those provinces of a system of village

⁷⁴Court of Directors' Public Despatch to the Governor General in Council. No. 62 of 13 Sept., 1854: E/4/977, pp. 517-37.

schools, by means of an assignment of land by Government for the support of a schoolmaster in each village.⁷⁵ In 1848 Mr. Thomason submitted amended proposals, confined to the establishment by Government of one school in each tehsel, as a model for the village schools, and the institution of a visiting agency, which, with a visitor-general at its head, should not only superintend the Government schools, but visit the village schools generally, for the purpose of assisting and aiding the masters, and rewarding the most deserving.⁷⁶ The cost of this scheme, for all the districts of the North-western Provinces, was estimated at upwards of £20,000; but it was considered best to introduce the plan experimentally in eight districts, at a cost of £3,600 per annum (exclusive of the salary of the visitor-general); and this measure proved so successful in the selected districts, that its extension to all the thirty-one districts of the North-western Provinces was subsequently sanctioned, at a total cost of £17,207.⁷⁷

Hulkabundee or Circle Schools

But valuable as were the general results of this scheme, and useful as were the tehsel schools to the inhabitants of the towns, the village schools (though the numbers attending them had considerably increased) did not improve as had been hoped; and a new plan was accordingly devised, with the best prospects of success, to meet the wants of the agricultural population. This is the establishment of hulkabundee or circle schools. Several villages conveniently situated for the purpose are grouped together, and in a central situation a school is established, at the joint cost of all the villages, none of which is more than two miles from the central school. For the support of these schools, the consent of landowners was sought to the appropriation of a small percentage on the amount of the Government revenue (one per cent being the amount fixed), of which half is contributed by Government and half by the landowners. The assent of the landowners to this plan has been obtained in many districts; and it will be made a condition of all future settlements, and has been so made as resettlements have taken place. It is estimated that when all the districts shall have been resettled (which will not be till 1874), £40,000 per annum will be thus available; of which £20,000 will be at the expense of Government, and £20,000 at that of the landowners.

In Bengal, the establishment of 101 vernacular schools had been authorized by

⁷⁵See "Plan No. 80a Annexed to Letter No. 1089 (18 Nov., 1846), from the Government of the North-western Provinces to the Government of India," in *Selections from the Records of the Government, North Western Provinces: Mr. Thomason's Despatches* (Agra: Secundra Orphan Press, 1856), Vol. I, pp. 329-33.

⁷⁶*Ibid.*, pp. 397-402.

⁷⁷Letters from the Court of Directors to the Government of the North-Western Provinces, 7 May (No. 24) and 8 May (No. 26), 1856; see *PP*, 1859 (II), XXIV, Pt. 1, 5, for extracts.

the Government in 1844,⁷⁸ shortly before the first proposals of Mr. Thomason. The schools were established at the places where they were thought most likely to succeed; but, except in a very few cases, they failed to attract scholars, the old indigenous schools, where nothing worthy of the name of education was afforded, proving more popular. In 1853 and 1854, accordingly, this system was superseded, in favour of the plan already adopted in the North-western Provinces, of a visitorial staff, model schools, and aid and encouragement to indigenous schools. The estimate for the plan, on the experimental scale proposed, amounted to about £7,000 per annum.⁷⁹

Schools for Teachers

There was a normal school for the masters of vernacular schools at this time at Agra, which was working very well. At Calcutta, the Sanscrit College furnished a considerable number of masters suited for village schools.

Thus stood the arrangements of the Government for native education in India, when a new impulse was given to the subject by the orders from home in 1854.⁸⁰ Before adverting to these, something must be said of what had previously been done in the two subordinate presidencies.

The history of education at Madras, up to a recent period, presents little beyond a record of failures. A plan was proposed by Sir Thomas Munro in 1822, and approved by the home authorities, for the establishment of provincial, district, and tehsel schools, throughout the Presidency, at an estimated cost of £5,000 per annum.⁸¹ Schools were established, but they proved failures, and were abolished. The University of Madras was nominally established by Lord Elphinstone's Government;⁸² but in the only department of it which was really proceeded with—the lower department, or “High School”—the success was by no means

⁷⁸“Letter from the Undersecretary to the Government of Bengal, to the Secretary to the Sudder Board of Revenue, 18 Dec., 1844,” in *General Report on Public Instruction in the Lower Provinces of the Bengal Presidency, for 1844-45* (Calcutta: Sanders and Cones, 1845), App. No. 2, pp. clxix-clxxiii.

⁷⁹See “Report of the Council of Education, dated the 3rd October, 1853, Reviewing the State of Vernacular Education and Proposing the Establishment of Model Vernacular Schools,” in *Selection from the Records of the Bengal Governments. No. 22: Correspondence Relating to Vernacular Education in the Lower Provinces of Bengal* (Calcutta: Jones, 1858), pp. 27-40.

⁸⁰I.e., the Despatch of 19 July, 1854; see n73 above.

⁸¹For Munro's plan, see his Minutes of 25 June, 1822, and 10 Mar., 1826, in *PP*, 1831-32, IX, 531-2, and 536-7; for the approval, see “Extract Letter, in the Revenue Department, from the Court of Directors to the Governor in Council of Fort St. George, dated 18th May, 1825,” *ibid.*, p. 536.

⁸²John Elphinstone (1807-60), Baron Elphinstone, was Governor of Madras 1837-42 (and then Governor of Bombay 1853-59).

great, and the number of pupils was quite disproportionate to the expense. The whole subject of education came under reconsideration in 1852, when a plan was laid down by the Government, which provided for the education of all classes in a way very much in accordance with that which has since been laid down for adoption throughout India; comprising a central institution at the Presidency, provincial colleges or high schools, zillah and tehseelee schools, with a system of inspection or visitation, and grants in aid.⁸³ The University at Madras was at once remodelled; but little progress had been made, up to 1854, in carrying out the other parts of the plan, beyond the establishment of provincial schools at Cuddalore and Rajahmundry.

Colleges and Schools in Western India

The principal places of education in the Bombay Presidency are the Elphinstone Institution at Bombay, and the College at Poonah. These institutions, partly founded by native subscriptions and partly by the Government, were designed to afford a collegiate education of a high class, through the medium of the English language, a staff of professors being maintained for giving instruction in mathematics, English literature, natural philosophy, logic, mental and moral philosophy, political economy, etc. A high school was attached to the Elphinstone Institution, and a Sanscrit department to the Poonah College. In 1854-55 there was only one district of the Presidency in which there was not a Government English school. Vernacular schools had been established in many places at the expense of Government, but as the plan had not long been adopted of requiring any part of the cost to be defrayed from local resources, operations in this direction had been much limited by want of funds. Under a plan brought into operation shortly before 1854, the establishment of a school by Government was made conditional on a portion of the expense being defrayed by the inhabitants;⁸⁴ and under this rule vernacular education was in course of steady extension up to 1854. A normal class for masters of Mahrattee schools existed at Poonah, and one for masters of Guzerattee schools at Surat.

Education Despatch of 1854

It is now time to advert to the despatch from the home authorities of the 19th of July 1854, which was designed to give as great an additional impulse to the

⁸³For the details, see "Minute, Board of Governors of the Madras University, dated 2nd July, 1852," in *Selections from the Records of the Madras Government, No. 2: Papers Relating to Public Instruction* (Madras: Male Asylum Press, 1855), App. C.C.C., pp. ccxcvii-ccciv.

⁸⁴See "Bombay. Notification, Dated 16th May, 1854, Relative to the Establishment of Vernacular Schools," in *Report of the Board of Education, Bombay, from 1st May 1854, to 30th April, 1855* (Bombay: Bombay Education Society's Press, 1855), App. XV, pp. 117-18.

operations of Government in the promotion of education, as had already been given to the department of Public Works. This despatch directed that the previous Boards of Education, which consisted of private persons and of Government officers in their private capacity, should be abolished, and that a department of Education, under a director, should be appointed in each Presidency and sub-Presidency. The limits which had previously been placed upon the total expenditure of each Government for educational purposes, were removed. The establishment of universities at the Presidency towns was directed, and minute instructions were given respecting the mode of their constitution. A great extension of vernacular education was contemplated, and orders were given for introducing the system of grants in aid to private institutions, dependent on the quality of the secular instruction given, as ascertained by a Government inspection.

Directors of Public Instruction

Effect was immediately given to these instructions, so far as regards the formation of the controlling establishments. Directors of Public Instruction were appointed in Bengal, the North-western Provinces, Madras, Bombay, and the Punjab, and under them inspectors and sub-inspectors of different grades, and in numbers proportioned to the territories to be superintended.

Grants in Aid

Rules for regulating grants in aid have been laid down,⁸⁵ and considerable grants have been made under all the Governments. The amount of these grants was at first limited by the authorities in India to a certain percentage on the expenditure on Government institutions; but this limit has been taken off by instructions from home.⁸⁶

Universities

Universities have been constituted, under acts of the Legislature of India, at Calcutta, Madras, and Bombay.⁸⁷ Measures are also in progress for carrying out the objects of the despatch of 1854, as regards vernacular education in Bengal, Madras, and Bombay. In the North-western Provinces it has only been necessary to give greater extension, as had been previously intended, to the measures already introduced.

⁸⁵See "Correspondence Relating to the Education Despatch of 19 July, 1854," *PP*, 1857-58, XLII, 354-9.

⁸⁶See "Extract Public (Education) Letter to India, dated 15 July (No. 96), 1857," *ibid.*, pp. 371-2.

⁸⁷By, respectively, Acts II (24 Jan.), XXVII (5 Sept.), and XXII (18 July) of 1857.

Medical Schools and Colleges

In addition to the institutions for giving a general education to the different classes of the community, either through English or the vernacular, colleges or schools for several branches of professional education are maintained at the different presidencies. Of the engineering colleges mention has already been made. Medical schools had from an early period been maintained at all the presidencies, to train persons for employment in the subordinate branches of the medical service, as compounders, dressers, native doctors, etc. These institutions were gradually raised in character, and for many years past have held the rank of colleges, in which medical education of a first-class character is afforded. They have, in consequence, received the "recognition" of the College of Surgeons in London; and the graduates of these colleges are entitled to all privileges which are conferred by the College of Surgeons on the members of the colonial medical institutions recognized by them.

Native Medical Service

The graduates almost invariably enter the service of Government, though some few, especially at Bombay, prefer private practice. To afford encouragement to the graduates of the colleges, and meet the want of well-qualified medical officers for the service of Government, a special native medical service has been created, under the title of Sub-Assistant Surgeons, for which a degree in one of the medical colleges of India is a necessary qualification. These officers are divided into three grades, promotion being regulated by the joint consideration of length of service and professional qualification, as ascertained by special examination. The principal use which has been made of this class, has been in connection with the Government dispensaries; but some few have been appointed to the charge of the smaller stations. Their professional qualifications are, in many cases, of a high order; and the triumph which has been effected over the religious prejudices of the natives, in popularizing the dissection of dead bodies, is a proof that this indirect mode of correcting their superstitions, by the influence of useful knowledge, is a highly effectual one.

School Books

The important subject of school books has been for many years attended to. In the North-western Provinces a very large number of vernacular books, either originals or translations, have been prepared under the auspices of the Director of Education; and a highly efficient system is in force for their sale and distribution among the schools of all classes. At Calcutta and Bombay, much has also been

done; and arrangements have more recently been made for the supply of school books in the difficult vernacular languages of the Madras Presidency.

Educational Test for Public Employment

As a powerful stimulus to the general population to avail themselves of the means of education now placed so generally within their reach, rules have been laid down absolutely requiring a certain amount of education in all persons employed in the public service, except in situations of the lowest class.⁸⁸ Even for those lower employments, the officers intrusted with the appointments are expected to select persons capable of reading and writing, provided they are qualified in other respects; and returns are required, under most of the Governments, of appointments made, with special reference to this point.

Female Education

An inroad has begun to be made upon native prejudices even in the department of female education. The late Mr. Drinkwater Bethune⁸⁹ benevolently established a school for Hindoo girls at Calcutta, which, after his death, was adopted by the Marchioness of Dalhousie,⁹⁰ supported by the Marquis of Dalhousie until he left India, and is now maintained as a Government institution under the special orders of the home authorities.

A highly satisfactory commencement of female education in the North-western Provinces was made in 1856, by the exertions of a meritorious native functionary, the sub-inspector of schools, Pundit Gopal Sing.⁹¹ By his influence ninety-seven female schools were established in the city and district of Agra, and each school was attended on an average by twenty pupils. The good example has been followed by the formation of female schools in the zillahs of Muttra and Mynpooree. In the Bombay Presidency, schools for females have been established by natives at Poonah, which are stated to be in satisfactory operation; and some native ladies of wealth and influence at Ahmedabad have lately endowed a female school at that city.

Female education is included within the operations of the enlarged Government scheme of education, and it is hoped that progress will be gradually made in its diffusion.

⁸⁸See "Resolution of 10 Oct., 1844," *PP*, 1845, XXXIV, 133-4.

⁸⁹John Elliot Drinkwater Bethune (1801-51), Member of the Governor-General's Council from 1848, and President of the Council of Education.

⁹⁰Susan Georgiana Ramsay (1817-53).

⁹¹Not otherwise identified.

MISCELLANEOUS IMPROVEMENTS

Various important measures have been adopted within the last twenty years, both for the improvement of the productions of India and for the introduction of new products.

Cotton Experiments

In 1840, ten experienced cotton-planters from the United States were engaged, and proceeded to India to conduct, on account of Government, the experimental cultivation of superior kinds of cotton. In the majority of the districts the experiment failed from unsuitability of climate, but in parts of South-western India it was successful, and a large cultivation of American cotton in those districts now takes place. It is to be remarked that these districts are near the coast, and united with it by improved roads; and, indeed, with the exception of Berar (into the heart of which a line of railway will shortly be carried), all the principal cotton districts of India have ready access to water-carriage, and are not materially impeded by the remaining imperfections of the internal communications.

A most complete body of information on the cotton cultivation of India, and on the suitability of the various local soils and climates to the cultivation both of the native and the foreign varieties of the plant, has been obtained through the exertions of the American planters and of the servants of Government, and has been condensed and made public in the two works entitled, *On the Culture and Commerce of Cotton in India*, and *Review of the Measures which have been adopted in India for the improved Culture of Cotton*, by an eminent officer of the East-India Company, the late lamented Dr. Royle;⁹² so distinguished as a man of science, and whose thorough knowledge and understanding both of the Indian climates, and of general climatology in its relation to vegetable productions, has never been excelled, if equalled.

Indian Fibrous Productions

The same eminent authority, in his work entitled, *The Fibrous Productions of India*, has made known an amount of internal resources, of the greatest value to this country (especially in the contingency of a Russian war), of which no one,

⁹²John Forbes Royle (1799-1858), botanist, doctor in India 1819-31, Professor at King's College from 1837, who supervised a new department of correspondence concerning vegetable productions at the East India House from 1838 till his death: *On the Culture and Commerce of Cotton in India and Elsewhere* (London: Smith, Elder, 1851), and *Review of the Measures Which Have Been Adopted in India for the Improved Culture of Cotton* (London: Smith, Elder, 1857).

even of those who had the strongest private interest in the subject, had a suspicion.⁹³ The collection of raw products, brought together from all parts of India for the Paris Exhibition of 1855, has vastly extended the knowledge accessible to manufacturers and merchants, of the numerous articles suited to the European market, and capable of being imported in any quantity, which only await the necessary attention and the necessary funds on the part of enterprising individuals. An Industrial Museum has recently been formed at the India House for the reception of these and other choice specimens of Indian produce and manufactures.

Tea Cultivation

The Assam tea has been brought into regular cultivation; and the teas of China have been introduced as a staple product of agriculture, at the expense of Government, into the parts of the Himalayas which are suitable in point of climate. Mr. Fortune was employed in China to obtain a large quantity of the best seeds, and to engage Chinese experienced in the growth and preparation of the article.⁹⁴ There is already a considerable production of the higher qualities of tea in these mountains; large tracts of waste land suited to the cultivation are now placed at the disposal of persons desirous of engaging in it, and seeds and plants are given largely and gratuitously from the Government experimental establishments, to all who apply for them with a view to cultivation.

Hospitals and Dispensaries

The Indian Governments have long been active in placing the means of medical relief within reach of the population. The rules in force provide for the establishment of a civil hospital or a dispensary, in every town the inhabitants of which have shown their appreciation of the benefit by either providing funds for the erection of a building, or contributing towards the support of the necessary establishments, or by having for some time actually supported a dispensary on a limited scale from their own resources. These institutions are mostly managed by natives trained at the medical colleges; a general superintendence resting with the civil surgeons of the different stations. Their success has been very great. The

⁹³*The Fibrous Plants of India, Fitted for Cordage, Clothing, and Paper* (London: Smith, Elder, 1855).

⁹⁴Robert Fortune (1813-80), who travelled to collect plants for the Royal Horticultural Society, went to China in 1848 to gather tea plants and seeds for the East India Company, and successfully introduced tea cultivation to the Himalayan region in 1851.

number of hospitals and dispensaries, and of the patients treated in them, during the last year for which returns have been received, was as follows:

| | Number of Institutions | Number of Patients |
|----------------------|---------------------------|-----------------------|
| Bengal | 43 | 153,161 |
| North-west Provinces | 47 | 245,171 |
| Madras | 35 | 184,069 |
| Bombay | 17 | 88,793 |
| | 142 | 671,194 |

Vaccination

Measures have also been taken for many years, and with much success, for the diffusion of vaccination, not only in the British territories, but also in the native states.

Libraries

Of late years, the establishment of public libraries in the provincial towns has been commenced. The assistance of Government is usually given in the form of a donation of books, and a regular supply of the publications issued by Government, which now include all the most interesting and important papers on the public records, relating to the condition and administration of the country.

Improvement of Native States

Independently of what has been done for the benefit of our own subjects, much has also been effected, through the influence of the British Government and its diplomatic officers, to improve the administration of native states. It is hardly possible to exaggerate the disorder and confusion in which most of these were plunged at the time when they first became connected with the British Government. Those among the Mahratta states which had any considerable military strength, made annual expeditions, called Mooluckgheery circuits, for the purpose of conquering or devastating the possessions of their weaker neighbours; and hordes of undisciplined adventurers, known by the name of Pindarries, ranged with fire and sword from one end to the other of the part of India which was under native rule, occasionally invading and ravaging even the British possessions. All this is at an end. The native states are as safe from one another, and from invaders and plunderers from without, as the British dominions. The princes and chiefs are

bound by treaties to refer to our arbitration all their differences;⁹⁵ and experience has given them the fullest reliance on our impartiality and justice. Boundary disputes between villages of different states, and complaints from the subjects of one against those of another for robberies or other injuries, are adjudicated either by a British officer, or by Courts of Vakeels, composed of representatives of the neighbouring chiefs, presided over by a British functionary. In some parts of India, and particularly of Guzerat, which are divided among a great number of petty chiefs, too weak or too little civilized to control effectually their turbulent subjects, Criminal Courts have been established, consisting of a British diplomatic officer and assessors selected from among the native chiefs or nobles, for the trial of offences against the general peace of the country. These courts are a powerful agent of civilization. They are gradually weaning a very backward portion of the natives of India from their barbarous usages. They have nearly suppressed all the classes of crimes which arose out of a generally disturbed state of society; and in dealing with offences which originate in real or supposed grievances, they make due allowance for provocation, and redress the wrongs even of those whom they are obliged to punish for seeking justice by unlawful means. In the more considerable native states, our influence is exerted on the side of good, in every mode permitted by positive engagement. Not only have the British representatives incessantly, and to a great degree successfully, incited native princes to prohibit and suppress the barbarous usages which we have ceased to tolerate in our own territories; but defects have been pointed out, and improvements suggested, in their revenue and judicial administrations. Financial disorder and general misgovernment have been the subject of grave remonstrance, followed up by such positive marks of displeasure as were consistent with the respective treaties. The minorities, which so often occur in native states, have been made use of to appoint capable ministers, to reform abuses, and restore the country in an improved condition to the young chiefs; who, having been in the mean time for the most part educated in European knowledge, and initiated into public business under the eye of a British officer, are often grateful for the care taken of their interest, and continue, after their accession to power, the improved systems commenced during their minority. The present Scindia and Holkar, and the Rao of Kutch, as well as many others, may be cited as instances.⁹⁶ One native ruler, the late Nuwab of Rampore, had actually been a deputy-collector in the service of the British Government.⁹⁷ Another, the Rao of Ulwur, on his accession, invited some of our

⁹⁵For examples, see Charles Umpherston Aitchison (1832-96), *A Collection of Treaties, Engagements, and Sunnuds, Relating to India and Neighbouring Countries*, 8 vols. (Calcutta: printed Savielle and Cranenburgh, 1862-65).

⁹⁶Respectively, Jiaji Rao Sindia (1835-86), Maharaja of Gwalior; Takoji Rao Holkar II (1832-86), Maharaja of Indore; and Maharaja Mizra Rao Dessuljee (1815-60), Rao of Kutch.

⁹⁷See p. 64 above.

native functionaries to conduct his administration, and reform it after the English model.⁹⁸ The Rajpoot states, formerly almost in a state of chronic anarchy, have been rendered peaceful and prosperous, by judicious mediation between the princes and their feudatories, and judicious guidance of both, through advice and influence.

Protection and Improvement of the Oppressed Races

There still remain to be commemorated a set of proceedings, among the most interesting and the most honourable to our Government, which have distinguished the present century—the measures for raising and civilizing the oppressed races.

There are numerous hill tribes in various parts of India, known under the names of Bheels, Coolies, Goands, Mhairs, Meenas, Mhangs, Ramoosees, and others, who are believed to have been the aboriginal population of the country, driven from the plains by the invasion of the Hindoos. These people had been treated like wild beasts by the native Governments, and, by a natural consequence, had become the scourge of the country. Whenever the Government was weak, they destroyed all security in the neighbouring plains by their depredations, and had universally acquired the character of irreclaimable robbers.

The first person who is known to have tried the effect of justice and conciliation on any of these tribes, was Mr. Cleveland, an officer high in the civil service of the Company, in the latter part of the last century.⁹⁹ The scene of his benevolent exertions was the Bhaugulpore Hills, in the north-east of Bengal; and the feelings which he left behind him among the rude people of the district were such, that they long continued to pay religious honours to his tomb. The example thus set has been largely followed in the present generation. One of the first signal instances of success was in the case of the Mhairs, who inhabit a hill district near Ajmere. Colonel Hall, now on the Company's retired list, originated the movement, and it was worthily carried on by Colonel Dixon, recently deceased.¹⁰⁰ In Western India, the honour of the initiative belongs to Mr. J.P. Willoughby, then a very young officer, who by similar means established peace and order among the Bheels of Rajpeepa, a wild district of Guzerat.¹⁰¹ The next instance was that of the Bheels of the Adjutee range, in Southern Candeish, through the agency chiefly of Colonel Ovans, and of the present Sir James Outram;¹⁰² and the measures which

⁹⁸Maharao Raja Banni Singh (d. 1857), Rao of Alwar.

⁹⁹Augustus Cleveland (1755-84), Collector of Bnagalpur.

¹⁰⁰Henry Hall (1789-1875) of the Bengal Army; for Dixon see n69 above.

¹⁰¹John Pollard Willoughby (1798-1866), who became Chief Secretary to the Bombay Government in 1835, was a Member of the Council in Bombay 1846-51, and became a Director of the Company in 1854.

¹⁰²For Charles Ovans, see p. 34 above. James Outram (1803-63) was agent for the North-eastern portion of the Bheel agency who, after defeating the Bheels, enrolled many of them in a light infantry corps under native officers.

proved successful with these Bheels, were successively extended to many similar tribes in different parts of Central India. Another example is that of the Khoonds in Orissa, among whom a policy of the same general character was carried into practice by Major Macpherson.¹⁰³ This was the tribe who, as mentioned in a previous part of the present paper, have been induced to abolish human sacrifices.

The mode in which these objects were accomplished was in all cases fundamentally the same. They were effected by the admirable power of individual character. Into fastnesses, through which bodies even of disciplined troops had vainly endeavoured to force their way, these officers penetrated, in some cases almost unattended. They trusted themselves to the people. By their courage and frankness they gained their confidence. They made them understand that they were not considered as wild animals to be hunted down; that nothing but their good was intended; and the object which had for years been vainly sought by force, was accomplished by explanation and persuasion. The robber tribes were induced to settle as peaceful cultivators. Lands were assigned to them, tools supplied, and money advanced, for cultivation. In Mhairwarra the Government also constructed important works of irrigation. The more daring spirits were formed into irregular corps, under British officers, and employed to preserve the peace of the districts of which they had once been the principal disturbers. In no single instance has this policy failed. The agricultural colonies composed of these people have all prospered, and the districts which they formerly devastated have become, and remained, among the most free from crime to be found in India. In the late disturbances, not one of the corps composed of these people is known to have mutinied. The Mhairwarra battalion has not only remained faithful, but is, in the present crisis, a valuable part of our local military strength; and there has been no disturbance whatever in that district. Among the Bheels of Candeish there has been a rising, which, by showing that the predatory spirit is not yet thoroughly extinct, enhances the merit of the system of measures by which, for nearly a quarter of a century, it has been kept dormant. But the corps formed from among these very people by Sir James Outram has done useful service to Government in the present emergency.

The last great example of the success of this policy was given by Colonel John Jacob in Sind, and only differs from the others because the tribes with whom he had to do were not oppressed aborigines, but the proud and warlike mountaineers of the Afghan and Beloochee frontier.¹⁰⁴ The success has been among the most striking yet experienced. For some time after the conquest of Sind, the frontier forays of these tribes kept the country in a perpetual state of disturbance. The

¹⁰³Samuel Charteris Macpherson (1806-60) became principal assistant to the Collector of Ganjam, Orissa, in 1842.

¹⁰⁴John Jacob (1812-58) was political superintendent and commandant of the frontier of Upper Sind from 1847 till his death.

attempts to retaliate on them in their hills had been failures, sometimes almost disasters, but had laid the foundation of that knowledge of our power, which enabled subsequent conciliatory measures to have their full effect. Colonel Jacob applied to these people the principles of Mhairwarra and Candeish. He settled on land those who were willing to cultivate, and organized from among the remainder a local military police. The effect is, that in the frontier districts, what was lately a desert waste, is now in great part a thriving agricultural country, yielding a rapidly increasing revenue. For some years there has been scarcely a crime of magnitude on the entire Sind frontier; and the corps which was raised partly from the former devastators of the country, is the celebrated Jacob's Horse.

The preceding review of the improvements in Indian administration, completed or commenced during the present generation, cannot more properly terminate than with this interesting piece of history. It is not pretended that the enumeration approaches to completeness. The instances given are merely some of the most important achievements of a Government, of which perpetual striving towards improvement is the vital principle. But it is believed that even so imperfect a summary is sufficient to justify the assertion, that few governments, even under far more favourable circumstances, have attempted so much for the good of their subjects, or carried so many of their attempts to a successful and beneficial issue. A Government of foreigners, over a people most difficult to be understood, and still more difficult to be improved,—a Government which has had all its knowledge to acquire, by a slow process of study and experience, and often by a succession of failures (generally, however, leading to ultimate success)—has a right to take pride to itself for having accomplished so much; and most certainly cannot be justly reproached, by any existing Government or people, with not having effected more.

APPENDIX A

BENGAL SURVEY

In answer to inquiries made by the Court of Directors in 1854 respecting the effects hitherto produced by the survey on litigation, crime, and the value of landed property, the Sudder Court say, in regard to "those classes of offences which would be likely to be influenced by the completion of the survey," that "it is satisfactory to observe" the "concurrent testimony" of the criminal judges "to the diminution which has taken place in this description of crime." This result is partly attributed to the successful operation of Act IV of 1840, which enables the magistrate to give an effectual remedy in cases of dispossession or ejectment;¹⁰⁵ but, they add, "the evidence of the survey papers must have greatly facilitated the

¹⁰⁵Act IV of 1840 (17 Feb.).

proceedings of the magistrate, whose proceedings under the Act in question are determined solely by possession.”

In regard to the effect on litigation, the judges say, “The ordinary result of the survey has been to elicit many local differences and disputes which were lying dormant, until the survey award presented an opportunity to gain an advantage over his adversary;” “but as, under Act XIII of 1848,¹⁰⁶ such suits must be instituted within three years from the final award of the revenue authorities, the litigation thus incidentally raised is afterwards almost entirely brought to an end.”

On the question as to the “result of the survey in giving further security to the titles of estates, and generally increasing the value of landed property, the opinions of the local officers are, on the whole, satisfactory. The testimony of all is strongly in favour of the additional security now given to title; and the judge of Shahabad observes, that on the whole the survey is felt to be a blessing to the community.”

The Board of Revenue, Lower Provinces, state that “it is quite clear that the value of the survey records as a basis for butwarrah and settlement proceedings is generally acknowledged. In some districts, butwarrah is applied for without any new measurement, solely on the data furnished by the survey. Their utility in the decision of boundary disputes, also, is universally admitted.” In regard to the effect of the survey on the repression of affrays, the Board quote the opinion of Mr. Elliott, Commissioner of Burdwan,¹⁰⁷ that, “by removing the cause of affrays, the survey cannot fail to produce an effect greater even than the most stringent legislation.”

In the province of Cuttack (not permanently settled) the survey and settlement operations were combined, and there “the improvement is very perceptible. In Cuttack the value of landed property is said to have increased twenty-five per cent, and fifty per cent in Balasore; but Pooree,* owing to frequent droughts and inundations, is an exception.” “The survey,” the Commissioner (of Cuttack) remarks, “is worth much more to Government and the people than it has cost.”¹⁰⁸

APPENDIX B

SURVEY AND ASSESSMENT OF THE NORTH-WESTERN PROVINCES

The objects of the survey were, first, to fix on each mehal or estate an assessment “calculated so as to leave a fair surplus profit;” and “for the punctual payment of that sum, the land is held to be perpetually hypothecated to the Government;”

¹⁰⁶Act XIII of 1848 (10 June).

¹⁰⁷William Henry Elliott (1811-70), Officiating Commissioner of Revenue and Circuit for Burdwan Division 1854-56, and Commissioner 1856-59.

*The three collectorates of the province of Cuttack proper.

¹⁰⁸The passage has not been located, and so not dated: the Commissioner January-May 1854 was Binney James Colvin (b. 1809), who was succeeded by Edward Alexander Samuells (1813-60).

secondly, to determine who are the "person or persons entitled to receive this surplus profit. The right thus determined is declared to be heritable and transferable, and the persons entitled to it are considered the proprietors of the land, from whom the engagements for the annual payment of the sum assessed by Government on the mehal are taken."¹⁰⁹ The proprietors, when there are more than one, being jointly and severally responsible for the sum assessed on each mehal, it also became necessary to determine the rule according to which they should share the profits, or make good the losses on the estate. When the proprietors were numerous, as was generally the case, engagements were taken only from a few of the body (lumberdars) who, for themselves and their co-proprietors, undertook to manage the mehal, and pay the sum assessed on it.

The first step in the process was to adjust the boundaries of each mouzah, or village, and to prepare a map, showing each field comprised in the mouzah. This being completed, the settlement officer proceeded to determine the assessment to be fixed on the land, by estimating, with as near an approach to accuracy as the means at his disposal would permit, what might be expected to be the net produce* to the proprietor during the period of settlement; and of this amount about two-thirds was fixed as the demand of Government. The village was then offered on these terms to the proprietors, and if they considered them too high, and declined to engage, the Government either leased the estate to a farmer, or collected the rents direct from the cultivators; the excluded proprietors being entitled to a percentage (called malikana) at not less than five per cent on the revenue, and also having the right, at the expiration of twelve years, of claiming to be readmitted to the management.

The fiscal operation of fixing the amount of revenue to be paid by the village being completed, the next process was to ascertain and record the rights possessed by all parties, whether called proprietors or not. When discordant claims were put forward, the question at issue was determined judicially on the spot. Provision is also made for maintaining the "Record of Rights" in a correct condition, by causing registers of all changes in the village to be kept by the putwarree, or village accountant, copies of which are annually forwarded to the collector's office.¹¹⁰

APPENDIX C

SURVEY AND ASSESSMENT OF THE BOMBAY TERRITORY

The first step in the process is to determine the boundaries of the village. The area is then measured and mapped off into survey-fields. If the land is unoccupied, no

¹⁰⁹"Directions for Revenue Officers in the North-Western Provinces of the Bengal Presidency, Regarding the Settlement and Collection of the Land Revenue, etc." (1 Nov., 1849), *PP*, 1852-53, LXXV, 20-1.

*By net produce is meant the surplus which the estate may yield after deducting the expenses of cultivation, including the profits of stock and wages of labour. [*Ibid.*, p. 35.]

¹¹⁰*Ibid.*, p. 39.

division of a field is afterwards permitted. When a survey-field actually occupied is owned by several proprietors or sharers, no joint responsibility is admitted, but the sharers of each are separately shown in the map, and the separate proprietorship continues until one of the sharers dies without heirs, or otherwise vacates his share; on which event the vacated share must be taken up by the remaining sharers, or, on their refusal, the whole field must be relinquished. The object of these rules is to consolidate the small holdings, and set limits to the minute subdivision of landed property naturally arising from the Hindoo law of inheritance. But it is believed that, in practice, no difficulty has in such cases been found in inducing the remaining sharers to undertake the responsibility.

The fields of the village being thus measured and mapped, the next process is that of classification, for the purpose of determining the relative values of the fields into which the land is divided. After a minute examination of the physical characters of the soil, its depth, composition, etc., the following considerations are taken into account as regards the fields of the same village; viz. "their natural productive capabilities; their position with respect to the village, as affording facilities or otherwise for agricultural operations; and, in the case of garden or rice lands, the supply of water for irrigation."¹¹¹

The measurement of the fields having been completed, and their classification determined, the amount of the assessment is next to be fixed. This operation is not performed by inquiring into the actual produce of the fields, but rather by an examination into the previous fiscal history of such groups of villages as are distinguished by similar physical characteristics. The statements of former collections, remissions, and balances, are collated, and compared with the existing rates of assessment. The "climate, position with respect to markets, agricultural skill, and the actual condition of the cultivators,"¹¹² are taken into account; and from a consideration of these combined circumstances, rates are determined for each class of land; the object being to keep those rates within the limit of the natural rent.

The rates, being thus fixed, have only to be applied to the surveyed fields. Thus a field of eight acres, in a class rated at twelve annas an acre, is assessed at six rupees. The assessment thus fixed is declared to be not liable to increase for "thirty years, during which period the full benefit of every improvement, such as the conversion of dry into irrigated land by the digging of wells and tanks, the planting of fruit-trees, etc., will be secured to the incumbent of the land, and no extra assessment levied on that account."¹¹³

The registered occupiers of fields are held to be the proprietors, so long as they pay the fixed assessment. They have full liberty annually to resign any portion of

¹¹¹"Official Correspondence," *PP*, 1852-53, LXX, 321.

¹¹²*Ibid.*, p. 326.

¹¹³*Ibid.*, p. 331.

their holdings, or to increase them by the occupation of waste fields, on giving due notice, and are thus enabled to extend or contract their cultivation according to their means of tillage. In either case, they are responsible only for the assessment of the fields which they actually hold, those relinquished by them being at the disposal of Government, to assign to any one willing to engage for them.

The annual settlement, as it is called, which still takes place in the surveyed districts of the Bombay Presidency, is now limited to an inspection of the fields by the village officers, to ascertain how many are cultivated and how many not. All those that are engaged for, whether cultivated or not, are liable to the payment of the assessment, and those not engaged for, if cultivated, are also liable. The plan of giving remissions for failure of crops, for lands taken but unsown, etc., is abolished; and it is now expressly made known that remissions are not claimable in individual cases, and will never be allowed unless under circumstances of calamity affecting whole districts.

APPENDIX D

EXEMPTION OF LANDS IMPROVED BY THE RYOTS FROM EXTRA ASSESSMENT

The general rule in force for many years in the Madras Presidency, was to make, in each case of a ryot improving his lands by digging a well or otherwise, an arrangement under which no increase of assessment was imposed until the expiration of a term sufficiently long, not only amply to compensate, but liberally to reward him for the labour and expenditure he might have applied.

After considerable correspondence, however, the Court of Directors determined (2nd June 1852) "to allow to the ryots the full benefit of their own improvements; the lands so improved being subjected to no additional assessment on that account, so long as the general rates of the district remain unaltered."¹¹⁴

The Circular Order of the Madras Government, publishing this rule, and announcing that in any general revision of the rates, "any modification in the assessment of lands so improved will be irrespective of the increased value conferred upon them by their holders,"¹¹⁵ was approved by the Court on the 20th April 1854.

A rule proposed by the Board of Revenue, requiring ryots proposing to sink wells, to give notice to the collector, was disallowed, as tending "to cause delay and obstruction, and to give an opening for exaction to the native servants."¹¹⁶

¹¹⁴"Circular Order of 25 Nov., 1852," p. 113 (cf. pp. 110 and 114-15). Approved in Court of Directors' Revenue Despatch to Madras, No. 7 of 2 June, 1852.

¹¹⁵*Ibid.*, p. 117.

¹¹⁶*Ibid.*, p. 118.

APPENDIX E

SALT REVENUE

The system actually in operation throughout India is as follows, viz.:

Lower Provinces of Bengal. Rate of duty 2 1/2 rupees per maund of 82 2/7 lbs. avoirdupois; Government salt sold to the people at cost price added to the duty; importation unrestricted, and facilities given to persons willing to manufacture salt under excise regulations.

North-western Provinces. Manufacture (from saliferous earths) prohibited. Duty on passing the frontier line, Rs. 2 per maund, and 8 annas additional on crossing the Allahabad special line of chokeys.

Punjab. Salt-mines worked by the Government, and the salt sold at the mines at Rs. 2 per maund.

Fort St. George. The manufacture of salt a Government monopoly, the price charged to purchasers being one rupee per maund. Importation permitted, on payment of a duty of 14 annas (seven-eighths of a rupee) per maund, supposed to be equivalent to the profit obtained on the monopoly of salt.

Bombay. No manufacture on the part of Government. An excise duty of 12 annas per maund levied on home-made salt, and a customs duty of equal amount on imported salt.

**REPORT TO THE GENERAL COURT OF PROPRIETORS,
DRAWING ATTENTION TO THE TWO BILLS
NOW BEFORE PARLIAMENT
RELATING TO THE GOVERNMENT OF INDIA**

1858

EDITORS' NOTE

London: Printed for the Court of Directors of the East India Company by Cox and Wyman, 1858. Published also under the heading, "Return to an Order of the House of Lords, dated 29th April 1858," in *Sessional Papers of the House of Lords*, 1857-58, XI, 449-54. The text is preceded by this explanation:

At a Court of Directors of the East-India Company, held on Tuesday, the 6th April, 1858:

The Chairman, drawing the Court's attention to the two Bills now before Parliament relating to the Government of India, submitted the Draft of a proposed Report to the General Court of Proprietors on the subject; Whereupon,

It was agreed, that the same be referred to the consideration of a Committee of the whole Court.

The Court being resumed, and a Report from the Committee being read:

Resolved,—That this Court approve the said Draft of a Report, as altered by the Committee; and that the same be laid before the General Court of Proprietors to be held to-morrow.

At a Special General Court of the East-India Company, held at the East-India House, on the 7th April, it was ordered, That the said Report be printed.

The two bills referred to are "A Bill for the Better Government of India," 21 Victoria (12 Feb., 1858), *PP*, 1857-58, II, 267-86, and "A Bill to Transfer the Government of India from the East India Company to Her Majesty the Queen," 21 Victoria (26 Mar., 1858), *PP*, 1857-58, II, 287-312. Unsigned. Not republished by Mill. Identified in his bibliography as "A report to the General Court of the E.I. Company from the Court of Directors upon the Two Bills Now before Parliament, relating to the Government of India; printed by the E.I. Company and also laid before the House of Lords and forming No. 87 of the Lords Papers of the Session of 1858" (MacMinn, 91).

Report to the General Court of Proprietors, Drawing Attention to the Two Bills Now before Parliament Relating to the Government of India

IT IS THE DUTY of your Directors to lay before the Proprietors the two Bills which have been introduced into Parliament by the late and by the present Ministry, for divesting the East-India Company of all participation in the government of India, and framing a new scheme of administrative agency.¹

On former occasions when the Ministers of the Crown have submitted measures to Parliament for altering, in any manner, the constitution of the Indian Government, the substance of the measures has been officially communicated to the Court of Directors, and an opportunity allowed to them of offering such remarks as their knowledge and experience in Indian affairs might suggest. The correspondence being afterwards laid before the Court of Proprietors, formed the most appropriate report which the Directors could make to their constituents on the measures under consideration by the Legislature. In the present instance, this opportunity not having been afforded to them, it appears desirable that they should adopt the present mode of laying before the proprietary body the observations which it is entitled to expect from its executive organ, on the Bills now before Parliament, and on the present posture of the Company's affairs.

The Directors cannot but advert with feelings of satisfaction to the altered tone which public discussion has assumed in regard to the character of the East-India Company, and the merits of the administration in which the Company has borne so important a part. The intention of proposing the abolition of the Company's government was announced in the midst of, and it may be surmised, in deference

¹The first bill was introduced by Henry John Temple, Lord Palmerston, in his speech of 12 February, 1858, and debated on that day, and on the 15th and 18th of February (*PD*, 3rd ser., Vol. 148, cols. 1276-1359, 1372-1457, and 1607-1718). The second, after the change of government on 21 February, was introduced by Benjamin Disraeli (1804-81) on behalf of the Ministry led by Edward George Geoffrey Smith Stanley (1799-1869), 14th Earl of Derby, on 26 March, 1858, and debated on that day (*ibid.*, Vol. 149, cols. 818-46).

to, a clamour, which represented the government of India by the Company as characterized by nearly every fault of which a civilized Government can be accused, and the Company as the main cause of the recent disasters.² But in the parliamentary discussions which have lately taken place, there has been an almost universal acknowledgment that the rule of the Company has been honourable to themselves and beneficial to India; while no political party, and few individuals of any consideration, have alleged anything seriously disparaging to the general character of the Company's administration. So far, therefore, the stand made by the Company against the calumnies with which they have been assailed, may be considered to have been successful.

But the admission generally made, and made explicitly by the proposers of both the Bills, that the existing system works well, has not had the effect of inducing doubt of the wisdom of hastily abolishing it. Neither does it seem to have been remembered, that if the system has worked well, there must be some causes for its having done so, and that it would be worth while to consider what these are, in order that they might be retained in any new system. If the constitution which has made the Indian Government what it is, must be abolished, because it is thought defective in theory, what is substituted should at least be theoretically unobjectionable. But the constitution of the East-India Company, however anomalous, is far more in accordance with the acknowledged principles of good government than either of the proposed Bills.

The nature of the case is, indeed, itself so anomalous, that something anomalous was to be expected in the means by which it could be successfully dealt with.

All English institutions and modes of political action are adapted to the case of a nation governing itself. In India, the case to be provided for is that of the government of one nation by another, separated from it by half the globe; unlike it in everything which characterizes a people; as a whole, totally unacquainted with it; and without time or means for acquiring knowledge of it or its affairs.

History presents only two instances in which these or similar difficulties have been in any considerable degree surmounted. One is the Roman Empire; the other is the government of India by the East-India Company.

The means which the Bills provide for overcoming these difficulties consist of the unchecked power of a Minister. There is no difference of moment in this respect between the two Bills. The Minister, it is true, is to have a Council. But the most despotic rulers have Councils. The difference between the Council of a despot and a Council which prevents the ruler from being a despot is, that the one is dependent on him, the other independent; that the one has some power of its own,

²See "Correspondence between the First Lord of the Treasury and the Directors of the East India Company Respecting Legislative Measures to be Proposed for the Future Government of Her Majesty's Dominions in India," *Sessional Papers of the House of Lords*, 1857-58, XI, 445-8.

the other has not. By the first Bill, the whole Council is nominated by the Minister; by the second, one-half of it is nominated by him.³ The functions to be intrusted to it are left, in both, with some slight exceptions, to the Minister's own discretion.⁴

The Minister is indeed subject to the control of Parliament and of the British nation. But though Parliament and the nation exercise a salutary control over their own affairs, it would be contrary to all experience to suppose that they will exercise it over the affairs of a hundred millions of Hindoos and Mahomedans. Habitually, they will doubtless be hereafter, as they have been heretofore, indifferent and inattentive to Indian affairs, and will leave them entirely to the Minister. The consequence will be, that in the exceptional cases in which they do interfere, the interference will not be grounded on knowledge of the subject, and will probably be for the most part confined to cases where an Indian question is taken up from party motives, as the means of injuring a Minister; or when some Indian malcontent, generally with objects opposed to good government, succeeds in interesting the sympathies of the public in his favour. For it is not the people of India, but rich individuals and societies representing class interests, who have the means of engaging the ear of the public through the press, and through agents in Parliament. And it is important to remark, that by the provisions of either of the Bills the House of Commons will be rendered even less competent, in point of knowledge of Indian affairs, than at present, since by both Bills all the members of the Council of India will be excluded from it.

The government of dependencies by a Minister and his subordinates, under the sole control of Parliament, is not a new experiment in England. That form of colonial government lost the United States, and had nearly lost all the colonies of any considerable population and importance. The colonial administration of this country has only ceased to be a subject of general condemnation since the principle has been adopted of leaving all the important colonies to manage their own affairs,—a course which cannot be followed with the people of India. If the control of Parliament has not prevented the habitual mismanagement of countries inhabited by Englishmen like ourselves, who had every facility for representing and urging their grievances, it is not likely to be any effectual protection to Musselmans and Hindoos.

All governments require constitutional checks; but the constitutional checks applicable to a case of this peculiar kind, must be found within the governing body itself.

Though England as a whole, while desiring nothing but to govern India well, is necessarily ignorant of India, and feels, under ordinary circumstances, no particular interest in its concerns, there are in England a certain number of persons who possess knowledge of India, and feel an interest in its affairs. It seems,

³In Clause 10 in both Bills.

⁴In Clause 18 of the first, and Clauses 25 and 26 of the second.

therefore, very desirable, for the sake of India, that England should govern it through, and by means of, these persons. This would be the case if the organ of government principally consisted of persons who have passed a considerable portion of their lives in India, or who feel that habitual interest in its affairs which is naturally acquired by having aided in administering them; and if this body, or a majority of it, were periodically elected by a constituency composed of persons in England who have served the Government for a certain length of time in India, or whose interests are connected with that country by some permanent tie. It would be an additional advantage if this constituency had the power of requiring information, and compelling a public discussion of Indian questions. These are conditions which, to a considerable extent, the existing constitution of the East-India Company fulfils.

The other great constitutional security for the good government of India lies in the forms of business. This is a point to which sufficient importance is not generally attached. The forms of business are the real constitution of India.

From the necessity of the case, recognized in both the proposed measures, the administration must be shared, in some proportion, between a Minister and a Council. The Council may consist of persons possessing knowledge of India. The Minister, except in very rare cases, can possess little or none. He is placed in office by the action of political party, which is governed by considerations totally unconnected with India, and, in the common course of politics, he is removed from office by the time he has been able to learn his duty. Even in the unusual case, of which present circumstances are an example, when the Minister has made himself acquainted with India through the discharge of high functions in India itself,⁵ his knowledge is but the knowledge of one man; and one man's knowledge of a subject like India, until corrected and completed by that of other men, is, it may safely be affirmed, wholly insufficient, and if implicitly trusted, even dangerous. The good government, therefore, of India, by a Minister and a Council, depends upon the amount of influence possessed by the Council; and their influence depends upon the forms of business.

However experienced may be the Council, and however inexperienced the Minister, he will have the deciding voice. The power will rest with one who may know less of the subject than any member of the Council, and is sure to know less than the Council collectively, if they are selected with ordinary judgment. The Council will have no substantive power, but only moral influence. It is therefore all important that this influence should be upheld. Unless the forms of business are such as to insure that the Council shall exercise its judgment on all questions; that all matters requiring decision shall be considered by them, and their views recorded in the initiatory stage, before the Minister has committed himself to an opinion, they will possess no more weight or influence than the same number of

⁵Edward Law, Earl of Ellenborough.

clerks in his office (whom also he can consult if he pleases), and the power of the Minister will be practically uncontrolled.

In both the Bills these considerations are entirely disregarded. The first Bill does not establish any forms of business, but leaves them to be determined by the Minister and his Council; in other words, by the Minister.⁶ Even, therefore, if the Minister first appointed should be willing to establish forms which would be any restraint upon himself, a subsequent Minister would have it in his power to alter the forms in any manner he pleased.

The second Bill, unlike the first, does establish forms of business; but such alone as would effectually prevent the Council from being a reality, and render it a useless pageant.

To make the Council a merely consultative body, without initiative, before whom subjects are only brought after the Minister has made up his mind, is already a fatal inroad upon its usefulness. But by the second Bill the Council are not even a consultative body. The Minister is under no obligation to consult them. They are not empowered to hold any regular meetings. They are to meet only when the Minister convenes them, or on a special requisition by six members. He may send orders to India without their knowledge when the case is urgent, of which urgency he is the sole judge. When it is not urgent, his orders must be placed in the council-room for the perusal of the members for seven days, during which they are not required, but permitted, to give their opinion, not collectively, but individually. Their only power, therefore, is that of recording dissent from a resolution not only taken, but embodied in a despatch. And as if this was not enough, provision is made that an office always invidious, shall be incapable of being fulfilled in any but the most invidious manner. The members of Council must come forward individually in declared opposition to the Minister, by volunteering a protest against his announced intentions, or signing a requisition for a meeting of Council to oppose them.⁷ Such a Council is fitted to serve as a shield for the Minister's responsibility when it may suit him to seek, and them to accord, their adhesion, rather than as a restraint on his power to administer India according to his individual pleasure.

The Directors are bound to admit, that the first of the Bills contains several provisions indicative of a wish to assure to the Council a certain, though small, amount of influence. The administration is to be carried on in the name of the President in Council, and not, as by the second Bill, in that of the Secretary of State alone.⁸ The Council, as well as the President, has a voice in the appointment of the home establishment; while in the second Bill all promotions and all appointments to the principal offices under the Council, rest with the Secretary of State,

⁶See Clause 14.

⁷The points mentioned in this paragraph are dealt with in Clauses 28, 31, and 33.

⁸Clause 5 of the first; Clause 3 of the second.

exclusively, a provision which divests the Council of all control or authority over their own establishment.⁹ Again, by section XII of the first Bill, no grant involving increase of expenditure, and no appointment to office or admission to service, can be made without the concurrence of half the Council. This, as far as it goes, is a real power, but its value is much diminished by the consideration that those by whom it is to be exercised, are the nominees of the Minister, dependent on him for their continuance in office after a few years.

In some other points the provisions of the second Bill seem to have the advantage. Its Council is more numerous;¹⁰ to which, however, little importance can be attached, if the Council has no substantial power. It also recognizes that the whole of the Council ought not to be nominated by the Minister, and that some part of it should be elected by a constituency specially qualified by a knowledge of India.¹¹ But even in these, the best points of the Bill, it is, in the opinion of the Directors, very far from unexceptionable. The nomination of even half the Council by the Minister, takes away all security for an independent majority. It may, indeed, be doubted whether there is any sufficient reason for the Minister's nominating any portion, except the supposed reluctance of some eligible persons to encounter a canvass. The proportion of one-third, whom the Minister now nominates to the Court of Directors, seems the largest which, consistently with full security for independence, can be so appointed.

The provision that each of the members nominated by the Crown shall be selected as the representative of some particular branch of the service in India, is still more objectionable. Not only would it preclude the nomination of the most distinguished man, if the seat in Council appropriated to the department in which he had served were not at the time vacant, but it would introduce a principle which cannot be too strongly deprecated,—that of class legislation. The Council should comprise the greatest attainable variety of knowledge and experience, but its members should not consider themselves as severally the representatives of a certain number of class interests.

The clause which continues to the Proprietors the power of electing some portion of the Council is, so far, deserving of support; and the principle of enlarging the constituency by the addition of persons of a certain length of Indian service and residence, is, in itself, unexceptionable;¹² but unless guarded by provisions, such as have never yet been introduced into any electoral system, so large and scattered a constituency as that proposed would greatly add to the inconvenience of canvass, especially as it is not certain that the new electoral body would adopt, from the old, the salutary custom of re-electing, as the general

⁹Clause 7 of the first; Clause 3 of the second.

¹⁰By Clause 9 (18 as opposed to 8 members).

¹¹By Clause 11; the first Bill provided in Clause 10 that all members be appointed by the Crown.

¹²By Clause 11 of the second Bill.

practice, whoever has been once chosen, and has not, by misconduct or incapacity, deserved to forfeit their confidence. The duties of a Member of Council would be entirely incompatible with a continually-recurring canvass of the constituency.

Respecting the proposition for giving the choice of five Members of Council to the Parliamentary constituencies of five great towns,¹³ the Court of Directors can only express a feeling of amazement. It is not the mere fact of election by a multitude that constitutes the benefits of the popular element in government. To produce those benefits, the affairs of which the people are enabled to control the management must be their own affairs. Election by multitudinous bodies, the majority of them of a very low average of education, is not an advantage of popular government, but, on the contrary, one of its acknowledged drawbacks. To assign to such a constituency the control, not of their own affairs, but of the affairs of other people on the other side of the globe, is to incur the disadvantages of popular institutions without any of the benefits. The Court of Directors willingly admit the desirableness, if not necessity, of some provision for including an English element in the Council of India; but a more objectionable mode than the one proposed of attaining the object, could scarcely, in their opinion, be devised.

Besides the provisions which relate to the organ of Government in England, the Bills contain provisions relating to India itself which are open to the strongest objection.

The appointments to the Councils at Calcutta and at the subordinate Presidencies, which are now made by the Court of Directors, with the approbation of the Crown, are transferred by both Bills to the Governor-General, and to the Governors of Madras and Bombay.¹⁴ The Court of Directors are convinced that this change would greatly impair the chances of good government in India. One of the causes which have most contributed to the many excellences of Indian administration, is that the Governor-General and Governors have always been associated with Councillors selected by the authorities at home from among the most experienced and able members of the Indian service, and who, not owing their appointments to the head of the Government, have generally brought to the consideration of Indian affairs an independent judgment. In consequence of this, the measures of a Government, necessarily absolute, have had the advantage, seldom possessed in absolute Governments, of being always preceded by a free and conscientious discussion; while, as the head of the Government has the power, on recording his reasons, to act contrary to the advice of his Council, no public inconvenience can ever arise from any conflict of opinion. These important officers, who, by their participation in the Government, form so salutary a restraint on the precipitancy of an inexperienced, or the wilfulness of a despotically-

¹³By Clause 12 of the second Bill.

¹⁴By Clause 4 of the first; Clause 36 of the second Bill.

tempered, Governor-General or Governor, are henceforth to be appointed by the great functionary whom they are intended to check. And this restraint is removed, when the necessity for an independent Council will be greater than ever, since the power of appointing the Governor-General, and of recalling him, is taken away from the Company, and from the body which is to be their substitute.¹⁵ It may be added, that the authorities at home have had the opportunity of being acquainted with the conduct and services of candidates for Council from the commencement of their career. The Governor-General or Governor would often have to nominate a councillor soon after their arrival in India, when necessarily ignorant of the character and merits of candidates, and would be entirely dependent on the recommendation of irresponsible advisers.

Another most objectionable provision demands notice, which is to be found only in the second Bill. A commission, appointed in England, is to proceed to India, for the purpose of inquiring and reporting on the principles and details of Indian finance, including the whole revenue system, and, what is inseparably involved in it, the proprietary rights and social position of all the great classes of the community.¹⁶ The Court of Directors cannot believe that such a project will be persisted in. It would be a step towards the disorganization of the fabric of government in India. A commission from England, independent of the local government of the country, deriving its authority directly from the higher power to which the local government is subordinate, and instructed to carry back to the higher power information on Indian affairs which the local government is not deemed sufficiently trustworthy to afford, would give a most serious shock to the influence of the local authorities, and would tend to impress all natives with the belief that the opinions and decisions of the local government are of small moment, and that the thing of real importance is the success with which they can contrive that their claims and objects shall be advocated in England. Up to the present time it has been the practice of the Home Government to uphold in every way the authority of the governments on the spot; even when reversing their acts, to do so through the governments themselves, and to employ no agency except in subordination to them.

From this review of the chief provisions of the Bills, which embody the attempts of two great divisions of English statesmen to frame an organ of government for India, it will probably appear to the Proprietors, that neither of them is grounded on any sufficient consideration of past experience, or of the principles applicable to the subject; that the passing of either would be a calamity to India; and that the attempt to legislate while the minds of leading men are in so unprepared a state, is altogether premature.

The opinion of your Directors is, that by all constitutional means the passing of

¹⁵By Clause 4 of the first; Clause 36 of the second.

¹⁶By Clause 55 of the second.

either Bill should be opposed; but that if one or the other should be determined on for the purpose of transferring the administration, in name, from the East-India Company to the Crown, every exertion should be used in its passage through committee to divest it of the mischievous features by which both Bills are now deformed, and to maintain, as at present, a really independent Council, having the initiative of all business, discharging all the duties, and possessing all the essential powers of the Court of Directors. And it is the Court's conviction, that measures might be so framed as to obviate whatever may be well founded in the complaints made against the present system, retaining the initiative of the Council, and that independence of action on their part which should be regarded as paramount and indispensable.

A CONSTITUTIONAL VIEW OF THE INDIA QUESTION

1858

EDITORS' NOTE

London: Penny, 1858. No running titles. Unsigned. Not republished. There are no emendations in the Somerville College copy. Identified in Mill's bibliography as "A Constitutional View of the India Question," the first item under the heading: "The following short pamphlets on the India Bills and Resolutions of the Session of 1858 viz:" (MacMinn, 91).

A Constitutional View of the India Question

THE PROPOSAL to extinguish the East-India Company,¹ and to place the whole administration of India in the hands of a Minister and a Council, without any substantial power, is an ominous advance in that centralisation of all the functions of Government in the hands of the Cabinet, so justly deprecated by the soundest thinkers, whether of Liberal or Conservative opinions.

Next to a national representation, the most important of all political principles is, that the only affairs directly administered by the Imperial Government should be the general affairs of the nation; and that all local affairs, whether they be those of any particular part of the United Kingdom or of any foreign dependency, should, if possible, be administered by some intermediate body, constituted expressly for the purpose.

The general concerns of the empire are sufficient to occupy the whole time and thoughts of her Majesty's Ministers. They cannot possibly make themselves properly acquainted with the affairs of every separate locality or dependency of the empire. They are not, and cannot be, appointed to office on account of their knowledge of the affairs of localities or dependencies.

Besides, it is admitted that the only security for the good conduct of any portion of the national affairs which is entrusted to Ministers, lies in the control of Parliament. And with regard to the general affairs of the empire, this control is efficacious. But Parliament, no more than Ministers, has time either to study or to deliberate on local affairs; and it is not in the nature of things that more than a few members of Parliament should be well acquainted with, or feel any strong interest in, the affairs of any particular locality. Local affairs, therefore, unless when private interests were concerned, would generally be left entirely to Ministers; and not only would they be almost sure to be mismanaged, but the power and patronage which their management would confer, and the habit engendered of looking entirely to the Ministers of the Crown as the source of all authority, would be dangerous to the liberty and safety of the nation.

These are not new doctrines, but the acknowledged principles of the

¹By the legislation then before Parliament, "A Bill to Transfer the Government of India from the East India Company to Her Majesty the Queen," 21 Victoria (26 Mar., 1858), *PP*, 1857-58, II, 287-312.

Constitution. All sound thinkers in other countries are sensible of their value, and declare with one accord that the power which the central Governments of the Continent exercise in local affairs, and the dependence upon the Government of every intermediate body which discharges important administrative functions, are the great cause why the principal nations of the Continent, among all their revolutions, have never yet succeeded in acquiring liberty.²

In England this evil has hitherto been avoided. The English people have always managed their local affairs for themselves, without the interference of the Government. Almost all the British Colonies have, from their first foundation or acquisition, enjoyed in a great degree the same advantage. They have had local Parliaments for their domestic administration; and though a Minister in London long continued to control and thwart the action of those local bodies, each colony as it advanced in prosperity showed such a determination to emancipate itself from the interference of the Imperial Government in affairs not of Imperial interest, that they at last succeeded in attaining their object.

The greatest dependency of the Crown, India, is, by general admission, not capable of administering its own affairs by a representative system. This, however, does not diminish, but increases, the mischief and danger of its administration by the unchecked power of a Cabinet Minister. There is far more danger in India than in any Colony, of the ignorant or corrupt misuse of Ministerial power; because India is less understood than any Colony, because its people are less capable of making their voice heard, and because it is more difficult for Parliament to interfere in its administration with adequate knowledge, than in the affairs of any Colony.

India has hitherto been administered, under the general control of Parliament, by a body, who holding aloof from the party conflicts of English politics, devoted their whole time and energies to Indian affairs. The great Corporation, which gained India for this country, has hitherto been considered the best qualified to conduct its administration, under the authority of the Crown, subject, when necessary, to the veto of the Board of Control.

It is now proposed to abolish this intermediate body, and to impose upon India the exclusive government of a Cabinet Minister, which every important Colony has found it impossible to bear. The yoke of the old Colonial Office, which the Colonies, one after another, have rejected and thrown off, is to be laid upon India.

The reason assigned is, the supposed evil of double government and divided responsibility.

Without discussing what is the value of these objections in the case of India, it is sufficient to observe that they are applicable to every British institution, under

²Authorities on this question cited by Mill elsewhere are Joseph Fievée (1767-1839), *Correspondance politique et administrative*, 3 vols. (Paris: Le Normant, 1815-19), Vol. I, Pt. 2, and Vol. III, Pt. 9; and Alexis Clérel de Tocqueville (1805-59), *De la démocratie en Amérique*, 2 vols. (Paris: Gosselin, 1835), Vol. I, Chaps. v and xvi.

which any of the affairs of the public are administered by an authority independent of the Cabinet.

Already the management of the Light-houses of Great Britain by the Corporation of the Trinity-House, a management which is the admiration of Europe, is assailed as a "double government," by (among others) a member of the late Administration.³ The Trinity-House is apparently marked out as the next victim.

The management of the poor, and the control of the poor-rates, are shared between a Government Board and the local Boards of the various Poor Law Unions.⁴ Double government; divided responsibility. Abolish the Boards of Guardians. Concentrate all power in the Central Board. Let the Crown appoint all overseers; and let them, under the Board's orders, fix the parochial rates, and exclusively control their expenditure.

The sanitary administration of towns is shared between a Government Board, and the Corporations and other local authorities.⁵ Double government; divided responsibility. Give all the power to the Board of Health; allow the Board to construct works and establish sanitary regulations at its pleasure, and to tax the inhabitants of the towns for defraying the expense.

The popular education of the country is partly administered by the Committee of Council for Education, and partly by private trustees or voluntary associations.⁶ The schools of the country are mostly supported by the one authority, and inspected by the other. Double government; divided responsibility. Let no trustees or voluntary associations have anything to do with schools. Place the whole responsibility on the Committee of Council: let them maintain schools for the whole country, levy school-rates to pay their expenses, appoint the teachers, and fix the course of instruction.

There was lately a Railway Board; and its powers still exist, though transferred to the Board of Trade.⁷ The general Government interferes largely in the affairs of railway companies. Parliament sanctions the lines, and fixes a maximum of rates. A Government officer inquires into all accidents, and no line can be opened until declared safe by a Government engineer. Double government; divided responsibility. Let the Government take possession of all the railways; or let it appoint the

³Robert Lowe (1811-92), then M.P. for Kidderminster, who had been Paymaster of the Forces and Vice-President of the Board of Trade in Lord Palmerston's government, *Speech on Lighthouses* (15 Apr., 1858), *PD*, 3rd ser., Vol. 149, col. 1130.

⁴By Sects. 2 and 28 of 4 & 5 William IV, c. 76 (1834).

⁵By Sects. 4 and 12 of 11 & 12 Victoria, c. 63 (1848).

⁶The Council was established in 1839 as a Committee of the Privy Council, with government grants to oversee and promote public education; it allowed private agencies to continue to support and administer schools.

⁷9 & 10 Victoria, c. 105 (1846), which established the Railway Board, was superseded by 14 & 15 Victoria, c. 64 (1851), which transferred its powers to the Board of Trade.

chairman of every railway company, and let him govern, consulting or not the directors and proprietors, as he pleases.

The highways, the gaols, the county rates, and the administration of justice at sessions, are conducted by intermediate bodies—the Justices of Peace. These are already nominated by the Minister (on the recommendation of the Lord Lieutenant), and removable by him; but as it is not usual to remove them except for proved misconduct, they are practically independent, and in the exercise of their functions they are not obliged to be the instruments of a Minister. This, in the opinion of the enemies of double government, must be a great evil. Why should not magistrates be appointed for six years only? Why should not the chairman of sessions be appointed by the Crown, and all county business be transacted by him and a few clerks; the other magistrates being only summoned when he thinks fit, and, when summoned, their opinion being only attended to if he chooses?

The general administration of justice is shared between a judge appointed by the Crown, and a jury of citizens. Double government; divided responsibility. Let the judge alone decide: if he pleases, he may consult a jury; and if he pleases, he may adopt their verdict.

It is superfluous to carry the illustration further. If the cry of Double Government is to prevail, none of the free institutions of this country, except perhaps the House of Commons, are safe; and we may be thankful if the principle is not applied to Parliament too. All government, except the single government of one man, is double government, or treble government, or quadruple government; and if the people of England, in a case of such magnitude as India, allow this plea to be successful, and the intermediate body which administers that country under the Crown to be superseded by the undivided power of a Minister and his subordinates, they will sanction a principle and establish a precedent which they may before long have reason to regret.

OBSERVATIONS ON THE PROPOSED COUNCIL OF INDIA

1858

EDITORS' NOTE

London: Penny, 1858. No running titles. Unsigned. Not republished. There are no emendations in the Somerville College copy. Not listed in Mill's bibliography, but clearly part of the series of pamphlets by Mill, located with the others in his library, and reflecting his approach (see the reference to Bentham on the first page) and manner. Perhaps the superficial similarity to the next title led the copyist to omit this one.

Observations on the Proposed Council of India

THE HOUSE OF COMMONS has virtually decided that the home administration of India shall be carried on by a Minister of the Crown with the assistance of a Council.

It is still to be determined in what manner the Council shall be composed.

The three principal leaders of sections in Parliament, have proposed as many different plans for the composition of the Council.

Lord Derby proposes that it should be partly nominated by the Minister, and partly elected by a constituency.¹

Lord Palmerston proposes that it should be wholly nominated by the Minister, and that each member should hold office for only six years, unless reappointed.²

Lord John Russell proposes that it should be wholly nominated by the Minister, but that the members should hold office, like the judges, during good behaviour, that is, virtually for life.³

Which of these is the preferable scheme?

The answer depends on whether it is intended that the Council to be associated with the Minister, should be a check, or a screen.⁴ It will necessarily be either the one or the other.

If it is intended to be a screen, Lord Palmerston's plan deserves the preference. The Council should be selected by the Minister, and should be dependent on him for remaining in office.

But if it is to be anything else than a screen, independence must be secured to it. For this purpose it is best of all, that either every member of Council, or a preponderant majority, should be elected. But if nominated, then it ought not to be in the power of any Minister to remove them.

If any one thinks that it is a matter of small importance whether the Council is independent or not, he must think that it is of small consequence whether there is a

¹The plan of the Conservatives, led by Edward Stanley, 14th Earl of Derby, was laid before the Commons by Disraeli in his speech of 26 Mar., 1858.

²Temple, speech of 12 Feb., 1858, in introducing the India Bill of that date.

³Russell, Speech on the Government of India Bill (26 Apr., 1858), *PD*, 3rd ser., Vol. 149, cols. 1695-1701.

⁴The image comes from Jeremy Bentham (see p. 84 above).

Council or not. For it is better there should be no Council at all, than a sham Council.

But to suppose that the existence and the independence of the Council are of little importance, is to overlook all the essential circumstances of the case. The good government of India will entirely depend upon the Council. If India is well governed, it will be because the Council will be capable of well governing it: for the Minister, as distinguished from the Council, usually will not.

All the requisites for the good government of India will be found in the Council, if rightly composed. None of the requisites are likely to be often found in the Minister to whom the tactics of party may transfer the Indian Department.

The members of the Council may be, and are intended to be, chosen for their knowledge of India. The Minister is chosen because he has a Parliamentary position, either from his rank, or from his powers of speaking, which are more likely to have been exercised on any other subject whatever than on India.

The Minister, before he has had time to learn his business, is out of office. The Council may be, and ought to be, a permanent body.

Even while the Minister is in office, India will be one of the smallest of his concerns. The maintenance in power of the Ministry and the party to which he belongs, and the support of the general policy of the Ministry and of the party, will be at all times his principal objects. And these objects will not be much promoted by good government in India, nor much impeded by bad; because neither the English Parliament, nor the English public, will generally know anything either of the one or of the other.

There is one point in which the Minister's position is supposed to be more favourable to good government than the position of the Council; responsibility. But there cannot be a greater error. The sort of responsibility to which the Minister is subject, is no security at all for good government. The only way to make responsibility of any use, is to impose the responsibility on the Council.

The Council, in the first place, has nothing to do with the general business of the empire. It is concerned with India, and India only. All its thoughts must be given to India. All the credit it can hope for, must be derived from India only.

The Council, moreover, is or ought to be a permanent body. Its interest, then, is identified with the *permanent results* of the mode in which India is governed. Its estimation, its position in opinion, perhaps its tenure of office, depend on permanent results. This is not the case with the Minister. He will have ceased to be in office long before the permanent results of his policy can disclose themselves; and when they do disclose themselves, it will hardly be remembered, and perhaps will hardly be distinguishable, whether his acts, or those of his predecessors or successors, are accountable for them.

The responsibility of the Minister, therefore, will not depend on the general results of his policy. He will seldom have either the credit of them if they are good, or the discredit if bad. What is called his responsibility to Parliament, will not be of

the kind which would maintain him in well-doing. It will operate in a totally different manner. Its principal tendency will be, to make him afraid of doing anything which any person who has the ear of the House of Commons, opposes; or of opposing anything which any such person demands. His responsibility will not be to Parliament, but to a few speakers in Parliament. It will mean, liability to a debate in the House of Commons. To get rid of a debate, by every sort of concession, will be the course to which his responsibility will prompt him; for he will have no reason to expect that he will be the person to answer for the ultimate consequences of the concession. And on these occasions, it is always the people of India who will be sacrificed. The people of India have no means of interesting any one in standing up for them; while all who prey upon the people of India have. It may be said, the Minister may be a man of principle; he may disregard these considerations, and follow his own conviction of right. But if he does so, it will not be in consequence of his responsibility. It will be in spite of his responsibility. It will be because he cares less for his responsibility than for his duty.

It is believed that an examination of several recent instances in which the responsibility for measures has been transferred from a Board out of Parliament, to a Minister in it, would show, that the result has been not to accelerate, but on the contrary, to arrest improvement. The permanent Boards were identified with the general success of their administration. The Minister is only responsible for keeping on good terms with all individuals and all interests powerful enough to give him trouble.

**PRACTICAL OBSERVATIONS ON
THE FIRST TWO OF THE PROPOSED RESOLUTIONS
ON THE GOVERNMENT OF INDIA**

1858

EDITORS' NOTE

London: Penny, 1858. No running titles. Unsigned. Not republished. There are no emendations in the Somerville College copy. Identified in Mill's bibliography as "Practical Observations on the first two of the proposed Resolutions on the Government of India," the second item under the heading: "The following short pamphlets on the India Bills and Resolutions of the Session of 1858 viz:" (MacMinn, 91). For the Resolutions, see "Government of India. Resolutions to be Proposed by Mr. Chancellor of the Exchequer in Committee of the Whole House upon the government of India, on Friday, the 30th of April [1858]," *PD*, 3rd ser., Vol. 149, Appendix.

Practical Observations on the First Two of the Proposed Resolutions on the Government of India

1. THAT, as the territories under the government of the East-India Company are by law to remain under such government only until Parliament shall otherwise provide;

FROM THE TERMS of this resolution it might be supposed that the renewal of the Company's powers in 1853 was a mere temporary arrangement, and that the phrase "until Parliament should otherwise provide,"¹ was the expression of an intention on the part of Parliament to provide otherwise, at some not remote period. But this is not the fact. As is well known, the words were only used to show that the powers of the Company were renewed for an indefinite period, and not, as on former occasions, for a definite period of twenty years.

It is no peculiarity of the East-India Company's authority, that it exists only until Parliament shall otherwise provide. This is the case with all our institutions; and is no more a reason for abolishing the East-India Company, than for abolishing the courts of justice, or trial by jury.

The first clause of the resolution thus appears to have for its object to excuse the proposed change, by giving to be understood that its expediency was duly considered and affirmed by a former Parliament, though no such consideration or affirmation took place.

The transfer of the "government" of India to the Crown is an improper expression. The government of India, like that of all the rest of the empire is already in the Crown. The

this House is of opinion that it is expedient that the transfer of such government to the Crown should now take place,

¹The first words of Clause 1 of 16 & 17 Victoria, c. 95.

power of the Crown, when actually exercised, is more absolute in India than in any other part of the British dominions, except perhaps Gibraltar, or some other mere military position without any local institutions.

It is the *administration*, not the *government* of India, which is carried on by the East-India Company; and the Company conducts it for and under the Crown. It is the *administration* of India which it is proposed should be taken from the Company, and made over bodily to a Minister of the Crown; contrary to the whole practice of the Constitution, according to which direct administration by the cabinet is limited to the general affairs of the empire, all local affairs being, wherever possible, administered by some intermediate body, constituted for the purpose, and exclusively devoted to it.

in order that the direct superintendence of the whole empire may be placed under one executive authority.

The *superintendence* of the empire by the Crown, so far as concerns India, is as direct and complete already, as any change could make it. The proposal is, that the superintendence should cease to be "superintendence," and should become direct administration. The word superintendence, as used in the Resolution, only serves to shelter the substitution of one idea for another totally distinct from it.

Is it true that the direct *administration* of all the affairs even of England, is "under one executive authority"? On the contrary, it is shared by a multitude of authorities.

The currency and paper credit of the country are, like all other great national concerns, under the *superintendence* of the Crown. But they are *administered* by the Bank of England.

The protection of the navigation of the country, by lighthouses, buoys, etc., is a matter of far too great national importance not to be *superintended* by the Crown; but it is *administered* by the corporation of the Trinity House.

The civil and criminal justice of the country is *superintended* by the Crown, and in part even administered by judges whom the Crown nominates, but whom it cannot remove. Justice however is also *administered*, not only by the county magistrates, but by independent juries, in whose appointment the Crown has no voice.

The public provision for the poor, and the levy and expenditure of the poor-rates, are *superintended* by a Commissioner who is one of her Majesty's Cabinet Ministers; but they are *administered* by the Boards of Guardians throughout the country, and by the parochial officers, under the orders of the Boards of Guardians.

The railway communication of the country is *superintended* by her Majesty's Board of Trade; but it is *administered* by the Boards of Directors of the various railway companies, under the provisions of their several Acts of Parliament.

Finally, the colonies are *superintended* by the governors appointed by the Crown; but, with some insignificant exceptions, they are *administered* by local cabinets virtually chosen by the parliaments of those colonies, and responsible to them, in the same manner as the Cabinet of the British empire is responsible to, and is virtually chosen by, the British Parliament.

So far therefore is the administration of India for and under the Crown by an independent body, from being an exception to the general practice, and an anomaly in the Constitution, that the exception and the anomaly would lie in its being administered in any other manner. There is scarcely a single department of the business of the empire, except the army and navy, in which the authority of the cabinet is not shared and in some degree checked, by some intermediate body. To establish the authority of a Cabinet

2nd. That for this purpose it is expedient to provide, that her Majesty, by one of her Principal Secretaries of State, shall have and perform all the powers and duties relating to the government of India, which are or may be now exercised and performed by the East-India Company, or by the Court of Directors or Court of Proprietors of the said Company, either alone or with the approbation of the Commissioners for the Affairs of India.

Minister single and unchecked, over so vast a country as India, will be the introduction of a new practice, dangerous in the extreme to the stability of our free institutions, and subversive of the existing securities for the good government of the empire.

This Resolution asserts two distinct propositions as if they were one and the same. One is that her Majesty, by one of her Secretaries of State, should have all the powers now held by the East-India Company. The other is, that the Secretary of State should perform all the duties now performed by the Company.

The first proposition is nothing new, and requires no new legislation. The President of the Board of Control already has, with a few exceptions, all the powers of the East-India Company. Whatever act the Company can do, he also can do, except, in some cases, to incur expense; and whatever act the Company does, can only be done with his assent, except the recall of a Governor-General.

But, from possessing all the powers of the Company, to performing all its duties, there is a wide interval. The duties of the Company consist in initiating all Indian business, appointing all the highest functionaries in India, and preparing all orders and despatches to India for the approval of the Indian Minister. If Parliament resolves that these *duties* ought to be performed by the Crown, it resolves that the Minister of the Crown shall have the initiative, in addition to (what he already possesses) the ultimate decision. It resolves that there shall be no intermediate body which shall have any responsible share in the administration of India. It reduces the council which is provided for in the succeeding Resolutions, to a body of mere assessors, who may be consulted or not, as the Indian Minister pleases, and who will, at most, have no power but that of recording an unavailing dissent.

The great and fatal change in the government of India, from a government of constitutional checks to the autocracy of a Minister, will thus be effected by the first two Resolutions. If these pass, whether the remaining twelve are passed or not, will make very little practical difference.

These considerations forcibly suggest the propriety of postponing the first two Resolutions, until the other Resolutions shall have been discussed. The first two pledge the House to transfer the whole duty of administering India to an officer of the Crown. By the other Resolutions, the House will be asked to provide aids, and frame rules, to guide the officer of the Crown in the performance of the duty thus intrusted to him. Would it not be wise in the House to begin by assuring itself that these aids and rules are sufficient, before pledging itself to confide the entire administration of a great portion of the British empire to a single Minister?

The preamble of a Bill is usually the last part voted. In the present case, the first two Resolutions are virtually a preamble; except that if passed they would be binding on the House even if all the other Resolutions were rejected; whereas the preamble of a Bill which does not pass, is never considered binding.

The first Resolution will pledge the House to abolish the present organ of Indian administration, before the House has begun to consider whether it can frame any new organ preferable to the present. The House will have bound itself to destroy the existing structure, before it has been asked to decide what shall be the plan of the new.

The second Resolution will decide that the new scheme of administration shall be the centralization of all functions in one man; before the House has had an opportunity of

considering whether by any subsidiary organization, it can be made possible for one man to fulfil all these functions, or safe to intrust them to him.

The postponement therefore of the first two Resolutions, until the House shall have discussed every provision of the new organization proposed by the remaining Resolutions, seems called for by every consideration of good sense and prudence.

THE MORAL OF THE INDIA DEBATE

1858

EDITORS' NOTE

London: Penny, 1858. No running titles. Unsigned. Not republished. There are no emendations in the Somerville College copy. Identified in Mill's bibliography as "The Moral of the India Debate," the fourth item under the heading: "The following short pamphlets on the India Bills and Resolutions of the Session of 1858 viz:" (MacMinn, 91).

The Moral of the India Debate

THE PROCEEDINGS AT HOME, consequent on Lord Canning's proclamation,¹ have a most important bearing on the intended changes in the mode of administering India. They are a timely warning, how a Minister governs India, when he is under no check but responsibility to Parliament, and how Parliamentary responsibility, when really enforced, is likely to work.

In writing his despatch, Lord Ellenborough was in the position, in which the Minister for India will always be, under the proposed new constitutions.² He was without a Council: or rather, he passed over his Council. The despatch was in the Secret Department, that is to say, it was not brought before the Court of Directors. There was no compulsion on Lord Ellenborough to write on this subject in the Secret Department. It would have been perfectly regular to lay the papers before the Directors, and allow, or if necessary require them, to prepare a despatch to the Governor-General on the proposed proclamation. But no such despatch as Lord Ellenborough's could have passed the Court of Directors; nor could such a despatch have been substituted for theirs by his authority as President, without giving rise to remonstrances and protests which no Minister would have liked to see produced in Parliament.

This despatch is therefore a fair specimen of what a Minister may do, when he is at liberty to disjoin himself from his Council. Let us now for a moment consider the despatch itself.

Observe, that it is the production of a man who is a favourable specimen of an Indian Minister. He is not such a man as we may generally expect, ignorant of India, appointed because a Cabinet office must be found for him, and because public opinion will not allow him to be placed in any other than that of Indian Minister. Again, the despatch was written with the very best intentions. Not only

¹Charles John Canning (1812-62), Viscount Canning, Governor-General of India 1856-58 and then Viceroy, "Proclamation" (18 Mar., 1858), in "Papers Relating to the Proclamation Ordered to be Published in Oude," *PP*, 1857-58, XLIII, 409-10. This proclamation, issued after the reconquest of Lucknow, thanked those who remained loyal, confiscated the lands of the insurgents, and threw them on the mercy of the British government.

²See "The Secret Committee of the Court of Directors of the East India Company to the Governor-General of India in Council" (19 Apr., 1858), *ibid.*, pp. 410-11. Ellenborough criticized Canning's proclamation, and requested that its severity be mitigated.

was its purpose good, but its principles were sound. Its principles were, to stigmatize confiscation, and condemn vindictive severity against a conquered enemy.

Wherein then did the despatch err? Its epigrammatic style was a minor fault, to which importance was only given by the publication of the despatch. Its errors were substantial and serious.

In the first place it gave Lord Canning no benefit from his well-ascertained and dearly-earned character for mercy. It did not allow the presumption drawn from the whole of his past conduct, to count in explanation of the particular act incriminated. If instead of firmly resisting the ravenous cry for blood, which by its effects has nearly rendered the good government of India impossible for a generation to come, Lord Canning had implicitly yielded to that savage howl, a worse interpretation could scarcely have been put on his intentions, than Lord Ellenborough hastened to put upon a single unexplained act of the man who had merited the designation of "Clemency Canning."

But the despatch had another fault no less grave, and which would have been equally a fault, even if Lord Canning had been less deserving of consideration. In a time of emergency, it arrested a policy in mid-course. There could be no doubt that Lord Canning had made a deliberate choice among several modes of action, each of which had its peculiar advantages. Lord Ellenborough might think that he had not chosen the best; but unless he was totally unfit to be Governor-General, the course he selected must have had some considerable recommendations, some chances, to say the least, of attaining the object. To have instructed him beforehand not to adopt that course, would have been one thing, which might have been either wise or foolish. But to stop him when he had adopted it, and committed himself to it, but before it had produced its results, was to throw away the chances of good which that course held out, without gaining those of any other. It was as if the Minister, under the belief that it would have been better to clear Rohilcund before attacking Oude, had by telegraph recalled Sir Colin Campbell from the gates of Lucknow.³

Contrast with this the conduct of the Court of Directors.

A few days after the date of Lord Ellenborough's despatch, but without being aware of it, they framed instructions to Lord Canning respecting the treatment of the Oude insurgents, which have been laid before Parliament, and which embodied all the sound and humane principles of the despatch, without its irritating language.⁴ As soon as they were made acquainted with the unmerited censure passed on Lord Canning, they recorded a vote of undiminished confidence

³Colin Campbell (1792-1863), Baron Clyde, became Commander-in-Chief during the Mutiny; he began the attack on Lucknow in November 1857, though the city was not finally relieved for four months.

⁴See "Copy of a Letter from the Court of Directors of the East India Company to the Governor-General of India in Council" (5 May, 1858), *PP*, 1857-58, XLIII, 113-16.

in his merciful intentions.⁵ They thus combined the inculcation of what is admitted to be the right rule of conduct, with full justice to the functionary who was prematurely charged with having infringed it.

This is what took place under the calumniated double government. Lord Ellenborough's despatch exemplifies the single government of a Minister responsible only to Parliament.

Let us now consider the second lesson to be derived from these proceedings; the light which they throw on the natural working of the boasted Parliamentary responsibility. For, through the rare accident that a Ministry is in office which does not possess a majority in the House of Commons, the present has happened to be the one case in a thousand in which the responsibility is real. The Minister really has lost office in consequence of his despatch.⁶ Now see at what price this result has been obtained.

In the first place, the greatest practical evil of the despatch arose from the publicity given to it. As long as its existence was a secret between Lord Canning and the Minister, it might have tied his hands in an emergency, but it could not have impaired his influence in India, and his justification might have arrived in time to change the reproof into approbation. But the publication of the despatch, which the Government itself condemns, and which all agree in regarding as the worst part of what has taken place, is the direct consequence of the accountability to Parliament. But for that accountability, Mr. Bright would not have asked for the despatch,⁷ nor would Lord Ellenborough have produced it. Neither was this premature publicity a casual consequence. It will be a natural and frequent one, when there is no check upon the administration of India except the control of Parliament. If the Minister is to be called to account *there* for the mistakes he commits in governing India, it must be done immediately. What Minister ever was censured by Parliament for the part he took in events long past and gone? His party opponents will seize on the subject while the public mind is intent on it; and unless he is strong enough to defy responsibility, all he has done or written will be published *then*, and will *then* become the text of criminary or defensive declamation; while the effect of the publicity on the interests of India, or on the security of our empire there, will be secondary to the important question, whether one man, or another much the same as he, shall sit for a while on the Treasury bench.

The accountability of Ministers to Parliament was carried into effect in this instance by a debate of one night's duration in the House of Lords, and three nights

⁵See *ibid.*, pp. 117-20.

⁶Following the debate in the Lords on 7 May (*PD*, 3rd ser., Vol. 150, cols. 228-47), reported in "The Revolt of Oude," *The Times*, 8 May, p. 9, Ellenborough resigned on 10 May.

⁷John Bright (1811-89), Question on Confiscation of Land in Oude (6 May, 1858), *PD*, 3rd ser., Vol. 150, col. 181.

in the House of Commons.⁸ A full half of the discussion, and the whole of the result, turned not upon India, but upon whether Members of Parliament desired, for English purposes, that Lord Derby's Government should or should not continue in office. Had it been known beforehand which of these was the desire of the majority, the issue of the debate could have been predicted. It issued in nothing at all, because neither party knew, and both shrunk from having it brought to the test of a division, whether there was a majority or not for turning Lord Derby out of office. This fortunate uncertainty has prevented great mischief. For if the debate had ended in any vote, that vote would have been understood in India either as a condemnation of clemency, or as a condemnation (followed probably by the resignation) of Lord Canning, the patron of clemency. Even as it is, the mischief is not trifling. On those great questions relating to the future government of India on which it was of the utmost importance that England should seem to be unanimous, she has been held forth as divided. Our enemies in Europe have been supplied with a fresh stock of calumnies against us from our own lips; while all Indian malcontents have had arguments put into their mouths which they themselves would never have dreamt of, and have been encouraged to hope that they may make or find a party in Parliament. All respect and fear of England as a nation will be materially weakened in the East; for, that there may be firm action notwithstanding divided councils, or that a government can be really formidable which allows itself to be bearded and its acts railed at to its face, is a truth which it requires a much higher civilization than that of Orientals to understand or credit.

All these things are necessary results of the play of the machinery through which Parliamentary responsibility operates. And if all other checks are taken away, these results may be expected more and more. No one denies it to be necessary that Parliamentary responsibility should exist in reserve; but the object should be, to dispense as much as possible with the need of actual recourse to it, by providing another restraint; a restraint acting before the mischief is done, not after, and producing its effect not by acrimonious controversy in the face of the world, but by peaceful discussion in a council-room. This can only be done by giving the Minister an independent Council, having the initiative of business, and by making it impossible for him to take any important measure without first listening to their advice.

⁸In the Lords on 7 May (see n6 above); in the Commons on 14, 17, and 20 May (*ibid.*, cols. 674-761, 764-857, and 931-1059).

**A PRESIDENT IN COUNCIL
THE BEST GOVERNMENT FOR INDIA**

1858

EDITORS' NOTE

London: Penny, 1858. No running titles. Unsigned. Not republished. There are no emendations in the Somerville College copy. Identified in Mill's bibliography as "A President in Council the best Government for India," the third item under the heading: "The following short pamphlets on the India Bills and Resolutions of the Session of 1858 viz:" (MacMinn, 91).

A President in Council the Best Government for India

THERE ARE two political functions devolving on the British nation. It has to provide for its own government; and for the government of the much more extensive and populous countries which are dependent on it.

The majority however of its dependencies it has, wisely and necessarily, divested itself of the duty of governing; having found, after long trial, that it was unable to govern them satisfactorily. The only great outlying possession of the British Crown which is not now left substantially to its own government, is India.

The question is, in what manner Great Britain can best provide for the government, not of three or four millions of English colonists, but of 150 millions of Asiatics, who cannot be trusted to govern themselves. This is evidently a far more difficult task, than the one which the British nation acknowledges itself to have failed in. It is not likely that the very plan which has failed everywhere else, should be perfectly sufficient and satisfactory in the case in which the difficulties are the greatest. One would say, even before the subject is considered, that if success can be attained in such a case, it must be by some arrangement much more carefully and nicely adapted to the purpose.

Consider in what way the government of England itself is conducted. The English people may be supposed to know something of their own affairs. It may also be reasonably presumed that they feel an interest in them. They have every possible means of making their necessities, their grievances, and their opinions, known. When they have any wish in regard to their own Government, they usually demonstrate the wish in a thousand channels, by the press, petitions, and public meetings, before the Government takes the first step on the subject. And if the Government adopts any measure which the people, or even any fraction of the people, consider injurious to their interest, the first announcement causes it to be at once questioned in the press and in the House of Commons, and if general opinion is unfavourable there is time for the measure to be stopped before it has come into practical effect. These securities, as we know and lament, do not always prevent bad measures; but they do, for the most part, suffice to prevent inconsiderate ones. No Government feels it safe, in the home affairs of England, to take any step likely to lead to serious consequences, without previous weighing and deliberation. The checks do not operate so quickly in foreign affairs, and therefore it is generally felt

that foreign, much more than home affairs, are conducted according to the individual and private preferences of the Minister, and much less according to either the interests or the wishes of the nation.

But in the government of India by a Parliamentary Minister, none of the checks exist at all. The public are never likely to hear of what is meditated, until actually done. When done, they seldom hear of it until the mischief, if there be mischief, is in part accomplished, and its reversal may be attended with greater evils than that of allowing it to subsist. Even when they do hear of it, they scarcely ever obtain, until long afterwards, the materials for judging whether the measure was right or wrong. There would be all these difficulties in controlling the Minister, even if the public and Parliament were deeply interested and intent on Indian affairs. But, on the contrary, all except a few are in general entirely without interest in the subject, because they have no knowledge of it, and because their time and attention are taken up by things nearer at hand. Among the few who do attend to the subject, neither the public nor Parliament have the means of distinguishing those who, from character and knowledge, have the best claim to be followed as guides. A Minister, probably very little acquainted with the questions which he is to decide, has nothing to compel him either to study them and deliberate on them in his own mind, or to attend to the suggestions of those who have already studied them, except a nominal responsibility to a body who have no means of accurate knowledge, and who are in general too indifferent to the subject to apply to it even such knowledge as they might obtain.

It is in circumstances like these that Parliament is asked to give over India to the sole government of a Minister, usually altogether ignorant of it when first appointed, and changed every two or three years. And it is gravely said that we need not fear to confide absolute power to absolute ignorance, in reliance that if the natural effects follow, Parliament will *punish* the Minister for his misconduct.

As it cannot be desired that the policy of the Indian Government should be a policy of ignorance, or that it should be changed every time a Minister is promoted or turned out; and as there is no public or Parliament to supply knowledge of Indian affairs, as knowledge of English affairs is in some measure supplied, the knowledge must be furnished to the Minister in his own office. There must be in the department itself a body which knows India, and is the guardian and conservator of the principles of administration which experience has approved, or which knowledge sanctions. Those who object to a Council constituted for the purpose, must intend that the clerks in the office should be this body. But the proposal to confide the habitual Government of India to persons whom the public generally do not know even by name, and never know whether their advice is taken or not, is rather remarkable as coming from the zealots for responsibility. The real friends of responsibility are those who would have this function exercised by a Council, who can be made responsible.

But a Council which the Minister need not consult, will be little better, if not worse, than leaving him with no other competent advisers than the clerks in his

office. He cannot shelter his own responsibility behind the clerks. They cannot serve him as a screen. The Council may. And if it is left to him to determine their functions, that is the chief use to which he will probably apply them. In no one of the three plans brought before the House of Commons by its accustomed leaders,¹ is there any inducement given to the Minister for consulting the Council, if he has reason to expect that they will differ from him in opinion. Lord Ellenborough has very truly and laudably said, that the Minister will want their support, to protect India from the mistakes of Parliament and of English opinion.² But India needs protection also against the Minister's own mistakes. Parliament, however misled, can only exert its power slowly, and after discussion: the Minister, in half an hour, may issue a despatch, the evil consequences of which years may not suffice to cure. If the Council is fit to support the Minister when he is right, it will be fit to check him when wrong. And its support is not likely to carry any weight when it agrees with him, if it is not allowed to differ, or is not asked its opinion unless willing to agree.

To make the Council a real security for good government, all business which requires deliberation, or admits of difference of opinion, ought to be transacted by the Minister *in Council*. It is on this principle that the British Government in India itself is constructed, and it works most effectively. The Governor-General, or the Governor of a Presidency, performs his manifold duties in conjunction with Councillors, not of his own nomination. They are appointed, theoretically, by the same authority which appoints himself; but practically by a different authority, the Governor-General or Governor being in fact selected by the Queen's Minister, the Members of Council by the Court of Directors. As an ordinary rule, all questions are decided in Council according to the opinion of the majority; but their opinion is not binding on the head of the government. When he pleases, he can, recording his reasons, set aside the opinion of the Council, and act on his own sole responsibility; but he must go through a particular form for that purpose, which gives a deliberate, and in some degree a solemn, character to the act. On this system the members of Council feel themselves a real and substantial element in the government; their best thoughts are given to every question which presents itself, their opinion is recorded and has its just weight, while they have no power of authoritatively opposing themselves to the deliberate opinions and purposes of the head of the government.

The same principle, applied to the home administration, would give probably the

¹For the first two Bills, introduced by Lord Palmerston and Disraeli, see pp. 162-3 above. The third was "A Bill for the Better Government of India," 21 Victoria (17 June, 1858), *PP*, 1857-58, II, 313-36; it was introduced by Henry Fitzroy (1807-59) on 17 June (*PD*, 3rd ser., Vol. 150, cols. 2253-4), but one of the "accustomed leaders" of the Conservatives, Edward Henry Stanley (1826-93), Lord Stanley (later 15th Earl of Derby), gave the first major speech on 24 June (*ibid.*, Vol. 151, cols. 315-30).

²Law, Speech on the Government of India (29 Apr., 1858), *PD*, 3rd ser., Vol. 149, cols. 1962-8.

best organ of Government for India, which circumstances admit of. The authority should be that of the President, but of the President in Council. The deliberation should be as much that of the whole body, as if the body and not the head had the power of deciding in the last resort. The general practice in that case would probably be, to decide, (as at Calcutta,) according to the sense of the majority, the President's vote only counting for one. But he would have the power, after he had consulted his Council, on declaring his intention in a prescribed form, and recording his reasons, to act on his own separate opinion in opposition to theirs. According to this plan, the ordinary conduct of business falls by the natural working of things, without any special provision for the purpose, into the hands of those who know most of the subject; and the minds which really determine what is done, are associated, as they ought to be, in the responsibility. Yet the Minister's responsibility, even for the ordinary business, would never be felt to be impaired, no more than the responsibility of Lord Wellesley or Lord Dalhousie was impaired by the advisers with whom they were associated; while the Minister would be subjected to an additional and special responsibility, when he chose to set aside his Council. And this is surely right. If there be any case whatever in which deliberation, and a sense of responsibility, are peculiarly necessary, it is when one man, often not qualified by special training, assumes to be a better judge of a subject, than a body of men expressly selected for their knowledge of it, and their competency to advise on it.

**LETTER FROM THE EAST INDIA COMPANY
TO THE PRESIDENT OF THE BOARD OF CONTROL**

1858

EDITORS' NOTE

Supplement to Votes, 1858, pp. 269-72. Headed: "Letter from the Chairman and Deputy Chairman of the Honourable East India Company to the President of the Board of Control. Presented to the Honourable House of Commons by Command of Her Majesty, 24th June, 1858." The letter is addressed "Lord Stanley," dated "East India House, / 23rd June, 1858," and concludes, "We have the honour to be, my Lord, / Your Lordship's most obedient humble Servants, / F. Currie, / Wm. J. Eastwick." (Frederick Currie, 1799-1875, was Chairman, and William Joseph Eastwick, 1808-89, Deputy Chairman, of the East India Company.) The Somerville College copy of the version in the *Supplement to Votes* contains inked corrections of punctuation, apparently by Mill. Also printed in *PP*, 1857-58, XLIII, 41-4, with the same heading and address. Several, but not all, of the changes in punctuation appear in the *PP* version, which also includes two other changes in punctuation here adopted (other accidental variants are ignored); see the list in App. G for details. Not otherwise republished. Identified in Mill's bibliography as "The letter from the Chairman and Deputy Chairman of the Court of Directors to Lord Stanley, respecting the third India Bill, dated 23rd June 1858, presented to the House of Commons 24th June" (MacMinn, p. 92).

Letter from the East India Company to the President of the Board of Control

MY LORD,

1. Although the Bill which has been newly brought in by Her Majesty's Ministers "for the better government of India"¹ has not yet been formally communicated to the Court of Directors, the Court, influenced by the desire which they have already expressed to give all aid in their power towards rendering the scheme of government which it is the pleasure of Parliament to substitute for the East India Company as efficient for its purposes as possible, have requested us to lay before your Lordship, and through you before Her Majesty's Government, a few observations on some portions of the Bill.

2. Having in documents which have been presented to Parliament expressed their sentiments fully on all the general features of the subject,² the Court refrain from offering any further arguments on points upon which the Government and the House of Commons seem to have pronounced a decided opinion. The joint government of a minister and a council, composed in majority of persons of Indian experience, deriving their appointments only partially from ministerial nomination, and all of them holding office on a tenure independent of the minister, is a combination which fulfils, to a considerable extent, the conditions of a good organ of government for India. The Court would have much preferred that in the constitution of the Council more extensive recourse had been had to the elective principle. But if they cannot hope that this course will be adopted, they see many advantages in the provision by which one-half the number, instead of being named by the Government, will be selected by a responsible body, intimately connected with India, to whom the qualifications of candidates will in general be accurately known, and who will be under strong inducements to make such a choice as will tend to increase the credit and consideration of the body.³

3. With regard to the qualifications prescribed for members of council, the

¹"A Bill for the Better Government of India," 21 Victoria (17 June, 1858), *PP*, 1857-58, II, 313-36.

²Including "The Petition of the East-India Company," and "Report to the General Court of Proprietors, Drawing Attention to the Two Bills Now before Parliament Relating to the Government of India," above.

³By Clause 8 of the Bill.

Court desire to offer a suggestion. Her Majesty's present Government have, on many occasions expressed a desire to secure the Crown appointments against the evils of abuse of patronage. The security against such abuse has hitherto consisted in the strict limitation of the appointments to persons who have served a considerable number of years in India. While the Court fully agree with Her Majesty's Government in recognising the desirableness of an English element, it does not seem to them advisable that this element should extend to nearly half the Council, only a bare majority being reserved for persons of Indian experience. Knowledge of India is, after all, the most important requisite for a seat in the Indian Council: while it is chiefly in the English nominations that there is any present danger lest appointments should be obtained through political or parliamentary influence; from which influence, unless introduced through that channel, the Council, like the Court of Directors, may be expected to be altogether free. The Court, therefore, recommend that the qualification of ten years' Indian service or residence⁴ be made imperative on at least two-thirds instead of a mere majority of the fifteen members of council. They also think it questionable if the interests of India will be promoted by the exclusion of the whole of the Members of the Council from seats in Parliament.⁵ These are the only modifications which we are requested to suggest in the provisions respecting the composition of the Council.

4. But we lament to see that the clauses which define its functions are liable to far greater objections. From the sentiments which have been publicly expressed both by your Lordship⁶ and by other Members of the Administration, as well as from the terms of clause 19, which declare that the Council, under the direction of the Secretary of State, is to "conduct the business transacted in the United Kingdom in relation to the Government of India and the correspondence with India," the Court are persuaded that Her Majesty's Government regard the Council, not as a body without regular functions or duties, whom the Minister is at full liberty habitually to disregard, but as a substantive part of the working organ of government. It is therefore incumbent on the Court to represent to your Lordship that the details of the Bill not only do not carry out this conception, but would appear to be inconsistent with it.

5. It is hardly necessary to remark that the Council cannot "conduct the business transacted in the United Kingdom in relation to the Government of India and the correspondence with India," unless provision be made for their meeting regularly at short intervals to dispose of the business as it arises. The Bill, however, makes no provision for any regular or periodical meetings of the Council, but leaves the time of convening it, and even the convening it at all, to the entire discretion of the Secretary of State, saving the case necessarily exceptional of a requisition in

⁴By Clause 10.

⁵By Clause 12.

⁶Stanley, Speech on the Government of India (7 June, 1858), *PD*, 3rd ser., Vol. 150, cols. 1673-8.

writing by five members, which would impose on the requisitionists the necessity of appearing to place themselves in a posture of opposition to him.⁷

6. By the 16th clause the Council are denied all power over the establishment, beyond the first appointments to junior clerkships and inferior offices, all promotions being made by the Secretary of State alone, and the appointment of secretaries or assistant secretaries and heads of departments being wholly reserved to him. While the officers, including those whose duty it is to prepare drafts of despatches, are thus entirely withdrawn from the control of the Council; the Bill does not even provide that the drafts, when prepared, shall, as a matter of necessity, be considered and discussed in Council. It only provides that they shall, seven days before being sent to India, be placed in the Council room for inspection by the Members, to afford them an opportunity for the invidious office of recording objections; and this power of dissent from a measure or a document already sanctioned by the Minister, is the only positive function which the Bill secures to the Council.⁸ It is obvious that the same comments which, if made in the early stage of the proceedings, before the Minister has made up his mind, have the character of cordial and zealous co-operation, will, if delayed until his intentions have been declared, assume the aspect of opposition or remonstrance, and are therefore much less likely either to be made at all, or if made, to be of any efficacy, unless by way of a protest.

7. The Court submit that the only mode by which the direct action of the Minister and the substantive existence of the Council as a co-operating body, can be brought into complete harmony, would be by enacting that all ordinary business, and as far as possible all business, shall be transacted by the Minister in Council. A perfect and most successful example of this mode of transacting business is afforded by the Local Government of India. All business is as a matter of course transacted by the Governor-General, or Governor in Council, and, as a general rule, the decision is according to the vote of the majority. But the Governor-General, or Governor, has the power of setting aside the decision, on assuming the formal responsibility and recording his reasons. No inconvenience of any kind has ever been experienced from this arrangement; it has never been found either to hamper the discretion, or in any degree impair the responsibility of the head of the Government. It cannot be doubted that the Minister for India would find the same advantage from this principle in superintending the Administration, which a Wellesley and a Dalhousie found in conducting it in all its complicated details.

8. The Court see no reason for withdrawing from the deliberation and knowledge of the Council even such subjects as are at present disposed of through the Secret Committee. It is their conviction that the power of carrying into effect

⁷By Clause 22.

⁸The drafting of despatches is detailed in Clauses 25-8.

measures of the highest importance without the advice, or even the knowledge of the Court of Directors, has been the source in times past of some of the greatest errors, and of the greatest calamities, which are recorded in our Indian history; and they earnestly recommend that a barrier be raised against the future exercise of this dangerous power, and that since it may be presumed that the Council will possess the confidence of Her Majesty's Ministers, the right and duty of advice be vested in the Council on all subjects of Indian administration, without excepting, as hitherto, from their cognizance, some of the most important of all.

9. The Court are of opinion that, on all questions regarding expenditure, the Council should have more than a consultative voice, and that these questions should be an exception to the power which the Secretary of State will in all other cases possess, of setting aside their opinion. The disposal of the entire revenues of India by the mere fiat of a minister, freed from the necessity of the assent of any co-ordinate authority, would, the Court conceive, be neither consistent with the principles of the constitution, nor conducive to the good administration of the Indian finances. The propriety of allowing to the Council in this one department a negative voice, was recognised in one of the Bills introduced into Parliament,⁹ and the omission to include such a provision in the present Bill is, the Court hope, only the effect of inadvertence.

10. The Court think it of great importance that the Council should be associated with the Minister in deciding on appointments to the higher as well as the inferior situations of the establishment, and on the position and the remuneration of the officers. They deem this important, both for securing the due influence of the Council over the establishment, and for promoting the legitimate interests of the officers themselves, with whose merits and services the Council, being a permanent body, is likely to possess a more intimate and detailed acquaintance than will generally be possessed by the Secretary of State.

11. The Court would also suggest that the Vice-President, who is to preside over the Council in the absence of the Secretary of State, should be chosen periodically by the Secretary of State in Council, but not by the Minister alone, it being of importance that this officer should possess the confidence of the Council, and should be their representative with the Minister in the intervals of their sittings.

12. There are other provisions not connected with the functions of the Council which the Court greatly regret to see transferred from the former into the present Bill. By one of these, forming clause 29, the Governments in India itself are radically altered in constitution, and their most characteristic excellence destroyed. Instead of a Governor-General or Governor and an independent Council, appointed by the authority to which he is himself responsible, the Government is now to consist of the Governor-General or the Governor, and advisers selected by himself. The Court have reason to believe that this proposal has met with

⁹By Clause 12 of the Bill of 12 February (the first Bill).

unanimous reprobation in India, and they would regard its adoption as one of the most fatal blows which could be struck against good government in that country. The association of the head of the government with advisers not of his own choice, but chosen for him by superior authority, has given to a government, necessarily absolute, an advantage rarely possessed by absolute governments, and the absence of which in India would be peculiarly mischievous; that of free, unrestrained, and conscientious discussion and deliberation. This advantage would be entirely sacrificed if the head of the government selected his constitutional advisers. Advisers who will merely echo his own opinions he can never want; what he is in need of are advisers who will think for themselves; who by the collision of judgments will cause subjects to be examined in a variety of lights; who will correct his mistakes, complete what is imperfect in his information, and whose very errors will be useful by being of a different kind from his own. Such are not the colleagues whom, even with the best intentions, that high functionary can safely be relied on for selecting; not to mention that for some time after his first arrival he will not be in a condition to distinguish such persons, even if he looks out for them.

13. The 48th clause proposes the appointment by the Crown of an auditor of the home accounts; a provision which, if carried into effect, must materially interfere with the independent action of the new government, and the necessity of which is completely obviated by the existing system both of pre-audit and post-audit, which is recognised and apparently approved in the 47th clause of the Bill, and which system would be greatly weakened by the introduction of a distinct auditor, acting under another authority.

14. The Court regret that it should be contemplated by the 50th clause to send a Commission to India to inquire and report to Her Majesty, on many important branches of Indian administration, passing over the local governments. It is impossible that such persons, however judiciously chosen, should collect in three years a tithe of the information which already exists so abundantly on the records of the Home Government, and is daily added to by the labours of the ablest functionaries in India; while their appearance in the country will be considered as opening up for re-consideration all the vital questions included in "the collection, receipt, and management of the revenues," as well as "the application of such revenues and public moneys in India:"¹⁰ the first, embracing the whole subject of the landed tenures and proprietary and possessory rights of the agricultural population, the other, the entire economy of the public resources, whether in relation to civil or military administration, public works, the contraction or liquidation of debt, or any other of the multifarious matters which require to be decided by a finance minister. The Court are as desirous as Her Majesty's Government that all practicable and well devised improvements should be made in

¹⁰Clause 50.

these branches of administration, and many such have been, and are even now being, made; but they are convinced that the proper mode of making these improvements is through the Governments on the spot, by whose instrumentality alone India can be governed or held, and whose ascendancy it is of the utmost importance to maintain, by making all orders and all benefits which proceed from the supreme authority, flow through them as the intermediate channel.

15. The Court are also apprehensive that the effect of clause 34 may be to remove from the Military College at Addiscombe the education of cadets for the engineers and artillery. That College has, during a long course of years, been most successful in training highly qualified cadets for the scientific branches, a result greatly attributable to the earnest competition for engineer and artillery appointments which exists within the College amongst the cadets appointed to it; and the Court would consider any change which involved the transfer of the education for these branches from the Military College to private establishments as being injurious to the public service.

16. These are the observations which, by the desire of the Court, we take the liberty of submitting to your Lordship, and we hope to be favoured with a communication from your Lordship of the intentions of Ministers on the several points hereinbefore adverted to, at a sufficiently early period to admit of their taking any further measures which may be necessary for bringing their views before Parliament.

MAINE ON VILLAGE COMMUNITIES

1871

EDITORS' NOTE

Fortnightly Review, n.s. IX (1 May, 1871), 543-56. MS (frag.), Library of Congress (Miscellany of the Andrew Carnegie Papers, Box 259), is signed "J.S. Mill" and inscribed in Mill's hand: "Proof to be sent to J.S. Mill, Blackheath Park, S.E."; and in Andrew Carnegie's: "MSS. presented to / me by my friend / John Morley / Andrew Carnegie." There are compositors' stint signatures in the manuscript. Titled in *Fortnightly*: "Mr. Maine on Village Communities"; title footnoted: "*Village-Communities in the East and West: Six Lectures Delivered at Oxford*. By Henry Sumner Maine [1822-88], Corpus Professor of Jurisprudence in the University, formerly Law Member of the Supreme Government of India, author of *Ancient Law*. London [: Murray], 1871." Running titles: "Maine on Village Communities." Signed "J.S. Mill." Republished (posthumously) in *Dissertations and Discussions*, Vol. IV (London: Longmans, *et al.*, 1875), 130-53. Identified in Mill's bibliography as "A review of Maine on Village Communities in the *Fortnightly Review* for May 1, 1871" (MacMinn, 100). In the footnoted variants, "MS" signifies the manuscript, "D&D" *Dissertations and Discussions*.

Maine on Village Communities

THIS BOOK is an important contribution to a branch of knowledge in which the author is as yet unrivalled—the philosophy of the history of institutions. It pursues into ulterior developments (at least in one great department, that of property) the line of research and speculation so brilliantly commenced in *Ancient Law: its Connection with the Early History of Society, and its Relation to Modern Ideas*.¹ It is superfluous at this time of day to say anything either in the way of information or of recommendation, concerning a treatise which has already become classical; but we may remark that its title indicates the double aspect of the important vein of thought which it has opened—the historical aspect, and the practical: the light which it throws on the ancient condition of mankind, and the intimate connection which it establishes between “the early history of society” and “modern ideas,” through the connection of both of them with “ancient law,” the great transmitter (next to religion) of influences from a barbarous age to a civilised one. Political thinkers, who at one time may have been over-confident in their power of deducing systems of social truth from abstract human nature, have now for some time shown a tendency to the far worse extreme, of postponing the universal exigencies of man as man, to the beliefs and tendencies of particular portions of mankind as manifested in their history. But if so much weight is attached to these historical characteristics, it is most essential to inquire how they came to be what they are; which of them are grounded in permanent necessities of humanity, and which are but relics of facts and ideas of the past, not applicable to the present. In this point of view, the historical truths brought into so strong a light by Mr. Maine have more than an historical value. Though assuredly not written with a view to any such purpose, his *Ancient Law* is a most powerful solvent of a large class of conservative prejudices, by pointing out the historical origin not only of institutions, but also of ideas, which many believe to be essential elements of the conception of social order.

The lesson is not less instructive, when the result of the researches is to prove, not that institutions and ideas belonging to past times have been unduly prolonged into an age to which they are unsuitable, but that old institutions and ideas have been set aside in favour of others of comparatively modern origin. For this result, as much as the other, strikes at the tendency to accept the existing order of things as

¹London: Murray, 1861.

final—as an indefeasible fact, grounded on eternal social necessities. The question is opened whether the older or the later ideas are best suited to rule the future; and if the change from the one to the other was brought about by circumstances which the world has since outgrown—still more if it appears to have been in great part the result of usurpation—it may well be that the principle, at least, of the older institutions is fitter to be chosen than that of the more modern, as the basis of a better and more advanced constitution of society. A question of this nature in regard to property in land is raised by Mr. Maine's new work; which has clearly shown that the absolute ownership, which constitutes the idea of landed property as commonly conceived in England, is both modern as to time and partial as to place.

Having been called, subsequently to the publication of *Ancient Law*, to take part in legislating for a country far less widely removed than civilised Europe from that early state of society which it is usual to call "primitive," Mr. Maine found that the state of things in regard to landed property which exists in India wherever it has not been disturbed by British legislation, is strikingly in accordance with that which recent historical investigations prove to have once existed in what are now the most advanced communities. The obstinate persistence of custom in India makes that country "the great repository of verifiable phenomena of ancient usage and ancient juridical thought" (p. 22), well worth studying, therefore, by all students of human nature and history, and by all English lawyers who consider "the study of historical and philosophical jurisprudence" not alien to their pursuit. The value of Mr. Maine's book for this purpose is the greater, since much of his materials has not yet found its way into books, but is derived from the "large and miscellaneous official literature" in the records of the Indian Government, and from "the oral conversation of experienced observers who have passed their maturity in administrative office."

The inferences suggested [says Mr. Maine] by the written and oral testimony would perhaps have had interest for few except those who had passed, or intended to pass, a life in Indian office; but their unexpected and (if I may speak of the impression on myself) their most startling coincidence with the writers who have recently applied themselves to the study of early Teutonic agricultural customs, gives them a wholly new value and importance.² It would seem that light is pouring from many quarters at once on some of the darkest passages in the history of law and of society. To those who knew how strong a presumption already existed that individual property came into existence after a slow process of change, by which it disengaged itself from collective holdings by families or

²Maine mentions below Erwin Nasse (1829-90), of Bonn University, author of *Ueber die mittelalterliche Feldgemeinschaft und die Einhegungen des sechszehnten Jahrhunderts in England* (Bonn: Marcus, 1869), and Georg Ludwig von Maurer (1790-1872), of Munich University, author of *Geschichte der Markenverfassung in Deutschland* (Erlangen: Enke, 1856), *Geschichte der Fronhöfe, der Bauernhöfe und der Hofverfassung in Deutschland* (Erlangen: Enke, 1862-63), and *Geschichte der Dorfverfassung in Deutschland* (Erlangen: Enke, 1865-66).

larger assemblages, the evidence of a primitive village system in the Teutonic and Scandinavian countries had very great interest; this interest largely increased when England, long supposed to have had since the Norman Conquest an exceptional system of property in land, was shown to exhibit almost as many traces of joint ownership and common cultivation as the countries of the north of the Continent; but our interest culminates, I think, when we find that these primitive European tenures and this primitive European tillage constitute the actual working system of the Indian village communities, and that they determine the whole course of Anglo-Indian administration. (Pp. 61-2.)

The ancient Teutonic cultivating community, as it existed in Germany itself, appears to have been thus organised. It consisted of a number of families, standing in a proprietary relation to a district divided into three parts. These three portions were the Mark of the Township or Village, the Common Mark or waste, and the Arable Mark or cultivated area. The community inhabited the village, held the Common Mark in mixed ownership, and cultivated the Arable Mark in lots appropriated to the several families. (P. 78.)

Of these the Village Mark was the only one of which the several portions were individual property in the modern English sense. The ownership of the Common Mark was "a strict ownership in common, both in theory and in practice. When cattle grazed on the common pasture, or when the householder felled wood in the common forest, an elected or hereditary officer watched to see that the common domain was equitably enjoyed." (P. 79.) But it will be more of a surprise to many readers to learn that the arable land also was held and cultivated on the same principle of common ownership. The Arable Mark "seems always in theory to have been originally cut out of the Common Mark, which, indeed, can only be described as the portion of the village domain not appropriated to cultivation" [p. 79]; and the Arable Mark "was occasionally shifted from one part of the general village domain to another" (p. 81).

The cultivated land of the Teutonic village community appears almost invariably to have been divided into three great fields. A rude rotation of crops was the object of this threefold division, and it was intended that each field should lie fallow once in three years. . . . Each householder has his own family lot in each of the three fields, and this he tills by his own labour, and that of his sons and his slaves. But he cannot cultivate as he pleases. He must sow the same crop as the rest of the community, and allow his lot in the uncultivated field to lie fallow with the others. Nothing he does must interfere with the right of other households to have pasture for sheep and oxen in the fallow and among the stubbles of the fields under tillage. (Pp. 79-80.)

The evidence seems to show "that the original distribution of the arable area was always into exactly equal portions, corresponding to the number of free families in the township. Nor can it be seriously doubted, upon the evidence, that the proprietary equality of the families composing the group was at first still further secured by a periodical redistribution of the several assignments." (P. 81.) This periodical redistribution has continued to our own day in the Russian villages, and "there appears to be no country inhabited by an Aryan race" in which traces of it do not remain [p. 82].

It is to "the school of German writers, among whom Von Maurer is the most

eminent" (p. 21), that we are indebted for the establishment of this important portion of the ancient history of society in relation to the Teutonic countries. Its extension to England is mainly the work of Professor Nasse, of Bonn, whose valuable treatise is about to be made, by translation, conveniently accessible to the ordinary English reader.³ But the simple statement of the ancient practice of Teutonic cultivation brings at once to the mind of any one acquainted with English rural usages, the traces of a similar village constitution in England. The remains of the former collective ownership of the lands of a village still linger among us under the denominations of Common Fields and Lammas lands.

Our law books trace all landed tenures in England to a feudal grant. From such grant, either actual or presumed, they all technically proceed; and the law writers seldom trouble themselves with anything anterior. But there were landed possessions and landed rights in England before there was feudality. The feudal lords were the successors of former holders; and in order to know what the lord could either claim for himself or grant to others, it is necessary to know whose rights he succeeded to. In this there is now no obscurity. The feudal lord took the place of the collective village community; the Mark system passed by transformation into the Manorial. The rights which had belonged to the village as a collective body, became the rights of the lord; the customary rights which the several households of the village could claim from the collective body, were not lost, but remained valid against the lord. The Common Mark became the lord's waste; but the village families retained their rights of pasture and of turf or wood cutting over it. Of the Arable Mark, a great though a gradually decreasing portion continued to be cultivated under much the same rules as before.

The lands which represent the cultivated portion of the domain of the ancient Teutonic village communities are found more or less in all parts of England, but more abundantly in some counties than in others. They are known by various names. When the soil is arable, they are most usually called "common," "commonable," or "open" fields, or sometimes simply "intermixed" lands. When the lands are in grass, they are sometimes known as "lot meadows," sometimes as "Lammas lands," though the last expression is occasionally used of arable soil. The "common fields" are almost invariably divided into three long strips, separated by green baulks of turf. The several properties consist in subdivisions of these strips, sometimes exceedingly minute; and there is a great deal of evidence that one several share in each of the strips belonged originally to the same ownership, and that all the several shares in any one strip were originally equal or nearly equal, though in progress of time a good many have been accumulated in the same hands. The agricultural customs which prevail in these common fields are singularly alike. Each strip bears two crops of a different kind in turn, and then lies fallow. The better opinion seems to be that the custom as to the succession of crops would not be sustained at law; but the right to feed sheep or cattle on the whole of one strip during the fallow year, or among the stubbles of the other two strips after the crops have been got in, or on the green baulks which divide the three fields, is generally treated as capable of being legally maintained. This right has in some cases passed to the

³It appeared later in 1871 as *On the Agricultural Community of the Middle Ages, and Inclosures of the Sixteenth Century in England*, trans. H. A. Ouvry (London: Macmillan).

lord of the manor, but sometimes it is vested in the body of persons who are owners of the several shares in the common fields. The grass lands bear even more distinct traces of primitive usage. The several shares in the arable fields sometimes, but very rarely, shift from one owner to another in each successive year; but this is frequently the rule with the meadows, which, when they are themselves in a state of severalty, are often distributed once a year by casting lots among the persons entitled to appropriate and inclose them, or else change from one possessor to another in the order of the names of persons or tenements on a roll. As a rule, the inclosures are removed after the hay harvest; and there are manors in which they are taken down by the villagers on Lammas day (that is, Old Lammas day) in a sort of legalised tumultuary assembly. The group of persons entitled to use the meadows after they have been thrown open is often larger than the number of persons entitled to inclose them. All the householders in a parish, and not merely the landowners, are found enjoying this right. The same peculiarity occasionally, but much more rarely, characterises the rights over common arable fields; and it is a point of some interest, since an epoch in the history of primitive groups occurs when they cease to become capable of absorbing strangers. The English cultivating communities may be supposed to have admitted new-comers to a limited enjoyment of the meadows, up to a later date than the period at which the arable land had become the exclusive property of the older families of the group. (Pp. 85-7.)

The minutely exact agreement of this description with what has been ascertained by quite independent evidence to have been the ancient custom of village communities in the countries from which our ancestors came, leaves no doubt that originally ownership of land was conceived in the same manner in both cases. And the rights which still survive in our own country over the lands which were once the collective property of the village—the rights of commoners over the common land, and of those who are entitled to the joint use of Lammas lands or common fields—are older than any manorial rights, older than any grants from a feudal ^a superior, and can claim more of the sacredness which the friends of existing land institutions consider to attach to prescription.

How dear these rights were to the people is strikingly shown by their persistency through many centuries, notwithstanding the powerful causes which have been at work during the whole time for their destruction. Beneficent and noxious influences conspired to favour the conversion of collective into individual property. On the one hand, the rigid customs which prevailed in the cultivation of the common fields provoked opposition by their tendency to perpetuate a bad system of agriculture; and as to the waste, then occupying so large a portion of the soil of the island, it was thought to be for the public good to promote almost any arrangement by which it could be brought into cultivation. This was the honourable side of the movement. There is a deeply disgraceful side which remains to be mentioned. The great landed proprietors, and owners of manorial rights, were the rulers of the country. From 1688 downwards they ruled it through the Parliament; but before the Parliament became absolute ruler of the State, each of them ruled his own neighbourhood with a power almost above legal control.

^a[the manuscript fragment, which runs to the end of the essay, begins here]

Among the consequences were perpetual encroachments by the great landholders, not only on the customary rights of the people in the land, but even on their separate properties: encroachments sometimes by abuse of the processes and forms of law, sometimes altogether lawless.^b In the words of the great Sir Thomas More, tenants were “got rid of by force or fraud, or tired out by repeated injuries into parting with their property.” Bishop Gilpin “complained that the great landowners scrupled not to drive people from their property, alleging that the land was theirs, and turning them out of their shelter like vermin.”* When even the separate properties of the peasantry were thus treated, no wonder that their rights of common were taken from them, in many cases without any compensation.^b This dreary history is not to be found in Mr. Maine’s work, but it has been related in other books, and recently by Mr. Cliffe Leslie, in his instructive volume on the *Land Systems of England, Ireland, and the Continent*.

Yet, notwithstanding the constant tendency of these customary rights to extinction, sometimes by usurpation and sometimes by voluntary agreement, the great extent of them as late as the early part of the present century is attested by Marshall, a writer of that period, of high authority on the statistics of agriculture, and whose facts have been largely used in the work of Professor Nasse. According to Marshall, “In almost all parts of the country, in the Midland and Eastern counties particularly, but also in the west—in Wiltshire, for example—in the south, as in Surrey, in the north, as in Yorkshire,” there were still, in his time, “extensive open and common fields. Out of 316 parishes in Northamptonshire, 89” were in this condition; “more than 100 in Oxfordshire; about 50,000 acres in Warwickshire; in Berkshire, half the county; more than half of Wiltshire; in Huntingdonshire, out of a total area of 240,000 acres, 130,000 were commonable meadows, commons, and common fields.” (Maine, pp. 88-9.)⁴ Mr. Maine adds: “The extent of some of the fields may be inferred from the fact, stated to me on good authority, that the pasturage on the dividing baulks of turf, which was not more than three yards wide, was estimated in one case at 80 acres” (p. 89). Since that time the commonable and common lands have undergone constant and rapid diminution, first by private Acts of Parliament, and at a still more accelerated pace since 1836, by inclosure, agglomeration, and exchange, under the Common Fields

**Land Systems and Industrial Economy of Ireland, England, and Continental Countries* [London: Longmans, Green, 1870], by Thomas Edward Cliffe Leslie [1826-82], p. 216 [quoting from Thomas More (1478-1535), *Utopia* (in Latin 1516), trans. Ralph Robinson (London: Vele, 1551), not paged; and Bernard Gilpin (1517-83), “A Sermon,” in George Carleton, *The Life of Bernard Gilpin* (London: W.I. and T.P., 1636), p. 292.]

⁴The statistics from William Marshall (1765-1818), *A Review (and Complete Abstract) of the Reports to the Board of Agriculture; from the Midland Department of England* (York: Longman, et al., 1815) and *idem*, . . . *from Southern and Peninsular Departments of England (idem)*, are taken by Maine (in his own translation) from Nasse, *Ueber die mittelalterliche Feldgemeinschaft*, p. 4.

^{b-b}-MS [one of JSM’s characteristic marks for insertion appears, but the passage is lacking]

Inclosure Act of that year,⁵ and under the general powers of the Inclosure Commissioners,⁶ “but both common fields and common meadows are still plentiful on all sides of us. Speaking for myself personally,” says Mr. Maine, “I have been greatly surprised at the number of instances of abnormal proprietary rights, necessarily implying the former existence of collective ownership and joint cultivation, which comparatively brief inquiry has brought to my notice.” (Pp. 87-8.)

It was not Mr. Maine’s business, in a purely historical and jurisprudential work, to deduce practical inferences from these facts; nor have we any knowledge^c whether he would coincide in the inferences which we ourselves draw from them. But there are certain truths, of a very important character, which the facts we have abridged from Mr. Maine’s work seem to us to support and illustrate very impressively.

They show, first, that even in our own history property in land has not been, and is not, one simple idea, one conception of rights always the same; but that different systems of property in land have existed, and even coexisted, both in this and in other countries; and that, by an operation not sudden, but extending over our entire history since the Norman Conquest, we have been gradually transforming one of these systems into another:

That the system under which nearly the whole soil of Great Britain has come to be appropriated by about thirty thousand^d families—the far greater part of it by a few thousands of these—^d is neither the only nor the oldest form of landed property, and that there is no natural necessity for its being preferred to all other forms:

That if the nation were to decide, after deliberation, that this transmutation of collective landed ownership into individual shall proceed no further, and that the various rights of the public or of particular neighbourhoods which in many cases still limit the absolute and exclusive control of the land by the proprietor—rights generally of older date than his—shall no longer be allowed to be extinguished, to the detriment of posterity; the nation, in so deciding, would not overpass the limits of its moral right. Nay, further, that if the nation thought proper to reverse the process, and move in the direction of reconverting individual property into some new and better form of collective, as it has so long been converting collective property into individual, it would be making a legitimate use of an unquestionable moral right; subject to the moral obligation which arises whenever rights sanctioned by established law are annulled by an act of authority, of satisfying all just claims to compensation:

That, having thus a full right to retrace the steps which it has taken under the

⁵6 & 7 William IV, c. 115.

⁶Established by 8 & 9 Victoria, c. 118 (1845).

^cMS of

^{d-d}MS families, and the . . . these,

predominant influence of the class of large landed proprietors, the nation ought to take into serious consideration which among the many footings on which the right of landed ownership might be placed, is the one most beneficial to the whole community, with a view to adopting, with the precautions justly demanded by vested interests, that most beneficial system. And, in the meantime, it should absolutely suspend all further proceedings in the old direction—all further conversion into the absolute property of individuals, of land which is now only their limited or qualified property, or which is not the private property of individuals at all. In particular, the inclosure of commons should be absolutely discontinued, until the principles on which it can rightly take place have been deliberately reconsidered, the classes who have been the chief sufferers by what has hitherto been done being included in the deliberation. ^e

This is the moral which we deduce from that part of Mr. Maine's researches which relates to the ancient landed institutions of England. The part which relates to India gives a practical warning of an even more urgent nature; since it shows that we have done, and are still doing, irreparable mischief, by blindly introducing the English idea of absolute property in land into a country where it did not exist and never had existed, and into which its introduction could only be effected by trampling upon the rights of all except some one of the classes which, by the customs of the country, shared among them the right of using and disposing of the soil. This injustice has been done by the English rulers of India, for the most part innocently, from sheer inability to understand institutions and customs almost identical with those which prevailed in their own country a few centuries ago.

In the purely native governments of India, property in land has never emerged from that primitive state in which absolute and unconditional ownership by individuals had no existence. Various beneficial interests existed in the soil. There was, first, the interest of the sovereign, who had at least one attribute of an universal proprietor; he was an universal receiver of rent. The share of the produce to which he was entitled, and which formed the bulk of the public revenue, was nominally limited by custom, but practically, in most cases, only by the impossibility of extracting more. Whether we call it rent or land-tax, it was usually of such an amount as to leave no surplus to constitute rent in the hands of any private individual, except those to whom, by a not uncommon act of favour, the sovereign made a grant of the revenues of a village or district. At the opposite extremity of the social scale were the actual cultivators. In some cases the whole of these, in others only certain classes of them, had a right to retain their holdings as long as they paid the Government demand. Between these co-proprietors (as they may be called), the sovereign and the cultivator, there were intermediate classes who had rights, of greater or less extent, and who were often extremely different in

^e[below this JSM has written (white line) to signal the line space]

different places. But there was nobody who could be called a proprietor in the absolute sense of English law. The English, however, when they came into possession of the Bengal provinces, assumed, as indisputable, that there must be an absolute proprietor of all land, the only question being how to find him; and the indication of ownership by which they were at first guided was the collection of rent. In the provinces over which the British dominion was first extended, this attribute was exercised by officers of Government, each of whom, at the head of an armed force, collected the rents of a particular district; and who were mostly hereditary, for all things tend to become hereditary in the East. In these officers the English rulers thought they had found the proprietors of the soil. It was not considered, that these collectors of rent were bound to pay over the whole of their collections to the State, except a commission of ten per cent deducted as their own remuneration. In spite of this, they were declared absolute owners of the land, and received a pledge that the Government demand of revenue from them should never be increased. The cultivating classes became their tenants. A reservation was made of the right of the tenants to be protected against eviction while they paid the customary rents; but the distance and expensiveness of the only courts of justice which for a long time were provided, put it out of the power of the cultivators to enforce this right. In the words used many years later by a British-Indian judge, the rights of the Bengal ryots (or peasants) passed away *sub silentio*.⁷ They sank generally into the miserable condition of Irish cottiers—rack-rented tenants-at-will. What little respect was anywhere paid to their rights or interests resulted solely from the still partially surviving influence of custom on the minds of persons whom the law had exempted from any necessity of observing it.

By degrees India began to be better known, and its English administrators came to be aware of the error which they had at first committed. They found that, in mistaking the collectors of revenue for the landed proprietors, they had overlooked the village communities; which, indeed, in the provinces first acquired, had almost become extinct, but in many of the more recently acquired British possessions still retained a substantial existence, and whose rights in the land could not without great injustice be ignored. The conclusion which was come to by the administrators of these later acquisitions was that the village communities were the real proprietors. And it is certain that, in adopting this opinion, they were nearer to the truth than they would have been in supposing absolute ownership to reside anywhere else. Further experience, however, made them aware that village communities were of very various composition, and that they, no more than any other persons or bodies, were absolute proprietors. Their rights, like those of all others in a country in which custom for the most part decides what is the law, were limited and hemmed in by the equally positive customary rights of other people. When this truth dawned on the most eminent Indian administrators, it taught them

⁷Francis Rawdon-Hastings; see p. 95 above.

at first the proper lesson. They made it their business to ascertain, by oral and documentary evidence on the spot, not who was proprietor of the soil—a question idle and unmeaning in the country with which they had to deal—but who were all those who had any rights over it, and what those rights were. When they had, with more or less completeness, ascertained this, they endeavoured to give equal protection to all these rights. These rational opinions and rational practices prevailed in the counsels of the Indian Government for about two generations. But of late official opinion has taken an unfortunate turn in the opposite direction.

In England, for some time past, the idea of absolute property in land has been sensibly weakened, and the tendency of the time is progressively inclining towards the opinion that proprietary rights in the mere raw material of the globe should not be absolute, but limited. While, however, English opinion has thus been advancing, official opinion in India, which had been much ahead of it, has retrograded. The change may be roughly dated from the time of the Mutiny. The feeling engendered by that calamitous event, of the unstable foundation on which our power in India rested, produced a strong impression of the necessity of conciliating the natives; and, as usual in such cases, “the natives” were taken to mean those small classes who were most conspicuous, who had the greatest opportunities of making themselves heard, and the greatest power of being troublesome. Before the Mutiny it had been the policy of our Government, not certainly to ignore or disregard the rights or vested interests of the so-called higher classes, but to construe them strictly, when they conflicted with the interests of the mass of the cultivating population, towards whom, it was rightly thought, were the first and most binding duties of our Government. Since the Mutiny a reaction has set in, which cannot be better illustrated than by the instance of Oude. We had taken this province from its Mahomedan Government and annexed it to British India,⁸ in consequence of the anarchy occasioned by the lawless usurpations and disorderly excesses of the Talookdars—a class of functionaries of very various origin, who collected the Government dues from large districts, and entertained for that purpose bodies of undisciplined mercenaries, which made them practically uncontrollable by the feeble native government. By means of these troops the country was kept in a state of bloodshed and warfare, the most high-handed violence was practised towards the people of the country, and the landed possessions of the Talookdars were swelled by the dispossession, and sometimes the extermination, of entire families of landholders. These Talookdars were naturally exasperated by the annexation, which deprived them of their misused position; they joined, and they were the only powerful class or body in all India that did join, with the mutineers. We subdued them, and what did we then proceed to do? We admitted these rebellious oppressors to engage with our Government for

⁸See “Draft of Treaty between the East India Company and the King of Oude,” *PP*, 1856, XLV, 597-9 (never signed by the King of Oude, but acted on by the British).

the revenue; we declared them proprietors of the soil, and delivered over the cultivating classes into their hands: and it is with great difficulty that, some years after, an Act was got passed, making some small reparation to a portion of the dispropertied classes, by giving to tenants who could prove a certain number of years' possession a guarantee against eviction.⁹ In other parts of Upper India, those to whom the absolute ownership has been conceded are the village communities; but there has been a growing disposition to restrict, instead of enlarging, the number of the inhabitants who are considered entitled to communal privileges. Even at an earlier period, single families from which by custom the headman of the village had been taken, had not unfrequently been recognised by our Government as sole owners. The remainder of the cultivators, including many who at the first settlement had been admitted, as proprietors, to enter into engagements for the Government revenue, have been reduced to the condition of tenants-at-will. There is great danger that if this tendency of opinion continues, the whole of the northern provinces* will be possessed, for the first time in India, by a comparatively small body of absolute owners, many of them peasants, with a vast population under them of tenants-at-will. And this—one of the greatest social revolutions ever effected in any country, with the evil peculiarity of being a revolution not in favour of ^fa^f majority of the people, but against them—its supporters defend in the name of civilisation and ^s political economy; though if there is a truth emphatically taught by political economy, and from which no one who has the smallest tincture of the knowledge of it withholds his assent, it is that the status of an agricultural tenant-at-will is intrinsically vicious, and in a really civilised community ought not to exist.

The exposition given by Mr. Maine of the real nature and history of agricultural customs in India, read, as it is sure to be, by all intelligent Indian administrators, and, we trust, by those who are in training for Indian administration, is well adapted to check this baneful reaction. We quote, both as a characteristic specimen of this part of the work, and for the important lessons it affords, his exposition of

⁹Act X of 1859 (29 Apr.).

*The statement is limited to the northern provinces, because in the south of India, with the exception of certain districts, a different system of land revenue has been adopted, and a different interpretation given to landed rights. "In the southern provinces of the peninsula the English Government" early "began to recognise nothing between itself and the immediate cultivators of the soil, and from them it took directly its share of the produce. The effect was to create a peasant proprietary. This system, of which the chief seat was the province of Madras," but of which the most improved form is to be found in the Presidency of Bombay, "has in my opinion," says Mr. Maine, "been somewhat unjustly decried. Now that it has been modified in some details, and that some mistakes first committed have been corrected, there is no more prosperous population in India than that which has been placed under it; but undoubtedly it is not the ancient system of the country." (Pp. 105-6.)

^fMS the

^sMS of

the manner in which, even in the absence of positive intention on our part, the introduction of our Government conferred upon those whom we recognised as representatives of the locality, powers and rights which enabled them to override those who were their co-partners in the land.

Let us suppose a province annexed for the first time to the British Indian Empire. The first civil act of the new Government is always to effect a settlement of the land revenue; that is, to determine the amount of that relatively large share of the produce of the soil, or of its value, which is demanded by the sovereign in all Oriental states, and out of which all the main expenses of government are defrayed. Among the many questions upon which a decision must be had, the one of most practical importance is, "Who shall be settled with?" With whom shall the settlement be made? What persons, what bodies, what groups, shall be held responsible to the British Government for its land revenue? What practically has to be determined is the unit of society for agrarian purposes; and you find that, in determining it, you determine everything, and give its character finally to the entire political and social constitution of the province. You are at once compelled to confer on the selected class powers coextensive with its duties to the sovereign. Not that the assumption is ever made that new proprietary powers are conferred on it; but what are supposed to be its rights in relation to all other classes are defined; and in the vague and floating order of primitive societies, the mere definition of a right immensely increases its strength. As a matter of fact, it is found that all agrarian rights, whether superior or subordinate to those of the person held responsible to Government, have a steady tendency to decay. . . . Do you, on entering on the settlement of a new province, find that a peasant proprietary has been displaced by an oligarchy of vigorous usurpers, and do you think it expedient to take the Government dues from the once-oppressed yeomen? The result is the immediate decline, and consequently bitter discontent, of the class above them, who find themselves sinking to the footing of mere annuitants on the land. Such was the land-settlement of Oudh, which was shattered to pieces by the Sepoy Mutiny of 1857, and which greatly affected its course. Do you, reversing this policy, arrange that the superior holder shall be answerable to Government? You find that you have created a landed aristocracy which has no parallel in wealth or power except the proprietors of English soil. Of this nature is the more modern settlement of the province of Oudh, only recently consummated; and such will ultimately be the position of the Talookdars, or Barons, among whom its soil has been divided. Do you adopt a policy different from either of those which I have indicated, and make your arrangements with the representative of the village community? You find that you have arrested a process of change which was steadily proceeding. You have given to this peculiar proprietary group a vitality which it was losing, and a stiffness to the relations of the various classes composing it which they never had before. (Pp. 149-51.)

Whether the Indian village communities had wholly lost their capacity for the absorption of strangers when the British dominion began, is a point on which I have heard several contradictory opinions; but it is beyond doubt that the influence of the British Government, which in this respect is nothing more than the ordinary influence of settled authority, has tended steadily to turn the communities into close corporations. The definition of rights which it has effected through its various judicial agencies—the process of law by which it punishes violations of right—above all, the money value which it has given to all rights by the security which it has established from one end of India to another—have all helped to make the classes in possession of vested rights cling to them with daily increasing tenacity. To a certain small extent this indirect and unintended process of shutting the door to the acquisition of new communal rights has been counteracted by a rough rule introduced by the

English, and lately engrafted on the written law, under which the cultivator of the soil who has been in possession of it for a period of years is, in some parts of India, protected against a few of the extreme powers which attach to ownership of the modern English type. But the rule is now in some discredit, and the sphere of its operation has of late been much curtailed. And my own opinion is that even if the utmost effect were given to it, it would not make up for some of the inequalities of distribution between classes actually included in the village group, which have made their way into it through the influence of economical ideas originating in the West. On the whole, the conclusion which I have arrived at concerning the village communities is, that, during the primitive struggle for existence, they were expansive and elastic bodies, and these properties may be perpetuated in them for any time by bad government. But tolerably good government takes away their absorptive power by its indirect effects, and can only restore it by direct interposition. (Pp. 166-8.)

These passages, greatly as space has made it necessary to curtail them, will help to show to the intelligent reader (over and above the example they afford of the singularly artificial and variable nature of the idea of ownership) what great difficulties the English Government has to encounter in endeavouring to do justice to each and all in India: and how great injustice may be, and has been, caused by the fact that its mere appearance on the scene destroys the balance of existing social relations; that "when an official appointed by a powerful Government acts upon the loose constitution of a primitive society, he crushes down all other classes, and exalts that to which he himself belongs" (p. 151).

Our desire to profit, as much as our space permits, by the practical lessons derivable from Mr. Maine's book, has led to our doing but scanty justice to its remarkable merits, both as a literary work and as a series of investigations of the ancient history of human society. But we must at least not omit to call attention to the concluding lecture;¹⁰ in which, from the facts of Indian experience, a flood of light is thrown upon the ideas of an early state of society respecting commercial transactions between man and man, and especially respecting prices and rents; and upon the widespread and long-enduring influence of custom in the determination of payments, as well as upon the particular points at which competition, as a rival principle, first comes in. Our space does not admit of our giving a summary of this lecture, and we can only refer the reader to the original, confidently promising to any one who studies it a rich reward.

The same hindrance prevents us from doing more than merely referring to the very few points on which we find ourselves dissenting in any respect from Mr. Maine, and which are questions of definition and classification rather than of fact. Did space permit, we should have something to say in behalf of Bentham and Austin¹¹ (of whose extraordinary merits as philosophic jurists Mr. Maine shows a full appreciation) on a point on which Mr. Maine differs from them (pp. 67-8);¹²

¹⁰"The Early History of Price and Rent," pp. 173-201.

¹¹John Austin (1790-1859), early teacher and friend of Mill, and disciple of Bentham.

¹²Maine holds that the customary law of Indian village communities does not fit Bentham and Austin's definition of law as a command by a political sovereign enforced by a sanction.

and again, in defence of political economists generally, ^hagainst^h a charge brought against them in the concluding lecture (p. 196), which we do not think will stand examination.¹³ But these small differences of opinion, though worth noting, are not, at least on the present occasion, worth entering into; and we will conclude by once more congratulating our readers and ourselves on the appearance of a second highly instructive work (to be followed, we hope, by many others) from an author so eminently qualified for the department of philosophical history which he has made his especial domain.

¹³Maine argues against the universality of the law of markets, asserting that it began to operate only when people met to trade at arm's length rather than as members of a unified group.

^h-^hD&D in regard to

APPENDICES



Bengal Political Department

answers India Political Department
 Answer to Letter } Dated 7th April 1824
 dated 15th January 1820
 (The first part of this Draft was written by Mr McCulloch)

Answer to Letter } Dated 25th June 1824
 dated 17th March 1820

Answer to Letter } Dated 10th November 1824
 dated 29th March 1820

Answer to Letters } Dated 6th April 1825
 dated 8th July 1820
 21st October 1820
 20th January 1821
 23rd November 1821
 18th December 1821
 6th March 1822
 15th March 1822

Answer to Letters } Dated 9th November 1825
 dated 24th April 1823
 9th May 1823

Answer to Letters } Dated 15th March 1826
 dated 17th June 1823
 31st July 1823

Answer to Letter } Dated 19th April
 dated 12th September 1823

First page of Mill's list of his despatches
 (IOR: MSS Eur B 405)

149

25th February 1875
1175

Bengal
Public Department.

Our Governor-General in Council
at Fort William
in Bengal.

Comdants
11 Feb 1875

have before the Council
at this, forward to the
for consideration.

The Council of the
No. 1000
(3 vols of
Supplement)
257 Pages

Our last Letter to
you in this Department,
was dated the 18th inst
We now proceed
to reply to Paras. 4, 6, & 7
of your Public Letter dated
1st

First page of Mill's first despatch
(IOR: Dr 246, E/4/711; see App. A, No. 1)

Public 25th February 1824

1177

Commanders of Ships

were in the habit of
pressuring crews through
the intervention of
Officers Serangs, who
were guilty of gross
abuses and irregularities.

Can Budge
11 Feb 1824
Coast 13th Feb
1824

During the same
period the wilful
burning of Ships by
Seamen whose Wages
had been advanced
to them, was by no
means an uncommon
offence.

Part of third paragraph of Mill's first despatch
(IOR: Dr 246, E/4/711; see App. A, No. 1)

*India
Public Department.*

*Recent changes in
Native Education.*

*I believe your plan for the
of the
to
will be*

*14. Collection in 16 volumes & Supplement to
Vol. 1. - 2869 pages.*

Title page of Mill's rejected draft on Native Education (IOR: PC 1828, L/P&J/1/92; see App. A, No. 1578X)

progression already far
greater under the existing
system, than the most
sanguine could have
anticipated we cannot
but consider it in the
highest degree imprudent
to expose to risk what
had thus been gained
by an innovation which
that very success had
shown to be unnecessary.

13 M^r. Macaulay we
observe considers it as demonstrated
first that the people are eager
for English tuition; and secondly
that they are altogether indifferent
to Oriental learning. If these
propositions were true, in the
comprehensive sense imagined
by that Gentleman, the measures
which you have adopted might
be unattended with risks. The
first however of M^r. Macaulay's
assertions is presented in an
altogether different light, and
the latter altogether denied, by
those Members of the Committee
who have the longest
experience

It is contending
measures
to enter into
a controversy
with him
It is said

such claims.

8 The state of
Affghanistan is
apparently becoming
more and more
unsettled, but the

A
any observations
which it may be
thought proper to make
on this subject will
be addressed to you
by the Secret Committee

quite proper
M

formation of political
relations with any
of the Chiefs, would
at present, not
be desirable. No

approve ~~of~~ of
the intimation you
have made to Shah
+ the King of Cabul Shooja that if he
makes any further
attempt

Part of paragraph 8 of draft despatch on states on and beyond the Indus (IOR: PC 2114, L/P&S/6/310; see App. A, No. 182)

[322]

PC 2114. No. 11. March 1858
Returned 24 April 1858

Pl
Came up as Staff to 15/5/58
May 1858
India

As laid in your
right in being an
Committee about
Alphonso and the
nature of the
Secret Committee
P. S. P.

This PC refers to some
important transactions
decided nothing in the
1858 to 1859
States on, and beyond

the Indus.

See Review by
Secretary and
additional
27/1/1858

The final page of draft despatch on states on and beyond the Indus (IOR: PC 2114, L/P&S/6/310; see App. A, No. 182)

Appendix A

Check List of Mill's Indian Despatches

(1823-58)

INDIA OFFICE LIBRARY AND RECORDS, BRITISH LIBRARY. Official copies of the Indian despatches drafted by Mill in the Examiner's Office of the East India Company exist normally in several different forms in the archives of the Company and of the Board of Control. There are two main relevant series, identified as E/4/612-1112 and L/P&S/6/233-399. A full account of the main stages in the drafting process will be found in the Introduction, xxiii-xxix above.

The E/4 series, Despatches to Bengal, India, Madras, and Bombay (1743-1858), comprise the Company's copies of the official drafts of all non-secret despatches, bound in order of date within carefully paginated volumes. Each document clearly shows, in addition to the final date of the despatch, any alterations made to the text of the draft by (a) the appropriate supervising committee of the Company's Court of Directors, (b) the Court itself, and (c) the government's Board of Control. Changes made by the Board at the earlier unofficial "Previous Communication" stage (PC) are not, however, shown on the E/4 documents, though occasionally signs of such alterations can be detected. From about 1835 onwards Mill's signature or initials often appear in pencil on the first page of those drafts for which he was originally responsible. In all cases the draft and despatch numbers are entered on the individual document, though the latter were assigned only from 1830 onwards. In most instances the earlier PC numbers are also given.

The L/P&S/6 series, Political and Foreign Previous Communications and Drafts (1811-58), originally part of the archives of the Board of Control, are specially important because they incorporate the only surviving set of the Political and Foreign Departments' PCs. They also include copies of the corresponding official drafts that were usually submitted by the Company to the Board some weeks after the completion of the unofficial exchanges. Further, the series contains (a) a variety of internal memoranda prepared by the Board's officials who regularly scrutinized the Company's PCs and drafts, and (b) related correspondence

between Company and Board officials, including some original notes written by Mill to explain specific points connected with the PCs for which he was responsible. In all cases the L/P&S/6 records also show in considerable detail which portions of the PCs and the drafts were altered by the Board, and why. In general the PCs are bound before the later official drafts, but the internal arrangement of the contents of the volumes in the series varies considerably, and the pagination is often irregular. Finally, it should be noted that the PCs for other departments of the Indian correspondence (e.g., Public, Public Works, etc.) were for the most part destroyed by the India Office during the 1860s.

The identification of the despatches drafted by Mill is greatly facilitated by a list he kept covering the years 1824-58. This now forms a separate volume in the European Manuscripts section of the India Office Records (MSS Eur B405, formerly identified as Home Miscellaneous 832). Mill evidently compiled the list in the course of his long period in the Examiner's Office (see the Introduction, xii-xxxix). The list is divided into sections covering the despatches sent to the main India governments in particular departments, starting with despatches sent to the Government of Bengal/India in the Political Department. Within each section the order of entries is determined not by the date of the despatch but evidently according to the date when Mill himself originally drafted the document. The entries briefly record the subject-matter, the final date and number of the despatch, and the dates of the letters from India to which the despatch replies. No PC or draft numbers are given by Mill. Mill's list does, however, also include some 44 crossed-out entries. Some of these are of no real significance (e.g., entries for despatches to Bombay initially put by mistake in the India section of his list). Others are of considerable interest, especially those which seem to refer to drafts originally written by Mill, but which were so drastically altered by the Board of Control at the Previous Communication stage that he evidently decided to withdraw them from the list of his own despatches. In a few other cases the crossed-out entries refer to PCs which were for some reason subsequently cancelled by the Board and never actually issued as despatches to India.

In general, Mill's original list provides an accurate and almost comprehensive record of the drafts he prepared. Many entries are confirmed by his pencilled signature or initials which, as noted above, appear on the first pages of many of the E/4 copies. Some entries are also confirmed by other evidence in the L/P&S/6 documents, and by Mill's list of his published writings in the Mill-Taylor Collection, British Library of Political Science and Economics (see Appendix B below), which gives references to those parts of his despatches printed in *Parliamentary Papers*. However, there are at least ten despatches in the E/4 volumes, dated between 1841 and 1853, which also bear Mill's signature or initials, but are not listed in MSS Eur B405.

The Checklist below consists of an edited and expanded version of Mill's own list (Nos. 1-1702), plus the additional draft despatches by him that are omitted from that list (Nos. 1703-13). The order of entries in Mill's list has been strictly

adhered to since, as explained above, it apparently reflects the order in which he originally drafted the documents. However, for ease of reference, the entries themselves, unnumbered in the original) have been assigned numbers in a continuous sequence. The Government/Department sections within the Checklist are:

- Bengal/India Political Department: Nos. 1-800
- Madras Political Department: Nos. 801-98
- Bombay Political Department: Nos. 899-1512
- Bengal Foreign Department: Nos. 1513-14
- India Foreign Department: Nos. 1515-21
- Madras Foreign Department: Nos. 1522-36
- Bengal Public Department: Nos. 1537-75
- India Public Department: Nos. 1576-85
- Madras Public Department: Nos. 1586-1604
- Bombay Public Department: Nos. 1605-30
- India Public Works Department: Nos. 1631-66
- Madras Public Works Department: Nos. 1667-71
- Bombay Public Works Department: Nos. 1672-8
- Bengal Ecclesiastical Department: Nos. 1679-80
- Madras Ecclesiastical Department: Nos. 1681-5
- Bombay Ecclesiastical Department: Nos. 1686
- Bombay Marine Department: Nos. 1687-91
- Bengal Law Department: No. 1692
- India Financial Department: No. 1692X
- Bombay Commercial Department: Nos. 1693-4
- Prince of Wales Island General Department: Nos. 1695-1702

The entries under these headings normally take the following form: date of despatch, subject description, and identifying and locating references. The despatch date refers to the date on which the Company's directors approved and signed the document. The subject descriptions, in view of the complexity of the subjects treated, are necessarily very brief. Usually they refer merely to the geographical area covered (e.g., Hyderabad) or the name of the person to whose case the despatch relates. Subject descriptions are omitted when the despatch deals with miscellaneous topics too numerous and varied to be summarized adequately. The identifying references are given for the Previous Communication (PC), official draft (Dr), and final despatch (D). When no PC numbers are shown, it may be inferred that the documents were not in fact sent to the Board of Control as PCs prior to their official submission as drafts. Separate despatch (D) numbers were assigned by the East India Company only from 1830 onwards. The locating references to the E/4 and L/P&S/6 series, where the documents now are bound, follow the identification reference. Exact page references within the volumes are given whenever possible, but it should be noted that the L/P&S/6 references sometimes include related working papers along with the actual PCs and drafts,

when these materials are inextricably linked. As noted earlier, the original pagination in the L/P&S/6 volumes is somewhat irregular and occasionally non-existent. The Check List records faulty pagination by “[sic],” and non-pagination by “n.p.” Whenever the last pages of the PCs and Drs have been left unnumbered in volumes, but with gaps allowing for sequential pagination, the appropriate page references have been given in square brackets.

An asterisk placed before an E/4 reference (e.g., No. 105) indicates that Mill’s signature or initials appear in pencil at the start of the document. An angled bracket entered immediately after an E/4 page reference (e.g., No. 1586) indicates that the draft despatch in question continues for a few pages after the last page number given but that there are good grounds for concluding that Mill himself was not responsible for the extra paragraphs, which usually deal with minor factual matters appended to certain long despatches for administrative convenience. The existence in the L/P&S/6 volumes of the few short letters or notes, written by Mill to officials in the Board of Control to explicate particular points in the PCs, etc., is signalled in the Check List by “+L” following the appropriate location references (e.g., No. 46). The location in *Parliamentary Papers* [PP] is given for those portions of Mill’s despatches therein printed. Finally, it should be noted that the Check List provides special entries to cover the 44 items crossed out in Mill’s original list (see above). Such entries are not given separate numbers but are indicated by adding an X to the number of the immediately preceding ordinary entry (e.g., 898X indicates the crossed-out item after 898). As explained above, many of these crossed-out entries refer to PCs that were either altered or cancelled by the Board so that Mill apparently no longer regarded them as “his” despatches. In the majority of cases, Mill’s original PC versions survive in the appropriate L/P&S/6 volumes. References to such documents have accordingly been included, wherever possible, in the Check List. In a very few instances (e.g., 379X, 1585X) it has not proved possible to trace the items listed; in some other cases (e.g., 1625X, 1692X) only the E/4 copies of the official drafts have survived.

In this list the spelling of Indian place names is based on the system used in *The Imperial Gazetteer of India* (Oxford: Clarendon Press, 1909). Mill’s original spelling of Indian personal names has, however, usually been retained.

*Bengal/India Political Department*¹

1 7 Apr., 1824. PC 132, Dr 246: E/4/711, pp. 359-433; L/P&S/6/239, n.p.; L/P&S/6/266, pp. 703-[742]. MSS Eur B 405: “The first part of this Draft was written by Mr. McCulloch” [Examiner of Indian Correspondence, 1817-30].

2 19 June, 1824. PC 152, Dr 388: E/4/711, pp. 807-928; L/P&S/6/239, n.p.; L/P&S/6/266, pp. 895-[958].

3 10 Nov., 1824. PC 195, Dr 19: E/4/712, pp. 878-953; L/P&S/6/239, n.p.; L/P&S/6/267, pp. 1-[50].

4 6 Apr., 1825. PC 212, Dr 234: E/4/714,

¹Under the Charter Act of 1833, which came into force the following year, the Governor-General of Bengal became Governor-General of India.

- pp. 367-507; L/P&S/6/239, n.p.; L/P&S/6/267, pp. 171-[252].
- 5 9 Nov., 1825. PC 242, Dr 40: E/4/715, pp. 633-873; L/P&S/6/239, n.p.; L/P&S/6/267, pp. 321-[354]. Paras. 153-66, *PP*, 1831-32, XIV, 347-9.
- 6 15 Mar., 1826. PC 288, Dr 183: E/4/716, pp. 535-622; L/P&S/6/239, n.p.; L/P&S/6/267, pp. 463-[522].
- 7 19 Apr., 1826. PC 316, Dr 254: E/4/716, pp. 1009-1069; L/P&S/6/241, n.p.; L/P&S/6/267, pp. 535-[582].
- 8 8 Nov., 1826. PC 316, Dr 16: E/4/718, pp. 77-120; L/P&S/6/241, n.p.; L/P&S/6/268, pp. 13-[40].
- 9 10 Nov., 1826. PC 325, Dr 17: E/4/718, pp. 145-235; L/P&S/6/241, n.p.; L/P&S/6/268, pp. 41-[78].
- 10 10 May, 1826; affairs of Nagpur. PC 325, Dr 275: E/4/717, pp. 77-98; L/P&S/6/241, n.p.; L/P&S/6/267, pp. 587-[598].
- 11 10 Apr., 1827; conquest of Bharatpur. PC 377, Dr 244: E/4/719, pp. 63-82; L/P&S/6/241, n.p.; L/P&S/6/268, pp. 223-[240].
- 12 12 Dec., 1827. PC 395, Dr 61: E/4/720, pp. 981-1115; L/P&S/6/241, n.p.; L/P&S/6/269, pp. 41-[108].
- 13 7 Nov., 1827; arrangements for future administration of Bharatpur. PC 433, Dr 25: E/4/720, pp. 743-71; L/P&S/6/241, n.p.; L/P&S/6/269, pp. 21-[40].
- 14 23 Jan., 1828; disposal of the Southern Maratha country. PC 452, Dr 128: E/4/721, pp. 105-18; L/P&S/6/241, n.p.; L/P&S/6/269, pp. 109-[120].
- 15 26 Mar., 1828; affairs of Sindhia. PC 453, Dr 240: E/4/721, pp. 545-72; L/P&S/6/241, n.p.; L/P&S/6/269, pp. 181-[200].
- 16 20 Feb., 1828; publication of papers concerning Sir D. Ochterlony [Resident in Malwa and Rajputana] and the affairs of Bharatpur. PC 457, Dr 175: E/4/721, pp. 279-308; L/P&S/6/242, n.p.; L/P&S/6/269, pp. 145-[160].
- 17 10 Dec., 1828. PC 469, Dr 60: E/4/724, pp. 73-269; L/P&S/6/242, n.p.; L/P&S/6/270, pp. 81-[186].
- 18 16 Apr., 1828; affairs of Alwar. PC 456, Dr 277: E/4/721, pp. 739-66; L/P&S/6/242, n.p.; L/P&S/6/269, pp. 201-[220].
- 19 1 Oct., 1828; affairs of Oudh. PC 464, Dr 471: E/4/723, pp. 775-895; L/P&S/6/242, n.p.; L/P&S/6/269, pp. 373-[434]. Paras. 9-20, *PP*, 1831-32, XIV, 349-52.
- 20 11 Mar., 1829. PC 529, Dr 200: E/4/725, pp. 157-215; L/P&S/6/271, pp. 415-[510].
- 21 1 Apr., 1829. PC 529, Dr 234: E/4/725, pp. 265-399; L/P&S/6/272, pp. 83-[196].
- 22 26 Nov., 1828; affairs of Nagpur. PC 528, Dr 52: E/4/723, pp. 1251-1278; L/P&S/6/270, pp. 21-[60]. Paras. 3-8, *PP*, 1831-32, XIV, 352.
- 23 28 Jan., 1829; affairs of Oudh and Bharatpur. PC 564, Dr 145: E/4/724, pp. 715-89; L/P&S/6/271, pp. 1-[90].
- 24 3 Dec., 1828; portrait of the King [Nawab] of Oudh. PC 574, Dr 59: E/4/724, pp. 67-72; L/P&S/6/270, pp. 61-[80].
- 25 15 Apr., 1829; mutiny at Mominabad. PC 582, Dr 264: E/4/725, pp. 523-58; L/P&S/6/272, pp. 219-[270].
- 26 24 June, 1829. PC 589, Dr 358: E/4/725, pp. 1023-1152; L/P&S/6/272, pp. 287-[442].
- 27 10 Nov., 1830. PC 756, Dr 21, D 13: E/4/729, pp. 717-886; L/P&S/6/279, pp. 169-[394].
- 28 10 Mar., 1830; slavery in Assam. PC 757, Dr 239, D 3: E/4/727, pp. 651-64; L/P&S/6/274, pp. 281-[304].
- 29 7 Jan., 1831; affairs of Oudh. PC 792, Dr 47, D 2: E/4/730, pp. 475-559; L/P&S/6/279, pp. 395-[498].
- 30 27 Oct., 1830; pensions and jagirs granted to Indian notables. PC 802, Dr 12, D 12: E/4/729, pp. 623-30; L/P&S/6/279, pp. 1-[92].
- 31 19 Jan., 1831; allowances of European officers. PC 802, Dr 20, D 6: E/4/730, pp. 887-931; L/P&S/6/279, pp. 1-[84], 93-[120].
- 32 24 Nov., 1830. PC 802, Dr 41, D 14: E/4/729, pp. 1141-1225; L/P&S/6/279, pp. 1-[84], 121-[168].
- 33 7 Jan., 1831; affairs of Hyderabad. PC 808, Dr 600, D 1: E/4/730, pp. 455-73; L/P&S/6/278, pp. 207-[234]. Paras. 2-5, 76, *PP*, 1831-32, XIV, 355.
- 34 18 Aug., 1830; memorial of J.M. Sinclair [ex-employee of the Nawab of Oudh]. PC 809, Dr 502, D 9: E/4/729, pp. 123-32; L/P&S/6/278, pp. 117-[134].
- 35 7 Jan., 1831. PC 829, Dr 93, D 3: E/4/730, pp. 561-673; L/P&S/6/280, pp. 101-[224].
- 36 1 Sept., 1830; administration of Central India. PC 822, Dr 547, D 10: E/4/729, pp. 201-10; L/P&S/6/278, pp. 135-[154].
- 37 6 Oct., 1830; affairs of Bharatpur. PC

- 826, Dr 581, D 11: E/4/729, pp. 537-50; L/P&S/6/278, pp. 155-[178].
- 38 15 Dec., 1830; affairs of Gwalior. PC 840, Dr 62, D 16: E/4/730, pp. 101-22; L/P&S/6/280, pp. 73-[100].
- 39 24 Nov., 1830; case of Sir Edward Colebrooke [ex-Resident at Delhi]. PC 846, Dr 49, D 15: E/4/729, pp. 1227-47; L/P&S/6/280, pp. 33-[64].
- 40 12 Jan., 1831; pensions and jagirs granted to Indian notables. PC 851, Dr 116, D 5: E/4/730, pp. 813-28; L/P&S/6/280, pp. 225-[252].
- 41 9 Feb., 1831. PC 853, Dr 171, D 7: E/4/731, pp. 303-85; L/P&S/6/280, pp. 253-[348].
- 42 12 Jan., 1831; Tanjore Residency and Chepauk Agency. Dr 48, D 4: E/4/730, pp. 791-811; L/P&S/6/280, pp. 21-[32].
- 43 9 Mar., 1831; allowances of Lt. Col. D. Macleod [Bengal Engineers]. PC 802, Dr 199, D 9: E/4/731, pp. 1065-84; L/P&S/6/279, pp. 1-[84]; L/P&S/6/281, pp. 1-[16].
- 44 17 Aug., 1831. PC 926, Dr 558, D 12: E/4/733, pp. 273-329; L/P&S/6/281, pp. 137-[206].
- 45 1 Feb., 1832; affairs of Nagpur and case of the Nagpur local officers. PC 996, Dr 30, D 1: E/4/734, pp. 277-308; L/P&S/6/282, pp. 1-[48]. Paras. 38-42, *PP*, 1831-32, XIV, 358.
- 46 23 May, 1832; settlements in the Straits of Malacca. PC 1010, Dr 237, D 3: E/4/734, pp. 1226-1316; L/P&S/6/283, pp. 1-[80], 95-[150]. (L.)
- 47 31 Oct., 1832; affairs of Hyderabad. PC 1059, Dr 529, D 9: E/4/735, pp. 707-47; L/P&S/6/283, pp. 561-[592], 601-[620]. Paras. 13-18, *PP*, 1831-32, XIV, 356.
- 48 6 June, 1832; memorial of Mrs. C.M. Browne concerning her father's estate. PC 1041, Dr 317, D 4: E/4/734, pp. 1420-30; L/P&S/6/283, pp. 193-[212].
- 49 26 June, 1832; misappropriation of funds in the treasury of the Gwalior Residency. Dr 318, D 5: E/4/734, pp. 1542-55; L/P&S/6/283, pp. 225-[236].
- 50 6 Feb., 1833. PC 1060, Dr 17, D 3: E/4/736, pp. 669-881; L/P&S/6/284, pp. 251-[600].
- 51 21 Nov., 1832; affairs of Kedah, Nanning, etc. [Straits Settlements]. PC 1069, Dr 642, D 10: E/4/735, pp. 1197-1250; L/P&S/6/283, pp. 621-[728].
- 52 6 Mar., 1833; assumption of Mysore. PC 1087, Dr 14, D 7: E/4/737, pp. 7-56; L/P&S/6/284, pp. 121-[250]. Extract, *PP*, 1831-32, XIV, 360.
- 53 24 Oct., 1832; charge of corruption against Lt. J. Wakefield [Bengal Native Infantry]. PC 1070, Dr 498, D 8: E/4/735, pp. 659-73; L/P&S/6/283, pp. 401-[424].
- 54 28 Nov., 1832; Thagi. PC 1072, Dr 643, D 11: E/4/735, pp. 1471-92; L/P&S/6/283, pp. 735-[762].
- 55 16 July, 1834; government and administration of Oudh. PC 1284, Dr 328, D 11: E/4/741, pp. 325-436; L/P&S/6/290, pp. 141-[398].
- 56 24 July, 1833. PC 1144, Dr 366, D 12: E/4/738, pp. 441-528; L/P&S/6/285, pp. 219-[454].
- 57 3 Jan., 1834. PC 1162, Dr 666, D 1: E/4/740, pp. 25-94; L/P&S/6/286, pp. 429-[651].
- 58 17 June, 1834; case of M. Ricketts [ex-Resident at Lucknow]. PC 1153, Dr 301, D 10: E/4/741, pp. 65-121; L/P&S/6/289, pp. 353-[last 25 pp. unnumbered]. +L.
- 59 12 Feb., 1834. PC 1219, Dr 55, D 2: E/4/740, pp. 407-80; L/P&S/6/287, pp. 5-[206].
- 60 23 Apr., 1834; affairs of Mysore. PC 1206, Dr 180, D 9: E/4/740, pp. 1125-49; L/P&S/6/288, pp. 787-[824] [*sic*].
- 61 20 Nov., 1833; appointment of Maj. W. Pasmore [Bengal Native Infantry] to the command of the Persian troops etc. PC 1212, Dr 503, D 16: E/4/739, pp. 353-61; L/P&S/6/286, pp. 45-[56], 77-[84].
- 62 6 Mar., 1834. PC 1223, Dr 118, D 3: E/4/740, pp. 607-56; L/P&S/6/287, pp. 755-[852].
- 63 25 Mar., 1834. PC 1229, Dr 140, D 4: E/4/740, pp. 743-96; L/P&S/6/288, pp. 1-[132].
- 64 17 Dec., 1833; affairs of Hyderabad. PC 1224, Dr 632, D 17: E/4/739, pp. 563-608; L/P&S/6/286, pp. 345-[424].
- 65 23 Oct., 1833; case of T.H. Maddock [Resident at Lucknow]. Dr 504, D 15: E/4/739, pp. 183-92; L/P&S/6/286, pp. 89-[98].
- 66 16 Apr., 1834; Thagi. PC 1272, Dr 200, D 8: E/4/740, pp. 1109-20; L/P&S/6/289, pp. 211-[232].
- 67 16 Apr., 1834. PC 1281, Dr 199, D 7: E/4/740, pp. 1043-1107; L/P&S/6/289, pp. 85-[210].
- 68 16 Apr., 1834. PC 1294, Dr 198, D 6:

- E/4/740, pp. 1009-42; L/P&S/6/289, pp. 25-[84].
- 69 13 Aug., 1834. PC 1308, Dr 412, D 12: E/4/741, pp. 627-702; L/P&S/6/290, pp. 453-[516], 523-[586]. +L.
- 70 3 Dec., 1834; territorial acquisitions and political connexions to the east of Bengal. PC 1327, Dr 534, D 14: E/4/742, pp. 131-370; L/P&S/6/291, pp. 311-[808].
- 71 20 Aug., 1834. PC 1323, Dr 422, D 13: E/4/741, pp. 727-816; L/P&S/6/290, pp. 603-[788].
- 72 2 July, 1834; case of Lt. Col. W.G.A. Feilding [officiating Resident in Gwalior]. Dr 342, D 1: E/4/741, pp. 245-50; L/P&S/6/290, pp. 405-[408].
- 73 21 Jan., 1835. PC 1357, Dr 12, D 2: E/4/742, pp. 774-854; L/P&S/6/292, pp. 57-[318].
- 74 14 Jan., 1835; memorial of Diwan Khait Singh of Charkhari. PC 1361, Dr 11, D 1: E/4/742, pp. 720-32; L/P&S/6/292, pp. 33-[60].
- 75 23 June, 1835; conquest of Coorg. PC 1402, Dr 343, D 26: E/4/744, pp. 287-346; L/P&S/6/294, pp. 405-[478].
- 76 27 May, 1835. PC 1403, Dr 274, D 19: E/4/743, pp. 1207-64; L/P&S/6/294, pp. 91-[156].
- 77 27 May, 1835; affairs of Bhopal. PC 1403, Dr 271, D 18: E/4/743, pp. 1189-1206; L/P&S/6/294, pp. 1-[20].
- 78 22 May, 1835. PC 1403, Dr 273, D 17: E/4/743, pp. 1157-69; L/P&S/6/294, pp. 73-[90].
- 79 1 May, 1835; affairs of Gwalior. PC 1411, Dr 221, D 10: E/4/743, pp. 759-805; L/P&S/6/293, pp. 281-[328]. +2L.
- 80 8 Sept., 1835; affairs of Hyderabad. PC 1418, Dr 485, D 39: E/4/745, pp. 83-145; L/P&S/6/295, pp. 605-[695].
- 81 1 May, 1835; affairs of Nagpur. PC 1414, Dr 229, D 11: E/4/743, pp. 807-31; L/P&S/6/293, pp. 329-[364].
- 82 1 Apr., 1835; slave trade. PC 1413, Dr 169, D 5: E/4/743, pp. 129-40; L/P&S/6/293, pp. 17-[36].
- 83 7 Apr., 1835; Merwara. PC 1412, Dr 193, D 8: E/4/743, pp. 195-210; L/P&S/6/293, pp. 209-[236].
- 84 10 June, 1835; affairs of Oudh. PC 1430, Dr 315, D 21: E/4/744, pp. 55-103; L/P&S/6/294, pp. 257-[316].
- 85 16 Sept., 1835; Bundelkhand States. PC 1468, Dr 502, D 41: *E/4/745, pp. 225-58; L/P&S/6/296, pp. 179-[218].
- 86 29 July, 1835; Sikh and Hill States. PC 1460, Dr 425, D 32: E/4/744, pp. 867-916; L/P&S/6/295, pp. 89-[150].
- 87 18 Mar., 1835; states beyond the Sutlej. PC 1422, Dr 143, D 4: E/4/743, pp. 69-80; L/P&S/6/293, pp. 1-[16].
- 88 1 May, 1835; the Delhi family [the family of the Mughal Emperor at Delhi]. PC 1425, Dr 232, D 14: E/4/743, pp. 857-69; L/P&S/6/293, pp. 405-[428].
- 89 7 Apr., 1835; cases of three female dependants of former assistants in the Political Department. PC 1435, Dr 192, D 7: E/4/743, pp. 187-94; L/P&S/6/293, pp. 189-[208].
- 90 16 June, 1835; political stipendiaries. PC 1441, Dr 272, D 24: E/4/744, pp. 171-207; L/P&S/6/294, pp. 21-[72].
- 91 7 Apr., 1835; villages in the Deccan belonging to Sindhia and Holkar. PC 1440, Dr 191, D 6: E/4/743, pp. 177-86; L/P&S/6/293, pp. 169-[188].
- 92 1 May, 1835; His Majesty's squadron in the Indian Seas. PC 1443, Dr 231, D 13: E/4/743, pp. 841-55; L/P&S/6/293, pp. 377-[404].
- 93 13 May, 1835; affairs of Travancore. PC 1444, Dr 244, D 16: E/4/743, pp. 1001-12; L/P&S/6/293, pp. 429-[448].
- 94 12 Aug., 1835; South-West Frontier. PC 1445, Dr 435, D 33: E/4/744, pp. 949-70; L/P&S/6/295, pp. 195-[228].
- 95 19 Aug., 1835; chiefs and jagirdars under the Saugor and Nerbudda Agency. PC 1470, Dr 456, D 36: E/4/744, pp. 1065-1134; L/P&S/6/295, pp. 351-[430].
- 96 10 June, 1835; Bhils of Western Malwa. PC 1466, Dr 317, D 23: E/4/744, pp. 123-49; L/P&S/6/294, pp. 341-[384].
- 97 22 July, 1835; smaller states in Malwa. PC 1472, Dr 404, D 29: E/4/744, pp. 599-648; L/P&S/6/294, pp. 499-[568].
- 98 16 June, 1835; affairs of Holkar. PC 1475, Dr 306, D 25: E/4/744, pp. 209-26; L/P&S/6/294, pp. 229-[256].
- 99 1 May, 1835; Rampur Jagir. PC 1474, Dr 230, D 12: E/4/743, pp. 833-9; L/P&S/6/293, pp. 365-[376].
- 100 7 Oct., 1835; chiefs and jagirdars in the Delhi territory. PC 1483, Dr 526, D 47: *E/4/745, pp. 849-78; L/P&S/6/296, pp. 299-[342].
- 101 10 June, 1835; Eastern Settlements [Straits Settlements]. PC 1489, Dr 316, D 22:

- E/4/744, pp. 105-21; L/P&S/6/294, pp. 317-[340].
- 102** 12 Aug., 1835; Nepal. PC 1488, Dr 439, D 34: E/4/744, pp. 971-82; L/P&S/6/295, pp. 229-[248].
- 103** 12 Aug., 1835; Thagi. PC 1499, Dr 457, D 35: *E/4/744, pp. 983-1014; L/P&S/6/295, pp. 431-[470].
- 104** 8 Sept., 1835; case of Lalla Sunt Lal [a Delhi banker]. PC 1526, Dr 484, D 38: *E/4/745, pp. 65-82; L/P&S/6/295, pp. 581-[606].
- 105** 16 Sept., 1835; political agencies in the Upper Provinces. PC 1530, Dr 504, D 43: *E/4/745, pp. 297-314; L/P&S/6/296, pp. 271-[298].
- 106** 11 Nov., 1835; Tenasserim provinces. PC 1535, Dr 544, D 50: *E/4/746, pp. 83-126; L/P&S/6/296, pp. 501-[554].
- 107** 16 Sept., 1835; affairs of Jodhpur. PC 1534, Dr 501, D 40: E/4/745, pp. 205-23; L/P&S/6/296, pp. 147-[178].
- 108** 22 July, 1835; affairs of Sikkim. PC 1531, Dr 424, D 31: E/4/744, pp. 653-65; L/P&S/6/295, pp. 69-[88].
- 109** 16 Sept., 1835; affairs of Jaipur. PC 1543, Dr 503, D 42: E/4/745, pp. 259-96; L/P&S/6/296, pp. 219-[270].
- 110** 11 Nov., 1835; states under the Rajputana Agency. PC 1556, Dr 611, D 52: *E/4/746, pp. 135-200; L/P&S/6/297, pp. 1-[130].
- 111** 25 Sept., 1835; North-Eastern and Eastern Frontier. PC 1566, Dr 527, D 44: *E/4/745, pp. 385-436; L/P&S/6/296, pp. 343-[422].
- 112** 14 Oct., 1835. PC 1577, Dr 543, D 48: *E/4/745, pp. 951-90; L/P&S/6/296, pp. 427-[500].
- 113** 4 Nov., 1835. PC 1578, Dr 602, D 49: *E/4/745, pp. 1-52; L/P&S/6/296, pp. 581-[660].
- 114** 22 July, 1835; memorial of Lt. Col. J. Caulfield [ex-Political Agent, Haraoiti]. Dr 403, D 28: E/4/744, pp. 593-8; L/P&S/6/294, pp. 495-[498].
- 115** 25 Nov., 1835; Persian Gulf. PC 1593, Dr 648, D 55: *E/4/746, pp. 411-20; L/P&S/6/297, pp. 247-[270].
- 116** 20 Jan., 1836. PC 1604, Dr 12, D 1: *E/4/746, pp. 835-81; L/P&S/6/298, pp. 1-[80].
- 117** 11 Nov., 1835; affairs of Coorg. PC 1597, Dr 625, D 54: *E/4/746, pp. 209-19; L/P&S/6/297, pp. 151-[170].
- 118** 11 Nov., 1835; cases of four widows of uncontracted civil servants. PC 1608, Dr 610, D 51: *E/4/746, pp. 127-34; L/P&S/6/296, pp. 661-[672].
- 119** 11 Nov., 1835; affairs of Gwalior. PC 1598, Dr 612, D 53: *E/4/746, pp. 201-8; L/P&S/6/297, pp. 131-[150].
- 120** 12 Feb., 1836; affairs of Mysore. PC 1599, Dr 52, D 5: *E/4/746, pp. 1186-1227; L/P&S/6/298, pp. 255-[324].
- 121** 10 Feb., 1836; Murshidabad Nizamut. PC 1609, Dr 21, D 4: *E/4/746, pp. 1120-49; L/P&S/6/298, pp. 89-[148].
- 122** 30 Mar., 1836. PC 1613, Dr 48, D 9: *E/4/747, pp. 423-71; L/P&S/6/298, pp. 171-[254].
- 123** 16 Mar., 1836; affairs of Oudh. PC 1618, Dr 81, D 7: *E/4/747, pp. 167-204; L/P&S/6/298, pp. 453-[500].
- 124** 24 Feb., 1836. PC 1617, Dr 64, D 6: *E/4/746, pp. 1278-1319; L/P&S/6/298, pp. 325-[394].
- 125** 27 Jan., 1836; financial claims against Company employees [H. Mackenzie, W.B. Martin, and Col. W. Feilding]. PC 1619, Dr 22, D 3: *E/4/746, pp. 1005-16; L/P&S/6/298, pp. 151-[170].
- 126** 7 Feb., 1838; personal surinjam lands in the Deccan. PC 1621, Dr 60, D 9: E/4/753, pp. 663-710; L/P&S/6/305, pp. 753-[778], 787-[812].
- 127** 31 May, 1838; claim of Sah Beharee Lall [a banker at Lucknow] upon the Government of Oudh. PC 2134, Dr 310, D 35: *E/4/755, pp. 679-711; L/P&S/6/310, pp. 195-[282].
- 128** 23 Mar., 1836. PC 1658, Dr 117, D 8: *E/4/747, pp. 229-60; L/P&S/6/298, pp. 521-[578].
- 129** 14 Apr., 1836; assumption of Jaintia. PC 1680, Dr 156, D 11: *E/4/747, pp. 745-55; L/P&S/6/299, pp. 1-[18].
- 130** 20 Apr., 1836; affairs of Jaipur. PC 1685, Dr 170, D 13: *E/4/747, pp. 787-826; L/P&S/6/299, pp. 27-[86].
- 131** 20 Apr., 1836; memorial of Mrs. M. Fraser [widow of Maj. G. Fraser, Nagpur Army]. Dr 157, D 12: *E/4/747, pp. 777-85; L/P&S/6/299, pp. 19-[26].
- 132** 8 June, 1836; affairs of Nepal. PC 1740, Dr 253, D 16: *E/4/747, pp. 1143-56; L/P&S/6/299, pp. 107-[132].
- 133** 19 Oct., 1836; Eastern Frontier. PC 1777, Dr 463, D 24: *E/4/748, pp. 1183-1236; L/P&S/6/299, pp. 423-[520].

- 133X** Murder of W. Fraser (Commissioner at Delhi). India PC 1788 approved by Board on 1 July, 1836; L/P&S/6/299, pp. 521-[534]. No Dr, no D.
- 134** 5 Oct., 1836; affairs of Oudh. PC 1798, Dr 459, D 23: *E/4/748, pp. 1035-55; L/P&S/6/299, pp. 391-[422].
- 135** 5 July, 1837; affairs of Jaipur. PC 1876, Dr 298, D 9: *E/4/751, pp. 463-504; L/P&S/6/300, pp. 235-[292].
- 136** 5 July, 1837; affairs of Gwalior. PC 1882, Dr 299, D 10: *E/4/751, pp. 505-41; L/P&S/6/300, pp. 293-[332].
- 137** 3 Mar., 1837; Sindhia and Holkar villages in the Deccan. PC 1883, Dr 97, D 5: *E/4/749, pp. 1008-16; L/P&S/6/300, pp. 61-[76].
- 138** 20 Sept., 1837. PC 1904, Dr 437, D 22: *E/4/752, pp. 719-864; L/P&S/6/302, pp. 33-[256].
- 139** 20 Sept., 1837. PC 1907, Dr 446, D 23: *E/4/752, pp. 865-951; L/P&S/6/302, pp. 257-[398].
- 140** 30 Aug., 1837. PC 1908, Dr 396, D 19: *E/4/752, pp. 531-47; L/P&S/6/301, pp. 143-[172].
- 141** 28 July, 1837; affairs of Holkar. PC 1910, Dr 315, D 14: *E/4/751, pp. 639-64; L/P&S/6/300, pp. 379-[408].
- 142** 28 Mar., 1838; affairs of Hyderabad. PC 2048, Dr 174, D 17: *E/4/754, pp. 601-32; L/P&S/6/308, pp. 187-[256].
- 143** 18 Oct., 1837. PC 1921, Dr 466, D 25: *E/4/752, pp. 1201-42; L/P&S/6/303, pp. 127-[202].
- 144** 20 June, 1837; Thagi. PC 1909, Dr 264, D 6: *E/4/751, pp. 245-64; L/P&S/6/300, pp. 103-[132].
- 145** 20 Sept., 1837; affairs of Mysore. PC 1919, Dr 395, D 20: *E/4/752, pp. 635-96; L/P&S/6/301, pp. 79-[142].
- 146** 28 June, 1837; affairs of Coorg. PC 1920, Dr 265, D 7: *E/4/751, pp. 337-65; L/P&S/6/300, pp. 133-[172].
- 147** 9 Aug., 1837; Eastern Frontier. PC 1931, Dr 342, D 17: *E/4/752, pp. 51-113; L/P&S/6/300, pp. 429-[512].
- 148** 15 Nov., 1837. PC 1935, Dr 487, D 29: *E/4/753, pp. 65-112; L/P&S/6/303, pp. 207-[254], 259-[300].
- 149** 18 July, 1838. PC 1936, Dr 3, D 41: E/4/756, pp. 147-206; L/P&S/6/305, pp. 55-[125], 189-[234]. (L.)
- 150** 20 Sept., 1837; North-West Frontier. PC 1959, Dr 436, D 21: *E/4/752, pp. 697-718; L/P&S/6/302, pp. 1-[32]. PP, 1839, XL, 266-7.
- 151** 13 Feb., 1838. PC 1943, Dr 612, D 11: *E/4/753, pp. 841-95; L/P&S/6/304, pp. 297-[346], 355-[390].
- 152** 28 June, 1837; explanation of T.H. Maddock [ex-Resident in Lucknow] of his conduct in connection with the enquiry concerning M. Ricketts. PC 1965, Dr 283, D 8: *E/4/751, pp. 369-90; L/P&S/6/300, pp. 201-[234].
- 153** 28 July, 1837; affairs of Jhabua. PC 1963, Dr 343, D 16: *E/4/751, pp. 677-94; L/P&S/6/301, pp. 1-[26].
- 154** 18 Oct., 1837; affairs of Kotah. PC 1962, Dr 464, D 24: *E/4/752, pp. 1127-1200; L/P&S/6/303, pp. 23-[50], 59-[94].
- 155** 28 July, 1837; restoration of Sindhia's districts in Khandesh. PC 1964, Dr 314, D 13: *E/4/751, pp. 619-38; L/P&S/6/300, pp. 345-[378].
- 156** 25 Oct., 1837; Murshidabad Nizamut. PC 1966, Dr 488, D 27: *E/4/752, pp. 1267-1300; L/P&S/6/303, pp. 305-[360].
- 157** 16 Aug., 1837; affairs of Jodhpur. PC 1976, Dr 382, D 18: *E/4/752, pp. 267-88; L/P&S/6/301, pp. 47-[78].
- 158** 10 Jan., 1838. PC 1981, Dr 613, D 4: *E/4/753, pp. 405-58; L/P&S/6/304, pp. 427-[478], 481-[512].
- 159** 24 Jan., 1838. PC 1982, Dr 30, D 7: *E/4/753, pp. 551-87; L/P&S/6/305, pp. 295-[334], 347-[368]. (L.)
- 160** 7 Feb., 1838; Agra. PC 1997, Dr 61, D 10: *E/4/753, pp. 711-90; L/P&S/6/307, pp. 61-[182].
- 161** 10 Jan., 1838; Bengal. PC 1990, Dr 2, D 5: *E/4/753, pp. 459-80; L/P&S/6/305, pp. 3-[43].
- 162** 14 Mar., 1838. PC 2005, Dr 40, D 15: *E/4/754, pp. 183-216; L/P&S/6/305, pp. 385-[418], 439-[462].
- 163** 7 Feb., 1838; death of the Begum Sumroo [widow of Walter Reinhardt] and lapse of estate. PC 1994, Dr 601, D 8: *E/4/753, pp. 647-62; L/P&S/6/304, pp. 119-[138], 151-[160].
- 164** 21 Feb., 1838. PC 2006, Dr 59, D 13: *E/4/753, pp. 953-97; L/P&S/6/305, pp. 621-[664], 669-[700].
- 165** 13 Feb., 1838; North-Western Provinces. PC 2007, Dr 63, D 12: *E/4/753, pp. 897-928; L/P&S/6/307, pp. 203-[262].

- 166** 8 Nov., 1837; succession to the estate of Jind. PC 1962, Dr 465, D 28: *E/4/753, pp. 23-48; L/P&S/6/303, pp. 23-[50], 111-[126].
- 167** 5 Jan., 1838; affairs of Bhopal. PC 2018, Dr 615, D 3: *E/4/753, pp. 359-72; L/P&S/6/304, pp. 545-[568].
- 168** 24 Jan., 1838; Sindhia's districts in the Deccan, Khandesh and Nimar. PC 2019, Dr 8, D 6: *E/4/753, pp. 537-50; L/P&S/6/305, pp. 255-[270], 279-[286].
- 169** 19 Dec., 1837; accounts of Sir John Campbell [ex-Envoy to Persia]. PC 2017, Dr 584, D 30: *E/4/753, pp. 257-82; L/P&S/6/304, pp. 1-[44].
- 170** 5 Jan., 1838; retrenchments against military officers in civil employment. PC 2016, Dr 600, D 1: *E/4/753, pp. 333-50; L/P&S/6/304, pp. 45-[64], 69-[80]. +L.
- 171** 5 Jan., 1838; embezzlements of H. Lindsay in Gwalior Residency. PC 2020, Dr 614, D 2: *E/4/753, pp. 351-8; L/P&S/6/304, pp. 525-[536].
- 172** 11 Apr., 1838; affairs of Oudh. PC 2071, Dr 132, D 26: *E/4/754, pp. 1005-1108; L/P&S/6/307, pp. 395-[478], 533-[628]. +L.
- 173** 28 Mar., 1838; Eastern Frontier. PC 2062, Dr 175, D 18: *E/4/754, pp. 633-73; L/P&S/6/308, pp. 289-[356].
- 174** 10 Apr., 1838; Mysore princes. PC 2080, Dr 212, D 25: *E/4/754, pp. 963-86; L/P&S/6/308, pp. 667-[702].
- 175** 10 Apr., 1838; affairs of Gwalior. PC 2078, Dr 196, D 22: E/4/754, pp. 851-67; L/P&S/6/308, pp. 421-[456].
- 176** 28 Mar., 1838; affairs of Mysore. PC 2079, Dr 180, D 19: *E/4/754, pp. 675-84; L/P&S/6/308, pp. 365-[384].
- 177** 10 Apr., 1838; Bengal. PC 2081, Dr 194, D 20: *E/4/754, pp. 837-46; L/P&S/6/308, pp. 389-[408].
- 178** 25 Apr., 1838; affairs of Jodhpur. PC 2083, Dr 236, D 28: *E/4/754, pp. 1139-58; L/P&S/6/308, pp. 711-[742].
- 179** 16 May, 1838. PC 2089, Dr 282, D 30: *E/4/755, pp. 477-520; L/P&S/6/309, pp. 169-[246].
- 180** 10 Apr., 1838; affairs of the Gaikwar of Baroda. PC 2095, Dr 209, D 24: *E/4/754, pp. 887-961; L/P&S/6/308, pp. 537-[658].
- 181** 20 Mar., 1838; Farrukhabad stipendiaries. PC 1997, Dr 118, D 16: *E/4/754, pp. 351-75; L/P&S/6/307, pp. 61-[138], 359-[374].
- 182** 31 May, 1838; states on and beyond the Indus. PC 2114, Dr 311, D 36: *E/4/755, pp. 713-32; L/P&S/6/310, pp. 303-[334].
- 183** 25 May, 1838; appointment of Lt. Col. G.E. Gowan as Commissioner in Kumaun. PC 2007, Dr 137, D 33: *E/4/755, pp. 593-600; L/P&S/6/307, pp. 203-[238]; L/P&S/6/308, pp. 45-[48]. (L)
- 184** 16 May, 1838. PC 2113, Dr 283, D 31: *E/4/755, pp. 521-54; L/P&S/6/309, pp. 267-[330].
- 185** 6 June, 1838. PC 2128, Dr 309, D 37: *E/4/755, pp. 963-1012; L/P&S/6/310, pp. 109-[154], 159-[194].
- 186** 22 Aug., 1838; North-Western Provinces. PC 2133, Dr 413, D 45: E/4/756, pp. 829-84; L/P&S/6/311, pp. 15-[102].
- 187** 22 Aug., 1838; North-Western Provinces. PC 2135, Dr 437, D 46: *E/4/756, pp. 885-920; L/P&S/6/311, pp. 209-[264].
- 188** 25 July, 1838. PC 2136, Dr 414, D 43: *E/4/756, pp. 243-88; L/P&S/6/311, pp. 103-[190].
- 189** 22 Aug., 1838; North-Western Provinces. PC 2139, Dr 450, D 47: E/4/756, pp. 921-56; L/P&S/6/311, pp. 279-[340].
- 190** 10 May, 1838; case of Rada Kishen, late Serishtadar of the Ambala Political Agency. PC 2129, Dr 284, D 32: *E/4/755, pp. 555-64; L/P&S/6/309, pp. 336-[354].
- 191** 31 May, 1838; insurrection in Kanara. PC 2148, Dr 308, D 34: *E/4/755, pp. 643-78; L/P&S/6/310, pp. 27-[82].
- 192** 2 May, 1838; charges against Thomas Metcalfe [Political Resident in Delhi]. PC 2130, Dr 258, D 29: *E/4/755, pp. 313-26; L/P&S/6/309, pp. 5-[20], 29-[36].
- 193** 22 Aug., 1838; North-Western Provinces. PC 2152, Dr 475, D 48: *E/4/756, pp. 957-84; L/P&S/6/312, pp. 1-[40].
- 194** 13 June, 1838; affairs of Hyderabad. PC 2163, Dr 342, D 38: *E/4/755, pp. 1057-68; L/P&S/6/310, pp. 421-[456].
- 195** 4 July, 1838; Thagi. PC 2167, Dr 399, D 40: *E/4/756, pp. 81-96; L/P&S/6/311, pp. 1-[24].
- 196** 17 Aug., 1838; affairs of Bhopal. PC 2195, Dr 477, D 44: *E/4/756, pp. 737-48; L/P&S/6/312, pp. 61-[80].
- 197** 18 July, 1838; Bengal. PC 2198, Dr 415, D 42: *E/4/756, pp. 207-18; L/P&S/6/311, pp. 191-[208].

- 198** 22 Aug., 1838; affairs of Gwalior. PC 2212, Dr 476, D 49: *E/4/756, pp. 985-1000; L/P&S/6/312, pp. 41-[60].
- 199** 19 Sept., 1838; disturbed state of Western Malwa. PC 2225, Dr 549, D 51: *E/4/757, pp. 399-428; L/P&S/6/312, pp. 152-[209].
- 200** 19 Sept., 1838; North-Western Provinces. PC 2222, Dr 564, D 52: *E/4/757, pp. 429-55; L/P&S/6/312, pp. 300-[341].
- 201** 19 Sept., 1838; Eastern Frontier. PC 2241, Dr 565, D 53: *E/4/757, pp. 457-82; L/P&S/6/312, pp. 342-[381].
- 202** 29 Aug., 1838; grant for the tomb of the Persian ambassador at Najaf. PC 1936, Dr 3, D 50: E/4/756, pp. 1065-73; L/P&S/6/305, pp. 55-[126], 189-[234].
- 203** 28 Nov., 1838; partition treaty with Kotah. PC 2248, Dr 654, D 66: *E/4/757, pp. 1141-74; L/P&S/6/313, pp. 183-[238].
- 204** 24 Oct., 1838; North-Western Provinces. PC 2226, Dr 577, D 60: *E/4/757, pp. 805-36; L/P&S/6/312, pp. 410-[461].
- 205** 17 Oct., 1838; affairs of Ava. PC 2244, Dr 604, D 56: *E/4/757, pp. 693-713; L/P&S/6/313, pp. 21-[62].
- 206** 24 Oct., 1838; affairs of Nepal. PC 2245, Dr 578, D 61: *E/4/757, pp. 837-48; L/P&S/6/313, pp. 1-[18].
- 207** 19 Sept., 1838; affairs of Mysore. PC 2246, Dr 566, D 54: *E/4/757, pp. 483-90; L/P&S/6/312, pp. 382-[393].
- 208** 5 Dec., 1838; states on the Indus. PC 2247, Dr 710, D 67: *E/4/758, pp. 57-68; L/P&S/6/313, pp. 325-[345].
- 209** 17 Oct., 1838; affairs of Jodhpur. PC 2252, Dr 605, D 57: *E/4/757, pp. 715-27; L/P&S/6/313, pp. 73-[96].
- 210** 17 Oct., 1838; abuses at Sambhar. PC 2253, Dr 606, D 58: *E/4/757, pp. 729-44; L/P&S/6/313, pp. 97-[120].
- 211** 6 Feb., 1839. PC 2261, Dr 41, D 4: *E/4/758, pp. 635-75; L/P&S/6/314, pp. 51-[118].
- 212** 14 Nov., 1838. PC 2265, Dr 655, D 63: *E/4/757, pp. 939-58; L/P&S/6/313, pp. 239-[268].
- 213** 17 Oct., 1838; allowances of Capt. C.M. Wade [Political Agent in Ludhiana]. PC 2268, Dr 613, D 59: *E/4/757, pp. 745-52; L/P&S/6/313, pp. 121-[132].
- 214** 6 Feb., 1839. PC 2277, Dr 42, D 5: *E/4/758, pp. 677-703; L/P&S/6/314, pp. 119-[163].
- 215** 14 Nov., 1838; rewards to the Coorgs, and allowances of the Superintendent of Coorg. PC 2272, Dr 656, D 64: *E/4/757, pp. 959-71; L/P&S/6/313, pp. 269-[286].
- 216** 30 Jan., 1839. PC 2278, Dr 20, D 3: *E/4/758, pp. 531-60; L/P&S/6/314, pp. 1-[49]. +L.
- 217** 21 Nov., 1838; claim of M.P. Edgeworth [Assistant Political Agent in Ambala] and others to compensation for plundered property. PC 2271, Dr 666, D 65: *E/4/757, pp. 1105-12; L/P&S/6/313, pp. 287-[300].
- 218** 13 Feb., 1839. PC 2308, Dr 52, D 6: *E/4/758, pp. 767-803; L/P&S/6/314, pp. 164-[219].
- 219** 9 Jan., 1839; affairs of Holkar. PC 2305, Dr 776, D 1: *E/4/758, pp. 297-312; L/P&S/6/313, pp. 352-[377].
- 220** 4 Dec., 1839; resumption of Upper Assam. PC 2303, Dr 498, D 24: *E/4/761, pp. 29-70; L/P&S/6/315, pp. 297-[364].
- 221** 9 Jan., 1839; Bengal. PC 2307, Dr 777, D 2: *E/4/758, pp. 313-21; L/P&S/6/313, pp. 384-[397].
- 222** 27 Mar., 1839; affairs of Gwalior. PC 2312, Dr 147, D 8: *E/4/758, pp. 1187-1210; L/P&S/6/314, pp. 256-[293].
- 223** 27 Mar., 1839. PC 2335, Dr 148, D 9: E/4/758, pp. 1211-58; L/P&S/6/314, pp. 294-[367].
- 223X** Affairs of Gaikwar. Bombay PC 2364 altered by Board on 17 June, 1839: L/P&S/6/315, pp. 67A-[n.p.]. No DR, no D.
- 224** 10 Apr., 1839; affairs of Jaipur. PC 2363, Dr 198, D 10: *E/4/759, pp. 163-87; L/P&S/6/315, pp. 1-[44].
- 225** 10 July, 1839; Eastern Frontier. PC 2365, Dr 329, D 13: E/4/759, pp. 1061-72; L/P&S/6/315, pp. 69-[88].
- 226** 30 Oct., 1839; affairs of Mysore. PC 2492, Dr 624, D 20: *E/4/760, pp. 1029-72; L/P&S/6/316, pp. 187-[260].
- 227** 11 Sept., 1839; affairs of Hyderabad. PC 2490, Dr 512, D 17: *E/4/760, pp. 483-502; L/P&S/6/316, pp. 1-[32].
- 228** 1 Apr., 1840; Eastern Frontier. PC 2499, Dr 61, D 12: *E/4/762, pp. 175-224; L/P&S/6/317, pp. 1-[72]. +L.
- 229** 23 Oct., 1839; affairs of Jaipur. PC 2504, Dr 583, D 19: *E/4/760, pp. 915-28; L/P&S/6/316, pp. 77-[104].
- 230** 13 Nov., 1839; Bengal. PC 2513, Dr

639, D 21: *E/4/760, pp. 1149-71; L/P&S/6/316, pp. 329-[372].

231 27 Nov., 1839. PC 2519, Dr 674, D 23: *E/4/760, pp. 1291-1318; L/P&S/6/316, pp. 377-[424].

232 22 Jan., 1840. PC 2524, Dr 22, D 3: *E/4/761, pp. 403-44; L/P&S/6/317, pp. 151-[226].

233 29 Jan., 1840. PC 2526, Dr 39, D 5: *E/4/761, pp. 611-39; L/P&S/6/317, pp. 275-[336].

234 11 Feb., 1840; North-Western Provinces. PC 2528, Dr 49, D 6: *E/4/761, pp. 741-836; L/P&S/6/317, pp. 337-[462].

235 19 Feb., 1840; North-Western Provinces. PC 2531, Dr 74, D 7: *E/4/761, pp. 883-912; L/P&S/6/317, pp. 463-[514].

236 12 Mar., 1840; North-Western Provinces. PC 2535, Dr 97, D 10: *E/4/761, pp. 1143-76; L/P&S/6/317, pp. 515-[574].

237 18 Sept., 1839; claims against Maj. Gen. J. Briggs [ex-Acting Resident at Nagpur]. Dr 513, D 18: *E/4/760, pp. 609-13; L/P&S/6/316, pp. 33-[36].

238 24 Dec., 1839; case of Maj. J.A. Moore [ex-Military Secretary with Nizam of Hyderabad]. PC 2591, Dr 723, D 26: *E/4/761, pp. 235-46; L/P&S/6/318, pp. 207-[222].

239 2 June, 1840. PC 2564, Dr 165, D 24: E/4/762, pp. 1351-1409; L/P&S/6/318, pp. 93-[189]. +2L.

240 29 Jan., 1840; affairs of Nagpur. PC 2603, Dr 38, D 4: *E/4/761, pp. 587-610; L/P&S/6/318, pp. 223-[260].

241 24 Dec., 1839; accounts of Sir John Campbell [ex-Envoy to Persia]. PC 2569, Dr 722, D 25: *E/4/761, pp. 227-34; L/P&S/6/318, pp. 191-[206].

241X Case of Diwan Khait Singh of Char-khari. See full entry at 254.

242 4 Mar., 1840; affairs of Oudh. PC 2615, Dr 85, D 9: E/4/761, pp. 979-1028; L/P&S/6/318, pp. 411-[476].

243 1 Apr., 1840; affairs of Jodhpur. PC 2629, Dr 135, D 13: E/4/762, pp. 225-72; L/P&S/6/318, pp. 623-[708]. +L.

244 25 Mar., 1840; depredations in Malwa and Rajputana. PC 2645, Dr 137, D 11: *E/4/761, pp. 1342-67; L/P&S/6/319, pp. 5-[44].

245 5 May, 1840; pension fund for the Nizam's local officers. PC 2524, Dr 96, D 20: E/4/762, pp. 717-24; L/P&S/6/317, pp. 151-[196]; L/P&S/6/319, pp. 477-[480].

246 24 Apr., 1840; Murshidabad Nizamut. PC 2650, Dr 208, D 17: *E/4/762, pp. 561-98; L/P&S/6/319, pp. 47-[92].

247 1 Apr., 1840; North-Western Provinces. PC 2661, Dr 149, D 14: E/4/762, pp. 273-319; L/P&S/6/319, pp. 119-[190].

248 27 May, 1840; North-Western Provinces. PC 2667, Dr 268, D 21: *E/4/762, pp. 1045-66; L/P&S/6/319, pp. 191-[226].

249 24 Apr., 1840. PC 2668, Dr 215, D 19: E/4/762, pp. 613-54; L/P&S/6/319, pp. 227-[294].

250 27 May, 1840; affairs of Mysore. PC 2674, Dr 269, D 22: *E/4/762, pp. 1067-92; L/P&S/6/319, pp. 347-[386]. +L.

251 2 June, 1840. PC 2695, Dr 286, D 25: *E/4/762, pp. 1411-43; L/P&S/6/319, pp. 489-[522], 525-[546]. +L.

252 26 Aug., 1840; supply of stores to the Nizam's army. PC 2659, Dr 238, D 29: *E/4/763, pp. 973-87; L/P&S/6/319, pp. 93-[118].

253 24 Apr., 1840; Murshidabad Nizamut. PC 2693, Dr 214, D 18: *E/4/762, pp. 599-611; L/P&S/6/319, pp. 465-[476], pp. 481-[488].

254 24 Apr., 1840; case of Diwan Khait Singh of Charkhari. PC 2614, Dr 136, D 16: *E/4/762, pp. 525-59; L/P&S/6/318, pp. 353-[410].

255 27 May, 1840; provision of information concerning jagirdars. Dr 270, D 23: *E/4/762, pp. 1093-1103; L/P&S/6/320, pp. 1-[4].

255X Deposition of Raja of Satara. India PC 2623 altered by Board on 3 Mar., 1840: L/P&S/6/318, pp. 477-[606]. Dr 186, D 1 of 1 Apr., 1840.

256 15 July, 1840; Thagi. PC 2749, Dr 387, D 26: *E/4/763, pp. 551-66; L/P&S/6/320, pp. 7-[28].

257 29 July, 1840; North-Western Provinces. PC 2750, Dr 415, D 27: *E/4/763, pp. 655-95; L/P&S/6/320, pp. 29-[102].

258 19 Aug., 1840; Eastern Frontier. PC 2770, Dr 491, D 28: *E/4/763, pp. 895-944; L/P&S/6/320, pp. 173-[248].

259 30 Sept., 1840; certain reductions in the pay of Madras officers. PC 2780, Dr 590, D 30: *E/4/763, pp. 1327-44; L/P&S/6/320, pp. 281-[304].

260 23 Dec., 1840. PC 2810, Dr 624, D 34: *E/4/764, pp. 907-1010; L/P&S/6/320, pp. 361-[496]. +2L.

261 23 June, 1841; Kanara insurrection. PC

2834, Dr 450, D 19: E/4/766, pp. 951-88; L/P&S/6/321, pp. 1-[56].

262 31 Oct., 1840; allowances of Sir H. Pottinger [Political Agent in Sind]. PC 2842, Dr 619, D 32: *E/4/764, pp. 109-16; L/P&S/6/321, pp. 127-[134].

263 7 Oct., 1840. PC 2841, Dr 605, D 31: *E/4/764, pp. 101-8; L/P&S/6/321, pp. 111-[126].

264 1 Jan., 1841; North-Western Provinces. PC 2866, Dr 763, D 1: *E/4/764, pp. 1079-1136; L/P&S/6/321, pp. 135-[228].

265 13 Jan., 1841. PC 2872, Dr 762, D 2: *E/4/764, pp. 1248-95; L/P&S/6/321, pp. 229-[272], 275-[304].

266 18 Nov., 1840; succession to the Rampur Jagir. PC 2873, Dr 678, D 33: *E/4/764, pp. 483-506; L/P&S/6/321, pp. 305-[340].

267 23 Dec., 1840; affairs of Rampur. PC 2922, Dr 776, D 35: *E/4/764, pp. 1011-18; L/P&S/6/322, pp. 13-[28].

268 21 Apr., 1841. PC 2944, Dr 252, D 8: *E/4/765, pp. 1135-70; L/P&S/6/322, pp. 73-[102], 105-[120].

269 13 Jan., 1841; allowances of Maj. F. Farrant and Lt. E. Pottinger [attached to the Persian mission]. PC 2945, Dr 3, D 3: *E/4/764, pp. 1296-1303; L/P&S/6/322, pp. 139-[146], 133-[136] [sic].

270 28 July, 1841. PC 2984, Dr 451, D 22: E/4/767, pp. 221-310; L/P&S/6/322, pp. 483-[558], 599-[646].

271 28 Apr., 1841; North-Western Provinces. PC 2981, Dr 280, D 10: *E/4/765, pp. 1421-74; L/P&S/6/322, pp. 319-[374], 383-[418]. Para. 45, PP, 1854, XLVII, 177.

272 16 Mar., 1841; presents given and received by Lord Keane [Commander-in-Chief, Bombay] and his suite. PC 2982, Dr 165, D 6: *E/4/765, pp. 459-72; L/P&S/6/322, pp. 427-[438], 443-[450].

273 24 Feb., 1841; claims to the allowance of second in command of the detachment in Persia. PC 2983, Dr 127, D 5: *E/4/765, pp. 365-72; L/P&S/6/322, pp. 453-[464].

274 13 July, 1841; North-Western Provinces. PC 3012, Dr 502, D 20: *E/4/767, pp. 5-56; L/P&S/6/323, pp. 49-[136].

275 2 June, 1841. PC 3011, Dr 372, D 15: *E/4/766, pp. 767-98; L/P&S/6/323, pp. 1-[48].

276 16 June, 1841; intrigues and conspiracies in the south of India. PC 3024, Dr 427,

D 18: *E/4/766, pp. 849-73; L/P&S/6/323, pp. 137-[178].

277 11 May, 1841; Eastern Frontier. PC 3027, Dr 338, D 12: E/4/766, pp. 59-99; L/P&S/6/323, pp. 179-[248].

278 28 Apr., 1841; affairs of Oudh. PC 3041, Dr 300, D 11: *E/4/765, pp. 1475-93; L/P&S/6/323, pp. 301-[332].

279 25 May, 1841; Mysore and Coorg. PC 3048, Dr 339, D 13: *E/4/766, pp. 619-38; L/P&S/6/323, pp. 333-[362].

280 27 Aug., 1841. PC 3068, Dr 588, D 31: E/4/767, pp. 875-920; L/P&S/6/323, pp. 387-[464].

281 2 June, 1841; case of Diwan Khait Singh. PC 3088, Dr 398, D 16: *E/4/766, pp. 799-810; L/P&S/6/323, pp. 609-[624].

282 31 Mar., 1841; the yacht *Prince Regent*. Dr 209, D 7: E/4/765, pp. 721-5; L/P&S/6/322, pp. 693-[696].

283 4 Aug., 1841. PC 3097, Dr 522, D 23: *E/4/767, pp. 437-84; L/P&S/6/323, pp. 697-[774].

284 4 Aug., 1841. PC 3105, Dr 543, D 24: *E/4/767, pp. 485-540; L/P&S/6/323, pp. 849-[930].

285 2 June, 1841; Eastern Frontier. PC 3104, Dr 399, D 17: *E/4/766, pp. 811-46; L/P&S/6/323, pp. 775-[848].

286 25 Aug., 1841; North-Western Provinces. PC 3173, Dr 589, D 30: *E/4/767, pp. 799-870; L/P&S/6/324, pp. 219-[334].

287 25 Aug., 1841. PC 3180, Dr 587, D 29: *E/4/767, pp. 725-98; L/P&S/6/324, pp. 109-[218].

288 1 Sept., 1841; Eastern Frontier. PC 3167, Dr 612, D 32: *E/4/767, pp. 1203-30; L/P&S/6/324, pp. 335-[380].

289 11 Aug., 1841; affairs of Nagpur. PC 3166, Dr 560, D 26: *E/4/767, pp. 553-64; L/P&S/6/324, pp. 77-[94].

290 19 July, 1841; slave trade. PC 3162, Dr 511, D 21: *E/4/767, pp. 167-71; L/P&S/6/324, pp. 25-[36].

291 11 Aug., 1841; Prince Jamhood Deen of Mysore. PC 3196, Dr 559, D 25: *E/4/767, pp. 547-51; L/P&S/6/324, pp. 57-[76].

292 25 Aug., 1841; vakils of the ex-Raja of Satara. PC 3198, Dr 585, D 27: *E/4/767, pp. 715-19; L/P&S/6/324, pp. 95-[104].

293 31 Dec., 1841; case of Tuanku Muhammad Saad of Kedah. PC 3232, Dr 917, D 47:

- *E/4/768, pp. 1021-40; L/P&S/6/325, pp. 529-[562].
- 294** 27 Oct., 1841; case of Hassan Ali Khan of Jhajjar. PC 3233, Dr 741, D 35: *E/4/768, pp. 337-48; L/P&S/6/324, pp. 603-[622].
- 295** 31 Dec., 1841; Bengal. PC 3235, Dr 868, D 42: *E/4/768, pp. 939-78; L/P&S/6/325, pp. 223-[288].
- 296** May 1842; affairs of the Gaikwar. PC 3238, Dr 776 cancelled by Board in May 1842: L/P&S/6/325, pp. 29-[68].
- 297** 26 Jan., 1842. PC 3261, Dr 12, D 1: *E/4/769, pp. 163-253; L/P&S/6/326, pp. 1-[146].
- 298** 20 Oct., 1841; ex-King of Johanna. PC 3253, Dr 728, D 34: *E/4/768, pp. 199-204; L/P&S/6/324, pp. 591-[602].
- 299** 21 Dec., 1841; Punjab and Afghanistan. PC 3276, Dr 871, D 41: *E/4/768, pp. 829-56; L/P&S/6/325, pp. 401-[444].
- 300** 31 Dec., 1841; affairs of Sindhia. PC 3255, Dr 918, D 48: *E/4/768, pp. 1041-60; L/P&S/6/325, pp. 563-[592].
- 301** 31 Dec., 1841; Mysore and Coorg. PC 3257, Dr 915, D 45: *E/4/768, pp. 989-1006; L/P&S/6/325, pp. 473-[504].
- 302** 21 Dec., 1841; affairs of Jaipur. PC 3252, Dr 869, D 39: *E/4/768, pp. 761-92; L/P&S/6/325, pp. 289-[340].
- 303** 21 Dec., 1841; affairs of Oudh. PC 3254, Dr 870, D 40: *E/4/768, pp. 793-828; L/P&S/6/325, pp. 341-[400].
- 304** 1 Dec., 1841; deductions from sums drawn by Capt. J.K. McCausland [ex-assistant to the Political Agent in Sabathu]. PC 3272, Dr 786, D 38: *E/4/768, pp. 607-20; L/P&S/6/325, pp. 201-[222].
- 305** 1 Feb., 1842; North-Western Provinces. PC 3273, Dr 13, D 3: E/4/769, pp. 329-88; L/P&S/6/326, pp. 147-[242].
- 306** 26 Jan., 1842; North-Eastern Frontier. PC 3310, Dr 26, D 2: *E/4/769, pp. 255-78; L/P&S/6/326, pp. 299-[442].
- 307** 22 Mar., 1842. PC 3321, Dr 147, D 5: *E/4/769, pp. 1119-64; L/P&S/6/326, pp. 575-[644].
- 308** 1 June, 1842; North-Western Provinces. PC 3374, Dr 286, D 8: *E/4/770, pp. 729-65; L/P&S/6/327, pp. 217-[274].
- 309** 16 Feb., 1842; case of Maj. E. Armstrong [Madras Light Infantry]. PC 3373, Dr 70, D 4: E/4/769, pp. 505-20; L/P&S/6/326, pp. 443-[468].
- 310** 30 Dec., 1842; assumption of Colaba. PC 3420, Dr 824, D 29: *E/4/772, pp. 1453-64; L/P&S/6/329, pp. 459-[478].
- 311** 24 May, 1842. PC 3442, Dr 285, D 7: *E/4/770, pp. 563-618; L/P&S/6/327, pp. 121-[216].
- 312** 13 July, 1842; North-Eastern Frontier. PC 3498, Dr 389, D 9: *E/4/771, pp. 63-92; L/P&S/6/328, pp. 69-[120].
- 313** 2 Nov., 1842; internal condition of the Rajput states. PC 3496, Dr 701, D 23: *E/4/772, pp. 464-93; L/P&S/6/329, pp. 115-[162].
- 314** 21 Dec., 1842. PC 3503, Dr 745, D 28: *E/4/772, pp. 1201-80; L/P&S/6/329, pp. 213-[326].
- 315** 13 July, 1842. PC 3501, Dr 390, D 10: *E/4/771, pp. 93-116; L/P&S/6/328, pp. 121-[156].
- 316** 17 Aug., 1842; claims to compensation for loss of property in the Kanara insurrection. PC 3502, Dr 441, D 12: *E/4/771, pp. 559-[570]; L/P&S/6/328, pp. 455-[472].
- 317** 24 May, 1842; adjustment in the allowances of Sir H. Pottinger [Resident in Sind]. PC 3499, Dr 284, D 6: *E/4/770, pp. 553-62; L/P&S/6/327, pp. 105-[120].
- 318** 17 Aug., 1842; North-Western Provinces. PC 3514, Dr 512, D 13: *E/4/771, pp. 541-612; L/P&S/6/328, pp. 229-[292].
- 319** 31 Aug., 1842; North-Western Provinces. PC 3516, Dr 561, D 15: *E/4/771, pp. 771-806; L/P&S/6/328, pp. 485-[544].
- 320** 21 Sept., 1842; affairs of Jodhpur. PC 3522, Dr 587, D 16: *E/4/771, pp. 919-48; L/P&S/6/328, pp. 545-[598].
- 321** 16 Nov., 1842; affairs of Hyderabad. PC 3552, Dr 661, D 24: *E/4/772, pp. 558-88; L/P&S/6/329, pp. 13-[72].
- 321X** Paragraphs on the assumption of Mandvi. See full entry at 1022.
- 322** 2 Nov., 1842; Mysore and Coorg. PC 3565, Dr 678, D 22: E/4/772, pp. 441-61; L/P&S/6/329, pp. 73-[114].
- 323** 1 Feb., 1843. PC 3640, Dr 65, D 2: E/4/773, pp. 345-446; L/P&S/6/330, pp. 305-[466].
- 324** 28 Sept., 1842; affairs of Oudh. PC 3598, Dr 598, D 19: *E/4/771, pp. 1171-94; L/P&S/6/328, pp. 661-[680] [sic].
- 325** 27 July, 1842; transmission of despatches directed to Lord Ellenborough [Governor-General]. PC 3581, Dr 453, D 11:

- *E/4/771, pp. 347-51; L/P&S/6/328, pp. 217-[228].
- 326** 21 Sept., 1842; ex-Raja of Satara. PC 3600, Dr 589, D 18: *E/4/771, pp. 957-64; L/P&S/6/328, pp. 619-[630].
- 327** 24 Aug., 1842; death of Csoma de Körös [Hungarian traveller]. PC 3601, Dr 520, D 14: *E/4/771, pp. 665-9; L/P&S/6/328, pp. 473-[484].
- 328** 21 Sept., 1842; proposed pension fund for the Nizam's local officers. PC 3608, Dr 588, D 17: *E/4/771, pp. 949-56; L/P&S/6/328, pp. 599-[618].
- 329** 14 Dec., 1842; affairs of Sindhia. PC 3618, Dr 768, D 26: *E/4/772, pp. 1060-75, L/P&S/6/329, pp. 327-[360].
- 330** 18 Jan., 1843. PC 3660, Dr 8, D 1: *E/4/773, pp. 27-98; L/P&S/6/330, pp. 1-[114].
- 331** 30 Dec., 1842. PC 3661, Dr 825, D 30: *E/4/772, pp. 1465-1510; L/P&S/6/329, pp. 477-[552].
- 332** 14 Dec., 1842; North-East Frontier. PC 3654, Dr 798, D 27: *E/4/772, pp. 1076-89; L/P&S/6/329, pp. 657-[682].
- 333** 30 Dec., 1842; ex-Raja of Kedah. PC 3688, Dr 826, D 31: *E/4/772, pp. 1511-29, L/P&S/6/329, pp. 553-[580].
- 334** 1 Feb., 1843. PC 3710, Dr 66, D 3: *E/4/773, pp. 447-98; L/P&S/6/330, pp. 467-[558].
- 335** 28 Sept., 1842; case of Charles Masson [traveller in Afghanistan and Baluchistan]. PC 3687, Dr 630, D 21: *E/4/771, pp. 1207-12, L/P&S/6/329, pp. 1A-[12].
- 336** 16 Nov., 1842; advance to Kurreem Khan [vakil to Nawab Hassan Ali Khan of Jhajjar]. Dr 731, D 25: *E/4/772, pp. 590-4; L/P&S/6/329, pp. 163-[166].
- 337** 1 Mar., 1843. PC 3796, Dr 113, D 4: *E/4/773, pp. 729-97; L/P&S/6/331, pp. 1-[114].
- 338** 28 Mar., 1843; affairs of Oudh. PC 3815, Dr 178, D 8: *E/4/773, pp. 1117-28; L/P&S/6/331, pp. 143-[166].
- 339** 21 Apr., 1843; North-East Frontier. PC 3798, Dr 221, D 9: *E/4/774, pp. 133-59; L/P&S/6/331, pp. 235-[282].
- 340** 30 May, 1843; affairs of the Nizam. PC 3801, Dr 304, D 11: E/4/774, pp. 801-30; L/P&S/6/331, pp. 383-[440].
- 341** 22 Mar., 1843; estate of Csoma de Körös. PC 3869, Dr 159, D 6: *E/4/773, pp. 855-60; L/P&S/6/331, pp. 127-[138].
- 342** 14 June, 1843; North-East Frontier. PC 3882, Dr 234, D 15: E/4/774, pp. 857-66; L/P&S/6/331, pp. 295-[310].
- 343** 4 Oct., 1843. PC 3901, Dr 627, D 30: *E/4/776, pp. 139-208; L/P&S/6/332, pp. 321-[434]. Paras. 118-20, PP, 1854, XLVII, 178.
- 344** 3 May, 1843; payments to Saleh Muhammad and Mohun Lall for services in Afghanistan. PC 3895, Dr 267, D 10: *E/4/774, pp. 503-10; L/P&S/6/331, pp. 369-[382].
- 345** 30 May, 1843; case of the family of Juggut Seth Indur Chund of Murshidabad. PC 3896, Dr 324, D 14: *E/4/774, pp. 845-52; L/P&S/6/331, pp. 465-[480].
- 346** 26 Sept., 1843; Mysore and Coorg. PC 3932, Dr 614, D 27: *E/4/775, pp. 945-62; L/P&S/6/332, pp. 203-[234].
- 347** 30 May, 1843; swords presented to Majs. Gen. Sir George Pollock, Sir William Nott, and Sir Robert Sale. PC 3937, Dr 323, D 13: E/4/774, pp. 837-44; L/P&S/6/331, pp. 453-[464].
- 348** 26 Sept., 1843. PC 3940, Dr 615, D 28: *E/4/775, pp. 963-90; L/P&S/6/332, pp. 235-[292].
- 349** 20 Sept., 1843; Bengal. PC 3953, Dr 598, D 23: *E/4/775, pp. 763-84; L/P&S/6/331, pp. 847-[882].
- 350** 20 Sept., 1843; North-Western Provinces. PC 3965, Dr 599, D 24: *E/4/775, pp. 785-812; L/P&S/6/331, pp. 883-[930].
- 351** 26 July, 1843; hostages and prisoners in Afghanistan. PC 3975, Dr 490, D 20: *E/4/775, pp. 239-46; L/P&S/6/331, pp. 685-[676] [sic]. 677-[684].
- 352** 25 Oct., 1843; North-Western Provinces. PC 3984, Dr 662, D 32: *E/4/776, pp. 341-75; L/P&S/6/332, pp. 527-[600].
- 353** 5 July, 1843; pensions to Afghans who had rendered service to the British. PC 3976, Dr 450, D 18: *E/4/775, pp. 85-92; L/P&S/6/331, pp. 603-[618].
- 354** 28 June, 1843; deficiency in the Shikarpur treasury. Dr 405, D 17: *E/4/774, pp. 1055-9; L/P&S/6/331, pp. 599-[602].
- 355** 20 Sept., 1843; North-East Frontier. PC 4019, Dr 601, D 26: *E/4/775, pp. 837-44; L/P&S/6/332, pp. 37-[50] [sic].
- 356** 20 Sept., 1843; affairs of Oudh. PC 4015, Dr 600, D 25: *E/4/775, pp. 813-36; L/P&S/6/332, pp. 1-[36].

- 357** 15 Nov., 1843. PC 4031, Dr 669, D 38: *E/4/776, pp. 602-57; L/P&S/6/333, pp. 41-[104], 113-[150].
- 358** 4 Oct., 1843; affairs of the Nizam. PC 4018, Dr 628, D 31: *E/4/776, pp. 209-24; L/P&S/6/332, pp. 435-[470].
- 359** 30 Aug., 1843; possible palace for the Governor-General at Agra. PC 4036, Dr 574, D 22: *E/4/775, pp. 559-72; L/P&S/6/331, pp. 783-[818].
- 360** 25 Oct., 1843; succession to the estate of Kythul. PC 4077, Dr 667, D 33: *E/4/776, pp. 376-97; L/P&S/6/332, pp. 619-[656].
- 361** 1 Nov., 1843; affairs of Jaipur. PC 4076, Dr 682, D 35: *E/4/776, pp. 552-69; L/P&S/6/333, pp. 175-[210].
- 362** 1 Nov., 1843; allowances of Lt. Col. T. Robinson [Officiating Political Agent in Mewar]. PC 4081, Dr 683, D 36: *E/4/776, pp. 570-8; L/P&S/6/333, pp. 211-[228].
- 363** 15 Nov., 1843; affairs of Gwalior. PC 4087, Dr 684, D 39: *E/4/776, pp. 658-75; L/P&S/6/333, pp. 229-[256].
- 364** 1 Nov., 1843; funeral of Prince Jamhooed Deen of Mysore. Dr 685, D 37: *E/4/776, pp. 580-5; L/P&S/6/333, pp. 257-[260].
- 365** 29 Nov., 1843; memorial from P. Friell [ex-employee of the Nawab of Oudh]. Dr 749, D 40: *E/4/776, pp. 822-5; L/P&S/6/333, pp. 281-[284].
- 366** 31 Jan., 1844; North-Western Provinces. PC 4159, Dr 23, D 3: *E/4/777, pp. 343-74; L/P&S/6/334, pp. 67-[134].
- 367** 6 Mar., 1844; North-Western Provinces. PC 4160, Dr 74, D 10: *E/4/777, pp. 751-84; L/P&S/6/334, pp. 223-[282].
- 368** 6 Dec., 1843; plunder of the ship *Sultana*. PC 4152, Dr 787, D 41: *E/4/776, pp. 886-90; L/P&S/6/333, pp. 285-[296].
- 369** 27 Mar., 1844. PC 4185, Dr 164, D 15: *E/4/777, pp. 1085-1174; L/P&S/6/334, pp. 549-[700].
- 370** 24 Jan., 1844; reductions in the allowances of Lt. Col. R. Taylor [Political Agent in Turkish Arabia]. PC 4182, Dr 24, D 2: *E/4/777, pp. 125-40; L/P&S/6/334, pp. 135-[162].
- 371** 28 Feb., 1844; Mysore and Coorg. PC 4186, Dr 75, D 6: *E/4/777, pp. 637-52; L/P&S/6/334, pp. 283-[310].
- 372** 21 May, 1844. PC 4205, Dr 259, D 21: *E/4/778, pp. 505-80; L/P&S/6/335, pp. 413-[548].
- 373** 27 Mar., 1844; North-East Frontier. PC 4193, Dr 163, D 14: *E/4/777, pp. 1045-84; L/P&S/6/334, pp. 469-[548].
- 374** 6 Mar., 1844; proposed pension fund for the Nizam's local officers. PC 4194, Dr 142, D 12: *E/4/777, pp. 793-802; L/P&S/6/334, pp. 441-[464]. +L.
- 375** 3 Apr., 1844; North-Western Provinces. PC 4219, Dr 180, D 18: *E/4/778, pp. 155-223; L/P&S/6/335, pp. 57-[174].
- 376** 31 Jan., 1844; claims of Charles Masson. PC 4207, Dr 71, D 5: *E/4/777, pp. 383-96; L/P&S/6/334, pp. 195-[222].
- 377** 24 Jan., 1844; recognition of foreign consuls. Dr 11, D 1: *E/4/777, pp. 119-24; L/P&S/6/334, pp. 1-[1A].
- 378** 6 Mar., 1844; compensation to Asst. Surgeon A. Leith and Capt. C.W. Whitelock of the Sind agency. PC 4220, Dr 97, D 11: *E/4/777, pp. 785-92; L/P&S/6/334, pp. 395-[410].
- 379** 1 May, 1844; North-Western Provinces. PC 4223, Dr 249, D 19: *E/4/778, pp. 391-428; L/P&S/6/335, pp. 267-[328].
- 379X** Paragraphs respecting documents required by the Dutch Government. Not traced.
- 380** 3 Apr., 1844; affairs of the Nizam. PC 4237, Dr 179, D 17: *E/4/778, pp. 121-54; L/P&S/6/335, pp. 1-[56].
- 381** 27 Mar., 1844; Jodhpur succession. PC 4226, Dr 165, D 16: *E/4/777, pp. 1175-84; L/P&S/6/334, pp. 701-[720].
- 382** 28 Feb., 1844; deficiency in the Shikarpur treasury. PC 4258, Dr 130, D 8: *E/4/777, pp. 657-61; L/P&S/6/334, pp. 421-[432].
- 383** 6 Mar., 1844; recognition of foreign consuls. Dr 148, D 13: *E/4/777, pp. 803-8; L/P&S/6/334, pp. 465-[468].
- 384** 17 July, 1844. PC 4344, Dr 424, D 27: *E/4/779, pp. 453-522; L/P&S/6/335, pp. 811-[946].
- 385** 26 June, 1844; Bengal. PC 4345, Dr 425, D 26; *E/4/778, pp. 1211-39; L/P&S/6/335, pp. 947-[1000].
- 386** 1 May, 1844; letter of G. Thompson [agent for the King of Delhi]. Dr 281, D 20: E/4/778, pp. 429-33; L/P&S/6/335, pp. 409-[412].
- 387** 28 Aug., 1844; annexation of the Cutch political agency to the government of Sind. PC 4356, Dr 626, D 32: *E/4/779, pp. 1177-88; L/P&S/6/336, pp. 447-[478].

388 2 Oct., 1844; disturbances in Saugor and Bundelkhand. PC 4445, Dr 718, D 33: *E/4/780, pp. 419-67; L/P&S/6/336, pp. 739-[830].

389 26 June, 1844; claim of Capt. J. Bean to compensation for his house at Quetta. PC 4384, Dr 411, D 25: *E/4/778, pp. 1203-10; L/P&S/6/335, pp. 637-[1656].

389X Paragraphs on the cases of Capt. C. Mackenzie, Capt. G. Lawrence, and Dr. G. Berwick. India PC 4385 altered by Board on 1 June, 1844: L/P&S/6/335, pp. 613-[620]. Dr 388, D 23 of 5 June, 1844.

390 2 Aug., 1844; frontier disputes with the Burmese; and removal of E. A. Blundell [Commissioner in Tenasserim]. PC 4391, Dr 584, D 30: *E/4/779, pp. 895-945; L/P&S/6/336, pp. 325-[404].

391 30 Oct., 1844. PC 4492, Dr 759, D 38: *E/4/780, pp. 709-821; L/P&S/6/337, pp. 349-[542].

392 6 Nov., 1844; affairs of Shorapur. PC 4495, Dr 769, D 39: *E/4/780, pp. 955-1002; L/P&S/6/337, pp. 21-[102].

393 2 Oct., 1844; charges against Capt. W. B. Jackson [Madras Native Infantry]. PC 4482, Dr 719, D 34: *E/4/780, pp. 469-92; L/P&S/6/336, pp. 831-[870].

394 6 Nov., 1844. PC 4510, Dr 794, D 44: *E/4/780, pp. 1031-95; L/P&S/6/337, pp. 543-[664].

395 6 Nov., 1844; Mysore and Coorg. PC 4515, Dr 795, D 45: *E/4/780, pp. 1109-40; L/P&S/6/337, pp. 219-[258].

396 6 Nov., 1844; North-Western Provinces. PC 4518, Dr 796, D 46: *E/4/780, pp. 1141-57; L/P&S/6/337, pp. 259-[288].

397 20 Nov., 1844; North-Eastern Frontier. PC 4525, Dr 821, D 48: *E/4/781, pp. 61-92; L/P&S/6/337, pp. 685-[746].

398 20 Nov., 1844; North-Western Provinces. PC 4543, Dr 822, D 49: *E/4/781, pp. 93-132; L/P&S/6/337, pp. 747-[818].

399 6 Nov., 1844; reduction in allowances of Maj. Sir W. C. Harris [ex-Envoy to Shoa]. PC 4523, Dr 770, D 40: *E/4/780, pp. 1003-8; L/P&S/6/337, pp. 103-[118].

400 6 Nov., 1844; affairs of the late Prince Jamhoo Deen. PC 4528, Dr 773, D 43: *E/4/780, pp. 1097-1108; L/P&S/6/337, pp. 159-[178].

401 6 Nov., 1844; further claims on account of services in Afghanistan. PC 4526, Dr 771, D

41: *E/4/780, pp. 1009-21; L/P&S/6/337, pp. 119-[142].

402 6 Nov., 1844; case of Seth Kishen Chund of Murshidabad. PC 4527, Dr 772, D 42: *E/4/780, pp. 1023-30; L/P&S/6/337, pp. 143-[158].

403 4 Dec., 1844; claims of the King of Delhi. PC 4571, Dr 854, D 53: *E/4/781, pp. 511-72; L/P&S/6/337, pp. 823-[906].

404 27 Nov., 1844; North-Western Provinces. PC 4556, Dr 855, D 52: *E/4/781, pp. 307-31; L/P&S/6/338, pp. 1-[44].

405 4 Dec., 1844. PC 4572, Dr 914, D 54: *E/4/781, pp. 573-91; L/P&S/6/338, pp. 153-[196].

406 6 Nov., 1844; cases of Moolla Moossa and Moolla Ibrahim of Meshed. PC 4573, Dr 819, D 47: *E/4/780, pp. 1159-66; L/P&S/6/337, pp. 665-[684].

407 19 Mar., 1845. PC 4651, Dr 113, D 9: *E/4/782, pp. 519-638; L/P&S/6/339, pp. 543-[747] [sic].

408 27 Nov., 1844; distribution of the arrears recovered from the Shah of Persia. Dr 846, D 51: *E/4/781, pp. 299-305; L/P&S/6/337, pp. 321-[328].

409 18 Dec., 1844; memorial from Capt. W. Hollings [ex-Assistant, Thagi and Dakaiti Department]. PC 4610, Dr 942, D 56: *E/4/781, pp. 673-80; L/P&S/6/338, pp. 377-[392].

410 15 Jan., 1845; North-East Frontier. PC 4635, Dr 16, D 1: E/4/781, pp. 1049-64; L/P&S/6/339, pp. 21-[52].

411 5 Feb., 1845; North-Western Provinces. PC 4660, Dr 37, D 4: *E/4/782, pp. 101-30; L/P&S/6/339, pp. 165-[224].

412 4 Dec., 1844; case of Sayd Hassan from Lahore. Dr 927, D 55: E/4/781, pp. 593-8; L/P&S/6/338, pp. 325-[328].

413 7 Mar., 1845; affairs of Oudh. PC 4669, Dr 111, D 5: *E/4/782, pp. 377-403; L/P&S/6/339, pp. 427-[474].

414 7 Mar., 1845; Mysore and Coorg. PC 4668, Dr 112, D 6: *E/4/782, pp. 405-14; L/P&S/6/339, pp. 475-[494].

415 19 Mar., 1845. PC 4670, Dr 164, D 11: *E/4/782, pp. 647-84; L/P&S/6/339, pp. 761-[838] [sic].

416 22 Jan., 1845; memorial from Capt. A. C. Rainey [Bengal Native Infantry]. Dr 36, D 3: *E/4/781, pp. 1177-80; L/P&S/6/339, pp. 163-[164].

- 417** 19 Mar., 1845; North-Eastern Frontier. PC 4711, Dr 165, D 12: *E/4/782, pp. 685-710; L/P&S/6/339, pp. 839-[876].
- 418** 7 Mar., 1845; claims of Capts. G. Lawrence and C. Mackenzie, and Dr. G. Berwick in connection with their captivity in Afghanistan. PC 4712, Dr 130, D 7: *E/4/782, pp. 415-30; L/P&S/6/339, pp. 495-[522].
- 419** 19 Mar., 1845; case of Asst. Surgeon A. Leith and Capt. C. W. Whitelock of the Sind Agency. PC 4715, Dr 163, D 10: E/4/782, pp. 639-46; L/P&S/6/339, pp. 749-[760].
- 420** 10 Dec., 1845; affairs of Gwalior. PC 5011, Dr 923, D 45: *E/4/786, pp. 215-56, L/P&S/6/342, pp. 351-[432].
- 421** 21 May, 1845; succession to the Holkar state. PC 4773, Dr 370, D 17: *E/4/783, pp. 1143-52; L/P&S/6/340, pp. 215-[238].
- 422** 4 June, 1845. PC 4811, Dr 411, D 22: *E/4/784, pp. 87-139; L/P&S/6/340, pp. 497-[590].
- 423** 21 May, 1845; debts of the Raja of Mysore. PC 4798, Dr 371, D 18: *E/4/783, pp. 1153-68; L/P&S/6/340, pp. 327-[352].
- 424** 2 Apr., 1845; correspondence with Capt. C. Mackenzie [Madras Native Infantry]. PC 4797, Dr 244, D 14: *E/4/783, pp. 241-5; L/P&S/6/340, pp. 1-[12].
- 425** 21 May, 1845; Bengal. PC 4812, Dr 384, D 21: *E/4/783, pp. 1201-22; L/P&S/6/340, pp. 353-[388].
- 426** 21 May, 1845; Bhopal succession. PC 4808, Dr 372, D 19: *E/4/783, pp. 1169-78; L/P&S/6/340, pp. 239-[258].
- 427** 21 May, 1845; North-Western Provinces. PC 4818, Dr 373, D 20: *E/4/783, pp. 1179-1200; L/P&S/6/340, pp. 259-[306].
- 428** 7 May, 1845; Mohun Lall's services in Afghanistan. Dr 359, D 16: *E/4/783, pp. 821-8; L/P&S/6/340, pp. 207-[214].
- 429** 1 Oct., 1845. PC 4881, Dr 701, D 32: *E/4/785, pp. 454-512; L/P&S/6/341, pp. 445-[550].
- 430** 2 July, 1845; acquisition of the Danish settlements in India. Dr 513, D 24: *E/4/784, pp. 347-55; L/P&S/6/340, pp. 595-[614].
- 431** 20 Aug., 1845; North-Eastern Frontier. PC 4903, Dr 637, D 28: *E/4/784, pp. 957-68; L/P&S/6/341, pp. 29-[48].
- 432** 5 Nov., 1845; presentation of nazzar [presents] to the King of Delhi. PC 4947, Dr 702, D 37: *E/4/785, pp. 918-36; L/P&S/6/341, pp. 551-[566], 595-[586] [sic].
- 433** 2 Jan., 1846; affairs of Shorapur. PC 5059, Dr 977, D 1: *E/4/786, pp. 501-17; L/P&S/6/342, pp. 503-[536].
- 434** 27 Aug., 1845; North-Western Provinces. PC 4918, Dr 638, D 29: *E/4/784, pp. 979-1000; L/P&S/6/341, pp. 49-[88].
- 435** 1 Oct., 1845; application of Maj. H. Rawlinson [Political Agent in Turkish Arabia] for leave of absence. PC 4981, Dr 746, D 33: *E/4/785, pp. 514-19; L/P&S/6/342, pp. 1-[12].
- 436** 10 Dec., 1845. PC 5002, Dr 885, D 44: *E/4/786, pp. 121-214; L/P&S/6/342, pp. 173-[334].
- 437** 1 Oct., 1845; allowances of Maj. G. Macgregor [ex-Political Agent at Jellalabad]. PC 4987, Dr 748, D 35: *E/4/785, pp. 528-33; L/P&S/6/342, pp. 25-[36].
- 438** 12 Nov., 1845; North-Western Provinces. PC 4998, Dr 844, D 41: *E/4/785, pp. 984-1011; L/P&S/6/342, pp. 113-[156].
- 439** 14 Jan., 1846; hostages and prisoners in Afghanistan. PC 5077, Dr 2, D 4: *E/4/786, pp. 653-64; L/P&S/6/343, pp. 25-[50].
- 440** 5 Nov., 1845; affairs of Oudh. PC 4986, Dr 824, D 38: *E/4/785, pp. 938-49; L/P&S/6/342, pp. 81-[100].
- 441** 28 Jan., 1846; Mysore and Coorg. PC 5065, Dr 34, D 7: *E/4/786, pp. 763-82; L/P&S/6/343, pp. 295-[325] [sic].
- 442** 2 Jan., 1846. PC 5041, Dr 978, D 2: *E/4/786, pp. 519-70; L/P&S/6/342, pp. 537-[626].
- 443** 14 Jan., 1846; allowances of Mohun Lall. PC 5076, Dr 3, D 5: *E/4/786, pp. 665-76; L/P&S/6/343, pp. 51-[77] [sic].
- 444** 14 Jan., 1846; case of Capt. W. B. Jackson [Madras Native Infantry]. PC 5085, Dr 1, D 3: *E/4/786, pp. 641-52; L/P&S/6/343, pp. 1-[24].
- 445** 14 Jan., 1846; North-Western Provinces. PC 5078, Dr 15, D 6: *E/4/786, pp. 677-700; L/P&S/6/343, pp. 77A-[120].
- 446** 23 Apr., 1846; rewards for Capts. G. Lawrence and C. Mackenzie and Maj. E. Pottinger for services rendered in Afghanistan. PC 5145, Dr 230, D 11: E/4/787, pp. 927-32; L/P&S/6/343, pp. 603-[618].
- 447** 23 Apr., 1846; North-Western Provinces. PC 5168, Dr 231, D 12: *E/4/787, pp. 933-54; L/P&S/6/343, pp. 619-[662].
- 448** 25 Feb., 1846; affairs of the Nizam. PC

- 5156, Dr 94, D 8: *E/4/786, pp. 979-84; L/P&S/6/343, pp. 403-[414].
- 449** 15 July, 1846; passports for British subjects in foreign countries. PC 5197, Dr 481, D 22: *E/4/788, pp. 617-24; L/P&S/6/344, pp. 561-[580].
- 450** 28 May, 1846. PC 5208, Dr 353, D 16; *E/4/787, pp. 1215-63; L/P&S/6/344, pp. 129-[216].
- 451** 13 May, 1846; Bengal. PC 5214, Dr 310, D 15: *E/4/787, pp. 1077-88; L/P&S/6/344, pp. 105-[127] [sic].
- 452** 19 Aug., 1846. PC 5249, Dr 535, D 25: *E/4/789, pp. 707-812; L/P&S/6/345, pp. 213-[382].
- 453** 12 Aug., 1846; North-East Frontier. PC 5247, Dr 463, D 24: *E/4/789, pp. 127-68; L/P&S/6/344, pp. 491-[560].
- 454** 24 June, 1846; Bengal. PC 5266, Dr 431, D 18: *E/4/788, pp. 399-407; L/P&S/6/344, pp. 307-[326].
- 455** 17 June, 1846; case of E. Blundell [ex-Governor of the Straits Settlements]. PC 5283, Dr 411, D 17: *E/4/788, pp. 355-61; L/P&S/6/344, pp. 245-[256].
- 456** 24 June, 1846; Sind. PC 5286, Dr 443, D 19: E/4/788, pp. 409-16; L/P&S/6/344, pp. 327-[342].
- 457** 24 June, 1846; ex-Raja of Satara. PC 5308, Dr 445, D 21: E/4/788, pp. 421-38; L/P&S/6/344, pp. 359-[392].
- 458** 9 Sept., 1846; Bundelkhand and Saugor disturbances. PC 5335, Dr 595, D 28: *E/4/789, pp. 917-24; L/P&S/6/345, pp. 513-[532].
- 459** 11 Nov., 1846; North-Western Provinces. PC 5392, Dr 762, D 31: *E/4/790, pp. 553-74; L/P&S/6/346, pp. 5-[50].
- 460** 22 Sept., 1846; North-Eastern Frontier. PC 5371, Dr 651, D 29: E/4/789, pp. 1119-30; L/P&S/6/345, pp. 561-[580].
- 460X** Affairs of the Nizam. See full entry at 466.
- 461** 25 Nov., 1846; North-Western Provinces. PC 5414, Dr 800, D 32: *E/4/790, pp. 685-701; L/P&S/6/346, pp. 105-[140].
- 462** 23 Dec., 1846; Mysore and Coorg. PC 5437, Dr 846, D 35: *E/4/790, pp. 1035-46; L/P&S/6/346, pp. 177-[196].
- 463** 2 Dec., 1846; affairs of Gwalior. PC 5438, Dr 817, D 34: *E/4/790, pp. 787-803; L/P&S/6/346, pp. 145-[176].
- 464** 23 Dec., 1846. PC 5453, Dr 883, D 37: *E/4/790, pp. 1061-1138; L/P&S/6/346, pp. 229-[366].
- 465** 23 Dec., 1846; North-Western Provinces. PC 5455, Dr 859, D 36: *E/4/790, pp. 1047-59; L/P&S/6/346, pp. 197-[224].
- 466** 27 Jan., 1847; affairs of the Nizam. PC 5474, Dr 12, D 1: *E/4/791, pp. 265-304; L/P&S/6/347, pp. 45-[118].
- 467** 30 Mar., 1847; North-Eastern Frontier. PC 5486, Dr 204, D 5: *E/4/791, pp. 996-1004; L/P&S/6/348, pp. 1-[20].
- 468** 10 Mar., 1847. PC 5511, Dr 141, D 2: *E/4/791, pp. 685-745; L/P&S/6/347, pp. 437-[546].
- 469** 23 Mar., 1847; affairs of Gwalior. PC 5523, Dr 181, D 4: *E/4/791, pp. 869-94; L/P&S/6/347, pp. 589-[632].
- 470** 14 Apr., 1847. PC 5529, Dr 205, D 6: *E/4/791, pp. 1092-1177; L/P&S/6/348, pp. 21-[96].
- 471** 28 Apr., 1847; North-Western Provinces. PC 5554, Dr 246, D 9: *E/4/791, pp. 1351-70; L/P&S/6/348, pp. 117-[152].
- 472** 21 Apr., 1847. PC 5561, Dr 262, D 7: *E/4/791, pp. 1232-80; L/P&S/6/348, pp. 287-[370].
- 473** 16 June, 1847; Bengal. PC 5662, Dr 409, D 10: *E/4/792, pp. 751-68; L/P&S/6/348, pp. 587-[622].
- 474** 16 June, 1847; pecuniary claims connected with Afghanistan. PC 5665, Dr 431, D 11: *E/4/792, pp. 769-83; L/P&S/6/349, pp. 1-[32].
- 475** 16 June, 1847; North-Eastern Frontier. PC 5666, Dr 434, D 14: *E/4/792, pp. 805-13; L/P&S/6/349, pp. 57-[78].
- 476** 16 June, 1847; ex-Raja of Satara. PC 5667, Dr 432, D 12: *E/4/792, pp. 789-98; L/P&S/6/349, pp. 37-[58].
- 477** 16 June, 1847; case of A. Reghelini [in service of the late Begum Sumroo]. PC 5665, Dr 433, D 13: *E/4/792, pp. 799-803; L/P&S/6/349, pp. 1-[20], 33-[36].
- 478** 8 Sept., 1847. PC 5700, Dr 639, D 19: *E/4/793, pp. 601-80; L/P&S/6/350, pp. 15-[158].
- 479** 14 July, 1847; Mysore and Coorg. PC 5697, Dr 534, D 15: *E/4/792, pp. 1235-46; L/P&S/6/349, pp. 509-[528].
- 480** 18 Aug., 1847; North-Western Provinces. PC 5716, Dr 616, D 17: *E/4/793, pp. 333-58; L/P&S/6/349, pp. 559-[602].

- 481** 25 Aug., 1847; house in Hyderabad of Capt. C.W. Whitelock [ex-Assistant Political Agent in Lower Sind]. PC 5720, Dr 638, D 18: *E/4/793, pp. 433-9; L/P&S/6/350, pp. 1-[14].
- 482** 18 Aug., 1847; accounts of Col. R. Taylor [ex-Political Agent in Turkish Arabia]. PC 5721, Dr 615, D 16: *E/4/793, pp. 321-32; L/P&S/6/349, pp. 541-[558].
- 483** 1 Dec., 1847; North-Western Provinces. PC 5852, Dr 908, D 24: *E/4/794, pp. 759-72; L/P&S/6/350, pp. 533-[560].
- 484** 19 Jan., 1848; affairs of the Nizam. PC 5859, Dr 1, D 1: *E/4/795, pp. 299-371; L/P&S/6/352, pp. 1-[88].
- 484X** Aden. India PC 5883 cancelled by Board on 9 Dec., 1847: L/P&S/6/350, pp. 685-[704]. Bombay DR 998, D 1 of 19 Jan., 1848.
- 485** 1 Feb., 1848; pensions recommended for Afghans. PC 5911, Dr 36, D 3: *E/4/795, pp. 541-62; L/P&S/6/352, pp. 93-[126].
- 486** 16 Feb., 1848; North-Western Provinces. PC 5931, Dr 79, D 5: *E/4/795, pp. 755-n1; L/P&S/6/352, pp. 179-[210].
- 487** 16 Feb., 1848; North-East Frontier. PC 5930, Dr 78, D 4: *E/4/795, pp. 745-53; L/P&S/6/352, pp. 159-[178].
- 488** 19 Apr., 1848. PC 5966, Dr 241, D 9: *E/4/796, pp. 363-455A; L/P&S/6/352, pp. 577-[734].
- 489** 6 Sept., 1848; claims connected with Afghanistan. PC 6193, Dr 610, D 21: *E/4/797, pp. 1015-26; L/P&S/6/354, pp. 381-[396], 401-[408].
- 489X** Death of ex-Raja of Satara. India PC 5965 altered by Board on 5 Feb., 1848: L/P&S/6/352, pp. 275-[286]. Dr 80, D 6 of 16 Feb., 1848.
- 490** 15 Mar., 1848; North-East Frontier. PC 5974, Dr 138, D 7: *E/4/795, pp. 1211-18; L/P&S/6/352, pp. 413-[428].
- 491** 29 Mar., 1848; Ava and Siam. PC 5975, Dr 175, D 8: *E/4/795, pp. 1475-83; L/P&S/6/352, pp. 477-[496].
- 492** 3 May, 1848; North-Western Provinces. PC 6027, Dr 267, D 10: *E/4/796, pp. 515-28; L/P&S/6/353, pp. 25-[50].
- 493** 4 July, 1848; affairs of Oudh. PC 6026, Dr 429, D 14: *E/4/797, pp. 11-26; L/P&S/6/353, pp. 623-[652].
- 494** 14 June, 1848. PC 6047, Dr 352, D 12: *E/4/796, pp. 1167-1204; L/P&S/6/353, pp. 375-[438].
- 495** 10 May, 1848; Capt. C.W. Whitelock's house in Hyderabad. PC 6056, Dr 305, D 11: *E/4/796, pp. 669-76; L/P&S/6/353, pp. 203-[218].
- 496** 26 July, 1848. PC 6064, Dr 449, D 16: *E/4/797, pp. 377-461; L/P&S/6/353, pp. 711-[862].
- 497** 21 June, 1848; North-Western Provinces. PC 6080, Dr 396, D 13: *E/4/796, pp. 1287-98; L/P&S/6/353, pp. 493-[520].
- 498** 19 July, 1848; Bengal. PC 6100, Dr 448, D 15: *E/4/797, pp. 301-32; L/P&S/6/353, pp. 653-[710] [sic].
- 499** 30 Aug., 1848; North-Western Provinces. PC 6171, Dr 580, D 20: *E/4/797, pp. 953-68; L/P&S/6/354, pp. 315-[340].
- 500** 16 Aug., 1848; medical school at Hyderabad. PC 6170, Dr 553, D 19: *E/4/797, pp. 825-45; L/P&S/6/354, pp. 249-[284].
- 501** 20 Sept., 1848; claims connected with Afghanistan. PC 6199, Dr 653, D 22: *E/4/797, pp. 1357-65; L/P&S/6/354, pp. 711-[730].
- 502** 22 Nov., 1848; debts of the Raja of Mysore. PC 6254, Dr 769, D 25: *E/4/798, pp. 791-806; L/P&S/6/354, pp. 619-[650].
- 503** 22 Nov., 1848; Doongur Sing and the Shikawattee plunderers. PC 6271, Dr 770, D 26: *E/4/798, pp. 807-21; L/P&S/6/354, pp. 651-[678].
- 504** 17 Jan., 1849; North-East Frontier. PC 6287, Dr 12, D 3: *E/4/799, pp. 125-44; L/P&S/6/355, pp. 37-[76].
- 505** 21 Feb., 1849. PC 6299, Dr 94, D 8: *E/4/799, pp. 539-616; L/P&S/6/355, pp. 481-[616].
- 506** 17 Jan., 1849. PC 6298, Dr 11, D 2: E/4/799, pp. 115-23; L/P&S/6/355, pp. 17-[36].
- 507** 14 Feb., 1849; Mysore and Coorg. PC 6302, Dr 83, D 6: *E/4/799, pp. 419-33; L/P&S/6/355, pp. 297-[320].
- 508** 24 Jan., 1849; lapse of the state of Satara. PC 6304, Dr 9, D 4: E/4/799, pp. 199-211; L/P&S/6/355, pp. 795-[810], 1035-[1046]. PP, 1849, XXXIX, 150-1.
- 509** 28 Mar., 1849; Cis and Trans-Sutlej and Hill Territories. PC 6343, Dr 203, D 12: *E/4/799, pp. 1081-1174; L/P&S/6/356, pp. 47-[148], 177-[240] [sic].
- 510** 31 Jan., 1849; North-Western Provinces. PC 6326, Dr 64, D 5: *E/4/799, pp. 265-89; L/P&S/6/355, pp. 105-[144].

511 18 Dec., 1849; affairs of the Nizam. PC 6524, Dr 746, D 40: *E/4/802, pp. 803-47; L/P&S/6/359, pp. 215-[272].

512 14 Mar., 1849. PC 6360, Dr 187, D 10: *E/4/799, pp. 903-26; L/P&S/6/356, pp. 1-[38].

513 14 Feb., 1849; North-Western Provinces. PC 6362, Dr 95, D 7: *E/4/799, pp. 435-46; L/P&S/6/355, pp. 617-[640].

514 18 Apr., 1849. PC 6390, Dr 247, D 14: *E/4/800, pp. 143-94; L/P&S/6/356, pp. 241-[332]. Para. 79. *Sessional Papers of the House of Lords*, 1857, Sess. I, VIII, 303-4.

515 18 Apr., 1849; application of Maj. H. Rawlinson [Political Agent in Turkish Arabia] for leave of absence. PC 6432, Dr 249, D 15: E/4/800, pp. 195-201; L/P&S/6/356, pp. 333-[352].

516 7 Mar., 1849; family of the ex-Raja of Satara. Dr 184, D 9: *E/4/799, pp. 777-86; L/P&S/6/355, pp. 787-[794].

517 24 Apr., 1849; North-Western Provinces. PC 6442, Dr 272, D 18: *E/4/800, pp. 303-18; L/P&S/6/356, pp. 389-[420].

518 24 Apr., 1849; North-East Frontier. PC 6441, Dr 271, D 17: *E/4/800, pp. 295-302; L/P&S/6/356, pp. 371-[388].

519 24 Apr., 1849; letters and presents from the Bali Rajas. PC 6445, Dr 270, D 16: *E/4/800, pp. 287-94; L/P&S/6/356, pp. 353-[370].

520 1 Aug., 1849. PC 6454, Dr 472, D 23: *E/4/801, pp. 121-80; L/P&S/6/357, pp. 195-[288].

521 18 Apr., 1849; recognition of foreign consuls. Dr 229, D 13: *E/4/800, pp. 135-41; L/P&S/6/356, pp. 239A-[240] [sic].

522 9 May, 1849; claims connected with Afghanistan. PC 6459, Dr 335, D 21: E/4/800, pp. 503-12; L/P&S/6/356, pp. 437-[456].

523 16 Jan., 1850. PC 6499, Dr 901, D 4: *E/4/803, pp. 211-76; L/P&S/6/359, pp. 803-[946].

524 15 Aug., 1849. PC 6538, Dr 525, D 30: *E/4/801, pp. 491-540; L/P&S/6/357, pp. 433-[526].

525 1 Aug., 1849; North-East Frontier. PC 6531, Dr 494, D 26: *E/4/801, pp. 303-12; L/P&S/6/357, pp. 301-[318].

525X Annexation of Punjab. India PC 6530 altered by Board on 16 June, 1849: L/P&S/6/357, pp. 155-[178]. Dr 487, D 24 of 1 Aug., 1849.

526 15 Aug., 1849; Mysore and Coorg. PC 6548, Dr 524, D 29: *E/4/801, pp. 475-90; L/P&S/6/357, pp. 405-[432].

527 5 Sept., 1849. PC 6577, Dr 573, D 32: *E/4/801, pp. 811-68; L/P&S/6/358, pp. 257-[360].

528 15 Aug., 1849; family of the ex-Raja of Satara. PC 6564, Dr 523, D 28: *E/4/801, pp. 465-74; L/P&S/6/357, pp. 381-[404].

529 1 Aug., 1849; Lt. W.H. Wyburd [Indian Navy]. PC 6569, Dr 505, D 27: *E/4/801, pp. 313-21; L/P&S/6/357, pp. 341-[360].

530 1 Aug., 1849; memorial of Khosroo Begum concerning gardens in Delhi. PC 6572, Dr 493, D 25: E/4/801, pp. 217-302; L/P&S/6/357, pp. 289-[300].

531 22 Aug., 1849; North-Western Provinces. PC 6571, Dr 545, D 31: *E/4/801, pp. 575-82; L/P&S/6/357, pp. 551-[570].

532 26 Sept., 1849; North-East Frontier. PC 6603, Dr 654, D 33: *E/4/801, pp. 1093-1101; L/P&S/6/358, pp. 361-[380].

532X Succession to the estate of Bughat. See full entry at 540.

533 3 Oct., 1849; claims of Maj. G. Lawrence and Capt. J. Nicholson [Deputy Commissioners in Trans-Indus Punjab]. PC 6610, Dr 655, D 34: *E/4/801, pp. 1251-8; L/P&S/6/358, pp. 381-[392].

534 13 Feb., 1850. PC 6630, Dr 33, D 7: *E/4/803, pp. 605-72; L/P&S/6/360, pp. 49-[172].

535 14 Nov., 1849; Bengal. PC 6648, Dr 750, D 36: *E/4/802, pp. 205-40; L/P&S/6/359, pp. 321-[384].

536 7 Nov., 1849; removal of Capt. J.D. Cunningham from the office of Political Agent in Bhopal. Dr 682, D 35: *E/4/802, pp. 19-27; L/P&S/6/358, pp. 441-[448], 449-[452].

537 5 Dec., 1849; Muslim relics. PC 6662, Dr 784, D 39: E/4/802, pp. 663-7; L/P&S/6/359, pp. 623-[634].

538 13 Feb., 1850. PC 6693, Dr 63, D 8: *E/4/803, pp. 673-713; L/P&S/6/360, pp. 233-[316].

539 28 Dec., 1849; Mysore and Coorg. PC 6692, Dr 859, D 41: *E/4/802, pp. 997-1006; L/P&S/6/359, pp. 709-[728].

540 21 Nov., 1849; succession to the estate of Bughat. PC 6656, Dr 761, D 37: *E/4/802, pp. 337-52; L/P&S/6/359, pp. 385-[408]. *PP*, 1854, XLVII, 180.

541 16 Jan., 1850; North-Western Provinces. PC 6696, Dr 6, D 5: *E/4/803, pp. 277-94; L/P&S/6/360, pp. 1-[36].

- 542** 16 Jan., 1850; affairs of Oudh. PC 6704, Dr 900, D 3: *E/4/803, pp. 165-210; L/P&S/6/359, pp. 729-[802].
- 543** 20 Feb., 1850. PC 6730, Dr 105, D 9: *E/4/803, pp. 813-58; L/P&S/6/360, pp. 465-[552].
- 544** 7 Jan., 1850; proposed mission from Nepal to England. PC 6760, Dr 18, D 1: E/4/803, pp. 69-75; L/P&S/6/360, pp. 37-[48].
- 545** 5 Mar., 1850; Lahore and the Sutlej districts. PC 6756, Dr 147, D 10: *E/4/803, pp. 989-97; L/P&S/6/360, pp. 629-[648].
- 546** 30 Jan., 1850; wish of the ex-Raja of Coorg to visit England. PC 6757, Dr 45, D 6: *E/4/803, pp. 427-31; L/P&S/6/360, pp. 221-[232].
- 547** 27 Mar., 1850; North-Western Provinces. PC 6811, Dr 198, D 12: *E/4/803, pp. 1293-1310; L/P&S/6/360, pp. 753-[784].
- 548** 31 July, 1850. PC 6902, Dr 493, D 22: *E/4/805, pp. 553-681; L/P&S/6/362, pp. 1-[252].
- 549** 27 Mar., 1850; North-East Frontier. PC 6824, Dr 197, D 11: *E/4/803, pp. 1283-91; L/P&S/6/360, pp. 733-[752].
- 550** 15 May, 1850. PC 6840, Dr 301, D 13: *E/4/804, pp. 559-644; L/P&S/6/361, pp. 181-[340].
- 551** 17 July, 1850; Jallundar jagirs. PC 6932, Dr 502, D 20: *E/4/805, pp. 401-11; L/P&S/6/362, pp. 253-[276].
- 552** 30 May, 1850; North-Eastern Frontier. PC 6888, Dr 359, D 14: *E/4/804, pp. 879-86; L/P&S/6/361, pp. 531-[542].
- 553** 20 June, 1850; North-Western Provinces. PC 6893, Dr 420, D 17: *E/4/804, pp. 1225-36; L/P&S/6/361, pp. 639-[656].
- 554** 3 July, 1850; Bengal. PC 6913, Dr 440, D 18: *E/4/805, pp. 217-50; L/P&S/6/361, pp. 705-[772].
- 555** 18 Sept., 1850. PC 6950, Dr 611, D 27: *E/4/806, pp. 505-608; L/P&S/6/363, pp. 327-[524].
- 556** 10 July, 1850; family of the ex-Raja of Satara. PC 6942, Dr 464, D 19: *E/4/805, pp. 353-63; L/P&S/6/361, pp. 773-[796]. *PP*, 1850, XLI, 210.
- 557** 5 June, 1850; Delhi succession. PC 6934, Dr 392, D 15: *E/4/804, pp. 923-8; L/P&S/6/361, pp. 623-[634].
- 558** 11 Sept., 1850; enquiry into the conduct of R.N. Hamilton [Resident at Indore].
- PC 6960, Dr 631, D 26: *E/4/806, pp. 367-86; L/P&S/6/363, pp. 167-[198].
- 559** 4 Sept., 1850; annexation of Sambalpur. PC 6063, Dr 610, D 24: *E/4/806, pp. 265-73; L/P&S/6/362, pp. 339-[358].
- 560** 11 Sept., 1850; case of Maj. H. Johnson [Bengal Native Infantry]. PC 7015, Dr 630, D 25: *E/4/806, pp. 361-6; L/P&S/6/362, pp. 411-[426].
- 561** 9 Oct., 1850; Bengal. PC 7010, Dr 680, D 29: E/4/806, pp. 1021-48; L/P&S/6/363, pp. 21-[68].
- 562** 2 Oct., 1850; claims connected with Afghanistan. PC 7021, Dr 699, D 28: *E/4/806, pp. 895-913; L/P&S/6/363, pp. 69-[100].
- 563** 30 Oct., 1850. PC 7020, Dr 746, D 30: *E/4/806, pp. 1237-48; L/P&S/6/363, pp. 303-[326].
- 564** 11 Dec., 1850; North-East Frontier. PC 7075, Dr 806, D 33: *E/4/807, pp. 669-82; L/P&S/6/363, pp. 805-[874].
- 565** 18 Dec., 1850. PC 7086, Dr 879, D 34: *E/4/807, pp. 775-860; L/P&S/6/363, pp. 661-[804] [*sic*].
- 566** 5 Mar., 1851; Punjab and North-West Frontier. PC 7128, Dr 916, D 9: *E/4/808, pp. 629-50; L/P&S/6/363, pp. 1091-[1136], 1153-[1168].
- 567** 3 Jan., 1851; charges against H. Inglis [assistant to the Political Agent, Khasi Hills]. PC 7110, Dr 906, D 2: *E/4/807, pp. 1115-30; L/P&S/6/363, pp. 1009-[1038].
- 568** 19 Feb., 1851; memorial from Lt. Col. G. Lawrence [Deputy Commissioner, Trans-Indus]. PC 7216, Dr 108, D 8: *E/4/808, pp. 381-5; L/P&S/6/364, pp. 317-[328].
- 569** 18 Dec., 1850; North-East Frontier. PC 7113, Dr 880, D 35: *E/4/807, pp. 861-8; L/P&S/6/363, pp. 875-[890].
- 570** 4 Dec., 1850; case of Capt. J.D. Cunningham [Deputy Commissioner, Trans-Indus]. PC 7111, Dr 864, D 32: *E/4/807, pp. 581-6; L/P&S/6/363, pp. 649-[660].
- 571** 19 Mar., 1851. PC 7158, Dr 158, D 11: *E/4/808, pp. 934A-88; L/P&S/6/364, pp. 381-[484].
- 572** 3 Jan., 1851; Mysore and Coorg. PC 7118, Dr 905, D 1: *E/4/807, pp. 1109-14; L/P&S/6/363, pp. 943-[954].
- 573** 18 Dec., 1850; conduct of the government of Mauritius with respect to the *Medea*. PC 7144, Dr 893, D 36: *E/4/807, pp. 869-73; L/P&S/6/363, pp. 915-[926].

574 22 Jan., 1851; Aga Khan Mehlatce. PC 7157, Dr 22, D 4: *E/4/807, pp. 1447-62; L/P&S/6/364, pp. 1-[32].

575 19 Feb., 1851; North-Western Provinces. PC 7154, Dr 62, D 7: *E/4/808, pp. 373-80; L/P&S/6/364, pp. 101-[108], 113-[116].

576 29 Jan., 1851; Afghan cases. PC 7186, Dr 61, D 6: *E/4/807, pp. 1607-14; L/P&S/6/364, pp. 85-[100].

577 29 Jan., 1851; Lt. W. H. Wyburd [Indian Navy]. PC 7206, Dr 60, D 5: *E/4/807, pp. 1601-6; L/P&S/6/364, pp. 73-[84].

578 18 June, 1851; Delhi royal family. Dr 215, D 21: *E/4/810, pp. 515-36; L/P&S/6/364, pp. 653-[676].

579 19 Mar., 1851. PC 7249, Dr 176, D 12: *E/4/808, pp. 989-1012; L/P&S/6/364, pp. 333-[380].

580 11 June, 1851; memorial of Mohun Lall. PC 7344, Dr 408, D 20: *E/4/810, pp. 397-405; L/P&S/6/365, pp. 451-[470].

581 19 Mar., 1851; family of the ex-Raja of Satara. PC 7271, Dr 197, D 13: *E/4/808, pp. 1013-21; L/P&S/6/364, pp. 537-[556].

582 4 June, 1851. PC 7298, Dr 369, D 19: *E/4/810, pp. 31-154; L/P&S/6/365, pp. 105-[330].

583 16 Apr., 1851; articles captured in the Punjab. PC 7278, Dr 262, D 16: *E/4/809, pp. 467-77; L/P&S/6/364, pp. 681-[700].

584 26 Mar., 1851; North-Western Provinces. PC 7272, Dr 198, D 14: *E/4/808, pp. 1155-64; L/P&S/6/364, pp. 557-[576].

585 30 July, 1851; recent transactions in Sikkim. PC 7299, Dr 409, D 28: *E/4/810, pp. 1265-86; L/P&S/6/365, pp. 471-[504].

586 18 June, 1851. PC 7310, Dr 410, D 22: *E/4/810, pp. 537-616; L/P&S/6/365, pp. 505-[630].

587 4 June, 1851; North-East Frontier. PC 7308, Dr 368, D 18: *E/4/810, pp. 1-30; L/P&S/6/365, pp. 331-[382].

588 18 June, 1851; North-Western Provinces. PC 7369, Dr 428, D 23: *E/4/810, pp. 617-27; L/P&S/6/365, pp. 687-[710].

589 16 July, 1851; affairs of Oudh. PC 7377, Dr 492, D 26: *E/4/810, pp. 1109-31; L/P&S/6/366, pp. 13-[48].

590 24 Sept., 1851; Meer Ali Morad of Khairpur. PC 7382, Dr 623, D 33: E/4/812, pp. 575-90; L/P&S/6/366, pp. 541-[564], 601-[612].

591 23 July, 1851. PC 7390, Dr 493, D 27: *E/4/810, pp. 1163-1204; L/P&S/6/366, pp. 49-[116].

591X Palanpur Districts. See full entry at 1271.

592 13 Aug., 1851. PC 7399, Dr 585, D 30: *E/4/811, pp. 251-65; L/P&S/6/366, pp. 302-[334].

593 13 Aug., 1851; North-East Frontier. PC 7422, Dr 551, D 29: *E/4/811, pp. 241-50; L/P&S/6/366, pp. 217-[236].

594 3 Dec., 1851; affairs of the Nizam. PC 7499, Dr 863, D 40: *E/4/813, pp. 551-90; L/P&S/6/367, pp. 607-[682].

595 10 Sept., 1851; Punjab and North-Western Frontier. PC 7461, Dr 633, D 32: *E/4/812, pp. 847-404; L/P&S/6/366, pp. 613-[712].

596 5 Nov., 1851; Bengal. PC 7522, Dr 796, D 37: *E/4/813, pp. 235-64; L/P&S/6/367, pp. 527-[580].

597 3 Sept., 1851; North-Western Provinces. PC 7469, Dr 634, D 31: *E/4/812, pp. 169-79; L/P&S/6/367, pp. 1177-[1200].

598 5 Nov., 1851. PC 7486, Dr 795, D 36: *E/4/813, pp. 173-233; L/P&S/6/367, pp. 411-[526].

599 1 Oct., 1851; Mysore and Coorg. PC 7481, Dr 721, D 34: *E/4/812, pp. 733-44; L/P&S/6/367, pp. 1-[26].

600 19 Nov., 1851; Punjab and North-Western Frontier. PC 7498, Dr 773, D 39: *E/4/813, pp. 425-77; L/P&S/6/367, pp. 235-[318]. Para. 14, *PP*, 1854, XLVII, 181.

601 29 Oct., 1851. PC 7492, Dr 774, D 35: *E/4/812, pp. 1165-86; L/P&S/6/367, pp. 377-[410].

602 2 Jan., 1852. PC 7566, Dr 916, D 2: *E/4/813, pp. 853-82; L/P&S/6/367, pp. 837-[884] [*sic*].

603 21 Jan., 1852. PC 7583, Dr 6, D 5: *E/4/813, pp. 1153-1200; L/P&S/6/368, pp. 1-[64].

604 28 Jan., 1852; Punjab and North-West Frontier. PC 7600, Dr 28, D 6: *E/4/813, pp. 1283-1332; L/P&S/6/368, pp. 221-[268], 287-[330] [*sic*].

605 10 Dec., 1851; memorial of Maharaja Tukhtsing of Jodhpur. PC 7569, Dr 874, D 41: *E/4/813, pp. 681-6; L/P&S/6/367, pp. 781-[792].

- 606** 2 Jan., 1852; North-East Frontier. PC 7599, Dr 915, D 1: *E/4/813, pp. 845-52; L/P&S/6/367, pp. 821-[836].
- 607** 2 Jan., 1852. PC 7617, Dr 932, D 3: *E/4/813, pp. 883-99; L/P&S/6/367, pp. 1049-[1080].
- 608** 18 Feb., 1852; North-Western Provinces. PC 7672, Dr 97, D 8: *E/4/814, pp. 363-74; L/P&S/6/368, pp. 455-[478].
- 609** 14 Jan., 1852; North-East Frontier. PC 7628, Dr 7, D 4: *E/4/813, pp. 1029-36; L/P&S/6/368, pp. 65-[82].
- 610** 17 Mar., 1852. PC 7663, Dr 172, D 11: *E/4/814, pp. 967-1022; L/P&S/6/368, pp. 649-[740].
- 611** 3 Mar., 1852; Punjab. PC 7682, Dr 137, D 9: *E/4/814, pp. 681-728; L/P&S/6/368, pp. 503-[584].
- 612** 18 Feb., 1852; Bengal. PC 7660, Dr 76, D 7: *E/4/814, pp. 347-62; L/P&S/6/368, pp. 415-[450].
- 613** 10 Mar., 1852; North-Western Provinces. PC 7699, Dr 152, D 10: *E/4/814, pp. 787-96; L/P&S/6/368, pp. 629-[648].
- 614** 16 June, 1852. PC 7741, Dr 403, D 21: *E/4/815, pp. 1469-1542; L/P&S/6/369, pp. 541-[600], 613-[674].
- 615** 17 Mar., 1852; Mysore and Coorg. PC 7738, Dr 173, D 12: *E/4/814, pp. 1023-34; L/P&S/6/369, pp. 1-[22].
- 616** 12 May, 1852; Bengal. PC 7767, Dr 315, D 15: *E/4/815, pp. 497-512; L/P&S/6/369, pp. 183-[214].
- 617** 23 June, 1852. PC 7773, Dr 444, D 22: *E/4/815, pp. 1583-1628; L/P&S/6/369, pp. 697-[788].
- 618** 21 Apr., 1852; Bughat succession. PC 7768, Dr 266, D 13: E/4/815, pp. 305-12; L/P&S/6/369, pp. 141-[160].
- 619** 5 May, 1852; North-East Frontier. PC 7770, Dr 314, D 14: *E/4/815, pp. 471-80; L/P&S/6/369, pp. 161-[182].
- 620** 19 May, 1852; North-Western Provinces. PC 7796, Dr 344, D 16: *E/4/815, pp. 593-602; L/P&S/6/369, pp. 215-[234].
- 621** 2 June, 1852; Punjab. PC 7809, Dr 362, D 18: *E/4/815, pp. 1007-63; L/P&S/6/369, pp. 235-[286], 307-[358].
- 622** 2 June, 1852; Delhi royal family. PC 7825, Dr 381, D 19: *E/4/815, pp. 1065-78; L/P&S/6/369, pp. 505-[524].
- 623** 18 Aug., 1852. PC 7863, Dr 608, D 26: *E/4/816, pp. 999-1055; L/P&S/6/370, pp. 423-[526].
- 624** 14 July, 1852; North-Western Provinces. PC 7879, Dr 498, D 24: *E/4/816, pp. 285-93; L/P&S/6/369, pp. 833-[852].
- 625** 15 Sept., 1852; Punjab. PC 7920, Dr 686, D 29: *E/4/817, pp. 303-53; L/P&S/6/371, pp. 21-[124].
- 626** 18 Aug., 1852; Bengal. PC 7908, Dr 609, D 27: *E/4/816, pp. 1057-66; L/P&S/6/371, pp. 125-[144].
- 627** 24 Nov., 1852. PC 7971, Dr 861, D 34: *E/4/817, pp. 1243-1307; L/P&S/6/371, pp. 429-[550].
- 628** 6 Oct., 1852; North-Western Provinces. PC 7953, Dr 741, D 31: *E/4/817, pp. 511-19; L/P&S/6/371, pp. 269-[288].
- 629** 6 Oct., 1852; North-East Frontier. PC 7952, Dr 740, D 30: *E/4/817, pp. 501-10; L/P&S/6/371, pp. 247-[268].
- 630** 20 Oct., 1852; Bengal. PC 7966, Dr 758, D 32: *E/4/817, pp. 555-62; L/P&S/6/371, pp. 289-[308].
- 631** 23 Mar., 1853; Southern Maratha claims in the Nizam's territory. PC 8116, Dr 184, D 8: *E/4/819, pp. 787-816; L/P&S/6/372, pp. 197-[240].
- 632** 20 Oct., 1852; Lt. W.H. Wyburd [Indian Navy]. PC 7993, Dr 784, D 33: *E/4/817, pp. 563-74; L/P&S/6/371, pp. 361-[384].
- 633** 15 Dec., 1852; affairs of Oudh. PC 7995, Dr 897, D 36: *E/4/818, pp. 389-410; L/P&S/6/371, pp. 563-[622].
- 634** 15 Dec., 1852. PC 8015, Dr 898, D 37: *E/4/818, pp. 411-38; L/P&S/6/371, pp. 623-[672].
- 635** 13 Apr., 1853; Punjab. PC 8177, Dr 242, D 11: *E/4/819, pp. 921-1006; L/P&S/6/372, pp. 461-[620].
- 636** 15 Dec., 1852. PC 8024, Dr 928, D 38: *E/4/818, pp. 439-58; L/P&S/6/371, pp. 701-[744].
- 637** 1 Dec., 1852; Lt. W.H. Wyburd [Indian Navy]. PC 8027, Dr 881, D 35: *E/4/818, pp. 119-26; L/P&S/6/371, pp. 551-[562].
- 638** 26 Jan., 1853; succession to the state of Kerowlee. PC 8028, Dr 982, D 1: *E/4/818, pp. 1147-55; L/P&S/6/371, pp. 785-[814]. *PP*, 1854-55, XL, 87-8.
- 639** 15 Dec., 1852; North-Western Provinces. PC 8033, Dr 930, D 40: *E/4/818, pp. 467-74; L/P&S/6/371, pp. 765-[784].

- 640** 15 Dec., 1852; North-East Frontier. PC 8031, Dr 929, D 39: *E/4/818, pp. 459-66; L/P&S/6/371, pp. 745-[764].
- 641** 31 Dec., 1852. PC 8046, Dr 944, D 41: *E/4/818, pp. 615-50; L/P&S/6/371, pp. 847-[910].
- 642** 20 Apr., 1853; Mysore and Coorg. PC 8126, Dr 289, D 13: *E/4/819, pp. 1393-1420; L/P&S/6/373, pp. 309-[366].
- 643** 26 Jan., 1853; Straits Settlements. PC 8098, Dr 22, D 2: *E/4/818, pp. 1157-72; L/P&S/6/372, pp. 1-[32].
- 644** 26 Jan., 1853. PC 8096, Dr 23, D 3: *E/4/818, pp. 1173-84; L/P&S/6/372, pp. 33-[52].
- 645** 20 Apr., 1853; North-Western Provinces. PC 8143, Dr 290, D 14: *E/4/819, pp. 1421-44; L/P&S/6/373, pp. 367-[428].
- 646** 27 Apr., 1853; Punjab. PC 8183, Dr 268, D 16: *E/4/819, pp. 1529-93; L/P&S/6/373, pp. 25-[146].
- 647** 2 Mar., 1853; Bengal. PC 8144, Dr 137, D 4: *E/4/819, pp. 471-81; L/P&S/6/372, pp. 127-[148].
- 648** 4 May, 1853. PC 8190, Dr 336, D 19: *E/4/820, pp. 106-42; L/P&S/6/374, pp. 13-[80].
- 649** 30 Mar., 1853; Straits Settlements. PC 8186, Dr 196, D 9: *E/4/819, pp. 873-80; L/P&S/6/372, pp. 285-[300].
- 650** 1 June, 1853. PC 8200, Dr 380, D 20: *E/4/820, pp. 413-71; L/P&S/6/374, pp. 329-[436].
- 651** 13 Apr., 1853; North-East Frontier. PC 8215, Dr 241, D 10: *E/4/819, pp. 1123-8; L/P&S/6/372, pp. 449-[460].
- 652** 16 Mar., 1853; Agra Presidency—suspension of powers under 3 & 4 William IV, c. 85, s. 38. Dr 155, D 5: *E/4/819, pp. 683-8; L/P&S/6/372, pp. 149-[152].
- 653** 23 Mar., 1853; memorial of Muhammad Hajeer Khan of Bahawalpur. Dr 183, D 7: E/4/819, pp. 781-5; L/P&S/6/372, pp. 193-[196].
- 654** 4 May, 1853; Bengal. PC 8245, Dr 335, D 18: *E/4/820, pp. 99-106; L/P&S/6/374, pp. 1-[12].
- 655** 4 May, 1853; memorial of Dhoondoo Punt Sahib [adopted son of ex-Peshwa]. PC 8244, Dr 334, D 17: *E/4/820, pp. 93-7; L/P&S/6/373, pp. 689-[700].
- 656** 13 July, 1853; Punjab. PC 8293, Dr 536, D 28: *E/4/821, pp. 255-318; L/P&S/6/376, pp. 225-[344].
- 657** 20 Apr., 1853; Chandernagore boundary. Dr 312, D 15: *E/4/819, pp. 1445-51; L/P&S/6/373, pp. 567-[570].
- 658** 1 June, 1853; North-Western Provinces. PC 8288, Dr 409, D 21: *E/4/820, pp. 473-8; L/P&S/6/374, pp. 635-[646].
- 659** 22 June, 1853; administration of Pegu. PC 8301, Dr 453, D 23: *E/4/820, pp. 977-95; L/P&S/6/376, pp. 33-[68].
- 660** 8 June, 1853; Baroda Residency. PC 8296, Dr 433, D 22: *E/4/820, pp. 577-98; L/P&S/6/374, pp. 675-[722].
- 661** 29 June, 1853; family of the late ex-Raja of Satara. PC 8347, Dr 490, D 25: *E/4/820, pp. 1167-74; L/P&S/6/376, pp. 109-[128].
- 662** 2 Aug., 1853; ex-Amirs of Sind. PC 8341, Dr 618, D 30: *E/4/821, pp. 999-1014; L/P&S/6/376, pp. 415-[460].
- 663** 6 July, 1853; revolution in Bahawalpur. PC 8340, Dr 517, D 26: *E/4/821, pp. 181-8; L/P&S/6/376, pp. 181-[200].
- 664** 17 Aug., 1853. PC 8370, Dr 659, D 32: *E/4/821, pp. 1247-1320; L/P&S/6/375, pp. 191-[302].
- 665** 27 July, 1853; North-Western Provinces. PC 8366, Dr 554, D 29: *E/4/821, pp. 789-96; L/P&S/6/376, pp. 349-[362].
- 666** 10 Aug., 1853; North-East Frontier. PC 8368, Dr 645, D 31: *E/4/821, pp. 1109-24; L/P&S/6/376, pp. 609-[642].
- 667** 22 June, 1853; Lt. Col. J. Outram [ex-Resident in Baroda]. PC 8372, Dr 507, D 24: *E/4/820, pp. 997-1005; L/P&S/6/376, pp. 161-[180].
- 668** 7 Dec., 1853; Bengal. PC 8376, Dr 709, D 47: *E/4/823, pp. 395-417; L/P&S/6/377, pp. 259-[302].
- 669** 17 Aug., 1853; Straits Settlements. PC 8380, Dr 660, D 33: *E/4/821, pp. 1321-33; L/P&S/6/375, pp. 1-[26].
- 670** 31 Aug., 1853. PC 8386, Dr 686, D 35: *E/4/821, pp. 1399-1423; L/P&S/6/375, pp. 75-[118].
- 671** 6 July, 1853; Sir James Brooke. Dr 542, D 27: *E/4/821, pp. 189-95; L/P&S/6/376, pp. 345-[348].
- 672** 17 Aug., 1853; Mysore and Coorg. PC 8395, Dr 673, D 34: *E/4/821, pp. 1335-47; L/P&S/6/375, pp. 27-[54].

- 673** 21 Sept., 1853; Punjab. PC 8422, Dr 761, D 39: *E/4/822, pp. 295-370; L/P&S/6/375, pp. 453-[588]. Para. 5, PP, 1854, XLVII, 181.
- 674** 2 Nov., 1853; new treaty with the Nizam. PC 8430, Dr 831, D 45: *E/4/822, pp. 937-64; L/P&S/6/375, pp. 637-[660], 663-[682]. PP, 1854, XLVII, 274-5.
- 675** 26 Oct., 1853; general report on the Punjab. PC 8467, Dr 855, D 42: *E/4/822, pp. 887-900; L/P&S/6/377, pp. 85-[112]. PP, 1854, LXIX, 465-6.
- 676** 4 Jan., 1854; Bengal. PC 8477, Dr 1059, D 1: *E/4/823, pp. 767-92; L/P&S/6/377, pp. 347-[390].
- 677** 26 Oct., 1853. PC 8480, Dr 856, D 43: *E/4/822, pp. 901-20; L/P&S/6/377, pp. 113-[150].
- 678** 26 Oct., 1853; Baroda Residency. PC 8488, Dr 857, D 44: *E/4/822, pp. 921-32; L/P&S/6/377, pp. 151-[170].
- 678X** Chutturpore succession. India PC 8598 altered by Board on 10 Apr., 1854: L/P&S/6/380, pp. 699-[728]. Dr 523, D 27 of 20 June, 1854.
- 679** 12 Apr., 1854. PC 8651, Dr 288, D 11: *E/4/825, pp. 319-426; L/P&S/6/378, pp. 505-[678].
- 680** 15 Mar., 1854; North-Western Provinces. PC 8629, Dr 176, D 7: *E/4/824, pp. 943-62; L/P&S/6/378, pp. 179-[216].
- 681** 12 Apr., 1854; Arabs in the Nizam's territory. PC 8653, Dr 304, D 12: *E/4/825, pp. 427-66; L/P&S/6/379, pp. 51-[94], 99-[134].
- 682** 15 Mar., 1854; Mysore and Coorg. PC 8625, Dr 175, D 6: *E/4/824, pp. 925-41; L/P&S/6/378, pp. 145-[178].
- 683** 1 Mar., 1854; Bengal. PC 8634, Dr 146, D 5: *E/4/824, pp. 577-86; L/P&S/6/378, pp. 37-[56].
- 684** 12 Apr., 1854; ex-Amirs of Sind. PC 8652, Dr 264, D 9: *E/4/825, pp. 289-302; L/P&S/6/378, pp. 389-[412].
- 685** 27 Apr., 1854; Punjab. PC 8689, Dr 335, D 15: *E/4/825, pp. 869-1010; L/P&S/6/379, pp. 237-[470].
- 686** 27 Apr., 1854. PC 8674, Dr 334, D 14: *E/4/825, pp. 831-67; L/P&S/6/379, pp. 175-[236].
- 687** 27 Apr., 1854. PC 8701, Dr 337, D 16: *E/4/825, pp. 1011-44; L/P&S/6/379, pp. 635-[722].
- 688** 5 July, 1854; Punjab. PC 8715, Dr 336, D 29: *E/4/826, pp. 773-871; L/P&S/6/379, pp. 471-[634].
- 689** 12 Apr., 1854; Straits Settlements. PC 8710, Dr 287, D 10: *E/4/825, pp. 303-18; L/P&S/6/378, pp. 473-[504].
- 690** 5 Apr., 1854; Pegu. PC 8703, Dr 265, D 8: *E/4/825, pp. 227-36; L/P&S/6/378, pp. 413-[432].
- 691** 12 Apr., 1854; territory in Sind resumed from Meer Ali Morad. PC 8711, Dr 305, D 13: *E/4/825, pp. 467-88; L/P&S/6/379, pp. 135-[174].
- 692** 17 May, 1854; endowment of the Murshidabad Nizamut. PC 8731, Dr 421, D 19: *E/4/825, pp. 1273-92; L/P&S/6/380, pp. 263-[308].
- 693** 27 Apr., 1854; relations with Kalat. PC 8721, Dr 338, D 17: *E/4/825, pp. 1045-64; L/P&S/6/380, pp. 1-[38].
- 694** 5 May, 1854; Bengal. PC 8732, Dr 371, D 18: *E/4/825, pp. 1117-33; L/P&S/6/380, pp. 161-[190].
- 694X** Affairs of Kerowlee. India PC 8752 altered by Board on 26 May, 1854: L/P&S/6/381, pp. 209-[236]. Dr 590, D 30 of 5 July, 1854.
- 695** 14 June, 1854. PC 8767, Dr 497, D 24: *E/4/826, pp. 291-340; L/P&S/6/380, pp. 399-[494].
- 696** 7 June, 1854; Baroda Residency. PC 8765, Dr 469, D 22: *E/4/826, pp. 87-97; L/P&S/6/380, pp. 343-[362].
- 697** 14 June, 1854; lapse of the state of Nagpur. PC 8778, Dr 496, D 23: E/4/826, pp. 279-90; L/P&S/6/380, pp. 363-[398].
- 697X** Jhansi and Orchha. India PC 8787 altered by Board on 20 June, 1854: L/P&S/6/381, pp. 449-[526]. Dr 699, D 34 of 2 Aug., 1854.
- 698** 28 June, 1854; Pegu. PC 8818, Dr 550, D 28: E/4/826, pp. 577-93; L/P&S/6/381, pp. 45-[84].
- 698X** Paragraphs on the allowances of Major John Jacob. See full entry at 1387.
- 699** 23 Aug., 1854; Punjab. PC 8852, Dr 750, D 36: E/4/827, pp. 285-342; L/P&S/6/381, pp. 675-[772].
- 700** 12 July, 1854; North-Western Provinces. PC 8858, Dr 613, D 31: E/4/826, pp. 933-42; L/P&S/6/381, pp. 249-[272].
- 701** 16 Aug., 1854; Straits Settlements. PC 8859, Dr 657, D 35: *E/4/827, pp. 205-17; L/P&S/6/381, pp. 305-[332].

- 702** 26 July, 1854. PC 8861, Dr 658, D 32: *E/4/826, pp. 1575-98; L/P&S/6/381, pp. 333-[374].
- 703** 2 Aug., 1854; Baroda. PC 8865, Dr 682, D 33: *E/4/827, pp. 43-60; L/P&S/6/381, pp. 375-[406].
- 704** 4 Oct., 1854. PC 8949, Dr 898, D 42: *E/4/827, pp. 1191-1231; L/P&S/6/382, pp. 229-[292].
- 705** 6 Sept., 1854; Straits Settlements. PC 8940, Dr 816, D 38: *E/4/827, pp. 491-504; L/P&S/6/382, pp. 29-[48].
- 706** 6 Sept., 1854; Mysore and Coorg. PC 8943, Dr 817, D 39: *E/4/827, pp. 505-13; L/P&S/6/382, pp. 49-[64].
- 707** 20 Sept., 1854; Bengal. PC 8941, Dr 838, D 40: *E/4/827, pp. 849-68; L/P&S/6/382, pp. 65-[100].
- 708** 4 Oct., 1854; Nawab Nazim of Murshidabad. PC 8950, Dr 899, D 43: *E/4/827, pp. 1233-56; L/P&S/6/382, pp. 297-[344].
- 709** 27 Sept., 1854; Baroda. PC 8953, Dr 873, D 41: *E/4/827, pp. 999A-1012; L/P&S/6/382, pp. 201-[228].
- 710** 4 Oct., 1854; Punjab. PC 8968, Dr 900, D 44: *E/4/827, pp. 1257-72; L/P&S/6/382, pp. 345-[380].
- 711** 18 Oct., 1854; Sati. PC 8973, Dr 872, D 45: *E/4/827, pp. 1511-16; L/P&S/6/382, pp. 189-[200].
- 712** 8 Nov., 1854; treaty with Kalat. PC 8972, Dr 935, D 49: *E/4/828, pp. 181-92; L/P&S/6/382, pp. 449-[468].
- 713** 18 Oct., 1854; Punjab. PC 8989, Dr 944, D 47: *E/4/827, pp. 1527-71; L/P&S/6/382, pp. 573-[652].
- 714** 29 Dec., 1854. PC 9000, Dr 1132, D 55: *E/4/828, pp. 1071-1116; L/P&S/6/382, pp. 1105-[1176].
- 715** 18 Oct., 1854; Bengal. PC 8990, Dr 936, D 46: *E/4/827, pp. 1517-25; L/P&S/6/382, pp. 469-[488].
- 716** 15 Nov., 1854; administration of Nagpur. PC 8995, Dr 1033, D 51: *E/4/828, pp. 287-316; L/P&S/6/382, pp. 705-[756]. Paras. 4-6, PP, 1856, XLV, 41.
- 717** 18 Oct., 1854; North-Western Provinces. PC 9011, Dr 945, D 48: *E/4/827, pp. 1573-77; L/P&S/6/382, pp. 653-[664].
- 718** 22 Nov., 1854; employment of the Hyderabad contingent. PC 9017, Dr 1059, D 52: *E/4/828, pp. 515-44; L/P&S/6/382, pp. 845-[916].
- 719** 15 Nov., 1854; Straits Settlements. PC 9031, Dr 1009, D 50: *E/4/828, pp. 275-86; L/P&S/6/382, pp. 665-[684].
- 720** 29 Dec., 1854. PC 9052, Dr 1188, D 57: *E/4/828, pp. 1125-80; L/P&S/6/382, pp. 1247-[1346].
- 721** 29 Nov., 1854; Mysore and Coorg. PC 9043, Dr 1083, D 53: *E/4/828, pp. 629-37; L/P&S/6/382, pp. 949-[968].
- 721X** Jagirs in the Punjab. India PC 9097 and earlier "Pre-PC" altered by Board in Nov. 1854: L/P&S/6/383, pp. 273-[292]. Dr 114, D 5 of 7 Feb., 1855.
- 722** 6 Mar., 1855; Punjab. PC 9114, Dr 113, D 6: *E/4/829, pp. 1097-1154, L/P&S/6/383, pp. 177-[272].
- 722X** Baroda guarantees. India PC 9251 altered by Board on 31 Mar., 1855: L/P&S/6/384, pp. 647-[658]. Dr 560, D 16 of 4 July, 1855.
- 723** 20 Dec., 1854; claims of Akram Khan Ishakzye. PC 9100, Dr 1159, D 54: *E/4/828, pp. 893-7; L/P&S/6/382, pp. 1177-[1188].
- 724** 31 Jan., 1855; Straits Settlements. PC 9109, Dr 80, D 4: *E/4/829, pp. 574A-82; L/P&S/6/383, pp. 91-[116] [sic].
- 725** 10 Oct., 1855. PC 9481, Dr 940, D 27: *E/4/829, pp. 1205-78; L/P&S/6/385, pp. 1-[134].
- 726** 3 Oct., 1855; Straits Settlements. PC 9458, Dr 916, D 25: *E/4/829, pp. 1085-1100; L/P&S/6/384, pp. 497-[524].
- 727** 31 Oct., 1855. PC 9473, Dr 959, D 31: *E/4/832, pp. 1649-88; L/P&S/6/384, pp. 253-[324].
- 728** 3 Oct., 1855; Punjab. PC 9474, Dr 915, D 24: *E/4/832, pp. 1045-84; L/P&S/6/384, pp. 421-[496].
- 728X** Kashmir tribute shawls. India PC 9156 altered by Board on 18 Jan., 1855: L/P&S/6/383, pp. 75-[82]. Dr 79, D 3 of 31 Jan., 1855.
- 729** 3 Oct., 1855; North-Western Provinces. PC 9468, Dr 914, D 23: *E/4/832, pp. 997-1043; L/P&S/6/384, pp. 345-[420].
- 730** 19 Sept., 1855; cession of the fort of Sindwah. PC 9465, Dr 867, D 22: *E/4/832, pp. 651-60; L/P&S/6/384, pp. 325-[344].
- 731** 24 Oct., 1855; Punjab. PC 9494, Dr 1006, D 29: *E/4/832, pp. 1515-51; L/P&S/6/385, pp. 225-[292].

- 732 21 Nov., 1855; affairs of Oudh. PC 9492, Dr 1105, D 33: *E/4/833, pp. 313-67; L/P&S/6/385, pp. 451-[482], 575-[622], 669-[694]. *PP*, 1856, XLV, 579-82.
- 733 31 Oct., 1855; Mysore and Coorg. PC 9514, Dr 1026, D 32: *E/4/832, pp. 1689-1700; L/P&S/6/385, pp. 305-[332].
- 734 30 Jan., 1856. PC 9579, Dr 22, D 2: *E/4/834, pp. 349-458; L/P&S/6/387, pp. 205-[374]. *Paras.* 67-8, *PP*, 1856, XLV, 43.
- 735 24 Oct., 1855; North-Western Provinces. PC 9519, Dr 1007, D 30: *E/4/832, pp. 1553-60; L/P&S/6/385, pp. 293-[304].
- 735X Lahore jewels. See full entry at 755.
- 736 12 Dec., 1855; Punjab. PC 9556, Dr 1153, D 34: *E/4/833, pp. 611-36; L/P&S/6/386, pp. 157-[208].
- 737 28 Dec., 1855; Bengal. PC 9574, Dr 1217, D 36: *E/4/833, pp. 849-79; L/P&S/6/386, pp. 527-[582].
- 738 12 Dec., 1855; North-Western Provinces. PC 9557, Dr 1154, D 35: *E/4/833, pp. 637-56; L/P&S/6/386, pp. 209-[248].
- 739 20 Feb., 1856. PC 9585, Dr 136, D 6: *E/4/834, pp. 975-1017; L/P&S/6/388, pp. 5-[48], 57-[88]. *Para.* 21, *PP*, 1856, XLV, 42.
- 740 6 Feb., 1856. PC 9615, Dr 77, D 3: *E/4/834, pp. 647-720; L/P&S/6/387, pp. 431-[554].
- 741 28 Dec., 1855; Straits Settlements. PC 9591, Dr 1218, D 37: *E/4/833, pp. 881-92; L/P&S/6/386, pp. 583-[602].
- 742 5 Mar., 1856. PC 9621, Dr 186, D 11: *E/4/834, pp. 1215-73; L/P&S/6/388, pp. 359-[446].
- 743 5 Mar., 1856. PC 9695, Dr 216, D 14: *E/4/834, pp. 1289-1323; L/P&S/6/388, pp. 475-[522].
- 744 7 May, 1856; Punjab. PC 9795, Dr 456, D 21: *E/4/835, pp. 777-828; L/P&S/6/389, pp. 545-[644].
- 745 5 Mar., 1856; succession to the state of Ajaigarh. PC 9675, Dr 154, D 9: *E/4/834, pp. 1199-1209; L/P&S/6/388, pp. 175-[198].
- 746 20 Feb., 1856; North-Western Provinces. PC 9678, Dr 137, D 7: *E/4/834, pp. 1019-34; L/P&S/6/388, pp. 89-[120].
- 747 26 Feb., 1856; Bengal. PC 9696, Dr 155, D 8: *E/4/834, pp. 1073-89; L/P&S/6/388, pp. 199-[230].
- 748 19 Mar., 1856; status and family of the Nawab of the Carnatic. PC 9736, Dr 279, D 15: *E/4/834, pp. 1587-1612; L/P&S/6/388, pp. 629-[668].
- 749 5 Mar., 1856; Mysore and Coorg. PC 9726, Dr 215, D 13: *E/4/834, pp. 1279-88; L/P&S/6/388, pp. 455-[474].
- 750 30 Apr., 1856. PC 9793, Dr 426, D 19: *E/4/835, pp. 543-97; L/P&S/6/389, pp. 441-[524].
- 751 17 June, 1856; Punjab. PC 9880, Dr 573, D 25: *E/4/836, pp. 871-906; L/P&S/6/390, pp. 187-[238].
- 752 23 July, 1856. PC 9883, Dr 784, D 28: *E/4/837, pp. 1189-1211; L/P&S/6/390, pp. 465-[522].
- 753 30 Apr., 1856; Bengal. PC 9807, Dr 427, D 20: *E/4/835, pp. 599-610; L/P&S/6/389, pp. 525-[544].
- 754 16 Apr., 1856; status of Raja of Tanjore. PC 9794, Dr 371, D 17: *E/4/835, pp. 323-31; L/P&S/6/389, pp. 349-[368].
- 755 30 Apr., 1856; Lahore jewels. PC 9526, Dr 340, D 18: *E/4/835, pp. 537-42; L/P&S/6/389, pp. 135-[146].
- 756 1 Oct., 1856. PC 9884, Dr 1010, D 36: *E/4/839, pp. 319-41; L/P&S/6/390, pp. 675-[760].
- 757 4 June, 1856; North-Western Provinces. PC 9892, Dr 575, D 24: *E/4/836, pp. 303-18; L/P&S/6/390, pp. 251-[278].
- 758 4 June, 1856; Bengal. PC 9893, Dr 574, D 23: *E/4/836, pp. 295-302; L/P&S/6/390, pp. 239-[250].
- 759 19 Nov., 1856; Ajaigarh succession. PC 150, Dr 1218, D 44: *E/4/840, pp. 651-61; L/P&S/6/391, pp. 307-[326].
- 760 17 Dec., 1856; surinjam of Chimnaje Wittul Poorundherry in Nimar. PC 135, Dr 1362, D 49: *E/4/840, pp. 1485-9; L/P&S/6/391, pp. 621-[632].
- 761 10 Dec., 1856; Punjab. PC 156, Dr 1287, D 48: *E/4/840, pp. 1093-1110; L/P&S/6/391, pp. 335-[368].
- 762 25 Feb., 1857; proposed territorial arrangements with Sindhia. PC 251, Dr 172, D 12: *E/4/842, pp. 855-906; L/P&S/6/392, pp. 807-[864], 867-[896].
- 763 28 Jan., 1857. PC 250, Dr 44, D 7: *E/4/841, pp. 1299-1320; L/P&S/6/392, pp. 241-[278].
- 764 11 Feb., 1857; North-Western Provinces. PC 279, Dr 136, D 11: *E/4/842, pp. 507-46; L/P&S/6/392, pp. 681-[745] [*sic*].

- 765** 28 Jan., 1857; Straits Settlements. PC 274, Dr 70, D 8: *E/4/841, pp. 1321-36; L/P&S/6/392, pp. 437-[464].
- 766** 7 Jan., 1857; Meer Ali Morad of Sind. Dr 1396, D 3: *E/4/841, pp. 633-7; L/P&S/6/391, pp. 691-[694].
- 767** 20 May, 1857. PC 328, Dr 510, D 20: *E/4/844, pp. 761-807; L/P&S/6/393, pp. 465-[540].
- 768** 17 Apr., 1857; North-Western Provinces. PC 358, Dr 390, D 18: *E/4/843, pp. 681-744; L/P&S/6/393, pp. 297-[396].
- 769** 11 Mar., 1857; Straits Settlements. PC 348, Dr 267, D 16: *E/4/842, pp. 1191-1200; L/P&S/6/393, pp. 97-[114].
- 770** 8 July, 1857; Mutiny or Revolt of 1857. PC 606, Dr 787, D 24: E/4/845, pp. 329-38; L/P&S/6/394, pp. 35-[52]. *PP*, 1857, Sess. 2, XXX, 12-13.
- 771** 18 Nov., 1857; affairs of Gujarat. PC 642, Dr 1362, D 42: *E/4/848, pp. 1500-41; L/P&S/6/395, pp. 105-[174].
- 772** 11 Nov., 1857; Bengal. PC 687, Dr 1325, D 40: *E/4/848, pp. 1050-77; L/P&S/6/394, pp. 673-[718].
- 773** 11 Nov., 1857; North-Eastern Frontier. PC 696, Dr 1326, D 41: *E/4/848, pp. 1078-1113; L/P&S/6/395, pp. 1-[56].
- 774** 3 Mar., 1858; North-Western Provinces. PC 831, Dr 221, D 11: *E/4/850, pp. 1179-1204; L/P&S/6/396, pp. 357-[398].
- 775** 13 Jan., 1858; Straits Settlements. PC 793, Dr 1607, D 3: *E/4/849, pp. 1413-36; L/P&S/6/395, pp. 451-[484].
- 776** 3 Mar., 1858; Bengal. PC 816, Dr 192, D 10: *E/4/850, pp. 1155-77; L/P&S/6/396, pp. 301-[340], 345-[356].
- 777** 2 June, 1858; affairs of Gujarat. PC 965, Dr 638, D 21: *E/4/852, pp. 209-24; L/P&S/6/397, pp. 291-[316].
- 778** 7 July, 1858; Carnatic family. PC 1009, Dr 778, D 31: *E/4/852, pp. 1198-1201; L/P&S/6/397, pp. 569-[580].
- 779** 13 July, 1858; Tanjore family. PC 1020, Dr 809, D 33: *E/4/852, pp. 1353-7; L/P&S/6/397, pp. 863-[874].
- 779X** Paragraphs on the Oudh proclamation. See full entry at 780.
- 780** 18 May, 1858; the Oudh proclamation. PC 1043, Dr 619, D 20: *E/4/851, pp. 1253-66; L/P&S/6/397, pp. 245-[290].
- 781** 29 June, 1858; Straits Settlements. PC 1058, Dr 747, D 29: *E/4/852, pp. 1048-63; L/P&S/6/397, pp. 505-[532].
- 782** 29 June, 1858; Bengal. PC 1068, Dr 746, D 28: *E/4/852, pp. 1034-46; L/P&S/6/397, pp. 477-[504].
- 783** 11 Aug., 1858. PC 1088, Dr 921, D 39: *E/4/853, pp. 786-835; L/P&S/6/398, pp. 121-[200].
- 784** 11 Aug., 1858. PC 1099, Dr 971, D 43: *E/4/853, pp. 889-932; L/P&S/6/398, pp. 327-[374], 377-[408].
- 785** 18 Aug., 1858. PC 1106, Dr 1020, D 45: *E/4/854, pp. 414-63; L/P&S/6/398, pp. 469-[522], 525-[564].
- 786** 30 Aug., 1858. PC 1117, Dr 1063, D 49: *E/4/854, pp. 1168-93; L/P&S/6/398, pp. 691-[744].
- 787** 30 Aug., 1858. PC 1119, Dr 1109, D 52: *E/4/854, pp. 1228-41; L/P&S/6/398, pp. 803-[828].
- 788** 13 July, 1858; Mysore and Coorg. PC 1103, Dr 808, D 32: *E/4/852, pp. 1341-52; L/P&S/6/397, pp. 843-[862].
- 789** 11 Aug., 1858; Punjab. PC 1113, Dr 969, D 41: *E/4/853, pp. 840-69; L/P&S/6/398, pp. 245-[272], 275-[298].
- 790** 18 Aug., 1858; Punjab. PC 1124, Dr 1019, D 44: *E/4/854, pp. 386-413; L/P&S/6/398, pp. 409-[444], 447-[468].
- 791** 30 Aug., 1858; Punjab. PC 1127, Dr 1062, D 48: *E/4/854, pp. 1138-66; L/P&S/6/398, pp. 639-[690].
- 792** 30 Aug., 1858; Punjab. PC 1156, Dr 1108, D 51: *E/4/854, pp. 1198-1227; L/P&S/6/398, pp. 749-[802].
- 793** 1 Sept., 1858; Punjab. PC 1159, Dr 1155, D 55: *E/4/855, pp. 683-702; L/P&S/6/399, pp. 69-[108].
- 794** 11 Aug., 1858; Punjab. PC 1132, Dr 970, D 42: *E/4/853, pp. 870-82; L/P&S/6/398, pp. 299-[326].
- 795** 1 Sept., 1858. PC 1192, Dr 1156, D 56: *E/4/855, pp. 703-57; L/P&S/6/399, pp. 109-[212].
- 796** 18 Aug., 1858; Bengal. PC 1163, Dr 1021, D 46: *E/4/854, pp. 464-73; L/P&S/6/398, pp. 565-[584].
- 797** 1 Sept., 1858. PC 1188, Dr 1205, D 58: E/4/855, pp. 763-82; L/P&S/6/399, pp. 221-[258].
- 798** 30 Aug., 1858; Bengal. PC 1190, Dr 1111, D 54: *E/4/854, pp. 1260-8; L/P&S/6/399, pp. 1-[18].

799 1 Sept., 1858. PC 1215, Dr 1209, D 62: *E/4/855, pp. 813-51; L/P&S/6/399, pp. 337-[404].

800 1 Sept., 1858; Punjab. PC 1226, Dr 1206, D 59: *E/4/855, pp. 783-94; L/P&S/6/399, pp. 279-[300].

Madras Political Department

801 26 Apr., 1825. PC 223, Dr 266: E/4/931, pp. 351-405; L/P&S/6/240, n.p.; L/P&S/6/267, pp. 253-[288].

802 10 Apr., 1827. PC 331, Dr 240: E/4/934, pp. 5-65; L/P&S/6/240, n.p.; L/P&S/6/268, pp. 173-[222].

803 21 May, 1828. PC 460, Dr 334: E/4/935, pp. 533-612; L/P&S/6/240, n.p.; L/P&S/6/269, pp. 313-[364] [sic].

804 14 Jan., 1829. PC 538, Dr 122: E/4/936, pp. 486-606; L/P&S/6/270, pp. 349-[414].

805 17 Nov., 1830; stipendiaries, and pensions and jagirs granted to Indians. PC 810, Dr 606, D 3: E/4/939, pp. 479-502; L/P&S/6/278, pp. 235-[278], 291-[306].

806 13 Oct., 1830; allowances of various European officers. PC 810, Dr 605, D 1: E/4/939, pp. 331-45; L/P&S/6/278, pp. 235-[290].

807 13 Oct., 1830. PC 810, Dr 607, D 2: E/4/939, pp. 347-82; L/P&S/6/278, pp. 235-[278], 307-[328].

808 25 May, 1831. PC 903, Dr 290, D 2: *E/4/940, pp. 237-59; L/P&S/6/281, pp. 25-[56].

809 4 Jan., 1832; case of Mr. R.F. Lewis [ex-clerk of the crown]. PC 986, Dr 767, D 1: E/4/941, pp. 9-44; L/P&S/6/281, pp. 323-[364].

810 1 Feb., 1832; position of Indian Christians, etc. PC 979, Dr 741, D 2: E/4/941, pp. 242-75; L/P&S/6/281, pp. 279-[322].

811 6 Mar., 1832; disturbances at Triplicane and conduct of E.P. Elliot [Superintendent of Police, Madras]. PC 995, Dr 115, D 4: E/4/941, pp. 504-34; L/P&S/6/282, pp. 447-[490].

812 6 Mar., 1832; affairs of Mysore. PC 1014, Dr 114, D 3: E/4/941, pp. 416-503; L/P&S/6/282, pp. 351-[446]. Paras. 1-27, *PP*, 1831-32, XIV, 358-60.

813 24 July, 1833. PC 1148, Dr 370, D 3: E/4/943, pp. 405-18; L/P&S/6/285, pp. [455]-[n.p.].

814 21 Aug., 1833. PC 1155, Dr 422, D 4: E/4/943, pp. 577-91; L/P&S/6/285, n.p.

815 28 Aug., 1833. PC 1165, Dr 452, D 5: E/4/943, pp. 605-14; L/P&S/6/286, pp. 21-[44].

816 9 Apr., 1834. PC 1286, Dr 171, D 2: E/4/944, pp. 561-70; L/P&S/6/288, pp. 141-[164].

817 17 June, 1834. PC 1301, Dr 317, D 3: E/4/944, pp. 979-1002; L/P&S/6/290, pp. 1-[20], 97-[124].

818 23 Feb., 1835. PC 1363, Dr 59, D 1: E/4/945, pp. 758-856; L/P&S/6/292, pp. 485-[690], 699-[764].

819 5 Nov., 1834; British subjects in the service of the Travancore government. PC 1362, Dr 520, D 4: E/4/945, pp. 263-79; L/P&S/6/291, pp. 159-[186].

820 27 Feb., 1835. PC 1384, Dr 58, D 2: E/4/945, pp. 890-938; L/P&S/6/292, pp. 377-[476].

821 27 Feb., 1835. PC 1398, Dr 109, D 3: E/4/945, pp. 939-56; L/P&S/6/292, pp. 777-[812].

822 19 Aug., 1835; removal of Capt. A. Douglas from Tanjore Residency. PC 1554, Dr 473, D 5: E/4/946, pp. 403-17; L/P&S/6/295, pp. 471-[502].

823 12 Aug., 1835. PC 1536, Dr 447, D 4: *E/4/946, pp. 287-311; L/P&S/6/295, pp. 249-[286].

824 18 Nov., 1835. PC 1612, Dr 642, D 6: E/4/946, pp. 1137-44; L/P&S/6/297, pp. 183-[198].

825 26 Apr., 1836; allowances of Surgeon A. Brown [Travancore Residency]. PC 1694, Dr 178, D 1: *E/4/947, pp. 471-9; L/P&S/6/299, pp. 91-[102].

826 30 Aug., 1837; affairs of Travancore and Cochin. PC 1925, Dr 408, D 3: *E/4/949, pp. 553-95; L/P&S/6/301, pp. 221-[300].

827 28 June, 1837; allowances of Lt. Col. T. Maclean [Resident in Tanjore]. PC 1929, Dr 235, D 1: *E/4/949, pp. 131-41; L/P&S/6/300, pp. 79-[100].

828 30 Aug., 1837. PC 1938, Dr 407, D 2: *E/4/949, pp. 525-52; L/P&S/6/301, pp. 173-[220].

829 27 Sept., 1837. PC 1950, Dr 425, D 4: *E/4/949, pp. 715-50; L/P&S/6/301, pp. 301-[368].

830 19 Sept., 1838. PC 2213, Dr 558, D 1: *E/4/951, pp. 663-702; L/P&S/6/312, pp. 210-[275].

831 17 Dec., 1839. PC 2525, Dr 716, D 2:

*E/4/953, pp. 339-70; L/P&S/6/317, pp. 227-[274].

832 13 Nov., 1839; memorial from Capt. A. Douglas [ex-Resident in Tanjore]. PC 2532, Dr 649, D 1: *E/4/953, pp. 251-62; L/P&S/6/316, pp. 289-[308].

833 23 Sept., 1840. PC 2792, Dr 571, D 3: E/4/954, pp. 741-79; L/P&S/6/320, pp. 305-[360].

834 23 June, 1841; Kanara insurrection. PC 2835, Dr 461, D 2: *E/4/955, pp. 1249-78; L/P&S/6/321, pp. 57-[110].

835 16 June, 1841. PC 3093, Dr 406, D 1: *E/4/955, pp. 1207-28; L/P&S/6/323, pp. 625-[678].

836 1 Sept., 1841; affairs of the Raja of Tanjore. PC 3128, Dr 596, D 3: *E/4/956, pp. 273-322; L/P&S/6/323, pp. 931-[1004].

837 16 Feb., 1842; Kurnool and Woodiagherry. PC 3375, Dr 72, D 1: *E/4/957, pp. 105-16; L/P&S/6/326, pp. 489-[526].

838 15 June, 1842; Tanjore and Pudukkottai. PC 3465, Dr 350, D 3: E/4/957, pp. 745-74; L/P&S/6/327, pp. 553-[600].

839 1 June, 1842. PC 3474, Dr 295, D 2: *E/4/957, pp. 705-38; L/P&S/6/327, pp. 275-[338].

840 30 Dec., 1842; corrupt practices of Capt. A. Douglas, ex-Resident at Tanjore. PC 3649, Dr 836, D 5: *E/4/959, pp. 181-224; L/P&S/6/329, pp. 581-[656].

841 22 Feb., 1843; Kurnool and Woodiagherry. PC 3655, Dr 79, D 1: *E/4/959, pp. 439-58; L/P&S/6/330, pp. 559-[590].

842 14 Dec., 1842; cases of Lts. E. Stevenson and W.H. Horsley [in employ of Travancore government]. PC 3732, Dr 803, D 4: *E/4/959, pp. 33-42; L/P&S/6/329, pp. 383-[402].

843 3 May, 1843; affairs of Kurnool. PC 3803, Dr 253, D 5: *E/4/959, pp. 897-908; L/P&S/6/331, pp. 343-[368].

844 28 Mar., 1843; Tanjore and Pudukkottai. PC 3802, Dr 186, D 4: *E/4/959, pp. 753-70; L/P&S/6/331, pp. 167-[198].

845 28 June, 1843. PC 3897, Dr 401, D 6: *E/4/960, pp. 139-80; L/P&S/6/331, pp. 521-[598].

846 20 Sept., 1843; affairs of the Nawab of the Carnatic. PC 3983, Dr 608, D 8: *E/4/960, pp. 495-516; L/P&S/6/332, pp. 51-[98].

847 1 Nov., 1843; affairs of Kurnool. PC 4000, Dr 675, D 9: *E/4/960, pp. 685-98; L/P&S/6/333, pp. 151-[174].

848 30 Aug., 1843; the family of the Nawab of the Carnatic. PC 3989, Dr 582, D 7: *E/4/960, pp. 433-48; L/P&S/6/331, pp. 819-[846].

849 31 July, 1844. PC 4346, Dr 472, D 3: *E/4/962, pp. 303-62; L/P&S/6/336, pp. 69-[188].

850 24 July, 1844; privileges of the Nawab of the Carnatic's family and household. PC 4390, Dr 517, D 2: *E/4/962, pp. 209-18; L/P&S/6/336, pp. 1-[24].

851 21 May, 1845. PC 4807, Dr 393, D 3: *E/4/963, pp. 1063-1104; L/P&S/6/340, pp. 389-[468].

851X Debts of the Nawab of Carnatic. Madras PC 4816 returned unaltered by Board on 12 Apr., 1845: L/P&S/6/340, pp. 619-[n.p.]. No Dr, no D.

852 16 Apr., 1845; Capt. G. Balfour [British Consul in Shanghai]. Dr 273, D 2: *E/4/963, pp. 789-93; L/P&S/6/340, pp. 15A-[17B].

853 17 Dec., 1845; houses at Bellary and Adoni belonging to the Nawab of Kurnool. PC 5053, Dr 951, D 5: *E/4/964, pp. 1263-70; L/P&S/6/342, pp. 465-[482].

854 11 Mar., 1846; Carnatic family and stipends. PC 5130, Dr 138, D 2: *E/4/965, pp. 301-28; L/P&S/6/343, pp. 447-[502].

855 22 July, 1846. PC 5246, Dr 455, D 5: *E/4/966, pp. 225-78; L/P&S/6/344, pp. 393-[490].

856 3 June, 1846; Carnatic stipendiaries. PC 5230, Dr 379, D 4: *E/4/965, pp. 931-6; L/P&S/6/344, pp. 217-[228].

857 2 Sept., 1846; affairs of Travancore and Cochin. PC 5337, Dr 587, D 6: *E/4/966, pp. 449-72; L/P&S/6/345, pp. 399-[454].

858 2 Sept., 1846; Carnatic stipendiaries. PC 5321, Dr 588, D 7: *E/4/966, pp. 473-504; L/P&S/6/345, pp. 455-[512].

859 14 Apr., 1847. PC 5555, Dr 255, D 3: *E/4/967, pp. 715-58; L/P&S/6/348, pp. 193-[266].

860 14 Apr., 1847; affairs of Travancore. PC 5560, Dr 254, D 2: *E/4/967, pp. 695-714; L/P&S/6/348, pp. 153-[192].

861 14 July, 1847. PC 5672, Dr 520, D 5: *E/4/968, pp. 311-33; L/P&S/6/349, pp. 465-[508].

862 19 Jan., 1848. PC 5860, Dr 675, D 1: E/4/969, pp. 519-85; L/P&S/6/349, pp. 565-[684].

863 10 May, 1848. PC 6044, Dr 291, D 2:

- *E/4/970, pp. 239-55; L/P&S/6/353, pp. 121-[152].
- 864** 31 May, 1848. PC 6060, Dr 342, D 3: *E/4/970, pp. 415-24; L/P&S/6/353, pp. 249-[268].
- 865** 4 Oct., 1848; case of Himmat Katom [widow of Abdul Wahab Khan of Kurnool]. PC 6221, Dr 679, D 5: *E/4/970, pp. 983-7; L/P&S/6/354, pp. 409-[420].
- 866** 6 Feb., 1849; affairs of the Nawab of the Carnatic. PC 6313, Dr 71, D 2: *E/4/971, pp. 583-97; L/P&S/6/355, pp. 145-[168].
- 867** 24 Jan., 1849; case of Alexander Maclean [Madras Board of Revenue]. PC 6303, Dr 24, D 1: *E/4/971, pp. 413-24; L/P&S/6/355, pp. 77-[104].
- 868** 18 July, 1849. PC 6446, Dr 459, D 5: *E/4/972, pp. 231-303; L/P&S/6/356, pp. 637-[778].
- 869** 31 Oct., 1849; case of A. Maclean [Madras Board of Revenue]. PC 6649, Dr 727, D 7: *E/4/972, pp. 949-61; L/P&S/6/359, pp. 1-[12], 77-[82]. +2L.
- 870** 31 Oct., 1849. PC 6621, Dr 705, D 6: *E/4/972, pp. 911-47; L/P&S/6/358, pp. 453-[526].
- 871** 22 May, 1850. PC 6861, Dr 308, D 6: *E/4/973, pp. 653-98; L/P&S/6/361, pp. 341-[428].
- 872** 11 Sept., 1850. PC 6998, Dr 641, D 2: *E/4/974, pp. 89-124; L/P&S/6/362, pp. 627-[696].
- 873** 5 Mar., 1851. PC 7153, Dr 75, D 1: *E/4/974, pp. 933-62; L/P&S/6/364, pp. 117-[144], 157-[182].
- 874** 25 Apr., 1851. PC 7296, Dr 301, D 2: *E/4/974, pp. 1113-24; L/P&S/6/364, pp. 709-[728].
- 875** 27 Aug., 1851. PC 7400, Dr 593, D 5: *E/4/975, pp. 687-712; L/P&S/6/366, pp. 335-[382].
- 876** 29 Oct., 1851. PC 7494, Dr 784, D 6: *E/4/975, pp. 1028-57; L/P&S/6/367, pp. 319-[376].
- 877** 10 Dec., 1851. PC 7570, Dr 903, D 7: *E/4/976, pp. 123-38; L/P&S/6/367, pp. 793-[820].
- 878** 2 June, 1852. PC 7766, Dr 369, D 1: *E/4/976, pp. 1115-30; L/P&S/6/369, pp. 359-[394].
- 879** 25 Aug., 1852. PC 7911, Dr 645, D 3: *E/4/977, pp. 393-420; L/P&S/6/370, pp. 579-[630].
- 880** 15 Dec., 1852. PC 8018, Dr 935, D 4: *E/4/977, pp. 1037-50; L/P&S/6/371, pp. 815-[846].
- 881** 4 May, 1853. PC 8210, Dr 322, D 2: *E/4/978, pp. 553-91; L/P&S/6/373, pp. 571-[640].
- 882** 31 Aug., 1853. PC 8400, Dr 697, D 4: *E/4/979, pp. 111-47; L/P&S/6/375, pp. 123-[190].
- 883** 12 Oct., 1853. PC 8448, Dr 845, D 5: *E/4/979, pp. 373-98; L/P&S/6/375, pp. 683-[730].
- 884** 12 Apr., 1854. PC 8695, Dr 294, D 1: *E/4/980, pp. 339-406; L/P&S/6/378, pp. 679-[780].
- 885** 18 Oct., 1854. PC 8975, Dr 938, D 3: *E/4/981, pp. 611-59; L/P&S/6/382, pp. 489-[572].
- 886** 31 Jan., 1855. PC 9095, Dr 86, D 1: *E/4/982, pp. 179-95; L/P&S/6/383, pp. 117-[146].
- 887** 30 Apr., 1856. PC 9635, Dr 348, D 3: *E/4/984, pp. 931-1040; L/P&S/6/389, pp. 147-[308].
- 888** 27 May, 1856. PC 9847, Dr 544, D 4: *E/4/984, pp. 1279-1300; L/P&S/6/390, pp. 71-[114].
- 889** 2 Jan., 1857. PC 177, Dr 1403, D 1: *E/4/986, pp. 1031-48; L/P&S/6/391, pp. 823-[854].
- 890** 28 Jan., 1857. PC 199, Dr 48, D 2: *E/4/986, pp. 1259-81; L/P&S/6/392, pp. 279-[304], 309-[328].
- 891** 8 Apr., 1857. PC 322, Dr 330, D 3: *E/4/987, pp. 499-552; L/P&S/6/393, pp. 207-[288].
- 892** 11 Nov., 1857. PC 661, Dr 1329, D 5: *E/4/988, pp. 1289-1305; L/P&S/6/395, pp. 57-[86].
- 893** 3 Mar., 1858. PC 825, Dr 159, D 4: *E/4/989, pp. 781-820; L/P&S/6/396, pp. 231-[300].
- 894** 7 July, 1858; Carnatic family. PC 1010, Dr 779, D 5: *E/4/990, pp. 629-72; L/P&S/6/397, pp. 581-[652].
- 895** 13 July, 1858; Tanjore family. PC 1021, Dr 810, D 7: *E/4/990, pp. 707-22; L/P&S/6/397, pp. 875-[900].
- 896** 7 July, 1858. PC 1042, Dr 782, D 6: *E/4/990, pp. 673-98; L/P&S/6/397, pp. 653-[702].
- 897** 30 Aug., 1858. PC 1176, Dr 1121, D 9:

*E/4/990, pp. 1315A-40; L/P&S/6/399, pp. 19-[68].

898 1 Sept., 1858. PC 1195, Dr 1218, D 10: *E/4/991, pp. 327-52; L/P&S/6/399, pp. 405-[434].

898X Miscellaneous. Madras Dr 182, D 1 of 27 Oct., 1858: L/P&S/6/610, n.p.

Bombay Political Department

899 11 Mar., 1829. PC 518, Dr 205: E/4/1050, pp. 593-610; L/P&S/6/272, pp. 1-[40].

900 23 Dec., 1828; Persian Gulf and insurrection at Kittar. PC 552, Dr 102: E/4/1050, pp. 279-384; L/P&S/6/270, pp. 191-[306].

901 19 Aug., 1829. PC 598, Dr 444: *E/4/1051, pp. 445-608; L/P&S/6/273, pp. 145-[330].

902 7 Oct., 1829; affairs of Kolhapur. PC 602, Dr 506: E/4/1051, pp. 777-807; L/P&S/6/273, pp. 331-[370].

903 28 Apr., 1830; Baroda finances and affairs of Gaikwar. PC 646, Dr 316, D 3: E/4/1052, pp. 465-514; L/P&S/6/274, pp. 443-[506].

904 31 Dec., 1829; affairs of Mahi Kantha. PC 652, Dr 98: E/4/1051, pp. 1039-1204; L/P&S/6/274, pp. 17-[244].

905 26 May, 1830; affairs of Cutch. PC 681, Dr 357, D 5: E/4/1052, pp. 575-625; L/P&S/6/277, pp. 33-[102], 119-[150]. Paras. 1-9, *PP*, 1831-32, XIV, 356-8.

906 26 May, 1830; salaries, allowances, and pecuniary grants. PC 681, Dr 356, D 4: E/4/1052, pp. 549-73; L/P&S/6/277, pp. 103-[118], 151-[202]. Para. 8, *PP*, 1831-32, IX, 423.

907 20 July, 1830. PC 681, Dr 367, D 6: E/4/1052, pp. 745-855; L/P&S/6/277, pp. 151-[264].

908 20 July, 1830; affairs of Kathiawar. PC 699, Dr 414, D 7: E/4/1052, pp. 857-971; L/P&S/6/277, pp. 265-[394].

909 28 July, 1830. PC 783, Dr 477, D 8: E/4/1052, pp. 973-1050; L/P&S/6/278, pp. 5-[108].

910 17 Nov., 1830. PC 828, Dr 589, D 9: E/4/1053, pp. 341-61; L/P&S/6/278, pp. 179-[206].

911 15 Dec., 1830; tent allowances drawn by Lt. Col. J. Briggs [ex-Resident in Satara].

Dr 58, D 10: E/4/1053, pp. 399-411; L/P&S/6/280, pp. 65-[72].

912 21 Sept., 1831. PC 964, Dr 624, D 5: *E/4/1054, pp. 353-401; L/P&S/6/281, pp. 211-[270].

913 1 Feb., 1832. PC 980, Dr 38, D 1: E/4/1054, pp. 705-83; L/P&S/6/282, pp. 49-[146].

914 29 Feb., 1832; case of Lt. Col. T.D. Ballantine [ex-Political Agent in Mahi Kantha]. PC 981, Dr 106, D 2: E/4/1054, pp. 1107-54; L/P&S/6/282, pp. 293-[350].

915 10 Apr., 1833; allowances of Lt. Col. R. Barnewall, and appointment of his successor as Political Agent in Kathiawar. PC 1136, Dr 194, D 2: *E/4/1056, pp. 349-64; L/P&S/6/284, pp. 909-[944].

916 1 Aug., 1832; grants of land to Indians for public service. PC 1062, Dr 454, D 5: *E/4/1055, pp. 585-603; L/P&S/6/283, pp. 277-[308].

917 1 Aug., 1832; case of an individual styling himself Govind Row Gorepuda of South Maratha country. Dr 424, D 4: *E/4/1055, pp. 565-83; L/P&S/6/283, pp. 261-[272].

918 21 Aug., 1833; affairs of Rajpipla. PC 1180, Dr 428, D 6: *E/4/1056, pp. 951-66; L/P&S/6/285, n.p.

919 10 July, 1833; affairs of Savantvadi. PC 1167, Dr 357, D 3: *E/4/1056, pp. 725-41; L/P&S/6/285, pp. 157-[192].

920 10 July, 1833; affairs of Mandvi. PC 1166, Dr 358, D 4: *E/4/1056, pp. 743-54; L/P&S/6/285, pp. 199-[218].

920X Affairs of Kathiawar. Bombay PC 1215 altered by Board on 3 Feb., 1834: L/P&S/6/288, pp. 333-[388]. Dr 176, D 5 of 16 Apr., 1834.

921 19 Feb., 1834; misappropriation of funds in the Baroda Residency treasury. PC 1168, Dr 79, D 3: E/4/1057, pp. 513-39; L/P&S/6/287, pp. 311-[366].

922 3 Jan., 1834; North-West Frontier. PC 1213, Dr 673, D 1: E/4/1057, pp. 375-88; L/P&S/6/286, pp. 652-[707].

923 11 June, 1834; Satara and the Southern Maratha country. PC 1218, Dr 177, D 8: E/4/1057, pp. 1089-1157; L/P&S/6/288, pp. 477-[630], 679-[746]. (L.)

924 4 Dec., 1833; affairs of Cutch. PC 1217, Dr 611, D 9: *E/4/1057, pp. 205-18; L/P&S/6/286, pp. 259-[306].

- 925** 16 Apr., 1834; Persian Gulf. PC 1230, Dr 183, D 6: *E/4/1057, pp. 779-91; L/P&S/6/289, pp. 1-[24].
- 926** 7 Apr., 1835; affairs of Mahi Kantha. PC 1394, Dr 187, D 2: E/4/1058, pp. 927-1006; L/P&S/6/293, pp. 57-[168].
- 927** 1 Apr., 1835; Bhils of Khandesh. PC 1410, Dr 186, D 1: E/4/1058, pp. 917-26; L/P&S/6/293, pp. 37-[56].
- 928** 7 Apr., 1835; affairs of the Gaikwar. PC 1416, Dr 202, D 3: E/4/1058, pp. 1007-16; L/P&S/6/293, pp. 237-[256].
- 929** 27 May, 1835; affairs of Kathiawar. PC 1438, Dr 284, D 4: E/4/1058, pp. 1153-1202; L/P&S/6/294, pp. 157-[208].
- 930** 10 June, 1835; treaty between the U.S.A. and the Imam of Muscat. PC 1453, Dr 267, D 5: E/4/1059, pp. 67-80; L/P&S/6/293, pp. 449-[468].
- 931** 12 Aug., 1835; affairs of Idar. PC 1482, Dr 452, D 11: E/4/1059, pp. 261-93; L/P&S/6/295, pp. 287-[350].
- 932** 28 July, 1835; Southern Maratha jagirdars. PC 1490, Dr 431, D 10: E/4/1059, pp. 245-60; L/P&S/6/295, pp. 151-[170].
- 933** 22 July, 1835; affairs of Rajpipla. PC 1497, Dr 419, D 8: *E/4/1059, pp. 211-32; L/P&S/6/295, pp. 37-[68].
- 934** 16 June, 1835; affairs of Palanpur. PC 1502, Dr 341, D 6: *E/4/1059, pp. 81-8; L/P&S/6/294, pp. 385-[404].
- 935** 19 Aug., 1835; affairs of Cutch. PC 1521, Dr 418, D 12: *E/4/1059, pp. 327-54; L/P&S/6/295, pp. 1-[36].
- 936** 22 July, 1835; affairs of Angria. PC 1541, Dr 417, D 7: E/4/1059, pp. 199-209; L/P&S/6/294, pp. 575-[594].
- 937** 22 July, 1835; affairs of Akalkot. PC 1540, Dr 432, D 9: *E/4/1059, pp. 233-40; L/P&S/6/295, pp. 171-[194].
- 938** 18 Nov., 1835. PC 1592, Dr 644, D 15: *E/4/1059, pp. 587-613; L/P&S/6/297, pp. 199-[246].
- 939** 29 Dec., 1835. PC 1631, Dr 696, D 17: *E/4/1059, pp. 747-56; L/P&S/6/297, pp. 291-[310].
- 940** 29 Dec., 1835; grant to Lt. Col. R. Barnewall [ex-Political Agent in Kathiawar]. PC 1637, Dr 695, D 16: *E/4/1059, pp. 733-45; L/P&S/6/297, pp. 271-[290].
- 941** 16 Mar., 1836; affairs of Cutch. PC 1673, Dr 104, D 1: *E/4/1059, pp. 1105-14; L/P&S/6/298, pp. 501-[520].
- 941X** Case of Col. T.D. Balantine (ex-Political Agent in Mahi Kantha). Bombay PC 1939 altered by Board on 24 Aug., 1837: L/P&S/6/306, pp. 173-[n.p.], but see also notes by T.L. Peacock in cited volume. Dr 62, D 6 of 4 Apr., 1838.
- 942** 27 Apr., 1836; affairs of Kathiawar. PC 1692, Dr 194, D 2: *E/4/1060, pp. 91-112; L/P&S/6/277, pp. 101a-[n.p.].
- 943** 8 June, 1836. PC 1721, Dr 266, D 3: *E/4/1060, pp. 310-51; L/P&S/6/299, pp. 133-[200].
- 944** 15 June, 1836; affairs of the Mahi Kantha. PC 1720, Dr 286, D 4: *E/4/1060, pp. 364-98; L/P&S/6/299, pp. 235-[294].
- 945** 7 Sept., 1836; affairs of Kathiawar. PC 1791, Dr 418, D 8: *E/4/1060, pp. 583-98; L/P&S/6/299, pp. 345-[372].
- 946** 18 Oct., 1837; affairs of the Mahi Kantha, and new political arrangements in Gujarat. PC 1934, Dr 472, D 3: *E/4/1061, pp. 617-64; L/P&S/6/302, pp. 399-[470]. +L.
- 947** 20 June, 1837; affairs of Kathiawar. PC 1900, Dr 279, D 1: *E/4/1061, pp. 229-46; L/P&S/6/300, pp. 171-[200].
- 948** 6 Sept., 1837; affairs of the Persian Gulf. PC 1944, Dr 432, D 1: *E/4/1061, pp. 513-32; L/P&S/6/301, pp. 369-[400].
- 949** 25 Oct., 1837; affairs of Cutch. PC 1948, Dr 497, D 4: *E/4/1061, pp. 807-39; L/P&S/6/303, pp. 365-[420].
- 950** 22 Nov., 1837. PC 1968, Dr 535, D 5: E/4/1061, pp. 923-74; L/P&S/6/303, pp. 433-[520].
- 951** 5 Jan., 1838. PC 1979, Dr 609, D 1: E/4/1062, pp. 5-27; L/P&S/6/304, pp. 191-[214], 219-[234].
- 952** 13 Feb., 1838; claims of the sons of Gungadhur Shastree on the Gaikwar of Baroda. PC 2057, Dr 69, D 3: *E/4/1062, pp. 239-50; L/P&S/6/307, pp. 271-[290].
- 953** 14 Mar., 1838; case of the adopted son of Wittul Row Dewanjee. PC 2002, Dr 70, D 4: *E/4/1062, pp. 469-83; L/P&S/6/307, pp. 323-[332]. +L. *PP*, 1850, XLI, 59-60.
- 954** 16 May, 1838; affairs of Kathiawar. PC 2072, Dr 292, D 10: *E/4/1062, pp. 1049-74; L/P&S/6/309, pp. 391-[418], 457-[472]. +L.
- 955** 13 Feb., 1838; affairs of Baroda. PC 2002, Dr 50, D 2: *E/4/1062, pp. 211-38; L/P&S/6/305, pp. 487-[566], 589-[608]. +L.
- 956** 14 Mar., 1838. PC 2077, Dr 146, D 5:

*E/4/1062, pp. 485-504; L/P&S/6/308, pp. 57-[90].

957 17 Aug., 1838; affairs of Mahi Kantha. PC 2111, Dr 471, D 14: *E/4/1063, pp. 369-400; L/P&S/6/311, pp. 426-[473].

958 2 May, 1838; claim of the Company upon the estate of the late J. Williams [Bombay Civil Service]. PC 2131, Dr 267, D 8: *E/4/1062, pp. 841-52; L/P&S/6/309, pp. 137-[156].

959 31 May, 1838; Southern Maratha country. PC 2132, Dr 329, D 11: *E/4/1062, pp. 1137-56; L/P&S/6/310, pp. 351-[386].

960 16 May, 1838; affairs of Cutch. PC 2147, Dr 291, D 9: *E/4/1062, pp. 1041-8; L/P&S/6/309, pp. 375-[390].

961 29 Aug., 1838. PC 2196, Dr 513, D 15. *E/4/1063, pp. 411-54; L/P&S/6/312, pp. 81-[151].

962 17 Aug., 1838; coolee insurrection in Gujarat. PC 2111, Dr 440, D 13: *E/4/1063, pp. 335-68; L/P&S/6/311, pp. 340-[365], 375-[425].

963 1 May, 1839; commission of inquiry at Dharwad. PC 2236, Dr 238, D 4: E/4/1064, pp. 723-62; L/P&S/6/314, pp. 378-[441] [sic].

964 24 Oct., 1838; affairs of Savantvadi. PC 2264, Dr 632, D 17: *E/4/1063, pp. 713-22; L/P&S/6/313, pp. 149-[164].

965 20 Mar., 1839; affairs of Savantvadi. PC 2302, Dr 105, D 1: E/4/1064, pp. 419-43; L/P&S/6/314, pp. 224-[255].

966 28 Aug., 1839; court martial on Maj. G. Paul [Bombay Light Cavalry]. PC 2369, Dr 494, D 9: *E/4/1064, pp. 1329-38; L/P&S/6/315, pp. 277-[296].

967 21 Aug., 1839; affairs of Kathiawar. PC 2367, Dr 461, D 8: *E/4/1064, pp. 1271-1318; L/P&S/6/315, pp. 205-[276].

968 26 June, 1839; operations against the Naikras in Gujarat. PC 2368, Dr 363, D 6: *E/4/1064, pp. 1037-52; L/P&S/6/315, pp. 93-[116].

969 9 Oct., 1839; Persian Gulf. PC 2491, Dr 550, D 10: *E/4/1065, pp. 242-60; L/P&S/6/316, pp. 37-[68].

970 12 Mar., 1840; affairs of Mahi Kantha. PC 2500, Dr 108, D 6: *E/4/1065, pp. 1284-1328; L/P&S/6/317, pp. 73-[150].

971 23 Oct., 1839; affairs of Cutch. PC 2507, Dr 596, D 11: *E/4/1065, pp. 304-24; L/P&S/6/316, pp. 113-[148].

972 23 Oct., 1839. PC 2508, Dr 597, D 12: *E/4/1065, pp. 326-41; L/P&S/6/316, pp. 153-[186].

973 12 Mar., 1840. PC 2540, Dr 81, D 5: *E/4/1065, pp. 1216-82; L/P&S/6/318, pp. 1-[92].

974 19 Feb., 1840; Savantvadi. PC 2613, Dr 68, D 2: *E/4/1065, pp. 986-1014; L/P&S/6/318, pp. 303-[352].

975 19 Feb., 1840; disturbances and attempts at disturbances in Bombay Presidency. PC 2610, Dr 69, D 3: *E/4/1065, pp. 1016-41; L/P&S/6/318, pp. 261-[302].

976 13 May, 1840; affairs of Kathiawar. PC 2671, Dr 245, D 11: *E/4/1066, pp. 199-218; L/P&S/6/319, pp. 313-[346].

977 13 May, 1840. PC 2683, Dr 244, D 10: *E/4/1066, pp. 173-98; L/P&S/6/319, pp. 389-[432].

978 20 May, 1840; succession to the estate of Limbdi. PC 2691, Dr 262, D 12: *E/4/1066, pp. 265-83; L/P&S/6/319, pp. 433-[464].

979 2 July, 1840; affairs of the Gaikwar. PC 2726, Dr 400, D 13: E/4/1066, pp. 561-98; L/P&S/6/319, pp. 555-[588], 627-[644]. +L. Paras. 8-10. *PP*, 1852-53, LXIX, 259.

980 8 July, 1840; disputes between the Rao of Cutch and certain Wagher chiefs. PC 2729, Dr 376, D 14: *E/4/1066, pp. 617-42; L/P&S/6/319, pp. 645-[682].

981 31 July, 1840. PC 2762, Dr 456, D 15: *E/4/1066, pp. 831-71; L/P&S/6/320, pp. 103-[172].

982 2 Sept., 1840; affairs of Satara. PC 2815, Dr 553, D 16: *E/4/1066, pp. 1011-62; L/P&S/6/320, pp. 497-[522]. In *Papers Respecting the Case of the Raja of Satara* (London, 1840), 388-9.

983 2 Sept., 1840; offer of the Rao of Cutch to educate two of Sir Henry Pottinger's children. PC 2820, Dr 554, D 17: *E/4/1066, pp. 1027-34; L/P&S/6/320, pp. 523-[536].

984 23 Dec., 1840. PC 2874, Dr 773, D 19: E/4/1067, pp. 701-27; L/P&S/6/321, pp. 341-[386].

985 25 Nov., 1840; affairs of Kathiawar. PC 2875, Dr 733, D 18: *E/4/1067, pp. 557-74; L/P&S/6/321, pp. 387-[412].

986 3 Mar., 1841; affairs of the Gaikwar. PC 2941, Dr 159, D 3: *E/4/1067, pp. 1047-71; L/P&S/6/322, pp. 29-[56], 59-[72]. Para. 8, *PP*, 1852-53, LXIX, 259.

- 987** 10 Feb., 1841; corruption in the establishment of the Political Commissioner in Gujarat. PC 2957, Dr 106, D 2: *E/4/1067, pp. 951-71; L/P&S/6/322, pp. 191-[222]. *PP*, 1852, XXXVII, Pt. 1, 49-50.
- 988** 7 Apr., 1841; Mahi and Rewa Kantha. PC 2954, Dr 230, D 6: *E/4/1068, pp. 39-60; L/P&S/6/322, pp. 153-[190]. (*L*).
- 989** 27 Jan., 1841; affairs of Cutch. PC 2953, Dr 72, D 1: E/4/1067, pp. 873-84; L/P&S/6/322, pp. 121-[132], 147-[152].
- 990** 16 Mar., 1841. PC 2961, Dr 169, D 4: *E/4/1067, pp. 1129-80; L/P&S/6/322, pp. 235-[318].
- 991** 31 Mar., 1841. PC 2987, Dr 203, D 5: *E/4/1067, pp. 1353-90; L/P&S/6/322, pp. 647-[692].
- 992** 7 Apr., 1841; affairs of Kathiawar. PC 2994, Dr 231, D 7: *E/4/1068, pp. 61-79; L/P&S/6/322, pp. 813-[842].
- 993** 21 Apr., 1841. PC 2991, Dr 294, D 10: *E/4/1068, pp. 185-258; L/P&S/6/322, pp. 697-[772], 775-[812].
- 994** 25 May, 1841; lapse of the territory of Colaba. PC 3010, Dr 315, D 11: *E/4/1068, pp. 395-412; L/P&S/6/322, pp. 843-[862], 945-[958]. *PP*, 1850, XLI, 624-5.
- 995** 27 July, 1842; court martial on Lt. W. Gibbard [Bombay Native Infantry]. PC 3537, Dr 435, D 14: *E/4/1071, pp. 117-56; L/P&S/6/328, pp. 157-[216].
- 996** 13 Apr., 1841; case of Ram Rao Ukburnavees at Kolhapur. PC 3034, Dr 270, D 9: *E/4/1068, pp. 145-65B; L/P&S/6/323, pp. 249-[300].
- 997** 25 May, 1841. PC 3087, Dr 381, D 12: *E/4/1068, pp. 413-50; L/P&S/6/323, pp. 547-[608].
- 998** 16 June, 1841. PC 3075, Dr 431, D 15: *E/4/1068, pp. 581-634; L/P&S/6/323, pp. 465-[546].
- 999** 7 Apr., 1841; wish of the Raja of Satara to confer lands on Ballajee Punt Nathoo. PC 3052, Dr 271, D 8: E/4/1068, pp. 81-6; L/P&S/6/323, pp. 375-[386].
- 1000** 21 Dec., 1842; affairs of the Gaikwar. PC 3237, Dr 777, D 21: *E/4/1072, pp. 25-48; L/P&S/6/325, pp. 69-[110]. Paras. 9-10, *PP*, 1852-53, LXIX, 260.
- 1001** 2 July 1841; case of Lt. W. Gibbard. PC 3163, Dr 500, D 16: *E/4/1068, pp. 859-63; L/P&S/6/324, pp. 13-[24].
- 1002** 22 Sept., 1841; affairs of Kathiawar. PC 3205, Dr 675, D 17: *E/4/1069, pp. 47-64; L/P&S/6/324, pp. 413-[444].
- 1003** 12 Jan., 1842; Mahi and Rewa Kantha. PC 3258, Dr 942, D 2: *E/4/1069, pp. 797-860; L/P&S/6/325, pp. 641-[738].
- 1004** 13 Oct., 1841; disturbances in the Deccan. PC 3219, Dr 689, D 18: *E/4/1069, pp. 221-56; L/P&S/6/324, pp. 445-[492].
- 1005** 17 Nov., 1841. PC 3230, Dr 783, D 21: E/4/1069, pp. 405-56; L/P&S/6/325, pp. 111-[192].
- 1006** 13 Oct., 1841. PC 3227, Dr 713, D 19: *E/4/1069, pp. 257-88; L/P&S/6/324, pp. 493-[522], 523-[542]. Para. 13, *PP*, 1850, XLI, 60.
- 1007** 13 Oct., 1841. PC 3228, Dr 714, D 20: *E/4/1069, pp. 289-312; L/P&S/6/324, pp. 543-[590].
- 1008** 26 Oct., 1842; surinjam lands in the Deccan. PC 3313, Dr 436, D 17: *E/4/1071, pp. 669-710; L/P&S/6/328, pp. 393-[454].
- 1009** 22 Mar., 1842; affairs of Kathiawar. PC 3312, Dr 145, D 7: *E/4/1070, pp. 119-44; L/P&S/6/326, pp. 527-[574]. Paras. 6-8, *PP*, 1852-53, LXIX, 15.
- 1010** 26 Jan., 1842. PC 3302, Dr 31, D 4: *E/4/1069, pp. 955-89; L/P&S/6/326, pp. 343-[404].
- 1011** 26 Jan., 1842. PC 3301, Dr 32, D 5: *E/4/1069, pp. 991-1001; L/P&S/6/326, pp. 243-[274], 291-[298].
- 1012** 31 Dec., 1841; allowances of A.N. Shaw [Acting Political Agent, Southern Maratha country]. PC 3311, Dr 911, D 23: *E/4/1069, pp. 773-84; L/P&S/6/325, pp. 449-[472].
- 1013** 12 Apr., 1842. PC 3334, Dr 195, D 8: *E/4/1070, pp. 255-303; L/P&S/6/327, pp. 31-[104].
- 1014** 26 Jan., 1842. PC 3332, Dr 33, D 6: *E/4/1069, pp. 1003-24; L/P&S/6/326, pp. 407-[442].
- 1015** 6 July, 1842; affairs of Baroda. PC 3345, Dr 356, D 13: *E/4/1070, pp. 1049-88; L/P&S/6/328, pp. 1-[40], 45-[68]. +*L*. Paras. 9-11, *PP*, 1852, XXXVII, Pt. 1, 50-1.
- 1016** 1 June, 1842; Mahi Kantha. PC 3344, Dr 303, D 10: *E/4/1070, pp. 661-89; L/P&S/6/327, pp. 339-[392]. Para. 6 in both *PP*, 1852, XXXVII, Pt. 1, 50; and *PP*, 1852-53, LXX, 38.
- 1017** 26 Jan., 1842; affairs of Savantvadi. PC 3301, Dr 19, D 3: *E/4/1069, pp. 931-53; L/P&S/6/326, pp. 243-[290].

1018 1 June, 1842. PC 3440, Dr 305, D 12: *E/4/1070, pp. 707-49; L/P&S/6/327, pp. 417-[490].

1019 1 June, 1842; affairs of Idar. PC 3439, Dr 304, D 11: *E/4/1070, pp. 691-706; L/P&S/6/327, pp. 393-[416].

1020 24 May, 1842. PC 3464, Dr 306, D 9: *E/4/1070, pp. 559-98; L/P&S/6/327, pp. 491-[552].

1021 28 Sept., 1842; affairs of Kathiawar. PC 3528, Dr 627, D 16: *E/4/1071, pp. 493-516; L/P&S/6/328, pp. 701-[738].

1022 30 Dec., 1842; assumption of the state of Mandvi. PC 3564, Dr 842, D 24: *E/4/1072, pp. 171-86; L/P&S/6/329, pp. 361-[382]. *PP*, 1850, XLI, 626-7.

1023 18 Jan., 1843. PC 3583, Dr 11, D 2: *E/4/1072, pp. 217-86; L/P&S/6/330, pp. 115-[214].

1023X Paragraphs respecting a charge incurred by Capt. A. Hamerton. See full entry at 1087.

1024 23 Nov., 1842. PC 3602, Dr 741, D 19: *E/4/1071, pp. 937-64; L/P&S/6/329, pp. 167-[212].

1025 21 Sept., 1842; slavery and the slave trade. PC 3593, Dr 596, D 15: *E/4/1071, pp. 329-48; L/P&S/6/328, pp. 631-[660].

1025X Memorial of Ram Row Bheemajee of Kolhapur. India PC 3648 altered by Board on 31 Aug., 1842; L/P&S/6/329, pp. 1-3A. Dr 609, D 18 of 16 Nov., 1842.

1026 25 Jan., 1843. PC 3659, Dr 41, D 3: *E/4/1072, pp. 357-410; L/P&S/6/330, pp. 215-[304]. *Para. 6, PP*, 1852, XXXVII, Pt. 1, 51.

1027 21 Dec., 1842; affairs of Kathiawar. PC 3689, Dr 822, D 23: *E/4/1072, pp. 55-66; L/P&S/6/329, pp. 437-[458].

1028 22 Feb., 1843. PC 3711, Dr 80, D 4: *E/4/1072, pp. 527-77; L/P&S/6/330, pp. 591-[678].

1029 4 Jan., 1843; Mahi and Rewa Kantha. PC 3702, Dr 843, D 1: *E/4/1072, pp. 191-211; L/P&S/6/329, pp. 683-[716].

1030 14 Dec., 1842; case of the *Bugla Bhowany Pursand*. PC 3727, Dr 807, D 20: *E/4/1072, pp. 5-17; L/P&S/6/329, pp. 403-[424].

1031 21 Dec., 1842; the wreck of the *Bugla Tyree*. PC 3757, Dr 821, D 22: *E/4/1072, pp. 49-53; L/P&S/6/329, pp. 425-[436].

1032 11 Apr., 1843; slave trade. PC 3822A,

Dr 227, D 7: *E/4/1072, pp. 971-8; L/P&S/6/331, pp. 283-[294].

1033 3 May, 1843. PC 3868, Dr 240, D 8: *E/4/1072, pp. 1121-38; L/P&S/6/331, pp. 311-[342].

1034 20 Sept., 1843. PC 3902, Dr 612, D 15: *E/4/1073, pp. 885-921; L/P&S/6/332, pp. 135-[202].

1035 19 July, 1843. PC 3900, Dr 475, D 12: *E/4/1073, pp. 449-80; L/P&S/6/331, pp. 625-[684]. *Paras. 6-7, PP*, 1852-53, LXX, 40.

1036 30 May, 1843; explanations by Lt. Col. E. Evans [Resident at Satara] and J.P. Willoughby [Bombay Civil Service]. PC 3894, Dr 345, D 9: *E/4/1073, pp. 167-75; L/P&S/6/331, pp. 481-[500].

1037 20 Sept., 1843; report of the Adhoi Commission. PC 3933, Dr 611, D 14: *E/4/1073, pp. 865-84; L/P&S/6/332, pp. 99-[134].

1038 26 Sept., 1843; affairs of the Gaikwar. PC 3946, Dr 624, D 16: *E/4/1073, pp. 967-80; L/P&S/6/332, pp. 293-[320].

1039 4 Oct., 1843; affairs of Kathiawar. PC 4055, Dr 635, D 17: *E/4/1074, pp. 13-26; L/P&S/6/332, pp. 471-[502].

1040 4 Oct., 1843; Southern Maratha country. PC 4054, Dr 636, D 18: *E/4/1074, pp. 27-34; L/P&S/6/332, pp. 503-[522].

1041 1 Nov., 1843; Mahi and Rewa Kantha. PC 4078, Dr 693, D 20: *E/4/1074, pp. 195-204; L/P&S/6/333, pp. 261-[284].

1042 15 Nov., 1843. PC 4101, Dr 727, D 21: *E/4/1074, pp. 267-313; L/P&S/6/331, pp. 721-[782].

1043 18 Oct., 1843; slave trade. PC 4079, Dr 666, D 19: *E/4/1074, pp. 51-62; L/P&S/6/332, pp. 601-[618].

1044 17 Jan., 1844. PC 4156, Dr 20, D 1: *E/4/1074, pp. 710-42; L/P&S/6/334, pp. 1A-[66].

1045 28 Feb., 1844; Southern Maratha country. PC 4169, Dr 106, D 3: *E/4/1074, pp. 922-75; L/P&S/6/334, pp. 311-[392].

1046 24 Jan., 1844. PC 4181, Dr 33, D 2: *E/4/1074, pp. 760-71; L/P&S/6/334, pp. 163-[182].

1047 27 Mar., 1844. PC 4188, Dr 178, D 5: *E/4/1074, pp. 1152-89; L/P&S/6/334, pp. 789-[860].

1048 2 Apr., 1844; affairs of Cutch. PC 4204, Dr 177, D 7: *E/4/1075, pp. 17-56; L/P&S/6/334, pp. 721-[788].

- 1049** 3 Apr., 1844; Mahi and Rewa Kantha. PC 4231, Dr 244, D 8: *E/4/1075, pp. 149-78; L/P&S/6/335, pp. 203-[266].
- 1050** 27 Mar., 1844; affairs of Kathiawar. PC 4230, Dr 197, D 6: *E/4/1074, pp. 1190-1204; L/P&S/6/335, pp. 175-[202]. Paras. 2-4, *PP*, 1852-53, LXXI, 17.
- 1051** 24 Apr., 1844; affairs of Colaba. PC 4271, Dr 263, D 11: *E/4/1075, pp. 223-38; L/P&S/6/335, pp. 377-[408]. *PP*, 1850, XLI, 625-6.
- 1052** 17 Apr., 1844; slave trade. PC 4278, Dr 253, D 10: *E/4/1075, pp. 193-206; L/P&S/6/335, pp. 349-[376].
- 1053** 2 Aug., 1844. PC 4291, Dr 558, D 21: *E/4/1076, pp. 1-70; L/P&S/6/336, pp. 193-[314]. Paras. 49-53, *PP*, 1850, XLI, 627.
- 1054** 17 Apr., 1844. PC 4282, Dr 252, D 9: *E/4/1075, pp. 185-92; L/P&S/6/335, pp. 329-[348].
- 1055** 21 Aug., 1844; extinction of the office and dignity of Nawab of Surat. PC 4289, Dr 614, D 22: *E/4/1076, pp. 191-219B; L/P&S/6/336, pp. 405-[446].
- 1056** 26 June, 1844; affairs of Kathiawar. PC 4298, Dr 420, D 15: *E/4/1075, pp. 775-91; L/P&S/6/335, pp. 693-[722].
- 1057** 26 June, 1844; affairs of Savantvadi. PC 4305, Dr 421, D 16: *E/4/1075, pp. 793-808; L/P&S/6/335, pp. 723-[750].
- 1058** 26 June, 1844. PC 4309, Dr 422, D 17: *E/4/1075, pp. 809-16; L/P&S/6/335, pp. 751-[770].
- 1059** 18 June, 1844; allowances of Lt. Col. J. Outram [ex-Political Agent in Sind]. PC 4318, Dr 326, D 13: E/4/1075, pp. 679-84; L/P&S/6/335, pp. 585-[608].
- 1060** 26 June, 1844; Mahi Kantha. PC 4326, Dr 419, D 14: *E/4/1075, pp. 755-73; L/P&S/6/335, pp. 657-[692].
- 1061** 26 June, 1844. PC 4343, Dr 423, D 18: *E/4/1075, pp. 817-40; L/P&S/6/335, pp. 771-[810].
- 1062** 31 July, 1844; affairs of Kathiawar. PC 4416, Dr 531, D 19: *E/4/1075, pp. 1152-63; L/P&S/6/336, pp. 25-[44].
- 1063** 16 Oct., 1844. PC 4479, Dr 746, D 28: *E/4/1076, pp. 489-94; L/P&S/6/336, pp. 875-[916].
- 1064** 31 July, 1844. PC 4399, Dr 532, D 20: *E/4/1075, pp. 1164-75; L/P&S/6/336, pp. 45-[68]. Para. 6, *PP*, 1852, XXXVII, Pt. 1, 51.
- 1065** 4 Sept., 1844; case of the ex-Raja of Satara. Dr 666, D 23: *E/4/1076, pp. 318-21; L/P&S/6/336, pp. 479-[482].
- 1066** 4 Sept., 1844; Meer Jafar Ali Khan [son-in-law of Nawab of Surat]. PC 4480, Dr 677, D 24: *E/4/1076, pp. 323-30; L/P&S/6/336, pp. 483-[502].
- 1067** 6 Nov., 1844; Mahi and Rewa Kantha. PC 4496, Dr 779, D 29: *E/4/1076, pp. 627-48; L/P&S/6/337, pp. 179-[218].
- 1068** 4 Sept., 1844; missionaries in Zanzibar. PC 4483, Dr 678, D 25: *E/4/1076, pp. 331-8; L/P&S/6/336, pp. 503-[522].
- 1069** 2 Oct., 1844; revenue of the ex-Raja of Mandvi. PC 4489, Dr 705, D 26: *E/4/1076, pp. 471-8; L/P&S/6/336, pp. 523-[538].
- 1070** 27 Nov., 1844; affairs of Satara. PC 4544, Dr 845, D 30: *E/4/1076, pp. 827-48; L/P&S/6/337, pp. 289-[320].
- 1071** 4 Dec., 1844; affairs of Kathiawar. PC 4553, Dr 922, D 36: *E/4/1077, pp. 161-92; L/P&S/6/338, pp. 197-[256]. Paras. 14-18, *PP*, 1852-53, LXXI, 19-20.
- 1072** 27 Nov., 1844; slave trade. PC 4548, Dr 873, D 32: *E/4/1076, pp. 863-72; L/P&S/6/337, pp. 329-[348].
- 1073** 27 Nov., 1844; present of horses from the Imam of Muscat to the Chairman of the Company. PC 4569, Dr 875, D 34: *E/4/1076, pp. 905-13; L/P&S/6/338, pp. 129-[152].
- 1074** 27 Nov., 1844. PC 4570, Dr 872, D 31: *E/4/1076, pp. 849-62; L/P&S/6/338, pp. 45-[72].
- 1075** 4 Dec., 1844. PC 4582, Dr 923, D 37: E/4/1077, pp. 193-230; L/P&S/6/338, pp. 257-[324].
- 1076** 27 Nov., 1844; case of the Parghur Gurkurrees [Southern Maratha country]. PC 4562, Dr 874, D 33: *E/4/1076, pp. 873-903; L/P&S/6/338, pp. 73-[128].
- 1077** 15 Jan., 1845; family of Gungadhur Shastree. PC 4616, Dr 33, D 3: *E/4/1077, pp. 563-91; L/P&S/6/339, pp. 101-[158].
- 1078** 24 Dec., 1844. PC 4589, Dr 964, D 42: *E/4/1077, pp. 386-422; L/P&S/6/338, pp. 505-[576]. Paras. 4-7, *PP*, 1852-53, LXX, 78-9.
- 1079** 17 Dec., 1844; affairs of Rajpipla. PC 4574, Dr 938, D 39: *E/4/1077, pp. 251-78; L/P&S/6/338, pp. 333-[376].
- 1080** 24 Dec., 1844; Mahi Kantha. PC 4585, Dr 963, D 41: *E/4/1077, pp. 346-85; L/P&S/6/338, pp. 445-[504].

1081 24 Dec., 1844. PC 4599, Dr 965, D 43: *E/4/1077, pp. 423-62; L/P&S/6/338, pp. 577-[656].

1082 15 Jan., 1845; affairs of Savantvadi. PC 4636, Dr 18, D 2: *E/4/1077, pp. 537-61; L/P&S/6/339, pp. 53-[100].

1083 5 Feb., 1845. PC 4624, Dr 78, D 5: *E/4/1077, pp. 767-822; L/P&S/6/339, pp. 265-[368].

1084 18 Dec., 1844; succession to estate of Nowlgoond. PC 4607, Dr 949, D 40: *E/4/1077, pp. 297-310; L/P&S/6/338, pp. 393-[416].

1085 5 Feb., 1845; affairs of Colaba. PC 4652, Dr 47, D 4: *E/4/1077, pp. 747-66; L/P&S/6/339, pp. 225-[264].

1086 5 Feb., 1845. PC 4640, Dr 79, D 6: *E/4/1077, pp. 823-55; L/P&S/6/339, pp. 369-[426]. Para. 5, *PP*, 1852-53, LXX, 290.

1087 3 Jan., 1845; complaints of Imam of Muscat against Capt. A. Hamerton [Political Agent in Muscat]. PC 4661, Dr 11, D 1: *E/4/1077, pp. 517-24; L/P&S/6/339, pp. 1-[20].

1088 19 Mar., 1845; Southern Maratha country. PC 4674, Dr 181, D 8: *E/4/1077, pp. 1113-58; L/P&S/6/339, pp. 887-[966].

1089 23 Apr., 1845; political establishment in Gujarat. PC 4726, Dr 321, D 12: *E/4/1078, pp. 337-55; L/P&S/6/340, pp. 109-[142].

1090 16 Apr., 1845. PC 4758, Dr 292, D 11: *E/4/1078, pp. 263-72; L/P&S/6/340, pp. 89-[108]. Para. 6, *PP*, 1850, XLI, 60.

1091 16 Apr., 1845. PC 4747, Dr 291, D 10: *E/4/1078, pp. 237-62; L/P&S/6/340, pp. 45-[88].

1092 16 Apr., 1845; slave trade. PC 4760, Dr 290, D 9: *E/4/1078, pp. 229-36; L/P&S/6/340, pp. 33-[44].

1093 23 Apr., 1845; affairs of Kathiawar. PC 4759, Dr 322, D 13: *E/4/1078, pp. 357-66; L/P&S/6/340, pp. 143-[162]. Para. 2, *PP*, 1852-53, LXXI, 111-12.

1094 12 Mar., 1845; proposal for conferring consular powers on Resident at Bushire. Dr 180, D 7: *E/4/1077, pp. 1077-82; L/P&S/6/339, pp. 879-[886].

1095 4 June, 1845. PC 4800, Dr 355, D 17: *E/4/1078, pp. 636-47; L/P&S/6/340, pp. 307-[326].

1096 7 May, 1845. PC 4796, Dr 356, D 14: *E/4/1078, pp. 413-29; L/P&S/6/340, pp. 163-[198].

1097 21 May, 1845; Mahi and Rewa Kantha. PC 4814, Dr 400, D 16: *E/4/1078, pp. 527-40; L/P&S/6/340, pp. 469-[496].

1098 17 Sept., 1845; disturbances in Kolhapur and Savantvadi. PC 4875, Dr 699, D 25: *E/4/1079, pp. 122-211; L/P&S/6/341, pp. 283-[432].

1099 21 Aug., 1845; case of Krustnajee, Suddassee, Bhedej and the ex-Raja of Satara. PC 4877, Dr 667, D 21: *E/4/1078, pp. 1132-47; L/P&S/6/341, pp. 181-[198], 213-[224].

1100 17 Sept., 1845. PC 4878, Dr 683, D 24: *E/4/1079, pp. 90-120; L/P&S/6/341, pp. 225-[282].

1101 27 Aug., 1845; family of the late Fyuz Ali Khan of Badnor. PC 4880, Dr 666, D 22: *E/4/1078, pp. 1164-76; L/P&S/6/341, pp. 153-[180].

1102 3 Sept., 1845; affairs of Kathiawar. PC 4879, Dr 653, D 23: E/4/1079, pp. 53-64; L/P&S/6/341, pp. 89-[108].

1103 20 Aug., 1845; Mahi and Rewa Kantha. PC 4901, Dr 654, D 20: *E/4/1078, pp. 1108-31; L/P&S/6/341, pp. 109-[152].

1104 1 Oct., 1845; Persian Gulf. PC 4958, Dr 755, D 26: *E/4/1079, pp. 270-93; L/P&S/6/342, pp. 41-[80].

1105 21 Jan., 1846. PC 5061, Dr 29, D 1: *E/4/1080, pp. 129-220; L/P&S/6/343, pp. 121-[294].

1106 19 Nov., 1845; slavery and the slave trade. PC 5013, Dr 872, D 27: E/4/1079, pp. 602-9; L/P&S/6/342, pp. 157-[172].

1107 10 Dec., 1845; affairs of Satara. PC 5035, Dr 939, D 28: E/4/1079, pp. 760-75; L/P&S/6/342, pp. 433-[464].

1108 18 Feb., 1846. PC 5108, Dr 77, D 3: *E/4/1080, pp. 341-68; L/P&S/6/343, pp. 327-[378].

1109 22 Apr., 1846. PC 5161, Dr 253, D 12: *E/4/1080, pp. 847-75; L/P&S/6/343, pp. 121-[294].

1110 4 Feb., 1846; affairs of Kathiawar. PC 5107, Dr 68, D 2: *E/4/1080, pp. 245-57; L/P&S/6/343, pp. 325a-[325o].

1111 18 Feb., 1846; memorial of Cmdr. H. Lynch [Indian Navy]. PC 5116, Dr 90, D 5: *E/4/1080, pp. 377-85; L/P&S/6/343, pp. 383-[402].

1112 5 Mar., 1846; memorial of Moolla Ibrahim. PC 5134, Dr 125, D 6: *E/4/1080, pp. 493-507; L/P&S/6/343, pp. 415-[434].

- 1113** 1 Apr., 1846; affairs of Kathiawar. PC 5147, Dr 205, D 9: *E/4/1080, pp. 719-39; L/P&S/6/343, pp. 547-[586].
- 1114** 22 Apr., 1846; Persian Gulf. PC 5171, Dr 252, D 11: *E/4/1080, pp. 835-46; L/P&S/6/343, pp. 663-[686].
- 1115** 1 Apr., 1846; Mahi and Rewa Kantha. PC 5152, Dr 204, D 8: *E/4/1080, pp. 697-717; L/P&S/6/343, pp. 503-[546].
- 1116** 18 Feb., 1846; sword to be presented to Chintamun Row of Sangli. Dr 89, D 4: *E/4/1080, pp. 369-75; L/P&S/6/343, pp. 379-[382].
- 1116X** Disposal of two oil paintings. See full entry at 1629.
- 1117** 29 Apr., 1846. PC 5191, Dr 282, D 13: *E/4/1080, pp. 885-904; L/P&S/6/344, pp. 1-[44].
- 1118** 13 May, 1846. PC 5196, Dr 323, D 14: *E/4/1080, pp. 973-92; L/P&S/6/344, pp. 65-[104].
- 1118X** Request of Chintamun Rao (ruler of Sangli) in favour of his minister. Bombay PC 5195 altered by Board on 15 May, 1846: L/P&S/6/344, pp. 661-[663]. Transferred to Judicial Department: see D 9 of 30 Mar., 1847.
- 1119** 17 June, 1846. PC 5240, Dr 422, D 16: *E/4/1081, pp. 141-65; L/P&S/6/344, pp. 257-[306].
- 1120** 3 June, 1846; applications for pensions. PC 5236, Dr 390, D 15: *E/4/1081, pp. 105-12; L/P&S/6/344, pp. 229-[244].
- 1121** 15 July, 1846. PC 5264, Dr 494, D 17: *E/4/1081, pp. 260-307; L/P&S/6/344, pp. 581-[660].
- 1122** 22 July, 1846. PC 5287, Dr 503, D 18: *E/4/1081, pp. 367-96; L/P&S/6/345, pp. 1-[52].
- 1123** 29 July, 1846. PC 5293, Dr 528, D 21: *E/4/1081, pp. 519-64; L/P&S/6/345, pp. 163-[212].
- 1124** 29 July, 1846; Mahi and Rewa Kantha. PC 5299, Dr 526, D 19: *E/4/1081, pp. 463-96; L/P&S/6/345, pp. 57-[116]. Para. 14, *PP*, 1852-53, LXX, 121.
- 1125** 29 July, 1846; affairs of Kathiawar. PC 5312, Dr 527, D 20: *E/4/1081, pp. 497-518; L/P&S/6/345, pp. 117-[162]. Paras. 2-7, *PP*, 1852-53, LXXI, 130.
- 1126** 9 Sept., 1846. PC 5351, Dr 607, D 22: *E/4/1081, pp. 703-18; L/P&S/6/345, pp. 533-[556].
- 1127** 30 Sept., 1846; affairs of Kathiawar. PC 5374, Dr 679, D 26: *E/4/1081, pp. 969-88; L/P&S/6/345, pp. 637-[676]. Paras. 7-8, *PP*, 1852-53, LXXI, 366.
- 1128** 22 Sept., 1846; Mahi and Rewa Kantha. PC 5373, Dr 664, D 25: *E/4/1081, pp. 851-63; L/P&S/6/345, pp. 609-[636].
- 1129** 22 Sept., 1846; Khandesh. PC 5372, Dr 663, D 24: *E/4/1081, pp. 835-50; L/P&S/6/345, pp. 581-[608]. Para. 4, *PP*, 1852-53, LXX, 309.
- 1130** 23 Dec., 1846. PC 5439, Dr 885, D 29: *E/4/1082, pp. 345-79; L/P&S/6/346, pp. 367-[426] [*sic*]. Paras. 2-4, *PP*, 1852-53, LXX, 290-1.
- 1131** 18 Nov., 1846; slave trade. PC 5410, Dr 786, D 27: *E/4/1082, pp. 179-99; L/P&S/6/346, pp. 51-[90].
- 1132** 3 Feb., 1847. PC 5440, Dr 55, D 2: *E/4/1082, pp. 637-67; L/P&S/6/347, pp. 167-[222].
- 1133** 24 Feb., 1847; affairs of Kolhapur and Savantvadi. PC 5477, Dr 118, D 5: *E/4/1082, pp. 879-924; L/P&S/6/347, pp. 255-[352].
- 1134** 23 Dec., 1846. PC 5456, Dr 886, D 30: *E/4/1082, pp. 381-400; L/P&S/6/346, pp. 427-[514].
- 1135** 27 Jan., 1847; affairs of Satara. PC 5475, Dr 33, D 1: *E/4/1082, pp. 553-80; L/P&S/6/347, pp. 119-[166]. Paras. 10-15, *PP*, 1852-53, LXX, 170.
- 1136** 3 Feb., 1847. PC 5476, Dr 10, D 3: *E/4/1082, pp. 669-94; L/P&S/6/347, pp. 1-[44].
- 1137** 30 Mar., 1847. PC 5507, Dr 197, D 9: *E/4/1083, pp. 267-373; L/P&S/6/347, pp. 633-[818].
- 1138** 24 Feb., 1847; Mahi and Rewa Kantha. PC 5506, Dr 119, D 6: *E/4/1082, pp. 925-76; L/P&S/6/347, pp. 353-[436].
- 1139** 17 Feb., 1847; affairs of Savantvadi. PC 5504, Dr 96, D 4: E/4/1082, pp. 783-99; L/P&S/6/347, pp. 223-[254].
- 1140** 18 May, 1847; case of Maj. Gen. J. Dalamotte [Bombay Army]. PC 5519, Dr 196, D 12: *E/4/1083, pp. 764-72; L/P&S/6/348, pp. 267-[286].
- 1141** 17 Mar., 1847. PC 5521, Dr 173, D 7: *E/4/1083, pp. 161-78; L/P&S/6/347, pp. 551-[588].
- 1142** 21 Apr., 1847. PC 5573, Dr 282, D 10: *E/4/1083, pp. 460-95; L/P&S/6/348, pp. 371-[438].

- 1142X** Case of Cristna Rao Wittul of Gujarat. Bombay PC 5578 altered by Board on 14 Apr., 1847: L/P&S/6/351, pp. 61-79. Dr 492, D 6 of 23 Feb., 1848.
- 1143** 23 Mar., 1847; loss of Mr. Wheatley, etc. from the schooner *Highflyer*. Dr 201, D 8: *E/4/1083, pp. 195-9; L/P&S/6/347, pp. 823-[826].
- 1144** 12 May, 1847. PC 5595, Dr 346, D 11: *E/4/1083, pp. 702-35; L/P&S/6/348, pp. 443-[506].
- 1145** 23 June, 1847; affairs of Kathiawar. PC 5643, Dr 474, D 16: *E/4/1083, pp. 1100-39; L/P&S/6/349, pp. 251-[326].
- 1146** 2 June, 1847; Mahi and Rewa Kantha. PC 5634, Dr 403, D 13: *E/4/1083, pp. 922-45; L/P&S/6/348, pp. 507-[546].
- 1147** 16 June, 1847; affairs of Savantvadi. PC 5635, Dr 451, D 15: *E/4/1083, pp. 1022-34; L/P&S/6/349, pp. 77-[100].
- 1148** 16 June, 1847. PC 5636, Dr 428, D 14: *E/4/1083, pp. 998-1021; L/P&S/6/348, pp. 547-[586]. Para. 12, *PP*, 1852-53, LXXI, 542.
- 1149** 25 Aug., 1847; trials of Kolhapur and Savantvadi insurgents. PC 5726, Dr 655, D 23: *E/4/1084, pp. 531-74; L/P&S/6/350, pp. 159-[240].
- 1150** 14 July, 1847; slave trade. PC 5698, Dr 542, D 19: *E/4/1084, pp. 145-9; L/P&S/6/349, pp. 529-[540].
- 1151** 18 Aug., 1847; affairs of Kolhapur. PC 5724, Dr 634, D 22: *E/4/1084, pp. 439-58; L/P&S/6/349, pp. 671-[710].
- 1152** 18 Aug., 1847. PC 5725, Dr 633, D 21: *E/4/1084, pp. 413-37; L/P&S/6/349, pp. 623-[670]. Para. 5, *PP*, 1852-53, LXXI, 542.
- 1153** 18 Aug., 1847; affairs of Satara. PC 5728, Dr 632, D 20: *E/4/1084, pp. 401-12; L/P&S/6/349, pp. 603-[622].
- 1154** 20 Oct., 1847. PC 5765, Dr 700, D 26: *E/4/1084, pp. 1103-66; L/P&S/6/350, pp. 329-[452].
- 1155** 8 Sept., 1847; Mahi and Rewa Kantha. PC 5753, Dr 690, D 24: *E/4/1084, pp. 655-82; L/P&S/6/350, pp. 241-[300].
- 1156** 8 Sept., 1847. PC 5759, Dr 691, D 25: *E/4/1084, pp. 683-94; L/P&S/6/350, pp. 301-[328].
- 1157** 3 Nov., 1847; affairs of Colaba. PC 5787, Dr 845, D 27: *E/4/1085, pp. 88-109; L/P&S/6/350, pp. 469-[508].
- 1158** 3 Nov., 1847; affairs of Kathiawar. PC 5790, Dr 846, D 28: *E/4/1085, pp. 110-20; L/P&S/6/350, pp. 509-[528].
- 1159** 1 Dec., 1847. PC 5881, Dr 897, D 29: *E/4/1085, pp. 301-24; L/P&S/6/350, pp. 765-[816].
- 1160** 19 Jan., 1848. PC 5878, Dr 1016, D 2: *E/4/1085, pp. 479-504; L/P&S/6/350, pp. 721-[764].
- 1161** 15 Mar., 1848; family of the late Nawab of Surat. PC 5884, Dr 54, D 7: *E/4/1085, pp. 852-77; L/P&S/6/352, pp. 211-[238], 255-[274].
- 1162** 1 Feb., 1848; affairs of Kathiawar. PC 5893, Dr 41, D 4: *E/4/1085, pp. 539-53A; L/P&S/6/352, pp. 127-[154].
- 1163** 15 Mar., 1848; cases of the Pole family and Govind Row Gaikwar. PC 5935, Dr 134, D 8: *E/4/1085, pp. 878-913; L/P&S/6/352, pp. 353-[412].
- 1164** 16 Feb., 1848; Mahi and Rewa Kantha. PC 5921, Dr 101, D 5: *E/4/1085, pp. 602-36; L/P&S/6/352, pp. 291-[352].
- 1165** 21 Mar., 1848. PC 5964, Dr 152, D 9: *E/4/1085, pp. 932-57; L/P&S/6/352, pp. 429-[476].
- 1166** 26 Jan., 1848; appointment of Mr. Walter Plowden as Consul in Abyssinia. Dr 43, D 3: *E/4/1085, pp. 519-23; L/P&S/6/352, pp. 155-[158].
- 1167** 29 Mar., 1848. PC 5976, Dr 184, D 10: *E/4/1085, pp. 1064-85; L/P&S/6/352, pp. 497-[532]. Paras. 6-7, *PP*, 1852-53, LXX, 292.
- 1168** 11 Apr., 1848; affairs of Satara. PC 5996, Dr 233, D 11: *E/4/1086, pp. 61-88; L/P&S/6/352, pp. 533-[576].
- 1169** 19 Apr., 1848; affairs of Savantvadi. PC 6001, Dr 259, D 12: *E/4/1086, pp. 127-42; L/P&S/6/353, pp. 1-[24].
- 1170** 7 June, 1848. PC 6046, Dr 345, D 19: *E/4/1086, pp. 537-98; L/P&S/6/353, pp. 269-[374].
- 1171** 3 May, 1848; gras dues of the rajas of the Mandvi. PC 6033, Dr 281, D 15: *E/4/1086, pp. 311-20; L/P&S/6/353, pp. 101-[120].
- 1172** 10 May, 1848; slave trade. PC 6029, Dr 294, D 16: *E/4/1086, pp. 371-84; L/P&S/6/353, pp. 153-[172].
- 1173** 10 May, 1848; affairs of Kathiawar. PC 6031, Dr 295, D 17: *E/4/1086, pp. 385-400; L/P&S/6/353, pp. 173-[202].

- 1174** 3 May, 1848; Mahi and Rewa Kantha. PC 6032, Dr 280, D 14: *E/4/1086, pp. 297-310; L/P&S/6/353, pp. 67-[100].
- 1175** 3 May, 1848; affairs of Kolhapur. PC 6030, Dr 279, D 13: *E/4/1086, pp. 291-6; L/P&S/6/353, pp. 51-[66].
- 1176** 10 May, 1848; affairs of Palanpur. PC 6040, Dr 311, D 18: *E/4/1086, pp. 401-17; L/P&S/6/353, pp. 219-[248].
- 1177** 7 June, 1848. PC 6059, Dr 377, D 21: *E/4/1086, pp. 605-31; L/P&S/6/353, pp. 451-[492].
- 1177X** Paragraphs on the slave trade treaties. See full entry at 1172.
- 1178** 12 July, 1848; Southern Maratha country. PC 6069, Dr 458, D 23: *E/4/1086, pp. 805-31; L/P&S/6/354, pp. 1-[58]. Para. 14, *PP*, 1852-53, LXX, 335.
- 1179** 2 Aug., 1848; Cutch and Morvi disputes. PC 6089, Dr 524, D 25: *E/4/1086, pp. 997-1016; L/P&S/6/354, pp. 71-[102].
- 1180** 9 Aug., 1848; affairs of Kathiawar. PC 6133, Dr 525, D 26: *E/4/1086, pp. 1045-84; L/P&S/6/354, pp. 103-[170]. Paras. 2-3, *PP*, 1852-53, LXXI, 133.
- 1181** 21 June, 1848; Savantvadi refugees at Goa. PC 6101, Dr 408, D 22: *E/4/1086, pp. 679-86; L/P&S/6/353, pp. 521-[540].
- 1182** 16 Aug., 1848; Mahi and Rewa Kantha. PC 6137, Dr 547, D 28: *E/4/1086, pp. 1179-1200; L/P&S/6/354, pp. 203-[240].
- 1183** 9 Aug., 1848. PC 6145, Dr 526, D 27: *E/4/1086, pp. 1085-1102; L/P&S/6/354, pp. 171-[202].
- 1184** 11 Oct., 1848. PC 6169, Dr 689, D 32: *E/4/1087, pp. 221-86; L/P&S/6/354, pp. 421-[536] [*sic*].
- 1185** 16 Aug., 1848; Ahmadnagar succession. PC 6166, Dr 575, D 30: *E/4/1086, pp. 1205-20; L/P&S/6/354, pp. 293-[314].
- 1185X** School at Rajkot (Kathiawar). See full entry at 1297.
- 1186** 20 Sept., 1848; affairs of Sind. PC 6189, Dr 664, D 31: *E/4/1087, pp. 153-63; L/P&S/6/354, pp. 731-[754]. Para. 8, *PP*, 1852-53, LXX, 420.
- 1187** 15 Nov., 1848; affairs of Savantvadi. PC 6234, Dr 765, D 34: *E/4/1087, pp. 465-74; L/P&S/6/354, pp. 553-[574].
- 1188** 6 Dec., 1848; Southern Maratha country. PC 6235, Dr 795, D 37: *E/4/1087, pp. 633-46; L/P&S/6/354, pp. 679-[710].
- 1189** 22 Nov., 1848; Mahi and Rewa Kantha. PC 6233, Dr 766, D 35: *E/4/1087, pp. 501-24; L/P&S/6/354, pp. 575-[614].
- 1190** 6 Dec., 1848; appeals by the Gaikwar. PC 6228, Dr 809, D 38: *E/4/1087, pp. 647-55; L/P&S/6/354, pp. 763-[784].
- 1191** 6 Feb., 1849. PC 6314, Dr 76, D 3: *E/4/1087, pp. 1089-1118; L/P&S/6/355, pp. 241-[296].
- 1192** 6 Feb., 1849; affairs of Kolhapur. PC 6325, Dr 74, D 1: *E/4/1087, pp. 1049-74; L/P&S/6/355, pp. 169-[216].
- 1193** 14 Feb., 1849. PC 6335, Dr 91, D 6: *E/4/1087, pp. 1163-95; L/P&S/6/355, pp. 381-[444].
- 1194** 14 Feb., 1849. PC 6332, Dr 92, D 7: *E/4/1087, pp. 1197-1219; L/P&S/6/355, pp. 445-[480].
- 1195** 6 Feb., 1849; affairs of Palanpur. PC 6334, Dr 75, D 2: *E/4/1087, pp. 1075-88; L/P&S/6/355, pp. 217-[240].
- 1196** 14 Feb., 1849; Mahi and Rewa Kantha. PC 6340, Dr 89, D 4: *E/4/1087, pp. 1131-48; L/P&S/6/355, pp. 321-[352].
- 1197** 21 Feb., 1849; affairs of Kathiawar. PC 6342, Dr 112, D 8: *E/4/1087, pp. 1303-25; L/P&S/6/355, pp. 641-[678]. Para. 14, *PP*, 1852-53, LXXI, 134.
- 1198** 14 Feb., 1849; affairs of Savantvadi. PC 6341, Dr 90, D 5: *E/4/1087, pp. 1149-61; L/P&S/6/355, pp. 353-[380].
- 1199** 22 May, 1849; personal surinjams in Deccan. PC 6354, Dr 292, D 15: *E/4/1088, pp. 625-94; L/P&S/6/356, pp. 457-[520], 525-[568].
- 1200** 27 Feb., 1849; appointment of Capt. P. French as officiating Resident at Baroda. PC 6361, Dr 153, D 9: *E/4/1087, pp. 1339-48; L/P&S/6/355, pp. 679-[702].
- 1201** 14 Mar., 1849; affairs of Rajpipla. PC 6388, Dr 179, D 12: *E/4/1088, pp. 183-94; L/P&S/6/355, pp. 727-[750].
- 1202** 14 Mar., 1849. PC 6392, Dr 180, D 13: *E/4/1088, pp. 195-214; L/P&S/6/355, pp. 751-[786]. Paras. 8-11, *PP*, 1852-53, LXXII, 261; paras. 8-9, *PP*, 1852-53, LXXII, 7.
- 1203** 27 Feb., 1849; slave trade. PC 6384, Dr 154, D 10: *E/4/1087, pp. 1349-53; L/P&S/6/355, pp. 703-[714].
- 1204** 22 May, 1849. PC 6422, Dr 293, D 16: *E/4/1088, pp. 695-728; L/P&S/6/356, pp. 569-[632].

1205 18 July, 1849. PC 6427, Dr 465, D 16: *E/4/1088, pp. 1169-1232; L/P&S/6/357, pp. 1-[122].

1206 18 July, 1849; Mahi and Rewa Kantha. PC 6461, Dr 466, D 18: *E/4/1088, pp. 1231-48; L/P&S/6/357, pp. 123-[154].

1207 24 Oct., 1849. PC 6466, Dr 586, D 28: *E/4/1089, pp. 585-646; L/P&S/6/358, pp. 133-[236].

1208 1 Aug., 1849. PC 6506, Dr 502, D 19: *E/4/1089, pp. 19-29; L/P&S/6/357, pp. 319-[340].

1209 1 Aug., 1849; affairs of Savantvadi. PC 6523, Dr 516, D 20: *E/4/1089, pp. 31-9; L/P&S/6/357, pp. 361-[380].

1209X Affairs of Kathiawar. See full entry at 1211.

1210 15 Aug., 1849; affairs of Cutch. PC 6532, Dr 542, D 21: *E/4/1089, pp. 85-98; L/P&S/6/357, pp. 527-[550].

1211 29 Aug., 1849; affairs of Kathiawar. PC 6547, Dr 565, D 24: *E/4/1089, pp. 211-31; L/P&S/6/358, pp. 1-[50]. Para. 5, *PP*, 1852-53, LXXI, 134.

1212 22 Aug., 1849. PC 6549, Dr 567, D 23: *E/4/1089, pp. 141-64; L/P&S/6/358, pp. 87-[128].

1213 22 Aug., 1849; Mahi and Rewa Kantha. PC 6558, Dr 566, D 22: *E/4/1089, pp. 113-40; L/P&S/6/358, pp. 41-[86].

1214 5 Sept., 1849; affairs of Palanpur. PC 6562, Dr 587, D 26: *E/4/1089, pp. 307-15; L/P&S/6/358, pp. 237-[256].

1215 28 Nov., 1849. PC 6635, Dr 776, D 35: *E/4/1090, pp. 43-131; L/P&S/6/359, pp. 473-[622]. Para. 16, *PP*, 1852, XXXVII, Pt. 1, 52; paras. 79-81, *PP*, 1852-53, LXX, 420-1; para. 43, *PP*, 1852-53, LXIX, 262; paras. 79-81 (again), *PP*, 1857-58, XLIII, 209-10.

1216 26 Sept., 1849; affairs of Kathiawar. PC 6602, Dr 668, D 27: *E/4/1089, pp. 407-34; L/P&S/6/358, pp. 393-[440].

1217 31 Oct., 1849. PC 6624, Dr 714, D 29: *E/4/1089, pp. 679-706; L/P&S/6/358, pp. 527-[578].

1218 31 Oct., 1849; the *Ant* currency tribute in Kathiawar. PC 6619, Dr 715, D 30: *E/4/1089, pp. 723-51; L/P&S/6/358, pp. 579-[626].

1219 21 Nov., 1849; Southern Maratha jagirdars. PC 6625, Dr 775, D 34: *E/4/1089, pp. 913-32; L/P&S/6/359, pp. 441-[472].

1220 21 Nov., 1849; affairs of Satara. PC 6638, Dr 774, D 33: *E/4/1089, pp. 899-912; L/P&S/6/359, pp. 409-[440].

1221 7 Nov., 1849; Mahi and Rewa Kantha. PC 6642, Dr 745, D 32: *E/4/1089, pp. 777-804; L/P&S/6/359, pp. 111-[158].

1222 7 Nov., 1849; relations with the Gaikwar. PC 6641, Dr 744, D 31: *E/4/1089, pp. 763-76; L/P&S/6/359, pp. 83-[110].

1223 5 Dec., 1849. PC 6667, Dr 817, D 36: *E/4/1090, pp. 197-214; L/P&S/6/359, pp. 669-[708].

1224 28 Dec., 1849. PC 6694, Dr 874, D 37: *E/4/1090, pp. 421-36; L/P&S/6/359, pp. 637-[668].

1225 9 Jan., 1850; affairs of Savantvadi. PC 6709, Dr 909, D 1: *E/4/1090, pp. 473-90; L/P&S/6/359, pp. 947-[976].

1226 30 Jan., 1850; affairs of Kolhapur. PC 6720, Dr 38, D 2: *E/4/1090, pp. 565-89; L/P&S/6/360, pp. 173-[220].

1227 13 Feb., 1850; subjects connected with Baroda. PC 6743, Dr 98, D 4: *E/4/1090, pp. 709-40; L/P&S/6/360, pp. 357-[416]. Paras. 2, 14-15, *PP*, 1852, XXXVII, Pt. 1, 52; paras. 14-16, *PP*, 1852-53, LXIX, 263.

1228 13 Feb., 1850; affairs of Kathiawar. PC 6740, Dr 77, D 3: *E/4/1090, pp. 685-707; L/P&S/6/360, pp. 317-[356]. Para. 5, *PP*, 1852-53, LXXI, 396.

1229 13 Feb., 1850. PC 6748, Dr 99, D 5: *E/4/1090, pp. 741-68; L/P&S/6/360, pp. 417-[464].

1230 13 Mar., 1850; affairs of Satara. PC 6758, Dr 178, D 9: *E/4/1090, pp. 1085-1101; L/P&S/6/360, pp. 697-[732].

1231 20 Feb., 1850; Mahi and Rewa Kantha. PC 6764, Dr 119, D 7: *E/4/1090, pp. 891-914; L/P&S/6/360, pp. 589-[628]. Para. 8, *PP*, 1852-53, LXX, 122.

1232 20 Feb., 1850; Palanpur districts. PC 6770, Dr 118, D 6: *E/4/1090, pp. 875-90; L/P&S/6/360, pp. 553-[588].

1233 5 Mar., 1850; the Surat family [of the ex-Raja of Surat]. PC 6798, Dr 165, D 8: *E/4/1090, pp. 979-97; L/P&S/6/360, pp. 649-[684].

1234 27 Mar., 1850; affairs of Kathiawar. PC 6809, Dr 212, D 11: *E/4/1090, pp. 1163-84; L/P&S/6/361, pp. 1-[42].

1235 27 Mar., 1850. PC 6827, Dr 213, D 12: E/4/1090, pp. 1185-96; L/P&S/6/361, pp. 43-[70]. Para. 7, *PP*, 1852-53, LXXI, 536.

- 1236** 17 Apr., 1850; Southern Maratha country. PC 6836, Dr 244, D 14: *E/4/1091, pp. 113-44; L/P&S/6/361, pp. 119-[168].
- 1237** 27 Mar., 1850; slave trade. PC 6826, Dr 189, D 10: *E/4/1090, pp. 1157-62; L/P&S/6/360, pp. 685-[696].
- 1238** 15 May, 1850. PC 6837, Dr 334, D 16: *E/4/1091, pp. 291-344; L/P&S/6/361, pp. 429-[530].
- 1239** 9 Apr., 1850; Mahi and Rewa Kantha. PC 6830, Dr 226, D 13: *E/4/1091, pp. 31-58; L/P&S/6/361, pp. 71-[118].
- 1240** 12 June, 1850; affairs of Savantvadi. PC 6887, Dr 390, D 17: *E/4/1091, pp. 545-60; L/P&S/6/361, pp. 543-[574].
- 1241** 12 June, 1850; subjects connected with Baroda. PC 6883, Dr 391, D 18: *E/4/1091, pp. 561-83; L/P&S/6/361, pp. 657-[676]. Para. 17, *PP*, 1852-53, LXXI, 543.
- 1242** 26 June, 1850; affairs of Kolhapur. PC 6903, Dr 433, D 19: *E/4/1091, pp. 635-44; L/P&S/6/361, pp. 169-[180].
- 1243** 26 June, 1850; Mahi and Rewa Kantha. PC 6890, Dr 434, D 20: *E/4/1091, pp. 645-62; L/P&S/6/361, pp. 677-[704].
- 1244** 31 July, 1850; affairs of Kathiawar. PC 6946, Dr 525, D 21: *E/4/1091, pp. 829-46; L/P&S/6/362, pp. 305-[336].
- 1245** 4 Sept., 1850. PC 6982, Dr 624, D 23: *E/4/1091, pp. 1007-26; L/P&S/6/362, pp. 379-[410].
- 1246** 4 Dec., 1850; affairs of Satara. PC 7023 (A & B), Dr 844, D 31: *E/4/1092, pp. 607-56; L/P&S/6/363, pp. 529-[648]. Para. 26, *PP*, 1852-53, LXX, 373.
- 1247** 11 Sept., 1850; Surat family. PC 6997, Dr 651, D 24: *E/4/1091, pp. 1093-1104; L/P&S/6/362, pp. 697-[720].
- 1248** 4 Sept., 1850; Palanpur districts. PC 6983, Dr 623, D 22: *E/4/1091, pp. 997-1005; L/P&S/6/362, pp. 359-[378].
- 1249** 11 Sept., 1850. PC 7009, Dr 652, D 25: *E/4/1091, pp. 1105-14; L/P&S/6/363, pp. 1-[20].
- 1250** 23 Oct., 1850; Mahi and Rewa Kantha. PC 7033, Dr 741, D 26: *E/4/1092, pp. 161-84; L/P&S/6/363, pp. 101-[144].
- 1251** 23 Oct., 1850; affairs of Savantvadi. PC 7032, Dr 742, D 27: *E/4/1092, pp. 185-96; L/P&S/6/363, pp. 145-[166].
- 1252** 23 Oct., 1850; Cutch and Morvi disputes. PC 7040, Dr 744, D 29: *E/4/1092, pp. 209-22; L/P&S/6/363, pp. 219-[242].
- 1253** 23 Oct., 1850. PC 7043, Dr 743, D 28: *E/4/1092, pp. 197-208; L/P&S/6/363, pp. 199-[218].
- 1254** 30 Oct., 1850. PC 7042, Dr 745, D 30: *E/4/1092, pp. 251-82; L/P&S/6/363, pp. 243-[302].
- 1255** 4 Dec., 1850; Palanpur districts. PC 7097, Dr 845, D 32: *E/4/1092, pp. 657-64; L/P&S/6/363, pp. 927-[942].
- 1256** 18 Dec., 1850; affairs of Savantvadi. PC 7105, Dr 892, D 33: *E/4/1092, pp. 723-36; L/P&S/6/363, pp. 891-[914].
- 1257** 3 Jan., 1851; Mahi and Rewa Kantha. PC 7114, Dr 911, D 1: *E/4/1092, pp. 817-42; L/P&S/6/363, pp. 1039-[1086].
- 1258** 15 Jan., 1851. PC 7131, Dr 931, D 2: *E/4/1092, pp. 917-39; L/P&S/6/363, pp. 1169-[1222].
- 1259** 12 Feb., 1851. PC 7155, Dr 91, D 4: *E/4/1092, pp. 1102-55; L/P&S/6/364, pp. 183-[290].
- 1260** 15 Jan., 1851; transactions connected with Baroda. PC 7132, Dr 38, D 3: *E/4/1092, pp. 941-60; L/P&S/6/364, pp. 33-[72]. Paras. 8-10 in both *PP*, 1852, XXXVII, Pt. 1, 53; and *PP*, 1852-53, LXXIII, 9-10.
- 1261** 19 Feb., 1851. PC 7199, Dr 106, D 5: *E/4/1092, pp. 1226-41; L/P&S/6/364, pp. 291-[316].
- 1262** 14 May, 1851; affairs of Satara. PC 7256, Dr 243, D 10: *E/4/1093, pp. 541-66; L/P&S/6/364, pp. 489-[536].
- 1263** 19 Mar., 1851. PC 7259, Dr 214, D 7: *E/4/1093, pp. 219-48; L/P&S/6/364, pp. 577-[628].
- 1264** 28 May, 1851; Southern Maratha jagirdars. PC 7305, Dr 382, D 12: *E/4/1093, pp. 719-56; L/P&S/6/365, pp. 383-[450].
- 1265** 25 Apr., 1851. PC 7291, Dr 307, D 8: *E/4/1093, pp. 443-64; L/P&S/6/365, pp. 1-[38].
- 1266** 25 Apr., 1851; affairs of Kathiawar. PC 7295, Dr 308, D 9: *E/4/1093, pp. 465-80; L/P&S/6/364, pp. 729-[756].
- 1267** 14 May, 1851; affairs of Kolhapur. PC 7307, Dr 358, D 11: *E/4/1093, pp. 567-96; L/P&S/6/365, pp. 59-[104].
- 1268** 18 June, 1851. PC 7324, Dr 424, D 13: *E/4/1093, pp. 933-54; L/P&S/6/365, pp. 631-[686].
- 1269** 16 July, 1851; Mahi and Rewa Kantha. PC 7383, Dr 513, D 15: *E/4/1093, pp. 1023-58; L/P&S/6/366, pp. 117-[176].

- 1270** 16 July, 1851; affairs of Savantvadi. PC 7387, Dr 514, D 16: *E/4/1093, pp. 1059-68; L/P&S/6/366, pp. 177-[196].
- 1271** 16 July, 1851; Palanpur districts. PC 7386, Dr 515, D 17: *E/4/1093, pp. 1069-77; L/P&S/6/366, pp. 197-[216].
- 1272** 20 Aug., 1851; affairs of Kolhapur. PC 7403, Dr 596, D 20: *E/4/1093, pp. 1325-56; L/P&S/6/366, pp. 383-[434].
- 1273** 13 Aug., 1851; affairs of Satara. PC 7401, Dr 563, D 19: *E/4/1093, pp. 1253-80; L/P&S/6/366, pp. 273-[308].
- 1274** 13 Aug., 1851; Kolhapur and Savantvadi military expenses. PC 7402, Dr 562, D 18: *E/4/1093, pp. 1231-52; L/P&S/6/366, pp. 237-[272].
- 1275** 1 Oct., 1851; Mandvi gras dues. PC 7460, Dr 670, D 23: *E/4/1094, pp. 239-50; L/P&S/6/367, pp. 203-[234].
- 1276** 10 Sept., 1851. PC 7442, Dr 630, D 22: *E/4/1094, pp. 103-62; L/P&S/6/367, pp. 95-[202]. Paras. 49-53, *PP*, 1852-53, LXIX, 265-6.
- 1277** 3 Sept., 1851; affairs of Cutch. PC 7446, Dr 619, D 21: *E/4/1094, pp. 29-36; L/P&S/6/366, pp. 435-[454].
- 1278** 2 July, 1851; claims of Cristina Rao Wital. Dr 485, D 14: E/4/1093, pp. 975-9; L/P&S/6/366, pp. 9-[12].
- 1279** 1 Oct., 1851; Mahi and Rewa Kantha. PC 7491, Dr 724, D 24: *E/4/1094, pp. 251-62; L/P&S/6/367, pp. 39-[62].
- 1280** 16 Oct., 1851; Palanpur districts. PC 7484, Dr 723, D 25: *E/4/1094, pp. 327-34; L/P&S/6/367, pp. 27-[38].
- 1281** 16 Oct., 1851; affairs of Kolhapur. PC 7489, Dr 725, D 26: *E/4/1094, pp. 335-52; L/P&S/6/367, pp. 63-[94].
- 1282** 5 Nov., 1851; affairs of Savantvadi. PC 7493, Dr 802, D 27: *E/4/1094, pp. 429-41; L/P&S/6/367, pp. 581-[602].
- 1283** 2 Jan., 1852; affairs of Kathiawar. PC 7579, Dr 923, D 1: *E/4/1094, pp. 661-710; L/P&S/6/367, pp. 885-[966]. Para. 15, *PP*, 1852-53, LXXI, 135.
- 1284** 4 Feb., 1852; Deccan surinjams. PC 7608, Dr 18, D 10: *E/4/1095, pp. 61-122; L/P&S/6/368, pp. 99-[184].
- 1285** 2 Jan., 1852; affairs of Satara. PC 7580, Dr 924, D 2: *E/4/1094, pp. 711-26; L/P&S/6/367, pp. 967-[996].
- 1286** 2 Jan., 1852. PC 7595, Dr 939, D 6: *E/4/1094, pp. 771-805; L/P&S/6/367, pp. 1109-[1176] [*sic*]. Para. 34, *PP*, 1852-53, LXIX, 266; and paras. 32-3, *PP*, 1852-53, LXXII, 8.
- 1287** 2 Jan., 1852; affairs of Cutch. PC 7581, Dr 925, D 3: *E/4/1094, pp. 727-43; L/P&S/6/367, pp. 997-[1028].
- 1288** 14 Jan., 1852. PC 7596, Dr 19, D 7: *E/4/1094, pp. 917-34; L/P&S/6/368, pp. 185-[220].
- 1289** 2 Jan., 1852; Palanpur districts. PC 7598, Dr 926, D 4: *E/4/1094, pp. 745-53; L/P&S/6/367, pp. 1029-[1048].
- 1290** 2 Jan., 1852; affairs of Kolhapur. PC 7611, Dr 938, D 5: *E/4/1094, pp. 755-70; L/P&S/6/367, pp. 1081-[1108].
- 1291** 21 Jan., 1852. PC 7615, Dr 34, D 9: *E/4/1094, pp. 973-1004; L/P&S/6/368, pp. 331-[390].
- 1292** 21 Jan., 1852; slave trade. PC 7604, Dr 17, D 8: *E/4/1094, pp. 967-72; L/P&S/6/368, pp. 83-[98].
- 1292X** Paragraphs on the memorial of Dr. B. Nicholson (Bombay surgeon). Bombay PC 7605 returned unaltered by Board on 16 Nov., 1851: L/P&S/6/368, pp. 741-[748]. No Dr, but see D 11 of 4 Feb., 1852 (entry at 1295).
- 1293** 13 Apr., 1852; Southern Maratha jagirdars. PC 7708, Dr 235, D 15: *E/4/1095, pp. 769-806; L/P&S/6/369, pp. 23-[140]. Para. 28, *PP*, 1852-53, LXX, 335-6.
- 1294** 3 Mar., 1852; Mahi and Rewa Kantha. PC 7678, Dr 148, D 14: *E/4/1095, pp. 351-75; L/P&S/6/368, pp. 585-[628].
- 1295** 4 Feb., 1852. PC 7645, Dr 69, D 11: *E/4/1095, pp. 123-35; L/P&S/6/368, pp. 391-[414].
- 1296** 18 Feb., 1852; affairs of Satara. PC 7661, Dr 109, D 13: *E/4/1095, pp. 259-72; L/P&S/6/368, pp. 479-[502].
- 1297** 2 June, 1852; subjects connected with Baroda. PC 7725, Dr 372, D 17: *E/4/1095, pp. 1065-98; L/P&S/6/369, pp. 441-[500]. *PP*, 1852, XXXVII, Pt. 1, 28-30.
- 1298** 2 June, 1852. PC 7753, Dr 371, D 16: *E/4/1095, pp. 1041-64; L/P&S/6/369, pp. 395-[440].
- 1299** 4 Aug., 1852; customs privileges of the Portuguese factory at Surat. PC 7851, Dr 594, D 23: *E/4/1096, pp. 509-28; L/P&S/6/370, pp. 309-[344].
- 1300** 23 June, 1852; subjects connected with Baroda. PC 7842, Dr 479, D 19: *E/4/1095, pp.

1211-79; L/P&S/6/370, pp. 1-[122] [incomplete]. *PP*, 1852, XXXVII, Pt. 1, 35-41.

1301 9 June, 1852; subjects connected with Baroda. PC 7828, Dr 416, D 18: *E/4/1095, pp. 1139-63; L/P&S/6/369, pp. 672-[692] [*sic*].

1302 1 July, 1852; Mahi and Rewa Kantha. PC 7845, Dr 455, D 21: *E/4/1096, pp. 123-48; L/P&S/6/369, pp. 789-[832]. Para. 12, *PP*, 1852-53, LXX, 161.

1303 4 Aug., 1852; affairs of Kathiawar. PC 7883, Dr 576, D 22: *E/4/1096, pp. 479-508, L/P&S/6/370, pp. 251-[308].

1303X Removal of Lt. Col. J. Outram from the Baroda Residency. Bombay PC 7875 altered by Board on 8 June, 1852: L/P&S/6/370, pp. 163-[186]. Dr 482, D 20 of 26 June, 1852.

1304 18 Aug., 1852; Palanpur districts. PC 7881, Dr 625, D 27: *E/4/1096, pp. 603-16; L/P&S/6/370, pp. 535-[558].

1305 11 Aug., 1852; affairs of Kolhapur. PC 7901, Dr 595, D 24: *E/4/1096, pp. 549-61; L/P&S/6/370, pp. 345-[368].

1306 15 Sept., 1852; subjects connected with Baroda. PC 7926, Dr 695, D 30: *E/4/1096, pp. 829-42; L/P&S/6/371, pp. 145-[172]. Para. 11 in both *PP*, 1852-53, LXXII, 8; and *PP*, 1852-53, LXIX, 266.

1307 11 Aug., 1852. PC 7903, Dr 597, D 26: *E/4/1096, pp. 583-91; L/P&S/6/370, pp. 405-[422].

1308 11 Aug., 1852. PC 7902, Dr 596, D 25: *E/4/1096, pp. 563-82; L/P&S/6/370, pp. 369-[404].

1309 18 Aug., 1852. PC 7912, Dr 626, D 28: *E/4/1096, pp. 617-25; L/P&S/6/370, pp. 559-[578].

1310 3 Nov., 1852. PC 7928, Dr 733, D 33: E/4/1096, pp. 955-1000; L/P&S/6/371, pp. 173-[246].

1311 15 Sept., 1852; Mahi and Rewa Kantha. PC 7927, Dr 680, D 29: *E/4/1096, pp. 817-28; L/P&S/6/371, pp. 1-[20].

1312 20 Oct., 1852. PC 7957, Dr 778, D 32: *E/4/1096, pp. 919-26; L/P&S/6/371, pp. 341-[360].

1313 20 Oct., 1852; affairs of Savantvadi. PC 7956, Dr 777, D 31: *E/4/1096, pp. 901-18; L/P&S/6/371, pp. 309-[340].

1314 10 Nov., 1852; Rewa Kantha. PC 7988, Dr 852, D 34: *E/4/1096, pp. 1219-43; L/P&S/6/371, pp. 385-[428].

1315 31 Dec., 1852. PC 8017, Dr 969, D 38: *E/4/1097, pp. 257-87; L/P&S/6/371, pp. 923-[982]. Paras. 6-10, and 29, *PP*, 1852-53, LXXIII, 10-11, and 81.

1316 15 Dec., 1852; Baroda. PC 8016, Dr 920, D 35: *E/4/1097, pp. 141-56; L/P&S/6/371, pp. 673-[700].

1316X Khutput [money as an instrument for influencing government decisions]. Bombay PC 8082 altered by Board on 22 Dec., 1852: L/P&S/6/372, pp. 621-[644]. Dr 178, D 15 of 20 Apr., 1853.

1317 9 Feb., 1853; affairs of Kathiawar. PC 8080, Dr 15, D 6: *E/4/1097, pp. 599-620; L/P&S/6/371, pp. 983-[1022].

1318 12 Jan., 1853; Palanpur districts. PC 8071, Dr 995, D 2: *E/4/1097, pp. 357-64; L/P&S/6/371, pp. 1053-[1064].

1319 12 Jan., 1853; affairs of Kolhapur. PC 8070, Dr 994, D 1: *E/4/1097, pp. 341-56; L/P&S/6/371, pp. 1023-[1052].

1320 26 Jan., 1853; Baroda. PC 8094, Dr 39, D 3: *E/4/1097, pp. 433-58; L/P&S/6/372, pp. 53-[94]. Paras. 4-7, 10-14; 8-9; and 16, *PP*, 1852-53, LXXIII, 85; 185; and 282.

1321 2 Feb., 1853; Mahi Kantha. PC 8081, Dr 996, D 5: *E/4/1097, pp. 525-37; L/P&S/6/371, pp. 1065-[1088].

1322 16 Mar., 1853; affairs of Cutch. PC 8120, Dr 177, D 7: *E/4/1097, pp. 789-804; L/P&S/6/372, pp. 161-[192].

1323 26 Jan., 1853; affairs of Satara. PC 8095, Dr 40, D 4: *E/4/1097, pp. 459-77; L/P&S/6/372, pp. 95-[126].

1324 6 Apr., 1853; Baroda. PC 8141, Dr 219, D 13: *E/4/1097, pp. 1001-22; L/P&S/6/372, pp. 331-[374]. Paras. 2-7, 8-9, 14, 15-20, *PP*, 1852-53, LXXIII, 88, 89, 90, 285.

1325 30 Mar., 1853. PC 8145, Dr 192, D 10: *E/4/1097, pp. 915-36; L/P&S/6/372, pp. 241-[284].

1326 30 Mar., 1853; affairs of Kathiawar. PC 8149, Dr 236, D 11: *E/4/1097, pp. 937-59; L/P&S/6/372, pp. 375-[412]. Paras. 9-12, *PP*, 1852-53, LXXI, 402-3.

1327 30 Mar., 1853. PC 8188, Dr 237, D 12: *E/4/1097, pp. 961-80; L/P&S/6/372, pp. 413-[448].

1328 24 May, 1853; Baroda. PC 8195, Dr 393, D 28: *E/4/1098, pp. 271-301; L/P&S/6/374, pp. 437-[538]. Paras. 19-20, 23, *PP*, 1852-53, LXXIII, 91, 186.

- 1329** 23 Mar., 1853; slave trade. PC 8187, Dr 217, D 8: *E/4/1097, pp. 853-6; L/P&S/6/372, pp. 301-[312].
- 1330** 4 May, 1853. PC 8214, Dr 350, D 22: *E/4/1098, pp. 89-147; L/P&S/6/374, pp. 101-[218].
- 1331** 23 Mar., 1853; affairs of Cutch. PC 8193, Dr 218, D 9: *E/4/1097, pp. 857-64; L/P&S/6/372, pp. 313-[330].
- 1332** 13 Apr., 1853. PC 8206, Dr 258, D 14: *E/4/1097, pp. 1103-16; L/P&S/6/373, pp. 1-[24] [pp. 1-6 missing and partly damaged].
- 1333** 27 Apr., 1853; affairs of Kolhapur. PC 8219, Dr 303, D 17: *E/4/1097, pp. 1262-76; L/P&S/6/373, pp. 429-[462].
- 1334** 20 Apr., 1853; affairs of Savantvadi. PC 8216, Dr 305, D 16: *E/4/1097, pp. 1253-61; L/P&S/6/373, pp. 515-[530].
- 1335** 27 Apr., 1853; Southern Maratha jagirdars. PC 8229, Dr 304, D 18: *E/4/1097, pp. 1277-98; L/P&S/6/373, pp. 463-[514].
- 1336** 4 May, 1853; Meer Ali Morad of Sind. PC 8231, Dr 326, D 20: *E/4/1098, pp. 39-78; L/P&S/6/373, pp. 645-[688].
- 1337** 18 May, 1853. PC 8233, Dr 306, D 26: *E/4/1098, pp. 195-212; L/P&S/6/373, pp. 531-[570].
- 1338** 18 May, 1853; Deccan surinjams. PC 8238, Dr 373, D 27: *E/4/1098, pp. 213-52; L/P&S/6/374, pp. 251-[328].
- 1339** 4 May, 1853. PC 8246, Dr 349, D 21: *E/4/1098, pp. 79-88; L/P&S/6/374, pp. 81-[100].
- 1340** 24 May, 1853; Mahi and Rewa Kantha. PC 8264, Dr 395, D 30: *E/4/1098, pp. 319-45; L/P&S/6/374, pp. 547-[598].
- 1341** 11 May, 1853; Baroda. PC 8249, Dr 372, D 25: *E/4/1098, pp. 179-88; L/P&S/6/374, pp. 235-[250]. Paras. 5, 2-4, *PP*, 1852-53, LXXIII, 93, 310.
- 1342** 1 June, 1853; Palanpur districts. PC 8266, Dr 431, D 32: *E/4/1098, pp. 451-7; L/P&S/6/374, pp. 619-[634].
- 1343** 1 June, 1853; affairs of Kathiawar. PC 8263, Dr 430, D 31: *E/4/1098, pp. 435-50; L/P&S/6/374, pp. 647-[674].
- 1344** 1 June, 1853; affairs of Savantvadi. PC 8265, Dr 432, D 33: *E/4/1098, pp. 459-67; L/P&S/6/374, pp. 599-[618].
- 1345** 11 May, 1853; letter from Lt. Col. J. Outram [Resident in Baroda]. PC 8272, Dr 371, D 24: *E/4/1098, pp. 173-7; L/P&S/6/374, pp. 223-[234].
- 1346** 6 June, 1853; Mahi and Rewa Kantha. PC 8289, Dr 445, D 34: *E/4/1098, pp. 513-29; L/P&S/6/376, pp. 1-[32].
- 1347** 22 June, 1853; Baroda guarantees. PC 8294, Dr 465, D 35: *E/4/1098, pp. 645-72; L/P&S/6/376, pp. 69-[108]. *PP*, 1852-53, LXIX, 267-8.
- 1348** 29 June, 1853; Southern Maratha jagirdars. PC 8319, Dr 505, D 36: *E/4/1098, pp. 739-54; L/P&S/6/376, pp. 129-[160].
- 1349** 10 Aug., 1853; investigations at Akalkot. PC 8338, Dr 639, D 43: *E/4/1099, pp. 151-180B; L/P&S/6/376, pp. 485-[536].
- 1350** 2 Aug., 1853; affairs of Satara. PC 8339, Dr 638, D 40: *E/4/1099, pp. 41-53; L/P&S/6/376, pp. 461-[484].
- 1351** 10 Aug., 1853. PC 8353, Dr 653, D 44: *E/4/1099, pp. 181-238; L/P&S/6/376, pp. 643-[754].
- 1352** 6 July, 1853; Mahi and Rewa Kantha. PC 8333, Dr 531, D 37: *E/4/1098, pp. 807-20; L/P&S/6/376, pp. 201-[224].
- 1353** 2 Aug., 1853; affairs of Kolhapur. PC 8344, Dr 640, D 41: *E/4/1099, pp. 55-80; L/P&S/6/376, pp. 537-[578].
- 1354** 27 July, 1853; Palanpur districts. PC 8364, Dr 612, D 39: *E/4/1098, pp. 1155-66; L/P&S/6/376, pp. 391-[414].
- 1355** 27 July, 1853; Akalkot and Southern Maratha country. PC 8365, Dr 611, D 38: *E/4/1098, pp. 1141-53; L/P&S/6/376, pp. 363-[390].
- 1356** 2 Aug., 1853; Baroda. PC 8373, Dr 641, D 42: *E/4/1099, pp. 81-97; L/P&S/6/376, pp. 579-[608].
- 1357** 31 Aug., 1853. PC 8399, Dr 705, D 47: *E/4/1099, pp. 389-400; L/P&S/6/375, pp. 303-[322].
- 1358** 14 Sept., 1853; affairs of Kathiawar. PC 8396, Dr 725, D 48: *E/4/1099, pp. 469-84; L/P&S/6/375, pp. 323-[350].
- 1359** 17 Aug., 1853; Palanpur districts. PC 8397, Dr 682, D 46: *E/4/1099, pp. 296-302; L/P&S/6/375, pp. 59-[74].
- 1360** 14 Sept., 1853; Mahi Kantha. PC 8413, Dr 746, D 49: *E/4/1099, pp. 485-504; L/P&S/6/375, pp. 363-[396].
- 1361** 14 Sept., 1853; affairs of Savantvadi. PC 8414, Dr 747, D 50: *E/4/1099, pp. 505-12; L/P&S/6/375, pp. 397-[408] [*sic*].

- 1362** 14 Sept., 1853; affairs of Kathiawar. PC 8425, Dr 748, D 51: *E/4/1099, pp. 513-28; L/P&S/6/375, pp. 409-[436].
- 1363** 14 Sept., 1853; Baroda. PC 8426, Dr 749, D 52: *E/4/1099, pp. 529-34; L/P&S/6/375, pp. 437-[448].
- 1364** 26 Oct., 1853; Surat family. PC 8434, Dr 825, D 56: *E/4/1099, pp. 857-81; L/P&S/6/375, pp. 597-[636].
- 1365** 12 Oct., 1853; affairs of Savantvadi. PC 8455, Dr 848, D 54: *E/4/1099, pp. 769-82; L/P&S/6/377, pp. 1-[28].
- 1366** 12 Oct., 1853; Deccan surinjams. PC 8460, Dr 849, D 55: *E/4/1099, pp. 783-806; L/P&S/6/377, pp. 29-[72].
- 1367** 26 Oct., 1853. PC 8476, Dr 877, D 58: *E/4/1099, pp. 901-32; L/P&S/6/377, pp. 203-[258].
- 1368** 26 Oct., 1853; Mahi and Rewa Kantha. PC 8470, Dr 876, D 57: *E/4/1099, pp. 883-900; L/P&S/6/377, pp. 171-[202].
- 1369** 29 Mar., 1854; Surat family. PC 8640, Dr 249, D 7: *E/4/1100, pp. 585-610; L/P&S/6/378, pp. 285-[330].
- 1370** 1 Mar., 1854. PC 8612, Dr 163, D 3: *E/4/1100, pp. 335-58; L/P&S/6/378, pp. 103-[144].
- 1371** 15 Mar., 1854; affairs of Kathiawar. PC 8630, Dr 202, D 5: *E/4/1100, pp. 441-57; L/P&S/6/378, pp. 217-[248].
- 1372** 1 Mar., 1854; Baroda. PC 8627, Dr 162, D 2: *E/4/1100, pp. 323-34; L/P&S/6/378, pp. 81-[102].
- 1373** 5 Apr., 1854; Southern Maratha jagirdars. PC 8635, Dr 283, D 10: *E/4/1100, pp. 681-702; L/P&S/6/378, pp. 433-[472].
- 1374** 15 Mar., 1854; affairs of Savantvadi. PC 8631, Dr 201, D 4: *E/4/1100, pp. 431-9; L/P&S/6/378, pp. 249-[268].
- 1375** 1 Mar., 1854; slave trade. PC 8626, Dr 161, D 1: *E/4/1100, pp. 309-22; L/P&S/6/378, pp. 57-[80].
- 1376** 29 Mar., 1854; affairs of Satara. PC 8656, Dr 250, D 8: *E/4/1100, pp. 611-26; L/P&S/6/378, pp. 331-[356].
- 1377** 29 Mar., 1854; Mahi and Rewa Kantha. PC 8657, Dr 251, D 9: *E/4/1100, pp. 627-42; L/P&S/6/378, pp. 357-[388].
- 1378** 22 Mar., 1854; Palanpur districts. PC 8653, Dr 228, D 6: *E/4/1100, pp. 515-22; L/P&S/6/378, pp. 269-[284].
- 1379** 12 Apr., 1854. PC 8662, Dr 296, D 11: *E/4/1100, pp. 729-42; L/P&S/6/379, pp. 1-[26].
- 1380** 27 Apr., 1854. PC 8709, Dr 358, D 13: *E/4/1100, pp. 933-1003; L/P&S/6/380, pp. 39-[160].
- 1381** 20 Apr., 1854; Baroda. PC 8705, Dr 297, D 12: *E/4/1100, pp. 791-802; L/P&S/6/379, pp. 27-[50].
- 1382** 24 May, 1854. PC 8729, Dr 420, D 15: *E/4/1100, pp. 1267-1305; L/P&S/6/380, pp. 191-[262].
- 1383** 17 May, 1854; Mahi and Rewa Kantha. PC 8761, Dr 432, D 14: *E/4/1100, pp. 1193-1206; L/P&S/6/380, pp. 307-[334].
- 1384** 28 June, 1854; Baroda. PC 8779, Dr 564, D 18: *E/4/1100, pp. 1681-1721; L/P&S/6/381, pp. 85-[152].
- 1385** 28 June, 1854; Southern Maratha jagirdars. PC 8783, Dr 539, D 17: *E/4/1100, pp. 1655-80; L/P&S/6/381, pp. 1-[44].
- 1386** 14 June, 1854; misappropriations in the Aden treasury. PC 8797, Dr 510, D 16: *E/4/1100, pp. 1511-36; L/P&S/6/380, pp. 495-[534].
- 1387** 26 July, 1854; Sind. PC 8822, Dr 639, D 19: *E/4/1101, pp. 177-94; L/P&S/6/381, pp. 273-[304].
- 1388** 2 Aug., 1854; affairs of Kolhapur. PC 8834, Dr 692, D 20: *E/4/1101, pp. 265-90; L/P&S/6/381, pp. 407-[448].
- 1389** 16 Aug., 1854. PC 8860, Dr 744, D 23: *E/4/1101, pp. 407-40; L/P&S/6/381, pp. 619-[674].
- 1390** 16 Aug., 1854; affairs of Kathiawar. PC 8868, Dr 743, D 22: *E/4/1101, pp. 361-406; L/P&S/6/381, pp. 555-[618].
- 1391** 20 Sept., 1854. PC 8946, Dr 858, D 27: *E/4/1101, pp. 687-706; L/P&S/6/382, pp. 157-[188].
- 1392** 20 Sept., 1854; Mahi and Rewa Kantha. PC 8945, Dr 857, D 26: *E/4/1101, pp. 667-86; L/P&S/6/382, pp. 121-[156].
- 1393** 20 Sept., 1854; Palanpur districts. PC 8944, Dr 856, D 25: *E/4/1101, pp. 657-66; L/P&S/6/382, pp. 101-[120].
- 1394** 4 Oct., 1854. PC 8964, Dr 908, D 29: *E/4/1101, pp. 771-800; L/P&S/6/382, pp. 401-[448].
- 1395** 4 Oct., 1854; affairs of Savantvadi. PC 8959, Dr 907, D 28: *E/4/1101, pp. 761-9; L/P&S/6/382, pp. 381-[400].
- 1396** 15 Nov., 1854; affairs of Kathiawar.

- PC 9002, Dr 1044, D 31: *E/4/1101, pp. 1011-38; L/P&S/6/382, pp. 801-[844].
- 1397** 15 Nov., 1854; Palanpur districts. PC 9007, Dr 1022, D 30: *E/4/1101, pp. 1001-9; L/P&S/6/382, pp. 685-[704].
- 1398** 22 Nov., 1854; slave trade. PC 9006, Dr 1045, D 32: *E/4/1101, pp. 1123-48; L/P&S/6/382, pp. 757-[800].
- 1399** 22 Nov., 1854; Mahi and Rewa Kantha. PC 9008, Dr 1062, D 33: *E/4/1101, pp. 1149-68; L/P&S/6/382, pp. 917-[948].
- 1400** 29 Nov., 1854. PC 9034, Dr 1094, D 34: *E/4/1101, pp. 1207-28; L/P&S/6/382, pp. 969-[1010].
- 1401** 20 Dec., 1854; affairs of Kolhapur. PC 9038, Dr 1117, D 37: *E/4/1101, pp. 1383-1410; L/P&S/6/382, pp. 1023-[1074].
- 1402** 29 Nov., 1854; affairs of Savantvadi. PC 9055, Dr 1095, D 35: *E/4/1101, pp. 1229-36; L/P&S/6/382, pp. 1011-[1022].
- 1403** 6 Dec., 1854; Rewa Kantha. PC 9056, Dr 1118, D 36: *E/4/1101, pp. 1275-90; L/P&S/6/382, pp. 1075-[1104].
- 1404** 17 Jan., 1855. PC 9068, Dr 20, D 2: *E/4/1102, pp. 96-123; L/P&S/6/383, pp. 33-[74].
- 1405** 20 Dec., 1854; Southern Maratha jagirdars. PC 9059, Dr 1170, D 38: *E/4/1101, pp. 1411-42; L/P&S/6/382, pp. 1189-[1238].
- 1406** 10 Jan., 1855; Capt. S. B. Haines [Political Agent in Aden]. PC 9096, Dr 19, D 1: *E/4/1102, pp. 42-54; L/P&S/6/383, pp. 5-[32].
- 1406X** Baroda guarantees. See full entry at 722X.
- 1407** 31 Jan., 1855. PC 9111, Dr 93, D 3: *E/4/1102, pp. 206-22; L/P&S/6/383, pp. 147-[178].
- 1408** 3 Oct., 1855; Southern Maratha jagirdars. PC 9471, Dr 926, D 18: *E/4/1103, pp. 756-79; L/P&S/6/384, pp. 549-[588].
- 1409** 3 Oct., 1855; affairs of Cutch. PC 9451, Dr 943, D 19: *E/4/1103, pp. 780-95; L/P&S/6/384, pp. 525-[548].
- 1410** 12 Dec., 1855. PC 9507, Dr 1075, D 26: *E/4/1103, pp. 1274-1301; L/P&S/6/385, pp. 405-[450].
- 1411** 19 Sept., 1855; Meer Moeenuddin Khan, called the Bukshee of Surat. PC 9450, Dr 878, D 16: *E/4/1103, pp. 652-67; L/P&S/6/384, pp. 221-[252].
- 1412** 3 Oct., 1855; affairs of Kolhapur. PC 9467, Dr 925, D 17: *E/4/1103, pp. 726-55; L/P&S/6/384, pp. 589-[634].
- 1413** 10 Oct., 1855. PC 9470, Dr 944, D 20: *E/4/1103, pp. 824-39; L/P&S/6/385, pp. 135-[166].
- 1414** 10 Oct., 1855. PC 9476, Dr 945, D 21: *E/4/1103, pp. 840-55; L/P&S/6/385, pp. 167-[190].
- 1415** 31 Oct., 1855; Palanpur districts. PC 9510, Dr 1036, D 24: *E/4/1103, pp. 976-1008; L/P&S/6/385, pp. 352-[404].
- 1416** 12 Dec., 1855; Deccan surinjams and pensions. PC 9501, Dr 1128, D 27: *E/4/1103, pp. 1302-85; L/P&S/6/386, pp. 33-[156].
- 1417** 16 Jan., 1856; Rewa Kantha. PC 9532, Dr 11, D 2: *E/4/1104, pp. 93-175; L/P&S/6/387, pp. 45-[204].
- 1418** 12 Dec., 1855; Mahi Kantha. PC 9529, Dr 1166, D 29: *E/4/1103, pp. 1444-1506; L/P&S/6/386, pp. 339-[430].
- 1419** 12 Dec., 1855; affairs of Kathiawar. PC 9515, Dr 1165, D 28: *E/4/1103, pp. 1386-1443; L/P&S/6/386, pp. 249-[338].
- 1420** 24 Oct., 1855; Capt. S. B. Haines [Political Agent in Aden]. PC 9509, Dr 992, D 22: *E/4/1103, pp. 914-32; L/P&S/6/385, pp. 195-[224].
- 1421** 28 Nov., 1855; affairs of Savantvadi. PC 9531, Dr 1100, D 25: *E/4/1103, pp. 1156-73; L/P&S/6/386, pp. 1-[32].
- 1422** 23 Jan., 1856; Sind. PC 9597, Dr 10, D 3: *E/4/1104, pp. 245-74; L/P&S/6/387, pp. 1-[44] [sic].
- 1423** 28 Dec., 1855; affairs of Satara. PC 9564, Dr 1219, D 32: *E/4/1103, pp. 1632-57; L/P&S/6/386, pp. 603-[642].
- 1424** 5 Mar., 1856. PC 9547, Dr 1266, D 13: *E/4/1104, pp. 952-77; L/P&S/6/386, pp. 687-[728].
- 1425** 20 Feb., 1856. PC 9594, Dr 120, D 8: *E/4/1104, pp. 616-75; L/P&S/6/387, pp. 683-[778] [sic].
- 1426** 2 Jan., 1856; affairs of Kolhapur. PC 9552, Dr 1220, D 1: *E/4/1104, pp. 5-22; L/P&S/6/386, pp. 643-[686].
- 1427** 19 Dec., 1855; slave trade. PC 9566, Dr 1199, D 30: *E/4/1103, pp. 1568-89; L/P&S/6/386, pp. 431-[474].
- 1428** 19 Dec., 1855; Southern Maratha jagirdars. PC 9580, Dr 1200, D 31: *E/4/1103, pp. 1590-1617; L/P&S/6/386, pp. 475-[526].
- 1429** 6 Feb., 1856; Mahi Kantha. PC 9618, Dr 87, D 5: *E/4/1104, pp. 447-507; L/P&S/6/387, pp. 555-[650].

- 1430** 23 Jan., 1856; Surat family. PC 9596, Dr 39, D 4: *E/4/1104, pp. 275-302; L/P&S/6/387, pp. 375-[430].
- 1431** 6 Feb., 1856; Palanpur districts. PC 9632, Dr 88, D 6: *E/4/1104, pp. 509-24; L/P&S/6/387, pp. 651-[678].
- 1432** 5 Mar., 1856; affairs of Kathiawar. PC 9686, Dr 232, D 14: *E/4/1104, pp. 978-99; L/P&S/6/388, pp. 563-[598].
- 1433** 26 Feb., 1856; Southern Maratha jagirdars. PC 9672, Dr 165, D 11: *E/4/1104, pp. 740-71; L/P&S/6/388, pp. 231-[278].
- 1434** 26 Feb., 1856. PC 9656, Dr 166, D 12: *E/4/1104, pp. 772-810; L/P&S/6/388, pp. 279-[354].
- 1435** 12 Mar., 1856; affairs of Kolhapur. PC 9703, Dr 233, D 16: *E/4/1104, pp. 1098-1116; L/P&S/6/388, pp. 599-[630].
- 1436** 27 May, 1856; Mandvi gras dues. PC 9806, Dr 521, D 26: *E/4/1105, pp. 345-72; L/P&S/6/389, pp. 653-[700].
- 1437** 19 Mar., 1856; Rewa Kantha. PC 9702, Dr 292, D 18: *E/4/1104, pp. 1194-1213; L/P&S/6/388, pp. 673-[704].
- 1438** 20 Feb., 1856; affairs of Cutch. PC 9647, Dr 146, D 9: *E/4/1104, pp. 676-98; L/P&S/6/388, pp. 121-[160].
- 1439** 19 Mar., 1856; Deccan surinjams. PC 9668, Dr 293, D 19: *E/4/1104, pp. 1214-37; L/P&S/6/389, pp. 1-[44].
- 1440** 20 Feb., 1856; slave trade. PC 9676, Dr 147, D 10: *E/4/1104, pp. 700-7; L/P&S/6/388, pp. 161-[174].
- 1441** 20 Apr., 1856. PC 9687, Dr 376, D 24: *E/4/1104, pp. 1480-1523; L/P&S/6/389, pp. 369-[440].
- 1442** 12 Mar., 1856; Mahi Kantha. PC 9679, Dr 231, D 15: *E/4/1104, pp. 1074-96; L/P&S/6/388, pp. 523-[562].
- 1443** 28 Mar., 1856. PC 9688, Dr 322, D 21: *E/4/1104, pp. 1322-9; L/P&S/6/389, pp. 69-[88].
- 1444** 19 Mar., 1856; affairs of Savantvadi. PC 9722, Dr 294, D 20: *E/4/1104, pp. 1238-49; L/P&S/6/389, pp. 45-[68].
- 1445** 28 Mar., 1856; Mahi and Rewa Kantha. PC 9752, Dr 323, D 22: *E/4/1104, pp. 1330-53; L/P&S/6/389, pp. 89-[126].
- 1446** 21 May, 1856. PC 9843, Dr 523, D 25: *E/4/1105, pp. 243-71; L/P&S/6/390, pp. 25-[70].
- 1447** 4 June, 1856; affairs of Kathiawar. PC 9853, Dr 549, D 28: *E/4/1105, pp. 483-502; L/P&S/6/390, pp. 115-[150].
- 1448** 11 June, 1856; Mahi and Rewa Kantha. PC 9851, Dr 522, D 30: *E/4/1105, pp. 567-82; L/P&S/6/390, pp. 1-[24].
- 1448X** Affairs of Kolhapur. See full entry at 1476.
- 1449** 11 June, 1856. PC 9888, Dr 633, D 32: *E/4/1105, pp. 605-32; L/P&S/6/390, pp. 315-[366].
- 1450** 4 June, 1856; Mahi and Rewa Kantha. PC 9861, Dr 550, D 29: *E/4/1105, pp. 503-26; L/P&S/6/390, pp. 151-[186].
- 1451** 1 Oct., 1856; affairs of Kolhapur. PC 9, Dr 1022, D 39: *E/4/1106, pp. 67-128; L/P&S/6/391, pp. 35-[132].
- 1452** 17 Dec., 1856; Deccan surinjams. PC 134, Dr 1361, D 42: *E/4/1106, pp. 844-927; L/P&S/6/391, pp. 499-[620].
- 1453** 7 Jan., 1857; Southern Maratha jagirdars. PC 138, Dr 1363, D 6: *E/4/1106, pp. 1244-93; L/P&S/6/391, pp. 743-[822].
- 1454** 7 Jan., 1857; Mahi and Rewa Kantha. PC 145, Dr 1482, D 7: *E/4/1106, pp. 1294-1355; L/P&S/6/391, pp. 1023-[1118].
- 1455** 17 Dec., 1856. PC 154, Dr 1364, D 43: *E/4/1106, pp. 928-47; L/P&S/6/391, pp. 633-[662].
- 1456** 2 Jan., 1857; affairs of Kathiawar. PC 164, Dr 1446, D 4: *E/4/1106, pp. 1120-83; L/P&S/6/391, pp. 911-[1010].
- 1457** 2 Jan., 1857; Palanpur districts. PC 157, Dr 1408, D 1: *E/4/1106, pp. 1058-82; L/P&S/6/391, pp. 695-[742].
- 1458** 17 Dec., 1856; affairs of Savantvadi. PC 162, Dr 1365, D 44: *E/4/1106, pp. 948-59; L/P&S/6/391, pp. 663-[686].
- 1459** 11 Feb., 1857. PC 192, Dr 52, D 16: *E/4/1107, pp. 349-97; L/P&S/6/392, pp. 329-[374], 387-[418].
- 1460** 2 Jan., 1857; slave trade. PC 174, Dr 1445, D 3: *E/4/1106, pp. 1102-19; L/P&S/6/391, pp. 879-[910].
- 1461** 2 Jan., 1857; affairs of Kolhapur. PC 190, Dr 1409, D 2: *E/4/1106, pp. 1090-1101; L/P&S/6/391, pp. 855-[878].
- 1462** 2 Jan., 1857; affairs of Savantvadi. PC 210, Dr 1447, D 5: *E/4/1106, pp. 1184-91; L/P&S/6/391, pp. 1011-[1022].
- 1463** 4 Feb., 1857; Mahi and Rewa Kantha. PC 270, Dr 117, D 12: *E/4/1107, pp. 167-229; L/P&S/6/392, pp. 583-[676].

- 1464** 14 Jan., 1857; affairs of Kathiawar. PC 239, Dr 31, D 9: *E/4/1106, pp. 1474-94; L/P&S/6/392, pp. 137-[170].
- 1465** 14 Jan., 1857; slave trade. PC 226, Dr 30, D 8: *E/4/1106, pp. 1462-73; L/P&S/6/392, pp. 115-[136].
- 1466** 14 Jan., 1857. PC 234, Dr 32, D 10: *E/4/1106, pp. 1496-1525; L/P&S/6/392, pp. 171-[232].
- 1467** 25 Feb., 1857; Deccan surinjams. PC 309, Dr 230, D 18: *E/4/1107, pp. 643-75; L/P&S/6/393, pp. 1-[56].
- 1468** 18 Feb., 1857; Southern Maratha jagirdars. PC 284, Dr 184, D 17: *E/4/1107, pp. 547-91; L/P&S/6/392, pp. 897-[962].
- 1469** 21 Jan., 1857; Palanpur districts. PC 253, Dr 53, D 11: *E/4/1106, pp. 1556-62; L/P&S/6/392, pp. 419-[436].
- 1470** 4 Feb., 1857; affairs of Kolhapur. PC 288, Dr 153, D 15: *E/4/1107, pp. 243-72; L/P&S/6/392, pp. 747-[792].
- 1471** 4 Mar., 1857; affairs of Kathiawar. PC 313, Dr 212, D 19: *E/4/1107, pp. 725-68; L/P&S/6/392, pp. 993-[1062].
- 1472** 11 Mar., 1857. PC 316, Dr 251, D 20: *E/4/1107, pp. 781-804; L/P&S/6/393, pp. 57-[94].
- 1473** 6 May, 1857. PC 340, Dr 308, D 26: *E/4/1107, pp. 1393-1408; L/P&S/6/393, pp. 137-[154], 193-[206].
- 1474** 17 Apr., 1857. PC 363, Dr 403, D 23: *E/4/1107, pp. 1149-72; L/P&S/6/393, pp. 397-[434].
- 1475** 18 Mar., 1857; affairs of Savantvadi. PC 360, Dr 307, D 21: *E/4/1107, pp. 867-78; L/P&S/6/393, pp. 119-[136].
- 1475X** Persian expedition. Bombay PC 370 altered by Board on 21 Feb., 1857; L/P&S/6/393, pp. 541-[552]. Transferred to Military Department, Dr 405, D 64 of 8 Apr., 1857; L/MIL/3/2220 (n.p.).
- 1476** 17 Apr., 1857; affairs of Kolhapur. PC 390, Dr 404, D 24: *E/4/1107, pp. 1173-85; L/P&S/6/393, pp. 435-[456].
- 1477** 18 Nov., 1857; Mahi and Rewa Kantha. PC 629, Dr 1307, D 39: *E/4/1109, pp. 267-362; L/P&S/6/394, pp. 457-[594].
- 1478** 18 Nov., 1857; affairs of Cutch. PC 624, Dr 1269, D 37: *E/4/1109, pp. 191-213; L/P&S/6/394, pp. 323-[344], 349-[364].
- 1479** 2 Dec., 1857. PC 635, Dr 1400, D 40: *E/4/1109, pp. 463-502; L/P&S/6/395, pp. 179-[240].
- 1480** 23 Sept., 1857; slave trade. PC 623, Dr 1017, D 30: *E/4/1108, pp. 1459-69; L/P&S/6/394, pp. 233-[242], 255-[262].
- 1481** 18 Nov., 1857; Deccan surinjams and pensions. PC 634, Dr 1306, D 38: *E/4/1109, pp. 215-66, L/P&S/6/394, pp. 369-[456].
- 1482** 2 Dec., 1857. PC 643, Dr 1401, D 41: *E/4/1109, pp. 503-30; L/P&S/6/395, pp. 241-[266], 271-[288].
- 1483** 4 Nov., 1857. PC 646, Dr 1308, D 34: *E/4/1109, pp. 41-54; L/P&S/6/394, pp. 595-[622].
- 1484** 4 Nov., 1857; affairs of Kolhapur. PC 663, Dr 1309, D 35: *E/4/1109, pp. 55-80; L/P&S/6/394, pp. 623-[672].
- 1485** 21 Oct., 1857; affairs of Savantvadi. PC 655, Dr 1239, D 32: *E/4/1108, pp. 1813-20; L/P&S/6/394, pp. 311-[322].
- 1486** 11 Nov., 1857; Palanpur districts. PC 703, Dr 1337, D 36: *E/4/1109, pp. 135-48; L/P&S/6/395, pp. 87-[104].
- 1487** 9 Dec., 1857; Kuria Muria Islands. PC 740, Dr 1494, D 42: *E/4/1109, pp. 627-38; L/P&S/6/395, pp. 301-[318].
- 1488** 10 Feb., 1858. PC 802, Dr 116, D 5: *E/4/1109, pp. 1191-1221; L/P&S/6/396, pp. 59-[100].
- 1489** 16 Dec., 1857; affairs of Savantvadi. PC 760, Dr 1496, D 44: *E/4/1109, pp. 741-6; L/P&S/6/395, pp. 341-[350].
- 1490** 16 Dec., 1857; affairs of Kolhapur. PC 765, Dr 1495, D 43: *E/4/1109, pp. 727-39; L/P&S/6/395, pp. 319-[340].
- 1491** 27 Jan., 1858; affairs of Cutch. PC 769, Dr 1618, D 1: *E/4/1109, pp. 1073-1100; L/P&S/6/395, pp. 485-[538].
- 1492** 31 Mar., 1858; Mahi and Rewa Kantha. PC 834, Dr 289, D 7: *E/4/1110, pp. 299-346; L/P&S/6/396, pp. 411-[454], 469-[502].
- 1493** 3 Feb., 1858; Southern Maratha jagirdars. PC 808, Dr 70, D 2: *E/4/1109, pp. 1113-39; L/P&S/6/396, pp. 13-[50].
- 1494** 7 July, 1858. PC 929, Dr 789, D 19: *E/4/1111, pp. 369-425; L/P&S/6/397, pp. 703-[798].
- 1495** 13 Apr., 1858; slave trade. PC 913, Dr 415, D 9: *E/4/1110, pp. 551-61; L/P&S/6/396, pp. 597-[614].
- 1496** 14 Apr., 1858; Surat family. PC 917, Dr 414, D 10: *E/4/1110, pp. 575-82; L/P&S/6/396, pp. 583-[596].

1497 21 Apr., 1858; Palanpur districts. PC 898, Dr 436, D 11: *E/4/1110, pp. 601-8; L/P&S/6/396, pp. 633-[646].

1498 5 May, 1858; surinjams. PC 921, Dr 493, D 14: *E/4/1110, pp. 775-813; L/P&S/6/397, pp. 119-[170].

1499 16 June, 1858; Southern Maratha jagirdars. PC 919, Dr 645, D 15: *E/4/1111, pp. 121-39; L/P&S/6/397, pp. 319-[354].

1500 5 May, 1858; Mahi and Rewa Kantha. PC 920, Dr 492, D 13: *E/4/1110, pp. 745-74; L/P&S/6/397, pp. 79-[118].

1501 29 June, 1858; affairs of Kolhapur. PC 1044, Dr 762, D 17: *E/4/1111, pp. 247-54; L/P&S/6/397, pp. 533-[548].

1502 29 June, 1858; affairs of Savantvadi. PC 1049, Dr 763, D 18: *E/4/1111, pp. 255-64; L/P&S/6/397, pp. 549-[568].

1503 21 July, 1858; affairs of Cutch. PC 1055, Dr 823, D 21: E/4/1111, pp. 583-98; L/P&S/6/397, pp. 901-[932].

1504 7 July, 1858; Mahi Kantha. PC 1067, Dr 790, D 20: *E/4/1111, pp. 427-42; L/P&S/6/397, pp. 799-[830].

1505 18 Aug., 1858; affairs of Savantvadi. PC 1137, Dr 1036, D 26: *E/4/1111, pp. 1083-96; L/P&S/6/398, pp. 613-[638].

1506 4 Aug., 1858; Mahi and Rewa Kantha. PC 1135, Dr 941, D 25: *E/4/1111, pp. 837-52; L/P&S/6/398, pp. 205-[240].

1507 1 Sept., 1858. PC 1201, Dr 1230, D 30: *E/4/1112, pp. 463-87; L/P&S/6/399, pp. 565-[608].

1508² 22 Oct., 1858; Mandvi gras dues. PC 1264, Dr 153, D 4: L/P&S/6/399, pp. 811-[830]; L/P&S/6/658, n.p.

1509 6 Oct., 1858. Southern Maratha jagirdars. PC 1265, Dr 103, D 2: L/P&S/6/399, pp. 381-[858]; L/P&S/6/658, n.p.

1510 27 Oct., 1858; Mahi and Rewa Kantha. Dr 189, D 5: L/P&S/6/658, n.p.

1511 13 Oct., 1858; affairs of Savantvadi. Dr 139, D 3: L/P&S/6/658, n.p.

1512 28 Oct., 1858; affairs of Cutch. Dr 230, D 6: L/P&S/6/658, n.p.

Bengal Foreign Department

1513 10 Apr., 1827; implementation of the treaty with the Dutch. PC 397, Dr 238: E/4/719,

pp. 83-109; L/P&S/6/240, n.p.; L/P&S/6/268, pp. 153-[172].

1514 19 Aug., 1829. PC 638, Dr 426: E/4/726, pp. 311-55; L/P&S/6/273, pp. 85-[144].

India Foreign Department

1515 18 Nov., 1835; revolution at Goa. PC 1624, Dr 632, D 1: *E/4/746, pp. 251-5; L/P&S/6/297, pp. 171-[182].

1516 28 July, 1837; affairs of Goa. PC 1937, Dr 313, D 1: *E/4/751, pp. 797-804; L/P&S/6/300, pp. 333-[344].

1517 5 Dec., 1838; proposed exchange of territory with the French government. PC 2256, Dr 667, D 1: *E/4/758, pp. 69-84; L/P&S/6/313, pp. 301-[324].

1518 13 Nov., 1839. PC 2530, Dr 640, D 1: *E/4/760, pp. 1173-80; L/P&S/6/316, pp. 309-[328].

1519 9 Sept., 1840. PC 2771, Dr 542, D 1: *E/4/763, pp. 1147-54; L/P&S/6/320, pp. 249-[258].

1520 28 July, 1841; Nicobar Islands. PC 3168, Dr 523, D 1: *E/4/767, pp. 311-20; L/P&S/6/324, pp. 37-[56].

1521 12 Apr., 1842. PC 3448, Dr 190, D 1: *E/4/770, pp. 53-60; L/P&S/6/327, pp. 1-[14].

Madras Foreign Department

1522 14 Apr., 1830. PC 680, Dr 298, D 1: E/4/938, pp. 653-769; L/P&S/6/274, pp. 309-[442].

1523 21 Jan., 1835. PC 1375, Dr 17, D 1: E/4/945, pp. 458-80; L/P&S/6/292, pp. 319-[354], 357-[376].

1524 8 July, 1835; office of the special agent for European settlements. PC 1529, Dr 396, D 2: E/4/946, pp. 163-8; L/P&S/6/294, pp. 479-[498].

1525 9 Aug., 1837. PC 1949, Dr 359, D 1: *E/4/949, pp. 355-66; L/P&S/6/301, pp. 27-[46].

1526 1 Aug., 1838. PC 2221, Dr 438, D 1: *E/4/951, pp. 251-8; L/P&S/6/311, pp. 269-[278].

1527 27 Nov., 1839. PC 2533, Dr 666, D 1: *E/4/953, pp. 283-95; L/P&S/6/316, pp. 261-[288].

²The despatches listed from 1508 to 1512 were issued by the Secretary of State for India after the dissolution of the East India Company and the Board of Control in Sept. 1858.

1528 16 Sept., 1840. PC 2772, Dr 572, D 1: *E/4/954, pp. 713-25; L/P&S/6/320, pp. 259-280.]

1529 25 May, 1841. PC 3094, Dr 376, D 1: *E/4/955, pp. 1013-20; L/P&S/6/323, pp. 679-696.]

1530 12 Apr., 1842. PC 3449, Dr 191, D 1: *E/4/957, pp. 397-404; L/P&S/6/327, pp. 15-30.]

1531 28 Mar., 1843. PC 3870, Dr 187, D 1: *E/4/959, pp. 771-5; L/P&S/6/331, pp. 199-210.]

1532 21 May, 1844. PC 4308, Dr 296, D 1: *E/4/961, pp. 775-82; L/P&S/6/335, pp. 575A-584.]

1533 16 Apr., 1845. PC 4757, Dr 287, D 1: *E/4/963, pp. 795-802; L/P&S/6/340, pp. 17-32.]

1534 20 May, 1846. PC 5205, Dr 294, D 1: *E/4/965, pp. 691-6; L/P&S/6/344, pp. 49-60.]

1535 25 Nov., 1846. PC 5411, Dr 782, D 2. *E/4/966, pp. 893-900; L/P&S/6/346, pp. 91-104.]

1536 30 Mar., 1847. PC 5550, Dr 215, D 1: *E/4/967, pp. 571-8; L/P&S/6/348, pp. 97-116.]

Bengal Public Department

1537 25 Feb., 1824; Marine Registry Office. PC 150, Dr 199: E/4/710, pp. 1173-1218.)

1538 17 Mar., 1824. PC 137, 153, Dr 245: E/4/711, pp. 151-274. Paras. 16-19, *PP*, 1831-32, IX, 636.

1539 21 July, 1824. PC 196, Dr 414: E/4/711, pp. 929-62.)

1540 12 Jan., 1825. PC 218, Dr 89: E/4/713, pp. 713-77.)

1541 9 Mar., 1825. PC 237, Dr 207: E/4/714, pp. 161-217. Para. 38, *PP*, 1831-32, IX, 518-19.

1542 11 May, 1825. Dr 256: E/4/714, pp. 677-741.)

1543 14 Sept., 1825. PC 263, Dr 451: E/4/715, pp. 383-418.

1544 8 Mar., 1826. PC 324, Dr 182: E/4/716, pp. 417-87. Paras. 8-9, *PP*, 1831-32, IX, 638.)

1545 16 May, 1827. PC 372, Dr 306: E/4/719, pp. 364-403.

1546 21 Feb., 1827; office of Chief Secretary in the Bengal government. PC 369, Dr 155: E/4/718, pp. 865-78.)

1547 13 Dec., 1826; Ladies' Society for Female Education. PC 366, Dr 71: E/4/718, pp. 445-56.

1548 25 Apr., 1827; post office. PC 380, Dr 237: E/4/719, pp. 159-82.)

1549 22 Aug., 1827; conclusion of a despatch dated 22 Aug., 1827. PC 383, Dr 433: E/4/720, pp. 129-83.

1550 29 Nov., 1826; printing of a selection from Company records relating to revenue, police, and justice. Dr 50: E/4/718, pp. 405-12

1551 28 Feb., 1827; Col. C. Mackenzie's collections. Dr 121: E/4/718, pp. 883-94.)

1552 14 Mar., 1827; purchase of the steamship *Enterprize*. Dr 197: E/4/718, pp. 947-53.

1553 5 Sept., 1827; conclusion of a despatch dated 5 Sept., 1827. Dr 442: E/4/720, pp. 373-412.

1554 10 Oct., 1827; Company's servants' connections with the press. PC 419, Dr 477: E/4/720, pp. 471-90.

1555 30 July, 1828. PC 458, Dr 410 & 411: E/4/722, pp. 425-76.

1556 5 Mar., 1828; abuses of the press regulations. Dr 202: E/4/721, pp. 335-61.

1557 13 Aug., 1828. PC 483 & 489, Dr 428: E/4/722, pp. 781-888.

1558 8 Apr., 1828; Dr. J. Bryce's connection with the *John Bull* newspaper. Dr 258: E/4/721, pp. 645-56.)

1559 27 Oct., 1830; connection of Company's servants with the press. PC 750, Dr 10, D 46: E/4/729, pp. 573-81.

1560 2 June, 1830; landed tenures and land revenues at the settlements in the Straits of Malacca. Dr 374, D 19: E/4/728, pp. 333-65.

1561 30 June, 1830; position of "East Indians" [mixed Indian and European population]. Dr 389, D 24: E/4/728, pp. 735-64. Paras. 11-12, *PP*, 1831-32, IX, 407.

1562 29 Sept., 1830; education. PC 818, Dr 577, D 39: E/4/729, pp. 357-468. *PP*, 1831-32, IX, 407-8 (para. 26 only), 523-8.

1563 9 Feb., 1831; landed tenures and land revenues at the settlements in the Straits of Malacca. PC 866, Dr 179, D 9: E/4/731, pp. 133-72.

1564 2 Feb., 1831; disabilities of Indian Christians, etc. Dr 169, D 8: E/4/731, pp. 7-32. *PP*, 1831-32, IX, 374-5.

1565 6 Apr., 1831; charges against Dr. J. Rind [superintendent of Bengal Lithographic Press]. PC 913, Dr 310, D 24: *E/4/732, pp. 19-36.

1566 4 May, 1831; Singapore. PC 925, Dr 335, D 34: E/4/732, pp. 213-27.

1567 21 Sept., 1831; personal cases and accounts in the Post Office department. Dr 616, D 78: E/4/733, pp. 431-73.

1568 15 Feb., 1832; settlements in the Straits of Malacca [known later as the Eastern Settlements or the Straits Settlements]. PC 970, Dr 80, D 8: E/4/734, pp. 353-469.

1569 24 Aug., 1831; education. PC 952, Dr 579, D.74: E/4/733, pp. 339-69. *PP*, 1831-32, IX, 528-9.

1570 20 July, 1831; appointment of Dr. J. Adamson to the Anglo-Indian College, Calcutta. Dr 530, D 63: E/4/732, pp. 1057-63.

1571 24 Oct., 1832; education. PC 1056, Dr 461, D 74: *E/4/735, pp. 565-86. *PP*, 1831-32, IX, 529-30.

1572 1 Aug., 1832; objection to the appointment of Dr. J. Adamson to the Anglo-Indian College. Dr 360, D 54: *E/4/735, pp. 183-92.

1573 22 Jan., 1833; revenues of the Eastern Settlements. PC 1108, Dr 8, D 6: E/4/736, pp. 565-88.

1574 23 Jan., 1833; education in the Eastern Settlements. PC 1107, Dr 730, D 5: E/4/736, pp. 553-64.

1575 16 Apr., 1834; education. PC 1282, Dr 159, D 28: E/4/740, pp. 895-920.

India Public Department

1576 8 Sept., 1835; Eastern Settlements. PC 1532, Dr 482, D 6: *E/4/745, pp. 9-60.

1577 23 Dec., 1835; education. PC 1639, Dr 681, D 12: *E/4/746, pp. 607-14.

1578 10 Feb., 1836; Eastern Settlements. PC 1650, Dr 51, D 2: *E/4/746, pp. 1095-1110.

1578X Recent changes in Indian education. India PC 1828 cancelled by Board on 12 Dec., 1836: H/723, pp. 1-113, and L/P&J/1/92 (n.p.). No Dr, no D. See also pp. xlvii-xlix.

1579 1 Sept., 1841; Eastern Settlements. PC 2907, Dr 641, D 19: *E/4/767, pp. 927-99.

1580 2 Aug., 1844; Eastern Settlements. PC 4222, Dr 579, D 23: *E/4/779, pp. 739-58.

1581 16 Apr., 1845; claim of Capt. W.

Goodfellow [Civil Architect at Bombay]. PC 4751, Dr 249, D 5: E/4/783, pp. 247-59.

1582 9 July, 1845; deputation of Dr. H. Goodeve to England in charge of medical students. PC 4872, Dr 518, D 10: *E/4/784, pp. 415-28.

1583 17 Sept., 1845; memorial from the Principal of Agra College. PC 4930, Dr 691, D 14: E/4/785, pp. 61-7.

1584 16 June, 1847; office of superintendent of the botanic garden at Calcutta. PC 5597, Dr 404, D 14: *E/4/792, pp. 551-65.

1585 2 Apr., 1851; Straits Settlements [or Eastern Settlements]. PC 7037, Dr 193, D 7: *E/4/809, pp. 1-32.

1585X Answer to India Public Letter of 16 Feb. (No. 32)—no subject or year given. Not traced.

Madras Public Department

1586 10 Mar., 1824. PC 165, Dr 236: E/4/929, pp. 429-63.)

1587 26 May, 1824. PC 182, Dr 354: E/4/929, pp. 993-1016.)

1588 15 Dec., 1824. Dr 73 & 77: E/4/930, pp. 801-25.)

1589 8 Feb., 1826. Dr 141: E/4/932, pp. 367-421.)

1590 20 June, 1826. PC 337, Dr 324: E/4/933, pp. 69-83.)

1591 12 Apr., 1826; J.M. Heath's proposal for establishing iron works. Dr 243: E/4/932, pp. 969-80.)

1592 8 Mar., 1826; salary of Capt. Grant [master attendant at Madras]. Dr 171: E/4/932, pp. 489-96.)

1593 16 Mar., 1827. PC 365, Dr 201: E/4/933, pp. 883-920.)

1594 5 Sept., 1827. PC 436, Dr 381: E/4/934, pp. 361-91.

1595 29 Nov., 1826; printing of a selection of Company records relating to revenue, police, and justice. Dr 54: E/4/933, pp. 609-15.)

1596 30 Apr., 1828. Dr 304: E/4/935, pp. 415-54.)

1597 16 Apr., 1828; education. Dr 278: E/4/935, pp. 359-414. Para. 17, *PP*, 1831-32, IX, 413-14.

1598 12 Mar., 1828; non-registration of the press regulations. PC 468, Dr 205: E/4/935, pp. 244-51.)

1599 23 July, 1828. PC 499, Dr 421: E/4/935, pp. 825-56.)

1600 3 Sept., 1828. PC 540, Dr 462: E/4/936, pp. 1-60. Paras. 34-6, *PP*, 1831-32, IX, 722.

1601 17 Dec., 1828. Dr 82: E/4/936, pp. 336-93.)

1602 29 Sept., 1830; education. PC 824, Dr 583, D 34: E/4/939, pp. 261-83. Paras. 5-8, *PP*, 1831-32, IX, 415-16.

1603 5 Feb., 1834; education. PC 1255, Dr 63, D 11: E/4/944, pp. 127-50.

1604 20 Aug., 1845; memorial of S. Crawford concerning re-employment. PC 4895, Dr 626, D 34: *E/4/964, pp. 497-504.

Bombay Public Department

1605 14 Sept., 1825. PC 278, Dr 454: E/4/1046, pp. 189-213.)

1606 21 Sept., 1825; education. PC 279, Dr 455: E/4/1046, pp. 217-57. Extract, and paras. 4-10, *PP*, 1831-32, IX, 552-3, 729-30.

1607 8 Mar., 1826. PC 323, Dr 193: E/4/1046, pp. 655-716.)

1608 25 Jan., 1826; town hall. Dr 117: E/4/1046, pp. 481-94.)

1609 29 Nov., 1826; printing of a selection of Company records relating to revenue, police, and justice. Dr 57: E/4/1047, pp. 349-54.)

1610 21 Feb., 1827; differences between the government and Sir E. West, Chief Justice of the Supreme Court, Bombay. Dr 158: E/4/1047, pp. 561-81.)

1611 5 Sept., 1827; regulations for the publication of libellous matter in newspapers and other printed works. PC 413, Dr 447: E/4/1048, pp. 155-68.) Para. 9, *PP*, 1831-32, IX, 422.

1612 23 Jan., 1828. PC 422, Dr 137: *E/4/1049, pp. 5-62.)

1613 16 Apr., 1828; education. Dr 284: E/4/1049, pp. 449-88. Paras. 3-15, *PP*, 1831-32, IX, 557-8.

1614 28 Nov., 1827; press. PC 422, Dr 53: E/4/1048, pp. 511-15.)

1615 6 Aug., 1828. PC 503, Dr 435: E/4/1049, pp. 645-70.)

1616 23 July, 1828; non-registration of proposed press regulations. PC 514, Dr 417: E/4/1049, pp. 623-8.

1617 10 Dec., 1828. PC 571, Dr 76: E/4/1050, pp. 217-52. Paras. 33-4, *PP*, 1831-32, IX, 558-9.

1618 18 Feb., 1829; education. Dr 159: E/4/1050, pp. 451-506.) Paras. 9, 15-17; 2, 9-21; and 3-6, *PP*, 1831-32, IX, 442-3; 559-61; and 730.

1619 8 July, 1829; proposed Elphinstone professorships. Dr 337: E/4/1051, pp. 169-98. Paras. 2-4, *PP*, 1831-32, IX, 561.

1620 29 Sept., 1830; education. PC 823, Dr 586, D 21: E/4/1053, pp. 215-50. *PP*, 1831-32, IX, 423 (para. 9 only), 571-3.

1621 9 Mar., 1831; town hall. PC 889, Dr 256, D 19: E/4/1053, pp. 681-708.

1622 16 Mar., 1831. PC 904, Dr 292, D 23: E/4/1053, pp. 757-812.

1623 12 Dec., 1832; education. Dr 653, D 56: E/4/1055, pp. 1141-78. *PP*, 1831-32, IX, 576-8.

1624 5 Sept., 1832; town hall. PC 1074, Dr 508, D 43: E/4/1055, pp. 653-74.

1625 10 July, 1833; education. PC 1179, Dr 354, D 23: E/4/1056, pp. 709-19.

1625X Powers of Governor when absent from the Presidency. Bombay Public PC 1238 not extant but see Dr 644, D 47 of 17 Dec., 1833: E/4/1057, pp. 283-96.

1626 9 Dec., 1835; education. PC 1625, Dr 667, D 40: *E/4/1059, pp. 633-61.

1627 17 Feb., 1836; education. PC 1677, Dr 74, D 9: *E/4/1059, pp. 975-82.

1628 21 Feb., 1838; on the mode of conducting the correspondence. PC 2054, Dr 82, D 4: *E/4/1062, pp. 251-76.

1629 25 Feb., 1846; disposal of two oil paintings of Virgin Mary and child. Dr 101, D 7: *E/4/1080, pp. 391-5.

1630 17 Apr., 1857; revision of the mode of conducting public business. PC 223, Dr 249, D 22: *E/4/1107, pp. 1073-1111.

India Public Works Department

1631 6 May, 1857. PC 382, Dr 486, D 16: *E/4/844, pp. 181-202.

1632 15 July, 1857. PC 411, Dr 644, D 24: *E/4/845, pp. 573-624.

1633 5 Aug., 1857; Patna and Gya Road. PC 453, Dr 825, D 27: *E/4/846, pp. 19-40.

1634 14 July, 1857; Bengal. PC 460, Dr 705, D 23: *E/4/845, pp. 377-428.

1635 13 May, 1857; inundating canals in the Punjab. PC 454, Dr 530, D 18: *E/4/844, pp. 433-48.

- 1636** 19 Aug., 1857; revenue: North-Western Provinces. PC 484, Dr 827, D 30: *E/4/846, pp. 535-646.
- 1637** 19 Aug., 1857; revenue. PC 483, Dr 826, D 29: *E/4/846, pp. 489-534.
- 1638** 1 July, 1857; judicial. PC 490, Dr 677, D 22: *E/4/845, pp. 67-127.
- 1639** 18 Nov., 1857; North-Western Provinces. PC 510, Dr 1280, D 44: *E/4/848, pp. 1188-1302.
- 1640** 9 Dec., 1857; North-Western Provinces. PC 551, Dr 1315, D 47: *E/4/849, pp. 123-241.
- 1641** 22 July, 1857; Straits Settlements. PC 541, Dr 794, D 25: *E/4/845, pp. 936-59.
- 1642** 6 Jan., 1858; Bengal. PC 578, Dr 1377, D 1: *E/4/849, pp. 1039-1117.
- 1643** 16 Dec., 1857; North-Western Provinces. PC 579, Dr 1378, D 48: *E/4/849, pp. 398-491.
- 1644** 19 Aug., 1857. PC 564, Dr 898, D 31: *E/4/846, pp. 647-66.
- 1645** 16 Dec., 1857. PC 599, Dr 1410, D 49: *E/4/849, pp. 492-629.
- 1646** 29 July, 1857; revenue: Bari Doab Canal. PC 587, Dr 864, D 26: *E/4/845, pp. 1244-67.
- 1647** 18 Nov., 1857; revenue. PC 620, Dr 1316, D 45: *E/4/848, pp. 1304-1465.
- 1648** 19 Aug., 1857; ecclesiastical. PC 600, Dr 937, D 32: *E/4/846, pp. 667-81.
- 1649** 28 Oct., 1857; judicial. PC 619, Dr 1249, D 43: *E/4/848, pp. 433-512.
- 1650** 2 Sept., 1857; tolls on the Grand Trunk Road. PC 608, Dr 965, D 35: *E/4/847, pp. 35-51.
- 1651** 16 Dec., 1857; North-Western Provinces. PC 704, Dr 1411, D 50: *E/4/849, pp. 630-713.
- 1652** 3 Feb., 1858; North-Western Provinces. PC 755, Dr 59, D 2: *E/4/850, pp. 25-108.
- 1653** 3 Mar., 1858; North-Western Provinces. PC 772, Dr 124, D 4: *E/4/850, pp. 929-1023.
- 1654** 3 Mar., 1858; irrigation: North-Western Provinces. PC 773, Dr 210, D 6: *E/4/850, pp. 1033-64.
- 1655** 21 Apr., 1858; Bengal. PC 794, Dr 417, D 11: *E/4/851, pp. 281-365.
- 1656** 3 Mar., 1858; roads in Assam. PC 833, Dr 211, D 7: *E/4/850, pp. 1065-89.
- 1657** 12 May, 1858; Dacca and Arakan Road. PC 873, Dr 502, D 16: *E/4/851, pp. 949-64.
- 1658** 28 July, 1858. PC 891, Dr 859, D 25: *E/4/852, pp. 1741-1840.
- 1659** 21 Apr., 1858; Straits Settlements. PC 888, Dr 418, D 12: *E/4/851, pp. 367-93.
- 1660** 4 Aug., 1858; revenue. PC 979, Dr 896, D 27: *E/4/853, pp. 136-221.
- 1661** 16 June, 1858; judicial. PC 969, Dr 652, D 19: *E/4/852, pp. 399-438.
- 1662** 2 June, 1858; ecclesiastical. PC 955, Dr 624, D 18: *E/4/852, pp. 29-44.
- 1663** 13 July, 1858; Bengal. PC 978, Dr 725, D 23: *E/4/852, pp. 1290-1336.
- 1664** 26 May, 1858; case of Lt. H. Goodwyn [Bombay Engineers]. PC 967, Dr 582, D 17: *E/4/851, pp. 1395-1408.
- 1665** 11 Aug., 1858. PC 994, Dr 951, D 28: *E/4/853, pp. 532-75.
- 1666** 30 Aug., 1858. PC 1008, Dr 1048, D 31: *E/4/854, pp. 762-816.

Madras Public Works Department

- 1667** 22 Apr., 1857. PC 364, Dr 437, D 3: *E/4/987, pp. 711-37.
- 1668** 16 Sept., 1857. PC 459, Dr 1010, D 7: *E/4/988, pp. 783-854.
- 1669** 15 July, 1857. PC 505, Dr 780, D 5: *E/4/988, pp. 225-44.
- 1670** 6 Apr., 1858. PC 885, Dr 361, D 2: *E/4/989, pp. 1069-88.
- 1671** 16 June, 1858. PC 930, Dr 663, D 7: *E/4/990, pp. 367-416.

Bombay Public Works Department

- 1672** 24 June, 1857. PC 394, Dr 664, D 10: *E/4/1108, pp. 269-344.
- 1673** 22 July, 1857. PC 486, Dr 811, D 11: *E/4/1108, pp. 759-836.
- 1674** 28 Oct., 1857. PC 524, Dr 1265, D 13: *E/4/1108, pp. 1829-82.
- 1675** 18 May, 1858. PC 856, Dr 572, D 5: *E/4/1110, pp. 919-66.
- 1676** 28 July, 1858. PC 938, Dr 880, D 11: *E/4/1111, pp. 647-716.
- 1677** 11 Aug., 1858. PC 939, Dr 992, D 13: *E/4/1111, pp. 905-52.

1678 4 Aug., 1858; abolition of forced labour in Sind. PC 954, Dr 929, D 12: *E/4/1111, pp. 791-818.

Bengal Ecclesiastical Department

1679 14 Mar., 1827; loan to St. Andrews Church, Calcutta. PC 367, Dr 200: E/4/718, pp. 955-71.

1680 17 Oct., 1827. PC 411, Dr 3: E/4/720, pp. 509-69. Paras. 11-12, PP, 1831-32, IX, 832.

Madras Ecclesiastical Department

1681 26 Apr., 1826. PC 338, Dr 260: E/4/932, pp. 1027-34.

1682 29 Nov., 1826. PC 364, Dr 35: E/4/933, pp. 621-45.

1683 5 Sept., 1827. PC 412, Dr 444: E/4/934, pp. 397-409.

1684 23 July, 1828. PC 486, Dr 414: E/4/935, pp. 859-81.

1685 7 May, 1845; "Black Town" male and female orphan asylums. PC 4813, Dr 351, D 5: *E/4/963, pp. 933-41.

Bombay Ecclesiastical Department

1686 12 Sept., 1827. PC 421, Dr 450: E/4/1048, pp. 191-216.

Bombay Marine Department

1687 5 Jan., 1825. PC 231, Dr 105: E/4/1045, pp. 471-86.

1688 2 Apr., 1828. Dr 247: E/4/1049, pp. 371-418.

1689 6 Aug., 1828; Marine and Forest Department. PC 509, Dr 437: E/4/1049, pp. 673-93.

1690 8 Apr., 1828; case of Capt. R. Goodridge [Bombay Marine]. Dr 245: E/4/1049, pp. 419-24.)

1691 3 Dec., 1828; Marine and Forest Department. PC 573, Dr 67: E/4/1050, pp. 165-99.

Bengal Law Department

1692 6 Feb., 1827; admission of W.L. Cleland as a barrister in Bengal. PC 385, Dr 115: E/4/718, pp. 831-47.

India Financial Department

1692X Allowances of Resident at Indore. India Financial PC 5587 not extant, but see Dr 550, D 25 of 21 July, 1847: E/4/792, pp. 1265-70.

Bengal Commercial Department

1693 25 Feb., 1824; claims of S. Garling [Benkulen establishment]. Dr 206: E/4/710, pp. 1251-4.)

1694 25 Oct., 1826; opening up of communication through Tibet to Peking. Dr 472: E/4/718, pp. 41-4.

Prince of Wales Island General Department

1695 11 Apr., 1826. PC 315, Dr 233: G/34/194, pp. 283-338.

1696 19 Apr., 1826. PC 329, Dr 257: G/34/194, pp. 345-94.

1697 11 Apr., 1827. PC 347, Dr 243: G/34/194, pp. 601-36.

1698 6 Aug., 1828. Dr 440: G/34/195, pp. 85-154.

1699 23 July, 1828; abuses of the press. PC 517, Dr 420: G/34/195, pp. 71-83.

1700 17 June, 1829. PC 587, Dr 367: G/34/195, pp. 373-600.

1701 30 Sept., 1829. PC 659, Dr 501: G/34/195, pp. 673-836.

1702 15 Apr., 1830. PC 748, Dr 306: G/34/195, pp. 921-85.

Despatches Identified as Written Wholly or Partly by J.S. Mill but not Included in MSS Eur B 405:

India Political Department

1703 17 Nov., 1841; re-employment of Lt. Col. H. Burney [ex-Resident in Ava]. PC 3291, Dr 785, D 37: *E/4/768, pp. 409-12; L/P&S/6/325, pp. 193-[200].

1704 28 Feb., 1844; petition of the daughters of Maj. G. Drew [officer in the Nizam's service]. PC 4236, Dr 109, D 7: *E/4/777, pp. 653-6; L/P&S/6/334, pp. 411-[420].

1705 23 Oct., 1844; case of Maj. E. Pottinger [Bombay Artillery]. PC 4524, Dr 748, D 35: *E/4/780, pp. 593-7; L/P&S/6/337, pp. 1-[12].

1706 30 Oct., 1844; appointment of Lt. Col. J. Sheil as envoy to Persia. Dr 758, D 37: *E/4/780, pp. 703-7; L/P&S/6/337, pp. 17-[20].

1707 22 July, 1846; Baron de Gazern [A.D.C. to King of Netherlands]. Dr 505, D 23: *E/4/788, pp. 835-9; L/P&S/6/345, pp. 53-[56].

1708 19 Aug., 1846; Dutch claims to Sumatra Coast. Dr 574, D 26: *E/4/789, pp. 813-17; L/P&S/6/345, pp. 383-[386].

1709 2 Sept., 1846; case of Lt. Col. W. Borthwick [ex-Political Agent in Indore and

Malwa]. Dr 578, D 27: *E/4/789, pp. 869-73; L/P&S/6/345, pp. 395-[398].

1710 7 Sept., 1853; Borneo enquiry. Dr 735, D 37: *E/4/822, pp. 35-9; L/P&S/6/375, pp. 359-[362].

Bombay Political Department

1711 17 Apr., 1850; claims of Cristna Rao Wittul of Gujarat. PC 6845, Dr 245, D 15: *E/4/1091, pp. 145-52; L/P&S/6/361, pp. 169-[180].

1713 24 May, 1853; investigation at Baroda. PC 8195, Dr 394, D 29: *E/4/1098, pp. 303-17; L/P&S/6/343, pp. 437-[518], 539-[546].

Appendix B

List of Published Extracts from Mill's Indian Despatches

MILL KEPT A MANUSCRIPT LIST of his published writings¹ in which he included entries for those portions of his Indian Despatches that were made public in official documents. Mill himself had no role in their publication, and they appeared not because he was the author (the despatches were of course official East India Company documents, not issued as his), but because the company, individuals, or the government had a special interest in the matters covered.² In Appendix A above, the complete list of Mill's despatches, there is indication of those that were in part published; however, because he kept the list of his published writings, it is appropriate to make the record complete up to the time of his death.³

In the list below, the items are arranged according to the order of their publication. The entries are numbered serially: each includes the number assigned to the full despatch in Appendix A,⁴ and the publication data, followed by the entry in Mill's list of his published writings (signalled by "JSM"). In many cases these entries were grouped by Mill under a general heading: to avoid annoying repetition, this heading is given only for the first such entry, and subsequent entries under it have the notation "General heading in No. 00 above" followed by the specific wording for the separate entries. There are a few mistakes in the original list, which exists only in a scribal copy,⁵ and in MacMinn's transcription of it, as well as in MacMinn's identification of the published sources: these have been corrected, and instances of the former two are described in footnotes.⁶ In the

¹Edited by Ney MacMinn, *et al.*, as *Bibliography of the Published Writings of John Stuart Mill* (Evanston: Northwestern University Press, 1945); referred to subsequently as MacMinn.

²The circumstances leading to the publication are briefly described in notes.

³No attempt has been made to comb *Parliamentary Papers* for extracts from Mill's despatches published after his death. One instance may be cited, however, an undated "Minute by Mr. John Stuart Mill [regarding the Legislative Council]," in *Papers Relating to East India (Legislation)*, PP, 1876, LVI, 32-4.

⁴In one case, No. 43 below, there is no corresponding entry in App. A.

⁵British Library of Political and Economic Science, London School of Economics, Mill-Taylor Collection, Vol. XXXVI.

⁶Because the manuscript is a copy, such oddities in punctuation as the placing of full stops after dates in the middle of sentences are standardized and corrected silently, and the abbreviations are normalized. The manuscript also indicates rather erratically in shoulder notes the years of entries;

volumes of *Parliamentary Papers* there are normally two sets of page numbers, one printed, reflecting the pagination of the parts when first separately published, the second, inked, giving the pagination of the gathered volume: we have used here, as throughout *Collected Works*, the inked numbers; Mill used the former (as he was referring to the separate Blue Books), while MacMinn used a mixture of the two, so our page numbers often differ from theirs. In a few cases, material was called for more than once in different circumstances: we have given entries for all printings, with cross-references.

1 App. A: 1564 "Letter in the General Department from the Court of Directors to the Bengal Government, dated the 2nd February, 1831," *Appendix to the Report of the Select Committee on the Affairs of the East India Company*, Pt. I: Public, *PP*, 1831-32, IX, 374-5. JSM: general heading: "The following Despatches to India printed in the Appendix of the Report of the Commons Committee on Indian affairs 1832 Part I. (Public Department)."⁷ Specifically: "Letter to Bengal, dated 2nd Feb., 1831, on the Disabilities of Native Christians (p. 344)."

2 App. A: 1561 "Extract Public Letter to Bengal, dated 30th June, 1830," *ibid.*, *PP*, 1831-32, IX, 407. JSM: general heading in No. 1 above; specifically: "Extract from a letter to Bengal, dated 30th June, 1830, on the Disabilities of Half-Castes (p. 377)."

3 App. A: 1562 "Extract Public Letter to Bengal, dated 29th September, 1830," *ibid.*, *PP*, 1831-32, IX, 407-8. JSM: general heading in No. 1 above; specifically: "Extract from a letter to Bengal, dated 29th September, 1830, on the Education of the natives (ib.) printed again further on." (Cf. No. 11 below.)

4 App. A: 1597 "Extract Letter, in the Public Department, from the Court of Directors to the Governor in Council at Fort St. George, dated 16th April, 1828," *ibid.*, *PP*, 1831-32, IX, 413-14. JSM: general heading in No. 1 above; specifically: "Extract from a letter to Madras, dated 16th April, 1828, on the same subject (p. 383)."

5 App. A: 1602 "Extract Letter, in the Public Department, from the Court of Directors to the Governor in Council at Fort St. George, dated 29th September, 1830," *ibid.*, *PP*, 1831-32, 415-16. JSM: general heading in No. 1 above; specifically: "Also from a letter, dated 29th September, 1830 (p. 385)."

6 App. A: 1611 "Extract Letter, in the Public Department, from the Court of Directors to the Governor in Council at Bombay, dated 5th September, 1827," *ibid.*, *PP*, 1831-32, 422. JSM: general heading in No. 1 above; specifically: "Extract from a letter to Bombay, dated 5th September, 1827, on the employment of natives in public offices (p. 392)."

7 App. A: 1618 "Extract Letter, in the Public Department, from the Court of Directors to the Governor in Council at Bombay, dated 18th February, 1829," *ibid.*, *PP*, 1831-32, IX, 422-3. JSM: general heading in No. 1 above; specifically: "Extract from a letter to Bombay, dated 18th February, 1829, on the education of natives (p. 392), printed again further on." (Cf. Nos. 17 and 25 below.)

8 App. A: 906 "Extract Political Letter to Bombay, dated 26th May, 1830," *ibid.*, *PP*, 1831-32, IX, 423. JSM: general heading in No. 1 above; specifically: "Extract from a letter to Bombay, dated 26th May, 1830, on the employment of natives (p. 393)."

9 App. A: 1620 "Extract Letter, in the Public Department, from the Court of Directors to the Governor in Council at Bombay, dated 29th September, 1830," *ibid.*, *PP*, 1831-32, IX, 423.

these are omitted. Gaps and unusual abbreviations in the manuscripts are filled in, with the added matter in square brackets.

⁷Discussion in the House of Commons in connection with the proposed revision of the Charter Act in 1833, particularly with reference to the China trade, led to the presentation of papers by the government, ordered printed 16 Aug., 1832.

JSM: general heading in No. 1 above; specifically: "Extract from a letter to Bombay, dated 29th September, 1830, on the education of natives (ib.) printed again further on." (Cf. No. 19 below.)

10 App. A: 1541 "Extract of a letter, in the Public Department, from the Court of Directors to the Governor-General in Council of Bengal, dated 9th March, 1825," *ibid.*, PP, 1831-32, IX, 518-19. JSM: general heading in No. 1 above; specifically: "Extract from a letter to Bengal, dated 9th March, 1825, on the same subject (p. 488)."

11 App. A: 1562 "Letter, in the Public Department, to Bengal, dated 29th September, 1830," *ibid.*, PP, 1831-32, IX, 523-8. JSM: general heading in No. 1 above; specifically: "Letter to Bengal, dated 29th Sept., 1830, on the education of the natives (p. 493)."⁸ (Cf. No. 3 above.)

12 App. A: 1569 "Letter, in the Public Department, to Bengal, August 24, 1831," *ibid.*, PP, 1831-32, IX, 528-9. JSM: general heading in No. 1 above; specifically: "Letter to Bengal, dated 24th August, 1831, on the same subject (p. 498)."

13 App. A: 1571 "Letter, in the Public Department, to Bengal, dated 24th October, 1832," *ibid.*, PP, 1831-32, IX, 529-30. JSM: general heading in No. 1 above; specifically: "Letter to Bengal, dated 24th October, 1832, on the same subject (p. 499)."

14 App. A: 1606 "Extract Letter, in the Public Department, to the Bombay Government, dated 21st September, 1825," *ibid.*, PP, 1831-32, IX, 552-3. JSM: general heading in No. 1 above; specifically: "Extract from a letter to Bombay, dated 21st September, 1825, on the same subject (p. 522)." (Cf. No. 24 below.)

15 App. A: 1613 "Extract of Letter, in the Public Department, from the Court of Directors to the Governor in Council of Bombay, dated 16th April, 1828," *ibid.*, PP, 1831-32, IX, 557-8. JSM: general heading in No. 1 above; specifically: "Also from letters dated 16th April, 1828 (p. 527)."

16 App. A: 1617 "Extract of Letter, in the Public Department, from the Court of Directors to the Governor in Council at Bombay, dated 10th

December, 1828," *ibid.*, PP, 1831-32, IX, 558-9. JSM: general heading in No. 1 above; specifically: "[Also from letters dated] 10th December, 1828 (p. 528)."

17 App. A: 1618 "Extract of Letter, in the Public Department, from the Court of Directors to the Governor in Council of Bombay, dated 18th February, 1829," *ibid.*, PP, 1831-32, IX, 559-61. JSM: general heading in No. 1 above; specifically: "[Also from letters dated] 18 Feb., 1829 (p. 529)." (Cf. No. 7 above and No. 25 below.)

18 App. A: 1619 "Extract of Letter, in the Public Department, from the Court of Directors to the Governor in Council of Bombay, dated 8th July, 1829," *ibid.*, PP, 1831-32, IX, 561. JSM: general heading in No. 1 above; specifically: "[Also from letters dated] 8th July, 1829 (p. 531)."

19 App. A: 1620 "Letter, in the Public Department, to the Governor in Council at Bombay, dated September 29th, 1830," *ibid.*, PP, 1831-32, IX, 571-3. JSM: general heading in No. 1 above; specifically: "Letter to Bombay, dated 29th September, 1830, on the same subject (p. 541)." (Cf. No. 9 above.)

20 App. A: 1623 "Letter, in the Public Department, to the Governor in Council at Bombay, dated 12th December, 1832," *ibid.*, PP, 1831-32, IX, 576-8. JSM: general heading in No. 1 above; specifically: "Letter to Bombay, dated 12th December, 1832, on the same subject (p. 546)."

21 App. A: 1538 "Extract Letter from the Court of Directors to the Bengal Government, dated March 17th, 1824," *ibid.*, PP, 1831-32, IX, 636. JSM: general heading in No. 1 above; specifically: "Extract from a letter to Bengal, dated 17th March, 1824, on the College of Fort William (p. 606)."

22 App. A: 1544 "Extract Letter from the Court of Directors to the Bengal Government, dated March 8th, 1826," *ibid.*, PP, 1831-32, IX, 638. JSM: general heading in No. 1 above; specifically: "Also from a letter dated 8th March, 1826 (p. 608)."

23 App. A: 1600 "Extract Public Letter to the Madras Government, dated 3rd September, 1828," *ibid.*, PP, 1831-32, IX, 722. JSM:

⁸MacMinn has 393-4 for the printed page nos. 493-8.

general heading in No. 1 above; specifically: "Extract from a letter to Madras, dated 3rd September, 1828, on the College of Madras (p. 692)."

24 App. A: 1606 "Extract Public Letter to the Bombay Government, dated September 21, 1825," *ibid.*, PP, 1831-32, IX, 729-30. JSM: general heading in No. 1 above; specifically: "Extract from a letter to Bombay, dated 21st Sept., 1825, on the Education of Civil Servants (p. 699)." (Cf. No. 14 above.)

25 App. A: 1618 "Extract Public Letter to the Bombay Government, dated February 18th, 1829," *ibid.*, PP, 1831-32, IX, 730. JSM: general heading in No. 1 above; specifically: "Also from a letter dated 18th Feb., 1829 (p. 700)." (Cf. Nos. 7 and 17 above.)

26 App. A: 1680 "Extract Ecclesiastical Letter to the Bengal Government, dated October 17th, 1827," *ibid.*, PP, 1831-32, IX, 832. JSM: general heading in No. 1 above; specifically: "Extract from a letter to Bengal, dated 17th Oct., 1827 on the Ecclesiastical Establishment (p. 802)."

27 App. A: 5 "Extract Political Letter to Bengal, dated 9th November, 1825," *ibid.*, Part VI: Political, or Foreign, PP, 1831-32, XIV, 347-9. JSM: "All the extracts from Despatches in the Political or Foreign Appendix to the same Report, except one (on [Travancore.])"⁹

28 App. A: 19 "Extract Political Letter to Bengal, dated 1st October, 1828," *ibid.*, PP, 1831-32, XIV, 349-52. JSM: general heading in No. 27 above.

29 App. A: 22 "Extract Political Letter to Bengal, dated 26th November, 1828," *ibid.*, PP, 1831-32, XIV, 352. JSM: general heading in No. 27 above.

30 App. A: 33 "Extract Political Letter to Bengal, dated 7th January, 1831," *ibid.*, PP,

1831-32, XIV, 355. JSM: general heading in No. 27 above.

31 App. A: 47 "Extract Political Letter to Bengal, dated 31st October, 1832," *ibid.*, PP, 1831-32, XIV, 356. JSM: general heading in No. 27 above.

32 App. A: 905 "Extract Political Letter to Bombay, dated 26th May, 1830," *ibid.*, PP, 1831-32, XIV, 356-8. JSM: general heading in No. 27 above.

33 App. A: 45 "Extract Political Letter to Bengal, dated 1st February, 1832," *ibid.*, PP, 1831-32, XIV, 358. JSM: general heading in No. 27 above.

34 App. A: 812 "Extract Political Letter to Fort St. George, dated 6th March, 1832," *ibid.*, PP, 1831-32, XIV, 358-60. JSM: general heading in No. 27 above.

35 App. A: 52 "Extract Political Letter to Bengal, dated 6th March, 1833," *ibid.*, PP, 1831-32, XIV, 360. JSM: general heading in No. 27 above.

36 App. A: 150 "The Court of Directors of the East India Company to the Governor-General of India in Council" [dated 20 Sept., 1837], in *Correspondence Relating to Afghanistan*, PP, 1839, XL, 266-7.¹⁰ JSM: "A Despatch to India in the Political Department, dated 20th September 1837, ordered by the House of Commons to be printed 27th March, 1839."

37 App. A: 982 "Extract Political Despatch to the Government of Bombay, dated 2nd September, 1840," in *Papers Respecting the Case of the Raja of Sattara* (London, 1840), 388-9. JSM: "A Despatch to Bombay in the Political Department, dated 2nd September, 1840, included in the "Papers respecting the Case of the Raja of Sattara"¹¹ printed by order of the Court of Proprietors¹² of the East India Company in that year."

⁹Before the entry (which is incomplete) there is a note: "(The Political Appendix has not yet appeared.)" The letter not by Mill is probably "Extract Political Letter to Bengal, dated 18th December, 1832," *ibid.*, PP, 1831-32, XIV, 361, the only extract not in Mill's India Office list in App. A. MacMinn, evidently not noticing that the extract is from India, lists as the exception "Extract Political Letter from Bombay, dated 20th July, 1830," *ibid.*, PP, 1831-32, XIV, 353-5.

¹⁰The government presented papers (ordered to be printed on 27 Mar., 1839) relating to Persia and Afghanistan. MacMinn gives 265-7 for the written nos. 266-7.

¹¹The manuscript reads "Suttara".

¹²The manuscript reads "Proprietries".

38 App. A: 508 "Despatch from the Court of Directors to the Government of India" [24 Jan., 1849], in "Despatches on the Subject of the Disposal of the Sattara State," *PP*, 1849, XXXIX, 150-1.¹³ JSM: "Political letter to Bombay, dated 20th Jan., 1849, printed in the Papers on Sattara"¹⁴ affairs laid before the Court of Proprietors in the spring of 1849."

39 App. A: 994 "Lapse of Colaba [25 May, 1841]," in "Papers Respecting the Succession, by Adoption, of Sovereign Princes in India," *PP*, 1850, XLI, 624-5.¹⁵ JSM: general heading: "The following despatches to India, printed in a return to the House of Commons of papers in succession by adoption to Indian Principalities, forming No. 50 of the papers of the Session of 1850" and continued after the specific headings, "All in the Polit[ical] Department: pp. 214-17 of the Return." Specific heading: "Letter to Bombay, dated 25th May, 1841, on the Lapse of Colaba."

40 App. A: 1051 "Political Department [24 Apr., 1844]," *ibid.*, *PP*, 1850, XLI, 625-6. JSM: general heading in No. 39 above; specifically: "Letter to Bombay, dated 24th April, 1844, on the s[ame] subject."

41 App. A: 1022 "Lapse of Mandavee—Political Department, 30 Dec., 1842," *ibid.*, *PP*, 1850, XLI, 626-7. JSM: general heading in No. 39 above; specifically: "Letter to Bombay, dated 30th Dec.,¹⁶ 1842, on the lapse of Mandava."

42 App. A: 1053 "Extract Political Letter to Bombay, dated 2 Aug., 1844," *ibid.*, *PP*, 1850, XLI, 627. JSM: general heading in No. 39 above; specifically: "Extract from a letter to Bombay, dated 2nd Aug., 1841, on the same subject."

43 Not in App. A "Extract Political Letter to Bombay, dated 31st Oct., 1832," in "Despatches from the Bombay Government Respecting the Claims of Chrisna Rao Withul," *PP*, 1850, XLI, 56.¹⁷ JSM: general heading: "The following extracts of Despatches to Bombay, printed in a return to the House of Commons in the case of Chrisna Rao Withul, forming No. 136 of the papers of the Session of 1850." Specific heading: "Extract Political Letter, dated 31st Oct., 1832 (p. 12)."

44 App. A: 953 "Political Department, 14 March, 1838," *ibid.*, *PP*, 1850, XLI, 59-60. JSM: general heading in No. 43 above; specifically: "Political Letter, dated 14th March, 1838."

45 App. A: 1006 "Extract Political Letter to Bombay, dated 13 Oct., 1841," *ibid.*, *PP*, 1850, XLI, 60. JSM: general heading in No. 43 above; specifically: "Extract Political Letter, dated 13th Oct., 1841 (pp. 15, 16)."

46 App. A: 1090 "Extract Political Letter to Bombay, dated 16 April, 1845," *ibid.*, *PP*, 1850, XLI, 60. JSM: general heading in No. 43 above; specifically: "Extract Political Letter, dated 16th April, 1845."

47 App. A: 556 "Our Governor-General of India in Council [10 July, 1850]," in "Papers Relative to the Raja of Sattara," *PP*, 1850, XLI, 210.¹⁸ JSM: "A political despatch to the [Governor-General] of India, dated 10th July, 1850, on the family of the ex Rajah of Sattara,¹⁹ printed in p. 8 of a return to the House of Commons forming No. 669 of the papers of the Session of 1850."

48 App. A: 1297 "Political Department, 2 June, 1852," in "Papers on the Removal of Col. Outram from the Office of Resident of Baroda," *PP*, 1852, XXXVII, Pt. 1, 28-30.²⁰ JSM: general

¹³Papers were called for in the House of Commons by Joseph Hume on 5 Feb., 1849, in connection with the disposal of the affairs of Sattara on the death of the Rajah, and were ordered to be printed 1 Mar., 1849.

¹⁴Again the manuscript reads "Suttara".

¹⁵Papers were called for in the House by Edward Colebrooke on 17 July, 1849, and ordered to be printed 15 Feb., 1850.

¹⁶The manuscript reads "30th Nov."

¹⁷Papers were called for in the House by Lord Dudley Stuart on 5 Feb., 1850, and ordered to be printed on 13 Mar., 1850.

¹⁸The government presented papers relating to the affairs of Sattara that had been ordered printed on 5 Aug., 1850.

¹⁹Once again the manuscript reads "Suttara".

²⁰Papers were called for in the House by Thomas Chisholm Anstey on 4 June, 1852.

heading: "The following Despatches to India, printed in a Return to the House of Commons of papers relating to the removal of Colonel Outram from the office of Resident at Baroda, forming No. 560 of the papers of the Session of 1852-53" and continued after the specific headings, "(Some of these letters and pamphlets underwent alteration in passing the Court of Directors and Board of Control.)" Specifically: "Political Letter to Bombay, dated 2nd June, 1852 (pp. 8-10)."

49 App. A: 1300 "Political Department, 23 June, 1852," *ibid.*, *PP*, 1852, XXXVII, Pt. 1, 35-41. JSM: general heading in No. 48 above; specifically: "Political Letter to Bombay, dated 23rd June, 1852 (pp. 15-21)."

50 App. A: 987 "Political Department, 10 February, 1841," *ibid.*, *PP*, 1852, XXXVII, Pt. 1, 49-50. JSM: general heading in No. 48 above; specifically: "Political Letter to Bombay, dated 10th Feb., 1841."

51 App. A: 1016 "Extract Political Letter to Bombay, dated 1 June, 1842," *ibid.*, *PP*, 1852, XXXVII, Pt. 1, 50. JSM: general heading in No. 48 above; specifically: "Extract Political Letter to Bombay, dated 1st June, 1842." (Cf. No. 58 below.)

52 App. A: 1015 "Extract Political Letter to Bombay, dated 6 July, 1842," *ibid.*, *PP*, 1852, XXXVII, Pt. 1, 50-1. JSM: general heading in No. 48 above; specifically: "Extract Political Letter to Bombay, dated 6th July, 1842."

53 App. A: 1026 "Extract Political Letter to Bombay, dated 25 Jan., 1843," *ibid.*, *PP*, 1852, XXXVII, Pt. 1, 51. JSM: general heading in No. 48 above; specifically: "Extract Political Letter to Bombay, dated 25 Jan., 1843."

54 App. A: 1064 "Extract Political Letter to Bombay, dated 31 July, 1844," *ibid.*, *PP*, 1852, XXXVII, Pt. 1, 51. JSM: general heading in No. 48 above; specifically: "Extract Political Letter to Bombay, dated 31st July, 1844."

55 App. A: 1215 "Extract Political Letter to Bombay, dated 28 Nov., 1849," *ibid.*, *PP*, 1852, XXXVII, Pt. 1, 52. JSM: general heading in No. 48 above; specifically: "Extract Political Letter to Bombay, dated 28th Nov., 1849." (Cf. Nos. 73, 111, and 132 below.)

56 App. A: 1227 "Extract Political Letter

to Bombay, dated 13 Feb., 1850," *ibid.*, *PP*, 1852, XXXVII, Pt. 1, 52. JSM: general heading in No. 48 above; specifically: "Extract Political Letter to Bombay, dated 13th²¹ Feb., 1850." (Cf. Nos. 112 and 113 below.)

57 App. A: 1260 "Extract Political Letter to Bombay, dated 15 Jan., 1851," *ibid.*, *PP*, 1852, XXXVII, Pt. 1, 53. JSM: general heading in No. 48 above; specifically: "Extract Political Letter to Bombay, dated 15th Jan., 1851." (Cf. No. 93 below.)

58 App. A: 1016 "Extract Political Letter to Bombay, dated 1 June, 1842," in "Papers Relating to the Alleged Corruption of Officers of the Bombay Government," *PP*, 1852-53, LXX, 38.²² JSM: general heading: "The following Despatches to India, printed in a further return to the House of Commons of papers relating to Baroda Intrigues, forming No. 615 of the papers of the session of 1852-53." Specifically: "Extract Political Letter to Bombay, dated 1st June, 1842 (p. 2)." (Cf. No. 51 above.)

59 App. A: 1035 "Extract Political Letter to Bombay, dated 19 July, 1843," *ibid.*, *PP*, 1852-53, LXX, 40. JSM: general heading in No. 58 above; specifically: "Extract Political Letter to Bombay, dated 19th July, 1843 (p. 4)."

60 App. A: 1078 "Extract Political Letter to Bombay, dated 24 December, 1844," *ibid.*, *PP*, 1852-53, LXX, 78-9. JSM: general heading in No. 58 above; specifically: "Extract Political Letter to Bombay, dated 24th Dec., 1844 (pp. 43-4)."

61 App. A: 1124 "Extract Political Letter to Bombay, dated 29 July, 1846," *ibid.*, *PP*, 1852-53, LXX, 121. JSM: general heading in No. 58 above; specifically: "Extract Political Letter to Bombay, dated 29th July, 1846 (p. 85)."

62 App. A: 1231 "Extract Political Letter to Bombay, dated 20 February, 1850," *ibid.*, *PP*, 1852-53, LXX, 122. JSM: general heading in No. 58 above; specifically: "Extract Political Letter to Bombay, dated 20th Feb., 1850 (p. 86)."

63 App. A: 1302 "Extract Political Letter to Bombay, dated 1 July, 1852," *ibid.*, *PP*, 1852-53, LXX, 161. JSM: general heading in

²¹MacMinn mistranscribes as "18th".

²²Papers were called for in the House by Mr. Otway on 24 Feb., 1853.

No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 1st July, 1852²³ (p. 125)."

64 App. A: 1135 "Extract Political Letter to Bombay, dated 27 January, 1847," *ibid.*, PP, 1852-53, LXX, 170. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 27th²⁴ Jan., 1847 (p. 134)."

65 App. A: 1086 "Extract Political Letter to Bombay, dated 5 February, 1845," *ibid.*, PP, 1852-53, LXX, 290. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 5th Feb., 1845 (p. 254)."

66 App. A: 1130 "Extract Political Letter to Bombay, dated 23 December, 1846," *ibid.*, PP, 1852-53, LXX, 290-1. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 23 Dec., 1846 (pp. 254-5)."

67 App. A: 1167 "Extract Political Letter to Bombay, dated 29 March, 1848," *ibid.*, PP, 1852-53, LXX, 292. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 29th March, 1848²⁵ (p. 256)."

68 App. A: 1129 "Extract Political Letter to Bombay, dated 22 September, 1846," *ibid.*, PP, 1852-53, LXX, 309. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 22nd Sept., 1846 (p. 273)."

69 App. A: 1178 "Extract Political Letter to Bombay, dated 12 July, 1848," *ibid.*, PP, 1852-53, LXX, 335. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 12th July, 1848 (p. 299)."

70 App. A: 1293 "Extract Political Letter to Bombay, dated 13 April, 1852," *ibid.*, PP, 1852-53, LXX, 335-6. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 13th April, 1852 (pp. 299-300)."

71 App. A: 1246 "Extract Political Letter to Bombay, dated 4 December, 1850," *ibid.*, PP, 1852-53, LXX, 373. JSM: general heading in

No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 4th Dec., 1850 (p. 337)."

72 App. A: 1186 "Extract Political Letter to Bombay, dated 20 September, 1848," *ibid.*, PP, 1852-53, LXX, 420. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 20th Sept., 1848 (p. 384)."

73 App. A: 1215 "Extract Political Letter to Bombay, dated 28 Nov., 1849," *ibid.*, PP, 1852-53, LXX, 420-1. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 28th Nov., 1849 (pp. 384-5)." [Cf. No. 55 above, and Nos. 111 and 132 below.]

74 App. A: 1009 "Extract Political Letter to Bombay, dated 22 March, 1842," *ibid.*, PP, 1852-53, LXXI, 15. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 22nd March, 1842 (p. 483)."

75 App. A: 1050 "Extract, Para. 2 to 4 of a Letter from the Honourable, the Court of Directors, dated 27th March, 1844," *ibid.*, PP, 1852-53, LXXI, 17. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 27th March, 1844 (p. 485)."

76 App. A: 1071 "Extract Political Letter to Bombay, dated 4 December, 1844," *ibid.*, PP, 1852-53, LXXI, 19-20. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 4th Dec., 1844 (487)."

77 App. A: 1093 "Extract Political Letter to Bombay, dated 23 April, 1845," *ibid.*, PP, 1852-53, LXXI, 111-12. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 23d April, 1845 (pp. 579-80)."

78 App. A: 1125 "Extract Political Letter to Bombay, dated 29 July, 1846," *ibid.*, PP, 1852-53, LXXI, 130. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 29th July, 1846 (p. 598)."

79 App. A: 1180 "Extract Political Letter to Bombay, dated 9 August, 1848," *ibid.*, PP,

²³The manuscript reads "1851".

²⁴The manuscript reads "29th".

²⁵The manuscript reads "1849".

1852-53, LXXI, 133. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 9th August, 1848 (p. 601)."

80 App. A: 1197 "Extract Political Letter to Bombay, dated 21 February, 1849," *ibid.*, PP, 1852-53, LXXI, 134. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 21st Feb., 1849 (p. 602)."

81 App. A: 1211 "Extract Political Letter to Bombay, dated 29 August, 1849," *ibid.*, PP, 1852-53, LXXI, 134. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 29th Aug., 1849 (p. 602)."

82 App. A: 1283 "Extract Political Letter to Bombay, dated 2 January, 1852," *ibid.*, PP, 1852-53, LXXI, 135. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 2nd Jan., 1852 (p. 603)."

83 App. A: 1127 "Extract Political Letter to Bombay, dated 30 September, 1846," *ibid.*, PP, 1852-53, LXXI, 366. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 30th Sept., 1846 (p. 832)."

84 App. A: 1228 "Extract Political Letter to Bombay, dated 13 February, 1850," *ibid.*, PP, 1852-53, LXXI, 396. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 13th Feb., 1850 (p. 862)."

85 App. A: 1326 "Extract Political Letter to Bombay, dated 30 March, 1853," *ibid.*, PP, 1852-53, LXXI, 402-3. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 30th March, 1853 (pp. 868-9)."

86 App. A: 1235 "Extract Political Letter to Bombay, dated 27 March, 1850," *ibid.*, PP, 1852-53, LXXI, 536. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 27th March, 1850 (1002)."

87 App. A: 1152 "Extract Political Letter to Bombay, dated 18 August, 1847," *ibid.*, PP,

1852-53, LXXI, 542. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 18th August, 1847 (p. 1008)."

88 App. A: 1148 "Extract Political Letter to Bombay, dated 16 June, 1847," *ibid.*, PP, 1852-53, LXXI, 542. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 16th June, 1847 (p. 1008)."

89 App. A: 1241 "Extract Political Letter to Bombay, dated 12 June, 1850," *ibid.*, PP, 1852-53, LXXI, 543. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 12th June, 1850 (p. 1009)."

90 App. A: 1202 "Extract Political Letter to Bombay, dated 14 March, 1849," *ibid.*, PP, 1852-53, LXXII, 7. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 14th March, 1849 (p. 1037). (Cf. No. 110 below.)"

91 App. A: 1286 "Extract Political Letter to Bombay, dated 2 January, 1852,"²⁶ *ibid.*, PP, 1852-53, LXXII, 8. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 2nd Jan., 1852 (p. 1038). (Cf. No. 115 below.)"

92 App. A: 1306 "Extract Political Letter to Bombay, dated 15 September, 1852," *ibid.*, PP, 1852-53, LXXII, 8. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 15th Sept., 1852 (p. 1038). (Cf. No. 116 below.)"

93 App. A: 1260 "Extract Political Letter to Bombay, dated 15 January, 1851," *ibid.*, PP, 1852-53, LXXIII, 9-10. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 15th Jan., 1851 (pp. 1635-6). (Cf. No. 57 above.)"

94 App. A: 1315 "Extract Political Letter to Bombay, dated 31 December, 1852," *ibid.*, PP, 1852-53, LXXIII, 10-11. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 31st Dec., 1852 (pp. 1636-7). (Considerably altered by the B[oard] of Control.)"²⁷ (Cf. No. 95 below.)"

²⁶MacMinn gives "1849".

²⁷In the manuscript, the words, "Extract Political Letter to Bombay," are signalled by a series of ditto marks in the entries from No. 87 to No. 106 inclusive. In each case the ditto marks are followed

95 App. A: 1315 "Extract Political Letter to Bombay, dated 31 December, 1852," *ibid.*, *PP*, 1852-53, LXXIII, 81. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 31st Dec., 1852 (p. 1707)." (Cf. No. 94 above.)

96 App. A: 1320 "Extract Political Letter to Bombay, dated 26 January, 1853," *ibid.*, *PP*, 1852-53, LXXIII, 85. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 26th Jan., 1853 (pp. 1711-3)." (Cf. Nos. 102 and 104 below.)

97 App. A: 1324 "Extract Political Letter to Bombay, dated 6 April, 1853," *ibid.*, *PP*, 1852-53, LXXIII, 88. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 6th April, 1853 (p. 1714)." (Cf. Nos. 98, 99, and 105 below.)

98 App. A: 1324 "Extract Political Letter to Bombay, dated 6 April, 1853," *ibid.*, *PP*, 1852-53, LXXIII, 89. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 6th April, 1853 (p. 1715)." (Cf. No. 97 above and Nos. 99 and 105 below.)

99 App. A: 1324 "Extract Political Letter to Bombay, dated 6 April, 1853," *ibid.*, *PP*, 1852-53, LXXIII, 90. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 6th April, 1853 (p. 1716)." (Cf. Nos. 97 and 98 above, and No. 105 below.)

100 App. A: 1328 "Extract Political Letter to Bombay, dated 24 May, 1853," *ibid.*, *PP*, 1852-53, LXXIII, 91. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 24th May,²⁸ 1853 (p. 1717)." (Cf. No. 103 below.)

101 App. A: 1341 "Extract Political Letter to Bombay, dated 11 May, 1853," *ibid.*, *PP*, 1852-53, LXXIII, 93. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 11th May, 1853 (p. 1719)." (Cf. No. 106 below.)

102 App. A: 1320 "Extract Political Letter to Bombay, dated 26 January, 1853," *ibid.*, *PP*, 1852-53, LXXIII, 185. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 26th Jan., 1853 (p. 1811)." (Cf. No. 96 above and No. 104 below.)

103 App. A: 1328 "Extract Political Letter to Bombay, dated 24 May, 1853," *ibid.*, *PP*, 1852-53, LXXIII, 186. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 24th May, 1853 (p. 1812)." (Cf. No. 100 above.)

104 App. A: 1320 "Extract Political Letter to Bombay, dated 26 January, 1853," *ibid.*, *PP*, 1852-53, LXXIII, 282. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 26th Jan., 1853 (p. 1908)." (Cf. Nos. 96 and 102 above.)

105 App. A: 1324 "Extract Political Letter to Bombay, dated 6 April, 1853," *ibid.*, *PP*, 1852-53, LXXIII, 285. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 6th April, 1853 (p. 1911)." (Cf. Nos. 97, 98, and 99 above.)

106 App. A: 1341 "Extract Political Letter to Bombay, dated 11 May, 1853," *ibid.*, *PP*, 1852-53, LXXIII, 310. JSM: general heading in No. 58 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 11th May, 1853 (p. 1936)." (Cf. No. 101 above.)

107 App. A: 979 "Extract Political Letter to Bombay, dated 2 July, 1840," in "Return of the Subjects of His Highness the Guicowar Now Enjoying the British Guarantee," *PP*, 1852-53, LXIX, 259.²⁹ JSM: general heading: "The following despatches to India, printed in a Return to the House of Commons of papers relating to Baroda Guarantees, forming No. 883 of the papers of the Session of 1852-53." Specifically: "Extract Political Letter to Bombay, dated 2nd July, 1840."

108 App. A: 986 "Extract Political Letter to Bombay, dated 3 March, 1841," *ibid.*, *PP*,

by a date that completes the line. Between the entries for Nos. 94 and 95 there is a line of ditto marks, without a date, concluding with the comment, "(Considerably altered by the B. of Control.)" We have inferred that the copyist erroneously added a line of ditto marks, and that the comment belongs to the previous entry.

²⁸The manuscript reads "20th May".

²⁹Papers were called for in the House by Mr. Bell on 26 May, 1853, and ordered to be printed on 5 Aug., 1853.

1852-53, LXIX, 259-60. JSM: general heading in No. 107 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 3rd March, 1841."

109 App. A: 1000 "Extract Political Letter to Bombay, dated 21 December, 1842," *ibid.*, PP, 1852-53, LXIX, 260. JSM: general heading in No. 107 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 21st Dec., 1842 (much altered)."

110 App. A: 1202 "Extract Political Letter to Bombay, dated 14 March, 1849," *ibid.*, PP, 1852-53, LXIX, 261. JSM: general heading in No. 107 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 14th March, 1849." (Cf. No. 90 above.)

111 App. A: 1215 "Extract Political Letter to Bombay, dated 28 November, 1849," *ibid.*, PP, 1852-53, LXIX, 262. JSM: general heading in No. 107 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 28th Nov., 1849." (Cf. Nos. 55 and 73 above, and No. 132 below.)

112 App. A: 1227 "Extract Political Letter to Bombay, dated 13 February, 1850," *ibid.*, PP, 1852-53, LXIX, 263. JSM: general heading in No. 107 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 13 Feb., 1850." (Cf. No. 56 above and No. 113 below.)

113 App. A: 1227 "Extract Political Letter to Bombay, dated 13 February,³⁰ 1850," *ibid.*, PP, 1852-53, LXIX, 264. JSM: general heading in No. 107 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 13th Feb., 1850." (Cf. Nos. 56 and 112 above.)

114 App. A: 1276 "Extract Political Letter to Bombay, dated 10 September, 1851," *ibid.*, PP, 1852-53, LXIX, 265-6. JSM: general heading in No. 107 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 10th Sept., 1851."

115 App. A: 1286 "Extract Political Letter to Bombay, dated 2 January, 1852,"³¹ *ibid.*, PP, 1852-53, LXIX, 266. JSM: general heading in No. 107 above; specifically: "Extract P[olitical] L[etter] to Bombay, dated 2nd Jan., 1852." (Cf. No. 91 above.)

116 App. A: 1306 "Extract Political Letter to Bombay, dated 15 September, 1852," *ibid.*, PP, 1852-53, LXIX, 266. JSM: general heading in No. 107 above; specifically: "E[xt]ract] Political Letter to Bombay, dated 15th Sept., 1852." (Cf. No. 92 above.)

117 App. A: 1347 "Political Department, 22 June, 1853," *ibid.*, PP, 1852-53, LXIX, 267-8. JSM: general heading in No. 107 above; specifically: "Political Letter to Bombay, dated 22nd June,³² 1853. (Considerably altered by the B[oard] of Control.)"

118 App. A: 675 "The Court of Directors of the East India Company to the Governor-General of India in Council [26 Oct., 1853]," in "General Report of the Administration of the Punjab for the Years 1849-50 and 1850-51," PP, 1854, LXIX, 465-6.³³ JSM: "The Political Letter to India, dated 26th October, 1853, on the affairs of the Punjab, printed by the Court of Directors with the General³⁴ Report on the Administration of the Punjab for 1849-50 and 1850-51."

119 App. A: 271 "Extract Political Letter to India, dated 28 April, 1841," in "Correspondence Respecting the Claim of Mean Oomaid Sing," PP, 1854, XLVII, 177.³⁵ JSM: general heading: "The following despatches to India, printed in a return to the H[ouse] of Commons of papers relating to the chiefship of Bughat, forming No. 188 of the papers of the Session of 1854." Specifically: "Extr[act] P[olitical] L[etter] to India, dated 28th April,³⁶ 1841."

120 App. A: 343 "Extract Political Letter to India, dated 4 October, 1843," *ibid.*, PP, 1854, XLVII, 178. JSM: general heading in No.

³⁰PP and the manuscript give January, but internal evidence makes it clear that the excerpt is from the despatch of 13 February, 1850, also excerpted in Nos. 56 and 112.

³¹MacMinn has 1851 for 1852.

³²The manuscript reads "23rd June".

³³The government routinely printed such reports.

³⁴The manuscript reads "Ground".

³⁵Papers were called for in the House by Isaac Butt on 21 Feb., 1854, and ordered to be printed on 11 Apr., 1854.

³⁶The manuscript reads "20th April".

119 above; specifically: "Extr[act] P[olitical] L[etter] to India, dated 4th October, 1843."

121 App. A: 540 "Our Governor-General of India in Council [21 Nov., 1849]," *ibid.*, PP, 1854, XLVII, 180. JSM: general heading in No. 119 above; specifically: "Political Letter to India, dated 21st Nov., 1849."

122 App. A: 600 "Extract Political Letter to India, dated 19 November, 1851," *ibid.*, PP, 1854, XLVII, 181. JSM: general heading in No. 119 above; specifically: "Extract P[olitical] L[etter] to India, dated 19th Nov., 1851."

123 App. A: 673 "Extract Political Letter to India, dated 21 September, 1853," *ibid.*, PP, 1854, XLVII, 181. JSM: general heading in No. 119 above; specifically: "Extract P[olitical] L[etter] to India, dated 21st Sept., 1853."³⁷

124 App. A: 674 "Political Department, 2 November, 1853," in "Papers Relative to Territory Ceded by the Nizam," PP, 1854, XLVII, 274-5.³⁸ JSM: "The Political Letter to India, dated 2nd November, 1853, on the New Treaty with the Nizam, printed in a return to the H[ouse] of Commons of papers on that subject, forming No. 418 of the papers of the Session of 1854. (Much altered by Board of Control.)"

125 App. A: 638 "Political Department, 26 January, 1853," in "Papers Relating to the Annexation of Kerowlee," PP, 1854-55, XL, 87-8.³⁹ JSM: "The political letter to India, dated 26th January, 1853, on the succession to the state of Kerowla, printed in a return to the H[ouse] of Commons of papers on that subject, forming No. 455 of the papers of the session of 1855."

126 App. A: 716 "Extract Political Letter to India, dated 15 November, 1854," in "Copies or Extracts of the Correspondence Which Has Taken Place between the Government of India

and the Commissioner of Nagpore. Relative to the Annexation of the Berar Territory to the British Territory (in Continuation of Former Returns)," PP, 1856, XLV, 41.⁴⁰ JSM: "The Extracts of Despatches to India contained in a return to the H[ouse] of Commons respecting the annexation of Berar,⁴¹ forming No. 82 of the papers of the Session of 1856."⁴²

127 App. A: 739 "Extract Political Letter to India, dated 20 February, 1856," *ibid.*, PP, 1856, XLV, 42. JSM: general heading in No. 126 above; no specific heading.

128 App. A: 734 "Extract Political Letter to India, dated 30 January, 1856," *ibid.*, PP, 1856, XLV, 43. JSM: general heading in No. 126 above; no specific heading.

129 App. A: 732 "The Court of Directors of the East India Company to the Governor-General of India in Council [21 Nov., 1855]," in "Papers Relating to Oude," PP, 1856, XLV, 579-82.⁴³ JSM: "The Political Despatch to India on Oude affairs forming pp. 233 to 236 of the Oude papers presented to Parliament in 1856."

130 App. A: 770 "The Court of Directors of the East India Company to the Governor-General of India in Council [8 July, 1857]," in "Papers Relating to the Mutinies," PP, 1857, Sess. II, XXX, 12-13.⁴⁴ JSM: "The Political Despatch to India on the Bengal Mutinies, dated July 8, 1857, forming pp. 10, 11 of the first Mutiny papers presented to Parliament in 1857."

131 App. A: 514 "Extract Political Letter from the Court of Directors to the Government of India, dated 18th April, 1849," in "Copies or Orders of the Indian Government Respecting the Amount and Conditions of the Allowances to Be Made to the Deposed Rajah of Coorg," *Sessional Papers of the House of Lords*, 1857, Sess. 1.

³⁷The manuscript reads "1843".

³⁸Papers were called for in the House by Joseph Hume on 6 Apr., 1854, and ordered to be printed on 26 July, 1854.

³⁹Papers were called for in the House by Erskine Perry on 23 July, 1855.

⁴⁰Papers were called for in the House by Mr. Otway on 25 Feb., 1856, and ordered to be printed on 5 Mar., 1856.

⁴¹The manuscript reads "Bevar".

⁴²MacMinn reads "1858".

⁴³Papers were presented by the government on 19 May, 1856, following discussion in both Houses of the affairs of Oude.

⁴⁴Papers were presented by the government, beginning on 14 July, 1857, in response to intense discussion in both Houses about the Mutiny.

VIII, 303-4.⁴⁵ JSM: "The Extract of Political Despatch to India on the Ex Rajah of Coorg,⁴⁶ dated 18th April, 1849, at p. 3 of the Coorg⁴⁷ papers forming No. 39 of the Lords papers of the Session of 1857."

132 App. A: 1215 "Extract, Paras. 79-81, from a Letter from the Honourable the Court of Directors, dated 28 November, 1849," in

"Correspondence on the Dismissal of Murza Ali Akbar," *PP*, 1857-58, XLIII, 209-10.⁴⁸ JSM: "The Extract of Political Letter to Bombay, dated 28th Nov., 1849, at pp. 3-4 of papers on the case of Mirza Ali Akbar⁴⁹ forming No. 159 of the Commons papers of the Session of 1858." (Cf. Nos. 55, 73, and 111 above.)

⁴⁵The treatment of the Rajah had been questioned in the House of Lords on 21 July, 1856; the government delivered the relevant papers on 5 Mar., 1857.

⁴⁶The manuscript reads "Cervy".

⁴⁷The manuscript reads "Cory".

⁴⁸Papers requested by De Lacy Evans were presented by the government on 24 Mar., 1858.

⁴⁹The manuscript reads "Alebar".

Appendix C

Editorial Emendations

IN THIS LIST, following the page and line numbers, the reading of the copy-text is given first, and then the amended reading in square brackets, with an explanation if required. If there is no explanation, it may be assumed that there is an obvious typographical error, or else that the change is made for sense or for consistency within the item.

- 23.2 chap. [chaps.]
- 27.4 suicide [such suicide] [*as in Source*]
- 30.4 Penal Code [penal code] [*as elsewhere*]
- 35.13 were [was] [*for sense*]
- 35.22 Was [Were] [*for sense*]
- 43.13 proposed [a proposed]
- 49.34 provided for it within [provided within] [*for sense*]
- 54.38 in [of]
- 55.35-6 Governor-governor [Governor-general]
- 56.13 Board of Control [Court of Directors] [*for sense*]
- 58.33 unwillingness [unwillingness]
- 63.12 Laurence [Lawrence] [*as in fact*]
- 79.10 her [Her] [*as elsewhere*]
- 81.4 changes [change] [*as in D, PD*]
- 82.23 principle [principle]
- 82.35-6 home government [Home Government]
- 83.10 capital; [capital,] [*as in D*]
- 88.16-17 home government [Home Government]
- 88.19 home [Home] [*as in D, PD, and elsewhere*]
- 88.38 Boardan [Board an]
- 106.1 to, individuals [to individuals]
- 107.27 enouragement [encouragement]
- 112.1 Her [her] [*as elsewhere*]
- 112.21 presidencies [Presidencies] [*as elsewhere*]
- 115.19 Non-regulation [Non-Regulation] [*as elsewhere*]
- 116.27 averages [averaged] [*as in Source*]
- 118.4 clerks [clerks]
- 130.5 annnm [annum]
- 159.24 land [lands] [*as in Source*]
- 209.7 him, while [him. While] [*corrected by JSM in SC copy; not adopted in PP*]
- 209.13 objections, and [objections; and] [*corrected by JSM in SC copy; PP reads objections. And*]
- 209.16 proceedings [proceedings.] [*corrected by JSM in SC copy; adopted in PP*]

- 209.34 Administration [Administration,] [*corrected by JSM in SC copy; not adopted in PP*]
- 210.3 calamities [calamities,] [*corrected by JSM in SC copy; not adopted in PP*]
- 210.17 voice [voice,] [*corrected by JSM in SC copy; not adopted in PP*]
- 211.9 want, [want;] [*corrected by JSM in SC copy; adopted in PP*]
- 211.10 themselves, [themselves;] [*corrected by JSM in SC copy; adopted in PP*]
- 211.15 selecting. Not [selecting; not] [*as in PP*]
- 211.30 Government [Government,] [*corrected by JSM in SC copy; adopted in PP*]
- 211.31 India, [India;] [*corrected by JSM in SC copy; adopted in PP*]
- 211.36 resources [resources,] [*corrected by JSM in SC copy; adopted in PP*]
- 212.2 being [being,] [*corrected by JSM in SC copy; not adopted in PP*]
- 212.2 made. But [made; but] [*as in PP*]
- 212.19 to [to,] [*corrected by JSM in SC copy; adopted in PP*]
- 214.6 *Village Communities* [*Village-Communities*]
- 217.34 'men [oxen] [*as in Source*]
- 219.30 people, [people] [*as in MS; printer's misreading of interlineation?*]
- 220n.2 T.E. [Thomas Edward Cliffe]
- 220.34 a hundred in Warwickshire [100 in Oxfordshire; about 50,000 acres in Warwickshire] [*as in Source*]
- 221.2 meadows" "are [meadows . . . are]
- 227.12 149-51 [166-8] [*printer's error; reference repeated from previous quotation*]

Appendix D

Index of Persons, and Works Cited, with Variants and Notes

LIKE MOST NINETEENTH-CENTURY AUTHORS, Mill is cavalier in his approach to sources, sometimes identifying them with insufficient care, and occasionally quoting them inaccurately. This Appendix is intended to help correct these deficiencies, and to serve as an index of names and titles (which are consequently omitted in the Index proper). Included here also are (at the end of the appendix and listed chronologically) references to official documents and to statute laws. The material otherwise is arranged in alphabetical order, with an entry for each person or work reviewed, quoted, or referred to. JSM's spelling of Indian names is generally used. Anonymous articles in *The Times* are entered in order of date under that newspaper. References to mythical and fictional characters are excluded. The following abbreviations are used: *DBF* (*Dictionnaire de biographie française*), *DIB* (*Dictionary of Indian Biography*), *DNB* (*Dictionary of National Biography*), *EB* (*Encyclopaedia Britannica*, 11th ed.), *GDU* (Larousse, *Grand dictionnaire universel du XIXe siècle*), *MEB* (Boase, *Modern English Biography*), *PD* (*Parliamentary Debates*), *PP* (*Parliamentary Papers*), *SC* (JSM's library, Somerville College, Oxford), *WWBMP* (*Who's Who of British Members of Parliament*).

The entries take the following form:

1. Identification of persons: birth and death dates are followed by a source of further biographical information; if there is no readily accessible source, available details not apparent from the text are given in a note.

2. Identification of works: author, title, etc. in the usual bibliographic form.

3. Notes (if required) giving information about JSM's use of the source, indication if the work is in his library, Somerville College, Oxford, and any other relevant information.

4. Lists of the pages where works are reviewed, quoted, and referred to.

5. In the case of quotations, a list of substantive variants between JSM's text and his source, in this form: Page and line reference to the present text. Reading in the present text | Reading in the source (page reference in the source).

The list of substantive variants also attempts to place quoted passages in their contexts by giving the beginnings and endings of sentences. The original wording is supplied where JSM has omitted two sentences or less; only the length of other omissions is given.

AHMAD ALI (Nawab of Rampore) (d. 1840). Referred to: 64

AITCHISON, CHARLES UMPHERSTON (1832-96). *A Collection of Treaties, Engagements, and Sunnuds, Relating to India and Neighbouring Countries*. 8 vols. Calcutta: printed Savielle and Cranenburgh, 1862-65.

NOTE: this ed. used for ease of reference.

REFERRED TO: 152

ANDERSON, GEORGE WILLIAM (1791-1857; *DNB*). Referred to: 20-3 *passim*, 28, 29, 30, 69, 116, 124

AUSTIN, JOHN (1790-1859; *DNB*). Referred to: 227

BAKER, WILLIAM ERSKINE (1808-81).

NOTE: in Bengal Engineers, 1826-77: Assistant on W. Jumna Canal 1829-36, Superintendent of Delhi Canals 1836-45, Director of Ganges Canal Works, 1845-48.

REFERRED TO: 127

BANNI SINGH, MAHARAO RAJA (Rao of Ulwur) (d. 1857). Referred to: 152-3

BARNEWALL, ROBERT (d. 1848). Referred to: 63

BENTHAM, JEREMY (1748-1832; *DNB*). Referred to: 21, 28, 227

——— *Letter to Lord Granville on the Proposed Reform in the Administration of Civil Justice in Scotland* (1807). In *Works*. Ed. John Bowring. 11 vols. Edinburgh: Tait, 1843, V, 1-53.

NOTE: in SC.

REFERRED TO: 84, 181

——— *The Rationale of Judicial Evidence, Specially Applied to English Practice*. Ed. J.S. Mill. 5 vols. London: Hunt and Clarke, 1827.

NOTE: in SC. In *Works*, VI-VII.

REFERRED TO: 21

BENTINCK, WILLIAM CAVENDISH (Lord) (1774-1839; *DNB*). Referred to: 112, 113, 123

BETHUNE, JOHN ELLIOT DRINKWATER (1801-51; *DNB*). Referred to: 148

BIRD, ROBERT MERTTINS (1788-1853; *DNB*).

NOTE: JSM uses the spelling Mertens.

REFERRED TO: 98

BIRD, WILLIAM WILBERFORCE (d. 1857; *DIB*). Referred to: 34, 35

——— Evidence in "Report of the Select Committee of the House of Lords, Appointed to Inquire into the Operation of the Act 3 & 4 William IV, . . . Together with the Minutes of Evidence, and an Appendix and Index Thereto," *PP*, 1852-53, XXX, 95-124.

REFERRED TO: 51

BLACK ACT. See "Act No. XI of 1836," *PP*, 1840, XXXVII.

BRIGHT, JOHN (1811-89; *DNB*). Question on the Confiscation of Land in Oude (6 May, 1858; Commons), *PD*, 3rd ser., Vol. 150, col. 181.

REFERRED TO: 197

CAMERON, CHARLES HAY (1795-1880; *DNB*). Referred to: 20-3 *passim*, 28, 29, 30, 69, 116, 124

CAMPBELL, COLIN (Baron Clyde) (1792-1863; *DNB*). Referred to: 196

CANNING, CHARLES JOHN (Viscount, later Earl) (1812-62; *DNB*). Referred to: 120, 195, 196, 197, 198

CARNAC, JAMES RIVETT (1785-1846; *DNB*). Referred to: 34, 35

CAUTLEY, PROBY THOMAS (1802-71; *DNB*). Referred to: 127

CLERK, GEORGE RUSSELL (1800-89; *DIB*). Referred to: 118

CLEVELAND, AUGUSTUS (1755-84; *DNB*). Referred to: 153

COLVIN, BINNEY JAMES (b. 1809). Referred to: 156

- COLVIN, JOHN (1794-1871). Referred to: 127
- COLVIN, JOHN RUSSELL (1807-57; *DNB*). Referred to: 115, 118
- "Report on the Administration of Public Affairs in the North-Western Provinces"
 In *General Report on the Administration of the Several Presidencies and Provinces of British India during the Year 1855-56*, Pt. I. Calcutta: Calcutta Gazette Office, 1857.
 QUOTED: 115, 127
 127.26 "presents] 268. The Canal itself, with its subordinate and terminal branches, extending to a length of nearly 800 miles, with upwards of 1250 miles of distributing Channels, many of which, from their size, deserve the name of Canals, presents (83)
- CONGREVE, RICHARD (1818-99; *DNB*). *India*. London: Chapman, 1857.
 REFERRED TO: 83
- CORNWALLIS, CHARLES (Marquis and Earl) (1738-1805; *DNB*). Referred to: 95, 97, 100, 104, 108, 111, 112
- COTTON, ARTHUR THOMAS (1803-99; *DNB*). Referred to: 130
- Extracts from the Report on the Godavery Anicut (17 Apr., 1845), *PP*, 1852-53, LXIX, 234-40.
 REFERRED TO: 130
- COTTON, FREDERIC CONYERS (1807-1901).
 NOTE: engineer and Commissioner of Public Works at Madras
 REFERRED TO: 130
- COTTON, JOHN (1784-1860; *MEB*). Referred to: 35
- DALHOUSIE, MARCHIONESS OF. See Susan Georgiana Ramsay.
- DALHOUSIE, MARQUIS OF. See James Ramsay.
- DESSULJEE, MAHARAJA MIZRA (Rao of Kutch) (1815-60). Referred to: 152
- DISRAELI, BENJAMIN (1804-81; *DNB*). Referred to: 203
- Speech on the Government of India (No. 2) Bill (26 Mar., 1858; Commons), *PD*, 3rd ser., Vol. 149, cols. 818-33.
 REFERRED TO: 163, 164, 181
- DIXON, CHARLES GEORGE (1795-1857).
 NOTE: colonel in the East India Company's army, appointed to the civil charge of Mhairwarra in 1835, and Commissioner of Ajmere 1853.
 REFERRED TO: 131, 153
- DOMAT, JEAN (1625-96; *DBF*). *Oeuvres de J. Domat . . . édition revue, corrigée et augmentée d'une table . . . de concordance entre les articles de nos codes et les passages de Domat qui s'y rapportent*. 9 vols. Paris: Kleffer, and Tenré, 1821-25.
 REFERRED TO: 19
- DUNDAS, HENRY (Viscount Melville) (1742-1811; *DNB*). Referred to: 38
- EDEN, GEORGE (Earl of Auckland) (1784-1849; *DNB*). Referred to: 22, 35
- ELLENBOROUGH, LORD. See Edward Law.
- ELLIOTT, WILLIAM HENRY (1811-70). Quoted: 156
- ELPHINSTONE, JOHN (Baron) (1807-60; *DNB*). Referred to: 144
- ELPHINSTONE, MOUNTSTUART (1779-1859; *DNB*). Referred to: 112-13
- FIEVÉE, JOSEPH (1767-1839; *DBF*). *Correspondance politique et administrative*. 3 vols. Paris: Le Normant, 1815-19.
 REFERRED TO: 176

FITZROY, HENRY (1807-59; *WWBMP*). Speech on the Government of India Bill (17 June, 1858), *PD*, 3rd ser., Vol. 150, cols. 2253-4.

REFERRED TO: 203

FORBES, CHARLES (1774-1849; *DNB*). Referred to: 40

FORBES, JOHN (1801-40; *MEB*). Referred to: 35, 40

FORLONG, JAMES GEORGE RORKE (1824-1904; *DIB*). Referred to: 133

FORTUNE, ROBERT (1813-80; *DNB*). Referred to: 150

FYZOOLA KHAN (d. 1794). Referred to: 64

GILPIN, BERNARD (1517-83; *DNB*). "A Sermon" (1552). In George Carleton, *The Life of Bernard Gilpin*. London: W.I. and T.P., 1636, 209-335.

NOTE: the quotation is in a quotation from T.E. Cliffe Leslie, *q.v.*

QUOTED: 220

GRANT, JOHN PETER (1807-93; *DNB*). Referred to: 120

GREENLAW, CHARLES BECKETT (1784-1844). Referred to: 62

HALL, HENRY (1789-1875; *DIB*). Referred to: 153

HALLIDAY, FREDERICK JAMES (1806-1901; *DNB*). Referred to: 120

HARRIS, GEORGE FRANCIS (1810-72; *DNB*). Referred to: 103

HASTINGS, FRANCIS RAWDON- (Marquis of, previously Earl of Moira) (1754-1826; *DNB*).
Referred to: 101

———"Minute by the Right Hon. the Governor-General on the Revenue Administration of the Presidency of Fort William, dated the 21st September 1815," Appendix 9 in *Minutes of Evidence Taken before the Select Committee of the House of Commons on the Affairs of the East India Company, III: Revenue, PP*, 1831-32, XI, 433-57.

REFERRED TO: 95, 223

HASTINGS, WARREN (1732-1818; *DNB*). Referred to: 64, 69

HOLKAR II, TAKOJI RAO (Maharaja of Indore) (1832-86; *DIB*). Referred to: 152

HUSKISSON, WILLIAM (1770-1830; *DNB*). Referred to: 4, 9

——— Speech on Trade with India, *The Times*, 16 May, 1827, 2.

QUOTED: 4, 5, 6

5.8-9 "experiments . . . progress,"] If he might be allowed to advise his friend, he would recommend him to wait until the results of those experiments, which . . . progress, had become apparent. (2)

5.11-12 "excite . . . alarms," . . . "earnest . . . allay.]" To bring this question now would be to excite . . . alarms which it was his earnest . . . allay; and for that reason, and not because he disliked the principles of his hon. friend, he felt obliged to object to the appointment of this committee. (2)

6.11 "no tonnage, or . . . description]" These ports were now as free and as open as possible, no tonnage or . . . description being demanded. (2)

6.14-16 great . . . he had recommended.]" With respect to another part of the speech of his honourable friend,—he meant that part in which he alluded to the cheering prospect which the number of islands in the Indian sea held out to him of a great extension of commerce,—he had to state, and with great . . . he (Mr. Huskisson) had recommended, that Singapore and other great *emporia* were included in those regulations which the East India Company had consented to adopt. (2)

JACOB, JOHN (1812-58; *DNB*). Referred to: 154

- LAW, EDWARD (Earl of Ellenborough) (1790-1871; *DNB*). Referred to: 72, 166, 195-6, 196-7
- Speech on the Government of India (29 Apr., 1858; Lords), *PD*, 3rd ser., Vol. 149, cols. 1962-8.
- REFERRED TO: 203
- LAWRENCE, HENRY MONTGOMERY (1806-57; *DNB*). Referred to: 63
- LAWRENCE, JOHN LAIRD MAIR (Baron) (1811-79; *DNB*). Referred to: 115-16
- "Report on the Administration of Public Affairs in the Punjab Territories." In *General Report on the Administration of the Several Presidencies and Provinces of British India during the Year 1855-56*, Pt. II. Calcutta: Calcutta Gazette Office, 1857.
- QUOTED: 115-16
- 116.12 But] 6. But (4)
- 116.16 district, and] District. And (4)
- 116.18 the information] information (4)
- 116.21-2 relief. [paragraph In] relief. [1 1/2-page omission] [paragraph] 9 In (4-5)
- 116.28 1855. As] 1855. These averages are unusually low; but the scale of stamps is light, there are usually no charges for professional advice, there being as yet no Native Bar; and the expense of summoning witnesses and others is strictly regulated by the Court. As (5)
- LESLIE, THOMAS EDWARD CLIFFE (1827-82; *DNB*). *Land Systems and Industrial Economy of Ireland, England, and Continental Countries*. London: Longmans, Green, 1870.
- QUOTED: 220
- REFERRED TO: 220
- 220.5 "got] Sir Thomas More declared that tenants were got (216)
- 220.5 force or fraud] *force or fraud* (216)
- 220.6 "complained] Bishop Gilpin complained (216)
- LOWE, ROBERT (1811-92; *DNB*). Speech on Lighthouses (15 Apr., 1858; Commons), *PD*, 3rd ser., Vol. 149, cols. 1130-1.
- QUOTED: 177
- 177.5 "double government"] He (Mr. Lowe) believed that the expense was mainly owing to the double government of the Board of Trade and the Trinity House. (1130)
- MACAULAY, THOMAS BABINGTON (1800-59; *DNB*). Referred to: 20-3 *passim*, 28, 29, 30, 69, 116, 124
- MACLEOD, JOHN (1792-1881; *DNB*). Referred to: 20-3 *passim*, 28, 29, 30, 69, 116, 124
- MACPHERSON, SAMUEL CHARTERS (1806-60; *DNB*). Referred to: 154
- MAINE, HENRY JAMES SUMNER (1822-88; *DNB*). Referred to: 215, 227
- *Ancient Law: Its Connection with the Early History of Society, and Its Relation to Modern Ideas*. London: Murray, 1861.
- NOTE: in SC.
- REFERRED TO: 215
- *Village-Communities in the East and West. Six Lectures Delivered at Oxford*. London: Murray, 1871.
- REVIEWED: 213-28
- QUOTED: 216, 216-17, 217, 217-18, 218-19, 220, 221, 225n, 226, 226-7, 227, 228
- 216.19-20 "the . . . thought"] Every man is under a temptation to overrate the importance of the subjects which have more than others occupied his own mind, but it certainly seems to me that two kinds of knowledge are indispensable, if the study of historical and philosophical jurisprudence is to be carried very far in England, knowledge of India, and knowledge of Roman law—of India, because it is the . . . thought—of Roman law, because, viewed in the whole course of its development, it connects these ancient usages and this ancient juridical thought with the legal ideas of our own day. (22)

- 216.21-2 "the . . . jurisprudence" [*see collation for 216.19-20*]
- 216.24-7 "large . . . literature" . . . "the oral . . . office." These materials are partly to be found in that large . . . literature which I described as having grown out of the labours of the functionaries who adjust the share of the profits of cultivation claimed by the British Government as supreme landlord; but much which is essential to a clear understanding can only be at present collected from the oral . . . office. (61)
- 217.17 "a] It is a (79)
- 217.22 "seems] It seems (79)
- 217.25 "was] The evidence appears to me to establish that the Arable Mark of the Teutonic village community was (81)
- 217.29 years. . . Each] years. [*paragraph*] The fields under tillage were not however cultivated by labour in common. Each (80)
- 217.36 "that] It also seems to show that (81)
- 217.42 "there . . . race"] But there . . . race in which traces do not remain of the ancient periodical redistribution. (82)
- 217.44-218.1 "the . . . writers, among . . . eminent"] The . . . writers, however, among . . . eminent, appears to me to have successfully generalised and completed the explanation given in respect of our country by English historical scholars, by showing that the primitive Teutonic proprietary system had everywhere a tendency, not produced from without, to modify itself in the direction of feudalism; so that influences partly of administrative origin and (so far as the Continent is concerned) partly traceable to Roman law may, so to speak, have been met half-way. (21)
- 220.21-2 Yorkshire." . . . "extensive] Yorkshire, there are extensive (88)
- 220.23 89" . . . "more] 89 are in this condition; more (89)
- 220.23-4 a hundred in Warwickshire] 100 in Oxfordshire; about 50,000 acres in Warwickshire (89) [*treated as printer's error in this ed.*]
- 220.28 was] were (89)
- 221.3 personally," . . . "I] personally, I (88)
- 221.6 notice."] notice; nor can I doubt that a hundred and fifty years ago instances of such rights could have been produced in vastly greater numbers, since Private Acts of Parliament for the inclosure of commonable fields were constantly passed in the latter part of the last and the earlier part of the present century, and since 1836 they have been extensively enclosed, agglomerated, and exchanged under the Common Fields Inclosure Act passed in that year, and under the general powers more recently vested in the Inclosure Commissioners. (88)
- 225n.5 Government" early "began] Government began (105)
- 225n.8-9 Madras," . . . "has . . . opinion," . . . "been] Madras, has . . . opinion, been (105-6)
- 226.21 decay. . . Do] decay. I will not ask you to remember the technical names of the various classes of persons 'settled with' in different parts of India—Zemindars, Talukdars, Lumberdars—names which doubtless sound uncouth, and which, in fact, have not an identical meaning throughout the country—but I dwell on the fact that the various interests in the soil which these names symbolize are seen to grow at the expense of all others. Do (150)
- 227.5 opinion is] opinion (which I shall state more at length in the next Lecture) is (167)
- 227.19 "when] It is found, however, that when (151)

MARSHALL, WILLIAM (1745-1818; *DNB*). *A Review (and Complete Abstract) of the Reports to the Board of Agriculture from the Midland Department of England*. York: Longman, et al., 1815.

NOTE: the reference derives from Nasse, *q.v.*

REFERRED TO: 220

——— *A Review (and Complete Abstract) of the Reports to the Board of Agriculture from the Southern and Peninsular Departments of England*. York: Longman, et al., 1815.

NOTE: the reference derives from Nasse, *q.v.*

REFERRED TO: 220

MARTINEAU, HARRIET (1802-76; *DNB*). *Suggestions towards the Future Government of India*. London: Smith, Elder, 1858.

REFERRED TO: 83

MAURER, GEORG LUDWIG VON (1790-1872; *EB*). *Geschichte der Dorfverfassung in Deutschland*. Erlangen: Enke, 1865-66.

NOTE: the reference is in a quotation from Maine, *Village-Communities*.

REFERRED TO: 216, 217-18

——— *Geschichte der Fronhöfe, der Bauernhöfe und der Hofverfassung in Deutschland*. 4 pts. Erlangen: Enke, 1862-63.

NOTE: the reference is in a quotation from Maine, *Village-Communities*.

REFERRED TO: 216, 217-18

——— *Geschichte der Markenverfassung in Deutschland*. Erlangen: Enke, 1856.

NOTE: the reference is in a quotation from Maine, *Village-Communities*.

REFERRED TO: 216, 217-18

MELVILL, JAMES COSMO (1792-1861; *DIB*). Evidence in "Report of the Select Committee of the House of Lords, Appointed to Inquire into the Operation of the Act 3 & 4 William IV, c. 85, . . . Together with the Minutes of Evidence, and an Appendix and Index Thereto," *PP*, 1852-53, XXX, 7-72.

REFERRED TO: 51

MELVILLE, LORD. See Henry Dundas.

MILL, JAMES (1773-1836; *DNB*). See, under Official Documents, "Dispatch Accompanying the Government of India Act, 1833" (10 Dec., 1834).

MILL, JOHN STUART (1806-73; *DNB*). "The Petition of the East-India Company." In *Memorandum of the Improvements in the Administration of India during the Last Thirty Years, and the Petition of the East-India Company to Parliament*. London: Cox and Wyman, 1858.

NOTE: 75-89 above.

REFERRED TO: 207

——— *Report to the General Court of Proprietors, Drawing Attention to the Two Bills Now before Parliament Relating to the Government of India*. London: Cox and Wyman, 1858.

NOTE: 161-71 above.

REFERRED TO: 207

MILLETT, FREDERICK (d. 1856; *DIB*). Referred to: 20-3 *passim*, 28, 29, 30, 69, 116, 124

MORE, THOMAS (1478-1535; *DNB*). *Utopia*. Trans. Ralph Robinson. London: Vele, 1551.

NOTE: the quotation is in a quotation from T.E. Cliffe Leslie, *Land Systems, q.v.* A Latin ed. (Glasgow, 1750) is in SC.

QUOTED: 220

MUHAMMAD SAIYID KHAN (Nawab of Rampore) (d. 1855; *DIB*). Referred to: 64-5, 152

MUNRO, THOMAS (1761-1827; *DNB*). Referred to: 63, 97, 101, 144

NASSE, ERWIN (1829-90). *Ueber die mittelalterliche Feldgemeinschaft und die Einhegungen des sechszehnten Jahrhunderts in England*. Bonn: Marcus, 1869.

NOTE: the reference at 218 is prospective, to the English ed.; the quotation at 220 is in a quotation from Maine, *Village-Communities*. Nasse's book appeared in English as *On the Agricultural Community of the Middle Ages, and Inclosures of the Sixteenth Century in England*, trans. H.A. Ouvry (London: Macmillan, 1871).

QUOTED: 220

REFERRED TO: 216, 217-18, 218

NEWMAN, FRANCIS WILLIAM (1805-97; *DNB*). "English Policy in India" (letter to the editor), *The Times*, 3 Dec., 1857, 5.

REFERRED TO: 83

OUTRAM, JAMES (1803-63; *DNB*). Referred to: 153, 154

OVANS, CHARLES (ca. 1793-1858; *MEB*). Referred to: 34, 35, 153

PALMERSTON, LORD. See Henry John Temple.

A Penal Code; Prepared by the Indian Law Commissioners. . . . See, under Official Documents, *PP*, 1837-38, XLI, 463-588.

PITT, WILLIAM (the younger) (1759-1806; *DNB*). Referred to: 56

POTHIER, ROBERT JOSEPH (1699-1772). *Oeuvres*. New ed. 13 vols. Paris: Beaucé, 1817-20.

REFERRED TO: 19

POTTINGER, HENRY (1789-1856; *DNB*). Referred to: 63

PRATAP SINGH (Rajah of Sattara) (d. 1847). Referred to: 34

RAMSAY, JAMES ANDREW BROWN (Marquis of Dalhousie) (1812-60; *DNB*). Referred to: 100, 148, 204, 209

RAMSAY, SUSAN GEORGIANA (Marchioness of Dalhousie) (1817-53). Referred to: 148

READ, ALEXANDER (d. 1804).

NOTE: JSM spells the name Reade.

REFERRED TO: 97

ROBERTSON, ARCHIBALD (d. 1847; *DNB*). Referred to: 63

ROBERTSON, THOMAS CAMPBELL (1789-1863; *DIB*). Referred to: 34, 35

ROSS, CHARLES (1799-1860; *MEB*). Speech on Trade with India (15 May, 1827; Commons), *PD*, 2nd ser., Vol. 17, col. 836.

REFERRED TO: 5

ROYLE, JOHN FORBES (1799-1858; *DNB*). Referred to: 149

——— *The Fibrous Plants of India, Fitted for Cordage, Clothing, and Paper; with an Account of the Cultivation and Preparation of Flax, Hemp, and Their Substitutes*. London: Smith, Elder, 1855.

REFERRED TO: 149-50

——— *On the Culture and Commerce of Cotton in India and Elsewhere; with an Account of the Experiments Made by the Hon. East India Company up to the Present Time*. London: Smith, Elder, 1851.

REFERRED TO: 149

——— *Review of the Measures Which Have Been Adopted in India for the Improved Culture of Cotton*. London: Smith, Elder, 1857.

REFERRED TO: 149

RUSSELL, JOHN (Lord, later Earl Russell) (1792-1878; *DNB*). Referred to: 28

——— Speech on the Government of India (No. 3) Bill (26 Apr., 1858; Commons), *PD*, 3rd ser., Vol. 149, cols. 1695-1701.

REFERRED TO: 181

RYAN, EDWARD (1793-1875; *DNB*). Referred to: 14

SAMUELLS, EDWARD ALEXANDER (1813-60). Referred to: 156

SARUP SINGH (Maharana of Odeypore) (d. 1861). Referred to: 123

SHEPHERD, JOHN (d. 1859; *MEB*). Referred to: 35

SINDIA, JIAJI RAO (Maharaja of Gwalior) (1835-86; *DIB*). Referred to: 152

SING, GOPAL. Referred to: 148

- SMITH, RICHARD BAIRD (1818-61; *DIB*). Referred to: 128
 ——— *Revenue Reports of the Ganges Canal for the Year 1855-56*. Roorkee: Thomason College Press, 1856.
 REFERRED TO: 128
- SMITH, WILLIAM (1756-1835; *DNB*). Speech on Trade with India (15 May, 1827; Commons), *PD*, 2nd ser., Vol. 17, cols. 836-8.
 REFERRED TO: 3
- STANLEY, EDWARD GEORGE GEOFFREY SMITH (14th Earl of Derby) (1799-1869; *DNB*). Referred to: 163, 181, 197-8
- STANLEY, EDWARD HENRY (15th Earl of Derby) (1826-93; *DNB*). Referred to: 203, 207, 208, 212
 ——— Speech on the Government of India (7 June, 1858; Commons), *PD*, 3rd ser., Vol. 150, cols. 1673-8.
 REFERRED TO: 208
 ——— Speech on the Government of India Bill (24 June, 1858; Commons), *PD*, 3rd ser., Vol. 151, cols. 315-30.
 REFERRED TO: 203
- TEMPLE, HENRY JOHN (Lord Palmerston) (1784-1865; *DNB*). Referred to: 84
 ——— Leave to Introduce a Bill on the Government of India (12 Feb., 1858), *PD*, 3rd ser., Vol. 148, cols. 1276-1304.
 NOTE: the references at 87 and 88 are to the objections raised concerning India's "double government."
 REFERRED TO: 84, 87, 88, 163, 164, 181, 203
- THOMASON, JAMES (1804-53; *DNB*). Referred to: 65-6, 142, 143
The Times.
 NOTE: anonymous articles follow in chronological order.
 ——— Leading article on the Criminal Code for India, 2 Apr., 1838, 4.
 REFERRED TO: 30
 ——— Letter to the Editor, 4 Apr., 1838, 5.
 REFERRED TO: 30
 ——— "Mr. T.B. Macaulay," 6 Apr., 1838, 3; rpt. from *Englishman* (Calcutta), 13 Jan., 1838.
 REFERRED TO: 30
 ——— "Indian Home Government" (letter; signed "Hadjee"), 31 Dec., 1857, 9.
 REFERRED TO: 83
 ——— "The Government of India" (letter; signed "Indolphilus"), 21 Jan., 1858, 10.
 REFERRED TO: 83
- TOCQUEVILLE, ALEXIS CLÉREL DE (1805-59; *GDU*) *De la démocratie en Amérique*. 2nd ed. 2 vols. Paris: Gosselin, 1835.
 NOTE: in SC.
 REFERRED TO: 176
- TUCKER, HENRY ST. GEORGE (1771-1851; *DNB*). Referred to: 35
- WARD, HENRY GEORGE (1797-1860; *DNB*). Speech on East India Policy (22 Mar., 1838; Commons), *PD*, 3rd ser., Vol. 41, cols. 1134-45.
 REFERRED TO: 30
- WELLESLEY, RICHARD COLLEY (Marquess) (1760-1842; *DNB*). Referred to: 56, 98, 204, 209

WENTWORTH-FITZWILLIAM, CHARLES (Lord Milton, later Earl Fitzwilliam) (1786-1857; *DNB*). "Speech on Trade with India," *The Times*, 16 May, 1827, 2.

QUOTED: 5

5.2 leave . . . to Government,"] Under all the circumstances, he thought it would be better to leave . . . to the Government,—the Government entertaining, as he firmly believed, sound and wholesome views on the subject,—rather than to appoint a committee, in which they would have witnesses stating one thing on one side, and others contradicting them on another. (2)

WHITMORE, WILLIAM WOLRYCHE (1787-1858; *MEB*). Motion for a Committee to Inquire into the Trade between Great Britain and India (15 May, 1827; Commons), *PD*, 2nd ser., Vol. 17, cols. 814-15. Reported in *Morning Chronicle*, 16 May, 1827, 2, which, though probably not Mill's real source, has been used for the collation.

NOTE: the quotations at 3 and 6 are identical.

QUOTED: 3, 4, 6

REFERRED TO: 3-4

3.8, 6.10 "emporia in the Eastern Archipelago."] Another subject to which he wished to direct the attention of a committee, if he succeeded in procuring its appointment, was the state of what one called the *emporia* for our India trade. (2)

4.1-4 "The Company secured . . . the right of preemption. Their resident . . . the Company."] The Company derived some of their most considerable benefits from what was called the right of pre-emption. The Company had commercial residents at each of the ports and settlements where free trade was carried on. These residents made advances to the factors who purchased the productions of this country, and by that means contrived so to keep them in dependence as to confine the whole trade, or nearly the whole trade, to the ships of the company. (2)

WILLOUGHBY, JOHN POLLARD (1798-1866; *DIB*). Referred to: 153

WYNN, CHARLES WATKIN WILLIAMS (1775-1850; *DNB*). Speech on the East-India Company's Charter (13 June, 1833; Commons), *PD*, 3rd ser., Vol. 18, cols. 741-51.
REFERRED TO: 41-2

YULE, HENRY (1820-89).

NOTE: assistant engineer on the Western Jumna canal 1843-45, and executive engineer on the Ganges canal 1846-54.

REFERRED TO: 127

OFFICIAL DOCUMENTS

"Reports from the Select Committee on the Affairs of the East India Company," *PP*, 1808, III, 149-230; 1810, V, 1-353; 1810-11, VII, 1-363; 1812, VI, 1-382; 1812, VII.

REFERRED TO: 77-8

"Minute of Sir Thomas Munro, Governor of Madras, June 25, 1822," *PP*, 1831-32, IX, 531-2.

REFERRED TO: 144

"Extract Letter, in the Revenue Department, from the Court of Directors to the Governor in Council of Fort St. George, dated 18th May 1825," *PP*, 1831-32, IX, 536.

REFERRED TO: 144

"Minute of Sir Thomas Munro, March 10, 1826," *PP*, 1831-32, IX, 536-7.

REFERRED TO: 144

"Extract Public Letter to Bengal, 18 Feb., 1829," *PP*, 1831-32, IX, App., 374-5.

REFERRED TO: 112

Letter from the Board of Control to the Court of Directors (13 Oct., 1829) (unpublished). In

India Office Records, *Letters from the Board of Control to the Company*: E/2/35, pp. 370-9.

REFERRED TO: 72-3

"Reports from the Select Committee Appointed to Inquire into the Present State of the Affairs of the East India Company, and into the State of Trade between Great Britain, the East Indies, and China, Relative to the China Trade; with Appendix of Documents" (8 July, 1830), *PP*, 1830, V.

REFERRED TO: 77-8

"Report of Charles H. Cameron, Esq., One of His Majesty's Commissioners of Inquiry, upon the Judicial Establishments and Procedure in Ceylon" (31 Jan., 1832), *PP*, 1832, XXXII, 119-52.

REFERRED TO: 21

"Report from the Select Committee Appointed to Inquire into the Present State of the Affairs of the East India Company, and into the State of Trade between Great Britain, the East Indies, and China; with Minutes of Evidence" (16 Aug., 1832), *PP*, 1831-32, VIII-XIV.

REFERRED TO: 77-8

"Revenue Department Despatch No. 3, 20 Feb., 1833. To Our Governor-General in Council at Fort William Bengal," *PP*, 1837, XLIII, 190-9.

REFERRED TO: 125

"First Report from His Majesty's Commissioners on Criminal Law" (24 June, 1834), *PP*, 1834, XXVI, 117-77.

REFERRED TO: 28

Dispatch Accompanying the Government of India Act, 1833 (3 & 4 William IV, c. 85), No. 44 (10 Dec., 1834). In Courtenay Peregrine Ilbert's *The Government of India*. Oxford: Clarendon Press, 1898, 492-532.

NOTE: by James Mill, according to East India House tradition.

REFERRED TO: 51

"Report from the Select Committee on Salt, British India; Together with the Minutes of Evidence, and Appendix" (2 Aug., 1836), *PP*, 1836, XVII, 1-371.

REFERRED TO: 107

Circular Order of 13 Nov., 1837. In John Maskell's *The Circular Orders of the Board of Revenue from A.D. 1820 to 1850*. Madras: Christian Knowledge Society's Press, 1851, 243-6.

REFERRED TO: 103

A Penal Code; Prepared by the Indian Law Commissioners, and Published by Command of the Governor-General of India in Council. Calcutta: Bengal Military Orphan Press, 1837. In *PP*, 1837-38, XLI, 463-588.

NOTE: passed in 1860 as Act XLV.

REVIEWED: 17-30

QUOTED: 22, 23-7, 28

REFERRED TO: 69, 114

22.17 "The] 5. The (473)

22.18 female." "The] female. [paragraph] 6. The (473)

22.19 age." "The] age. [2-page omission] [paragraph] 24. The (473-5)

22.20 acts." "The] acts. [3-sentence omission] [paragraph] 25. The (475)

25.3 injury;] injury. (507)

25.6 choice;] choice. (507)

25.8 concealment;] concealment. (507)

27.4 suicide] such suicide (508) [treated as printer's error in this ed.]

- 28.13 life. . . . The] [*ellipsis indicates that JSM is going back 10 sentences*] (469)
- 28.17 cases. . . . Thus] [*ellipsis indicates that JSM is returning to the text at life—see entry for 28.13 above*] [*paragraph*] Thus (469)
- Report of the Committee on Prison-Discipline to the Governor-General of India in Council, 8 January, 1838.* Calcutta: Baptist Mission Press, 1838.
REFERRED TO: 116
- “Memorial of the Inhabitants of Calcutta and Others, of All Classes of His Majesty’s Indian Subjects, to the President and Board of Commissioners for the Affairs of India, and the Court of Directors of the East India Company,” *PP*, 1837-38, XLI, 264-6.
REFERRED TO: 11-15 *passim*
- “Report of the Indian Law Commissioners on Slavery” (15 Jan., 1841), *PP*, 1841, Sess. 1, XXVIII, 279-873.
REFERRED TO: 124
- “A Copy of the Letter from the Governor-General of India in Council, in the Legislative Department, 10 May (No. 8), 1841, and of the Minute of the Governor-General Enclosed Therein, on the Subject of Slavery in the East Indies,” *PP*, 1841, Sess. 2, III, 109-14.
REFERRED TO: 124
- “Letter from the Court of Directors to the Governor-General of India in Council, Revenue Department, 1 Sept. (No. 12), 1841,” *Sessional Papers of the House of Lords*, 1851, XVI, 66-7.
REFERRED TO: 127
- “Copies or Extracts of Correspondence and Papers Relating to, and Explanatory of, the Deposition of the Raja of Sattara, and the Appointment of His Brother as His Successor,” *PP*, 1843, XXXVIII, Pt. 1, 109–Pt. 2, 675.
REFERRED TO: 34
- “Extract of a Despatch in the Separate Revenue Department, from the Court of Directors to the Governor-General in Council, 3 July (No. 9), 1844,” *PP*, 1845, XXXIV, 78-9.
REFERRED TO: 107
- “Resolution of 10 October, 1844,” *PP*, 1845, XXXIV, 133-4.
REFERRED TO: 148
- Letter from the Undersecretary to the Government of Bengal, to the Secretary to the Sudder Board of Revenue, dated Fort William, No. 828, 18 Dec., 1844. In *General Report on Public Instruction in the Lower Provinces of the Bengal Presidency, for 1844-45*. Calcutta: Sanders and Cones, 1845, App. 2, clxix)cclxxiii.
REFERRED TO: 144
- “Engagements with the Raja of Biccaneer and the Nawab of Bahawalpore, Respecting Transit Duties,” *PP*, 1845, XXXIV, 70-1.
REFERRED TO: 108
- “Letter from the Court of Directors to the Governor-General of India in Council, Separate Revenue Department, 22 Apr. (No. 3), 1846,” *Sessional Papers of the House of Lords*, 1847-48, XXX, 461-3.
REFERRED TO: 109
- Plan No. 80a Annexed to Letter No. 1089 (18 Nov., 1846) from the Government of the North-Western Provinces to the Government of India. In *Selections from the Records of the Government, North Western Provinces, Mr. Thomason’s Despatches*. 2 vols. Agra: Secundra Orphan Press, 1856-58, I, 329-33.
REFERRED TO: 143
- Letter, Dated 19 April 1848, Government of the North-Western Provinces to the Government of India. In *Selections*, I, 397-402.
REFERRED TO: 143

"Minute by the Honourable Sir George Clerk" (28 Apr., 1848), *Sessional Papers of the House of Lords*, 1852-53, XIII, 176-90.

REFERRED TO: 118

"Directions for Revenue Officers in the North-Western Provinces of the Bengal Presidency, Regarding the Settlement and Collection of the Land Revenue, &c." (1 Nov., 1849), *PP*, 1852-53, LXXV, 19-136.

QUOTED: 156, 157, 157n

REFERRED TO: 156-7

156.32-3 "calculated . . . profit;" and "for . . . Government;"] All the inhabited part of the country is divided into portions with fixed boundaries, called mehals or estates; on each mehal a sum is assessed for the term of 20 or 30 years, calculated . . . profit over and above the net produce of the land; and for . . . Government. (20)

157.1 "person] It is determined who are the person (21)

157n.4-5 "By . . . labour." (By . . . labour, and this, in an estate held entirely by cultivating proprietors, will be the profit on their seer cultivation, but in an estate held by a non-cultivating proprietor, and leased out to cultivators or asamees, paying at a known rate, will be the gross rental.) (35)

"Letter from the Court of Directors to the Governor-General of India in Council, Revenue Department, 5 Dec. (No. 11), 1849," *PP*, 1851, XLI, 723-4.

REFERRED TO: 128

"Letter from the Court of Directors to the Government of India, Public Department, 30 Jan. (No. 2), 1850," *PP*, 1852-53, LXXV, 1-10.

REFERRED TO: 135

"Letter from the Court of Directors to the Governor in Council in Fort St. George, Revenue Department, 8 Jan. (No. 1), 1851," *PP*, 1851, XLI, 726-7.

REFERRED TO: 130

"Letter from the Court of Directors to the Governor-General of India in Council, Revenue Department, 25 Apr. (No. 5), 1851," *PP*, 1851, XLI, 724-5.

REFERRED TO: 128

"Despatch of the Court of Directors, 13 August, 1851, on the Settlement of the North-Western Provinces," *PP*, 1852-53, LXXV, 237-307.

QUOTED: 99

99.27-8 "improvements . . . date"] We are of opinion that the only satisfactory principle on which all future renewals of settlements can be made will be, that reference must be had to the value of the land at the time, a liberal consideration being given for the improvements . . . date, and with regard to which he has reaped the advantage only for a short period under the old settlement. (304)

"Returns (in Part) to an Order of the House of Lords, dated 29th April 1852, Relative to the Affairs of the East India Company," *Sessional Papers of the House of Lords*, 1852, XI, 247-74.

REFERRED TO: 40, 46

Minute. Board of Governors of the Madras University, dated 2nd July, 1852. In *Selections from the Records of the Madras Government, No. 2. Papers Relating to Public Instruction*. Madras: Male Asylum Press, 1855, App. C.C.C., ccxcvii-ccciv.

REFERRED TO: 145

Court of Directors' Revenue Despatch to Madras, No. 14 of 22 Sept., 1852 (unpublished). In *India Office Records: E/4/977*, pp. 517-37.

REFERRED TO: 108

CIRCULAR ORDER OF 25 NOV., 1852. IN JOHN MASKELL'S *The Circular Orders of the Board of Revenue Issued during the Years 1851-1852-1853*. Madras: Christian Knowledge Society's Press, 1854, 110-19.

QUOTED: 159

REFERRED TO: 103

- 159.23 "to] 4. Having fully considered all the circumstances set before us, we have resolved to authorize you to extend to the whole of the Madras Presidency, the rule which prevails in the districts noted in the margin, and to (110)
- 159.24 land] lands (113) [*treated as printer's error in this ed.*]
- 159.27 any] 5. Under these considerations, the Government are of opinion, that the commands of the Court giving the ryots the full benefit of their own improvements should be carried into complete operation in every district under the Madras Presidency, and that in all, the ryots should receive the most distinct assurance, that the tax on lands cultivated by means of wells henceforth to be constructed by them at their own cost, will never be enhanced, unless on a general revision of the district rates, and that in such revision, any (117)
- 159.29 holders,"] holders. (117)
- 159.32 "to] It would merely tend to (118)
- "Report of the Commissioners of Public Works in the Madras Presidency" (23 Dec., 1852), *Sessional Papers of the House of Lords*, 1852-53, LXV, 43-458.
REFERRED TO: 130
- "First Report of the Commissioners Appointed to Inquire into and Report upon the System of Superintending and Executing Public Works in the Madras Presidency" (23 Dec., 1852), *PP*, 1852-53, LXXIV, 40-460.
REFERRED TO: 129
- "Report of the Council of Education, Dated the 3rd October, 1853, Reviewing the State of Vernacular Education and Proposing the Establishment of Model Vernacular Schools." In *Selection, from the Records of the Bengal Governments. No. 22. Correspondence Relating to Vernacular Education in the Lower Provinces of Bengal*. Calcutta: Jones, 1858, 27-40.
REFERRED TO: 244
- "Reports from the Select Committee of the House of Lords Appointed to Inquire into the Operation of the Act 3 & 4 William IV, c. 85, for the Better Government of Her Majesty's Indian Territories; Together with the Minutes of Evidence, and Appendices," *PP*, 1852-53, XXX-XXXIII.
REFERRED TO: 78
- "Official Correspondence on the System of Revenue Survey and Assessment Best Adapted for, and More or Less Completely Carried into Effect in the Collectorates of Poona, Sholapoor, Ahmednuggur, Belgaon and Dharwar, in the Bombay Presidency," *PP*, 1852-53, LXXV, 312-402.
QUOTED: 158
REFERRED TO: 101, 158-9
- 158.15 "their] The circumstances affecting the values of fields within the limits of the same village, where the climate may be considered uniform, are, their (321)
- 158.25-6 "climate . . . cultivators,"] Among the most important of these influences must be ranked climate . . . cultivators. (326)
- 158.32-3 "thirty years, during] With a view to the improvement of the country and people, the assessment now introduced by the superintendent revenue survey, [blank] has been fixed by Government for a period of 30 years, viz., from Fuslee [blank] to [blank] during (331)
- 158.34 digging of wells] digging or repairing of wells (331)
- Bombay. Notification, Dated 16th May, 1854, Relative to the Establishment of Vernacular Schools. By Order of the Board of Education, M. Stovell Secretary. In *Report of the Board of Education, Bombay, from 1st May 1854, to 30th April 1855*. Bombay: Bombay Education Society's Press, 1855, App. XV, 117-18.
REFERRED TO: 145
- "Despatch from the Court of Directors of the East India Company to the Governor-General in Council, 19 July (No. 49), 1854," *PP*, 1854, XLVII, 155-74.
REFERRED TO: 136, 144, 145-6

- "Correspondence Relating to the Education Despatch of 19 July, 1854," *PP*, 1857-58, XLII, 339-507.
 REFERRED TO: 146
- "Minute of the Right Honourable Lord Harris, on the Proposed General Survey and Assessment" (26 Oct., 1854), *PP*, 1857, Sess. 2, XXIX, 173-85.
 REFERRED TO: 103
- Report on the Administration of Public Affairs in the Madras Presidency. In *General Report on the Administration of the Several Presidencies and Provinces of British India during the Year, 1855-56*, Pt. 1. Calcutta: Calcutta Gazette Office, 1857.
 QUOTED: 97
 97.23 "has] The Ryot, under this system, is virtually a proprietor on a simple and perfect title, and has (11)
 97.25 as long] so long (11)
 97.25 dues."] dues: he receives assistance in difficult seasons, and is irresponsible for the payment of his neighbours. (11)
- "Despatch from the Court of Directors to the Governor-General of India in Council, Judicial Department, 24 Sept. (No. 41), 1856," *PP*, 1857, Sess. 1, XI, 127-32.
 REFERRED TO: 120
- "Letter from the Court of Directors to the Governor-General of India in Council, Revenue Department, 5 Nov. (No. 17), 1856," *PP*, 1857, Sess. 2, XXIX, 412-14.
 REFERRED TO: 109
- "Letter from the Court of Directors to Government of Fort St. George" (17 Dec., 1856), *PP*, 1857, Sess. 2, XXIX, 186-93.
 REFERRED TO: 103-4
- "Reports of Her Majesty's Commissioners Appointed to Consider the Reform of the Judicial Establishments, Judicial Procedure, and Laws of India," *PP*, 1856, XXV.
 REFERRED TO: 114
- "Draft of Treaty between the East India Company and the King of Oude," *PP*, 1856, XLV, 597-9.
 REFERRED TO: 224
- "Letter from the Government of India to the Hon. Court of Directors, Home Department, Judicial, 14 May (No. 18) of 1857," *PP*, 1857, Sess. 2, XXIX, 287-8.
 REFERRED TO: 120
- "Despatch in the Public Works Department of the Court of Directors to the Governor-General of India in Council, 9 Sept. (No. 13), 1857" [summary], *PP*, 1861, XLIII, 308.
 REFERRED TO: 131
- "Despatch from the Court of Directors to the Governor at Madras, Judicial Department, 30 Sept. (No. 13), 1857," *PP*, 1857-58, XLIII, 415-17.
 QUOTED: 120-1
 120.28 in direct communication] in communication (415)
 121.1 The appointment] Secondly, the appointment (416)
 121.1 a] an (416)
 121.2 peons or constables;] peons: (416)
 121.3 The entire] Thirdly, the entire (416)
 121.4-5 administration, . . . crime;] administration; (416) [*i.e.*, *JSM was using the fuller India Office draft*]
 121.6-9 And, . . . people.] And, Fifthly. The re-organization of the village police. (416) [*i.e.*, *JSM was using the fuller India Office draft*]
- "Despatch from the Court of Directors to the Governor-General of India in Council, Judicial Department, 4 Nov. (No. 61), 1857," *PP*, 1857-58, XLIII, 413-15.
 REFERRED TO: 120

"Letter from the Court of Directors to the Governor-General of India in Council, Military Department, 25 Nov. (No. 236), 1857," *PP*, 1857-58, XLIV, Pt. 1, 48-9.

REFERRED TO: 78

"Papers Relating to the System of Police in the Bengal Presidency," *PP*, 1857, Sess. 2, XXIX, 327-87.

REFERRED TO: 120

"Papers Relative to the Mutinies in the East Indies," *PP*, 1857, Sess. 2, XXX; and 1857-58, XLIV, Pts. 1-4.

REFERRED TO: 78

"Correspondence between the First Lord of the Treasury and the Directors of the East India Company Respecting Legislative Measures to Be Proposed for the Future Government of Her Majesty's Dominions in India," *Sessional Papers of the House of Lords*, 1857-58, XI, 445-8.

REFERRED TO: 78, 163-4

"A Copy of Any Proceedings or Communications from the Court of Directors of the East India Company to the Governor-General of India Relating to the Proposed Proclamation of Lord Canning, and to the Late Despatch from the Secret Committee with Reference Thereto," *PP*, 1857-58, XLIII, 117-20.

REFERRED TO: 196-7

"Papers Relating to the Proclamation Ordered to Be Published in Oude," *PP*, 1857-58, XLIII, 407-12.

REFERRED TO: 195-7

"A Bill for the Better Government of India," 21 Victoria (12 Feb., 1858), *PP*, 1857-58, II, 267-86.

NOTE: not enacted.

REFERRED TO: 78-81, 89, 161-71 *passim*, 181, 203, 210

"A Bill to Transfer the Government of India from the East India Company to Her Majesty the Queen," 21 Victoria (26 Mar., 1858), *PP*, 1857-58, II, 287-312.

NOTE: not enacted.

REFERRED TO: 161-71 *passim*, 175, 203

Government of India. Resolutions to Be Proposed by Mr. Chancellor of the Exchequer in Committee of the Whole House upon the Government of India, on Friday, the 30th of April (1858), *PD*, 3rd ser., Vol. 149, Appendix.

QUOTED: 187, 187-8, 188, 190

REFERRED TO: 187-91, 191-2

190.6 (left col.) government of] Government and Revenues of

"Copy of a Letter from the Court of Directors of the East India Company to the Governor-General of India in Council" (5 May, 1858), *PP*, 1857-58, XLIII, 113-16.

REFERRED TO: 196

"A Bill for the Better Government of India," 21 Victoria (17 June, 1858), *PP*, 1857-58, II, 313-36.

NOTE: enacted as 21 & 22 Victoria, c. 106.

QUOTED: 208, 211

REFERRED TO: 203, 207-12

208.32-4 "Conduct . . . correspondence with India,"] The Council shall, under the Direction of the Secretary of State, and subject to the Provisions of this Act, conduct . . . Correspondence with India, but every Order or Communication sent to India shall be signed by one of the Principal Secretaries of State; and, save as expressly provided by this Act, every Order in the United Kingdom in relation to the Government of India under this Act shall be signed by such Secretary of State; and all despatches from Governments and Presidencies in India, and other Despatches

from India, which if this Act had not been passed should have been addressed to the Court of Directors or to their Secret Committee, shall be addressed to such Secretary of State. (322)

- 211.32-4 "the collection, receipt, and management of the revenues." . . . "the application of such revenues and public moneys in India"] It shall be lawful for Her Majesty, by Commission under Her Royal Sign Manual, countersigned by the Chancellor of the Exchequer, to appoint any Number of Persons, not exceeding *Three*, as to Her Majesty may seem fit, to proceed to India, and inquire there into the Finances and Financial Accounts of the Several Presidencies and Governments, and especially into the Collection, Receipt, and Management of and the Manner of accounting for the Revenues of India, and the Mode of auditing the Accounts of the Receipts and Expenditure of such Public Monies, and securing the due Application thereof, and to report to Her Majesty on the matters aforesaid, and to Recommend such Regulations and Provisions in relation thereto as in their Judgement may seem expedient; and such Commissioners shall have full Power to call before them and examine any Persons in the Service of Her Majesty in India, and to Require such Returns and Explanations, and the Production of such official Documents, as such Commissioners may think fit; and there shall be paid to such Commissioners out of the Revenues of India such Salaries and Allowances as by such Commission may be directed, but so that the same shall not be payable for a longer Period than *Three* Years from the arrival of the said Commissioners respectively to India. (332)

STATUTES

ENGLAND

- 13 George III, c. 63. An Act for Establishing Certain Regulations for the Better Management of the Affairs of the East India Company, As Well in India As in Europe (1773).

REFERRED TO: 45, 48, 69, 81

- 21 George III, c. 70. An Act to Explain and Amend So Much of an Act, Made in the Thirteenth Year of the Reign of His Present Majesty, Intituled, "An Act for Establishing Certain Regulations for the Better Management of the Affairs of the East India Company, As Well in India As in Europe," As Relates to the Administration of Justice in Bengal (1781).

QUOTED: 81

REFERRED TO: 111-12

81.18-19 "in . . . natives,"] And, in . . . said natives, be it enacted, That the rights and authorities of fathers of families, and masters of families, according as the same might have been exercised by the Gentû, or Mahomedan law, shall be preserved to them respectively within their said families; nor shall any acts done in consequence of the rule and law of caste, respecting the members of the said families only, be held and adjudged a crime, although the same may not be held justifiable by the laws of England. (sect. 18)

81.20-2 "that suits . . . natives" . . . "as may . . . natives.]" And be it further enacted, That it shall and may be lawful for the supreme court of judicature at Fort William in Bengal, to frame such process, and make such rules and orders for the execution thereof, in suits . . . natives of Bengal, Bahar, and Orissa, as may . . . natives, so far as the same may consist with the due execution of the laws and attainment of justice. (sect. 19)

- 24 George III, c. 25. An Act for the Better Regulation and Management of the Affairs of the East India Company, and of the British Possessions in India; and for Establishing a Court of Judicature for the More Speedy and Effectual Trial of Persons Accused of Offences Committed in the East Indies (1784).

REFERRED TO: 77

- 33 George III, c. 52. An Act for Continuing in the East India Company, for a Further Term, the Possession of the British Territories in India, together with Their Exclusive Trade,

under Certain Limitations; for Establishing Further Regulations for the Government of the Said Territories, and the Better Administration of Justice within the Same; for Appropriating to Certain Uses the Revenues and Profits of the Said Company; and for Making Provision for the Good Order and Governments of the Towns of Calcutta, Madras and Bombay (11 June, 1793).

REFERRED TO: 77-8

53 George III, c. 155. An Act for Continuing in the East India Company, for a Further Term, the Possession of the British Territories in India, together with Certain Executive Privileges; for Establishing Further Regulations for the Government of the Said Territories, and the Better Administration of Justice within the Same; and for Regulating the Trade to and from the Places within the Limits of the Said Company's Charter (21 July, 1813).

REFERRED TO: 4, 78, 83

3 & 4 William IV, c. 85. An Act for Effecting an Arrangement with the East India Company, and for the Better Government of His Majesty's Indian Territories (28 Aug., 1833).

REFERRED TO: 20, 21, 30, 43, 45, 47, 48, 51, 64, 69, 78, 83, 113, 114

4 & 5 William IV, c. 76. An Act for the Amendment and Better Administration of the Laws Relating to the Poor in England and Wales (14 Aug., 1834).

REFERRED TO: 177

6 & 7 William IV, c. 115. An Act for Facilitating the Inclosure of Open and Arable Fields in England and Wales (20 Aug., 1836).

REFERRED TO: 220-1

2 & 3 Victoria, c. 52. An Act for the Further Regulation of the Duties on Postage until the Fifth Day of October 1840 (17 Aug., 1839).

REFERRED TO: 110

8 & 9 Victoria, c. 118. An Act to Facilitate the Inclosure and Improvement of Commons and Lands Held in Common, the Exchange of Lands, and the Division of Intermixed Lands; to Provide Remedies for Defective or Incomplete Executions, and for the Nonexecutions, of the Powers of General and Local Inclosure Acts; and to Provide for the Revival of Such Powers in Certain Cases (8 Aug., 1845).

REFERRED TO: 221

9 & 10 Victoria, c. 105. An Act for Constituting Commissioners of Railways (28 Aug., 1846).

REFERRED TO: 177

11 & 12 Victoria, c. 63. An Act for Promoting the Public Health (31 Aug., 1848).

REFERRED TO: 177

12 & 13 Victoria, c. 29. An Act to Amend the Laws in Force for the Encouragement of British Shipping and Navigation (26 June, 1849).

REFERRED TO: 109

14 & 15 Victoria, c. 64. An Act to Repeal the Act for Constituting Commissioners of Railways (7 Aug., 1851).

REFERRED TO: 177

16 & 17 Victoria, c. 95. An Act to Provide for the Government of India (20 Aug., 1853).

QUOTED: 187

REFERRED TO: 78, 83, 86, 93, 113, 114, 168

FRANCE

Code Napoléon (1803-04). Bulletin 154 *bis*, No. 2653 *bis* (3 Sept., 1807), *Bulletin des lois de l'empire français*, 4th ser. Numéros *bis*.

NOTE: separately paginated, 1-383, with index 1-80. The "Bulletins *bis*" are not included in their numerical places in the annual volumes, but are gathered, for each period, in a separate volume.

REFERRED TO: 19

INDIA

A Regulation for re-enacting with modifications and amendments, the rules for the decennial settlement of the public revenue payable from the lands of the zemindars, independent talookdars, and other actual proprietors of land, in Bengal, Behar, and Orissa, passed for those provinces respectively on the 18th September 1789, the 25th November 1789, and the 10th February 1780, and subsequent dates (1 May, 1793). In *Regulations of the Government of the Presidency of Fort William in Bengal, 1793-1834*, Regulation VIII of 1793.

REFERRED TO: 96

A Regulation for re-enacting with modifications, the existing rules for the collection of the government and Calcutta customs (1 May, 1793). In *Regulations*, Regulation XLII of 1793.

REFERRED TO: 108

A Regulation for forming into a regular code all rules that may be enacted for the internal government of the territories subordinate to the Presidency of Bombay (1 Jan., 1827), *PP*, 1829, XXIII, 251-4, Regulation I of 1827.

NOTE: known as Elphinstone's Code or Bombay Code.

REFERRED TO: 113

A Regulation for declaring the practice of Suttee, or of burning or burying alive the widows of Hindoos, illegal, and punishable by the Criminal Courts (4 Dec. 1829). In *Regulations*, Regulation XVII of 1829.

NOTE: also in *PP*, 1830, XXVIII, 44-6.

REFERRED TO: 123

A Regulation for modifying certain of the Provisions of Regulation V 1831, and for providing Supplementary Rules to that Enactment (16 Oct., 1832). In *Regulations*, Regulation VII of 1832.

REFERRED TO: 125

Act XI of 1836 (9 May, 1836), *PP*, 1840, XXXVII, 31.

REFERRED TO: 11-15 *passim*, 30

Act XIV of 1836 (30 May, 1836), *PP*, 1840, VI, 414-20.

REFERRED TO: 107, 108

Act XVII of 1837 (24 July, 1837), *PP*, 1840, XXXVI, 65-9.

REFERRED TO: 108

Act X of 1840. An Act for the Abolition of Certain Pilgrim Taxes, and for the Superintendence of the Temple of Juggernath (20 Apr., 1840), *PP*, 1842, XXX, 36.

REFERRED TO: 125

Act IV of 1840. An Act for Preventing Affrays Concerning the Possession of Land, and for Providing Relief in Cases of Forcible Dispossession, within the Presidency of Fort William in Bengal (17 Feb., 1840), *PP*, 1842, XXX, 11.

REFERRED TO: 155

Act V of 1843. An Act for Declaring and Amending the Law Regarding the Condition of Slavery within the Territories of the East India Company (7 Apr., 1843), *PP*, 1845, XXXIV, 86.

REFERRED TO: 124

Act XIV of 1843. An Act for Regulating the Levy of Customs Duties, and the Manufacture of Salt in the North-Western Provinces of the Presidency of Bengal (5 Aug., 1843), *PP*, 1845, XXXIV, 111-13.

REFERRED TO: 45

Act VI of 1844. An Act for Abolishing the Levy of Transit or Inland Customs Duties, for Revising the Duties on Imports and Exports by Sea, and for Determining the Price at Which Salt Shall be Sold for Home Consumption within the Territories Subject to the Government of Fort St. George (16 Mar., 1844), *PP*, 1846, XXXI, 36-48.

REFERRED TO: 107, 108

Act XVI of 1844. An Act for Increasing the Excise and Import Duties Heretofore Payable to the Government on Salt Manufactured within or Imported into the Territories Subject to the Government of the Presidency of Bombay (27 July, 1844), *PP*, 1845, XXXIV, 67.

REFERRED TO: 107

Act VI of 1848. An Act for Equalizing the Duties on Goods Imported and Exported on Foreign and British Bottoms, and for Abolishing Duties on Goods Carried from Port to Port in the Territories Subject to the Government of the East India Company (4 Mar., 1848), *PP*, 1851, XLV, 115.

REFERRED TO: 109

Act XIII of 1848. An Act for Limiting the Time within Which a Suit May be Brought to Contest the Awards of the Revenue Authorities in the Presidency of Bengal (10 June, 1848), *PP*, 1851, XLI, 123.

NOTE: the reference is in a quotation from the Sudder Court.

REFERRED TO: 156

Act V of 1850. An Act for Freedom of the Coasting Trade of India, *PP*, 1852, XXXVI, 39.

REFERRED TO: 109

Act XXI of 1850. An Act for Extending the Principle of Section 9, Regulation VII, 1832, of the Bengal Code, throughout the Territories Subject to the Government of the East India Company (11 Apr., 1850), *PP*, 1852, XXXVI, 65-6.

REFERRED TO: 125

Act XXVII of 1852 (2 July, 1852).

REFERRED TO: 118

Act XXVIII of 1852 (2 July, 1852).

REFERRED TO: 118

Act XVII of 1854. An Act for the Management of the Post Office, for the Regulation of the Duties of Postage, and for the Punishment of Offences against the Post Office (12 Aug., 1854).

REFERRED TO: 110

Act XV of 1856. To Remove All Legal Obstacles to the Re-Marriage of Hindoo Widows (13 June, 1856).

REFERRED TO: 125

Act XX of 1856. An Act to Make Better Provision for the Appointment and Maintenance of Police Chowkeydars in Cities, Towns, Stations, Suburbs, and Bazaars in the Presidency of Fort William in Bengal (14 Nov., 1856).

REFERRED TO: 118

Act II of 1857. An Act to Establish and Incorporate an University at Calcutta (24 Jan., 1857).

REFERRED TO: 146

Act XXII of 1857. An Act to Establish an University at Bombay (18 July, 1857).

REFERRED TO: 146

Act XXVII of 1857. An Act to Establish and Incorporate an University at Madras (5 Sept., 1857).

REFERRED TO: 146

Act X of 1859. To Amend the Law Relating to the Recovery of Rent in the Presidency of Fort William in Bengal (29 Apr., 1859).

REFERRED TO: 225

Act XLV of 1860. The Indian Penal Code (6 Oct., 1860).

NOTE: the reference is prospective.

REFERRED TO: 114

Index

FOR specific laws and documents, as well as people and books, see App. C. The abbreviations EIC and JSM are used for East India Company and John Stuart Mill. In general, Indian proper names are given in the form in which they appear in JSM's original texts, with the later standardized *Imperial Gazetteer* renderings added in square brackets.

- ADDISCOMBE MILITARY COLLEGE**, 73-4, 212
Administration, use of subordinate bodies for, 177-8, 188-90
Agra, Lieutenant-Governor at, 61, 65-6. *See also* North-Western Provinces
Australia, 45
- BANK OF ENGLAND**, role of, 188
Barbarisms, suppression of by EIC, 121-4, 151-5
Baree [Bari] Doab Canal, 128-9
Bengal Presidency: use of native talent in, 64, 112; Governor-General as ruler of, 65; land settlement in, 95-6, 104, 155-6, 223; salt revenue in, 107, 160; police in, 118, 120; financing of roads in, 133-4; education in, 142, 143-4, 146, 148; mentioned, 117
Bhaugulpore [Bhagalpur] Hills, 153
Bheels [Bhils], 153, 154
Board of Control. *See* India, government of
Bombay Presidency: its relation to supreme government of India, 61, 67-8; land settlement in, 100-2, 104, 105, 157-9, 225n; salt revenue in, 106-7, 160; use of native talent in, 112; and Bombay Code, 112-13; police in, 118-19; roads in, 134-5; colleges and schools in, 145, 146, 148; mentioned, 63
British Empire, administration of, 187-90
- CALCUTTA**: judicial system in, 14; as seat of government, 66. *See also* Bengal Presidency
Canada, 30, 45
Canals. *See* Irrigation works
Candeish [Khandesh], 154
Capital, behaviour of under free trade, 6-7
Centralization, dangers of excessive, 175-6
Ceylon, judicial system of, 21
Christianity, in India, 125
Civilization, EIC as agent of, 121-4, 151-5
- Class (social)**, and selection of EIC personnel, 38-9
Codification (legal), feasibility of, 19-20; illustrated, 22-30, 114-15
Coleroon irrigation works, 129-30
Colonial Office: innovations of, 21; unbearable, 176
Colonies, British: possible Council for, 44-5; policy of local self-government in, 49-50, 51, 165, 175-6, 189, 201
Commons, enclosure of, condemned, 220-1, 222
Constitution, British, divided responsibility in, 188, 189
Cotton, cultivation of in India, 103, 149
Council of India. *See* India, government of
Court of Directors, **Court of Proprietors**. *See* East India Company
Courts: English and natives in India to be subject to the same, 13-15, 20, 30, 114; reform of Indian, 111-15; in Punjab, 115-16. *See also* Law
Custom, effect of on rents and prices, 227
Customs duties: on Indian trade, 3-6, 7, 108-9; as legitimate charge for expenses, 7-9
Cuttack, revenue system of, 104
- DACOITS**, 121-2
Dissection, 147
- EAST INDIA COMPANY**: its trading practices, 3-4; renewal of its Charter (1833), 4-5, 20, 83; its courts of justice, 14; as protector of natives of India, 15, 30, 82; JSM's employment in, 33; its system of written records, 33, 71-3; securities for good government in its rule, 33-7, 42; its Court of Proprietors, 35, 36, 40-1, 46-7, 57-9, 71; its civil service, 37-41, 61-5, 73-4; drafting of despatches in, 42-4, 48, 54; and

- relation between Home Government and government in India, 43-4, 69-70, 87-8; its Secret Committee, 55, 58, 195, 209-10; public examinations in, 60; its Presidency system, 61, 65-6, 67-8; and 1858 transfer of government of India to Crown, 77-9, 163-4, 175, 176, 178, 187-8, 190-1; defence of its rule, 77-83, 93, 110-11, 125-6, 155, 163-4; renewal of its Charter (1853), 78, 83, 187; its army, 89; its museum, 150
- Court of Directors of: its relation to Board of Control, 35-6, 42, 44-5, 52-7, 79, 87-8; patronage exercised by, 37-41, 59-60, 85; its election by Court of Proprietors, 40-1, 46-7; new organization of, after 1833, 47-9; its relation to Court of Proprietors, 57-9; its reduction in 1853, 83, 86; its superiority to proposed Council, 85, 87; its reaction to proposed transfer, 163, 170-1, 207-12 *passim*; and Lord Canning's Proclamation, 195, 196-7
- See also* India, government of
- Education: EIC's measures to promote Indian, 141-8; divided responsibility for, in Britain, 177
- Election, not advantage of popular government, 169
- Elphinstone College, 145
- Enclosure movement, 220-1, 222
- England, government of: principle of divided responsibility in, 177-8, 188-90; influence of public opinion on, 201-2
- English abroad, an oppressive crew, 15
- FEUDAL SYSTEM, origins of, 218
- France, law in, 19
- Free trade, meaning of, 6-9
- GANGES CANAL, 127-8
- Germany, land tenure in ancient, 216-18
- Gibraltar, 188
- Godavery [Godavari] Anicut, 130
- Government: role of, in trade and industry, 7-8, 126; popular, 169; importance of local, 175-6; local self-government in colonial, 49-50, 51, 165, 175-6, 189, 201. *See also* England, government of; India, government of
- Grand Trunk Road, 132
- Great Deccan Road, 132
- Great Indian Revolt. *See* Mutiny of 1857
- HAILYBURY COLLEGE, 64, 73
- Hindus: character of, 30, 96; religious laws of, and EIC, 125; and hill tribes, 153; mentioned, 121, 158. *See also* Indians, Religion
- History, and lesson of relativism, 215-16
- Hospitals, in India, 150-1
- House of Commons. *See* Parliament
- Huslee [Hasli] Canal, 128
- Improvements, generally not believed possible till seen, 19
- India, government of: outlook for British ascendancy in, 15, 65; dangers of English parliamentary interference in, 30, 33-4, 36-7, 50, 57; as double government, by Court of Directors and Board of Control, 35-6, 42, 44-5, 52-7, 77, 79, 87-8, 176, 190; factors peculiar to, 49-50, 164, 176, 201; utilizing native talents in, 51, 63-5, 112; and appointment and powers of Governor-General, 55-6, 61, 65-7; and Governor-General's Council (Legislative Council), 67-9, 113, 203, 209
- proposals for new constitution of (1858): unreasonably exclude EIC, 77-9, 164, 175, 176, 178, 187-8; should include influential Council, 83-7, 164-70, 171, 181-2, 202-4, 207-11; should not give power to parliamentary Minister alone, 165, 176, 182-3, 190-2, 195-8, 202; miscellaneous considerations on, 169-70, 210-12
- See also* East India Company, Revenue system
- Indian Law Commission, 20-2, 28, 30, 69, 113-15
- Indian States. *See* Native States
- Indians: need protection from English, 13, 14, 20, 30; national character of, 117. *See also* Hindus
- Infanticide, suppression of in India, 122-3
- Ireland, land system of, 96, 223
- Irrigation works in India, 126-31
- JUBBULPORE SCHOOL OF INDUSTRY, 121
- Jumna canals, 126-7
- Jurisprudence, Bentham's and Austin's contributions to, 227
- Justice: difficulty of attaining in India, 117; administration of in England, 178, 189. *See also* Courts, Law
- Justices of the Peace, 178
- KHOONDS [Khonds], 154
- Kistna Anicut, 130-1
- LABOUR, abolition of compulsory, in India, 124
- Land, tenure of: by villages, in ancient Germany, 216-18; by villages, in ancient

- England, 217, 218-21; as private property, not absolute right, 221-2, 224
- in India: and British revenue settlements, 94-104, 155-9, 222-7; and rent, 104-5; similar to ancient European, 216-17
- Landlords, as dominant class in England, 219-20
- Law: possibility of codification of, 19-20; codification of, illustrated in draft Indian Penal Code, 22-30; civil and criminal, 22; reform of English, 28-9; feudal remnants in English, 111; Maine on history of, 215
- Indian: and Act XI of 1836, 13-15, 30; and labours of Law Commissioners, 20-2, 28-30, 69, 113-15; reform of, 111-15; in Punjab, 115-16
- See also* Justice
- Libel, truth not always justification in private, 29
- Libraries, public, in India, 151
- MADRAS PRESIDENCY:** its relation to supreme government of India, 61, 67-8; land settlement in, 95, 97-8, 102-4, 105, 159, 225n; salt revenue in, 106-7, 160; tobacco revenue in, 107-8; use of native talent in, 112; police in, 118, 120-1; canals in, 129-31; roads in, 134; colleges and schools in, 144-5, 146; mentioned, 109
- Mahratta [Maratha] States, 151
- Mahratta [Maratha] Wars, 98, 101
- Malacca, trade of, 6-9 *passim*
- Medicine, teaching and practice of in India, 147, 150-1
- Mhairwarra [Merwara], 131, 153, 154
- Middle class, and government of India, 38, 85
- Murder, definition of in Indian Penal Code, 23-7
- Mutiny of 1857, 78-9, 81-2, 89, 164, 196, 224, 226
- NAGPORE [Nagpur], 104**
- Native States, their relations with British government, 151-3
- Navigation Laws, abolition of in India, 109
- North-Western Provinces: use of native talents in, 64-5; land settlement in, 98-9, 100, 104, 105, 156-7; police in, 118; financing of roads in, 134; progress of education in, 142-3, 146-8; salt revenue in, 160
- OPTUM, 105-6**
- Orissa, 124, 154
- Oudh: money-lenders and, 56; land policy in, 104, 224-5, 226; Lord Canning's Proclamation to insurgents of, 195-8; mentioned, 101
- PALAR ANICUT, 131**
- Paris, Exhibition of 1855 in, 150
- Parliament: inadequacy of, as governor of Indian affairs, 30, 33-4, 36-7, 50, 57, 165, 176, 182-3, 197-8, 202; as check on executive government, 175, 201
- Pegu, roads in, 133
- Penang, trade of, 6-9 *passim*
- Persian (language), 113
- Piracy, suppression of, 122
- Police, reform of Indian, 117-21
- Poonah [Poona], College at, 145
- Poor Laws, administration of, in Britain, 177, 189
- Post Office, Indian, 110
- Press, character of Indian, 70-1
- Price, effect of custom on, 227
- Principles, danger of misapplying, 6, 9
- Prisons, reform of Indian, 116-17
- Public health, government role in British, 177
- Public opinion, as check on government, 33-4, 201
- Public works, organization of in India, 135. *See also* Irrigation works, Railways, Roads
- Punjab: government of, 63; land settlement in, 100, 104; customs duties in, 109; judicial system of, 115-16; police in, 119; canals in, 128-9; roads in, 132; salt revenue in, 160
- RAILWAYS:** construction of in India, 136-40; government role in administration of British, 177-8, 189
- Rajpoot [Rajput] States, 153
- Rampore [Rampur], improvements in, 64-5, 152
- Religion, EIC and native, 81, 124-5, 142
- Rent: in India, 104-5, 222-3; effect of custom on, 227. *See also* Land, tenure of
- Revenue system, Indian: based on land, 94-5; how applied to land, 95-105, 155-9, 222-7; and taxation, 106-8, 160; and customs duties, 108-9; and Post Office, 110; proposed investigation into, 170, 211-12
- Roads, construction of in India, 131-5
- Roman Empire, government of, 164
- Roorkee, Thomason Civil Engineering College at, 136
- Russia, 217
- Ryotwar [Ryotwari] system, 97, 101, 102
- SALT, taxation of in India, 106-7, 160**
- Sanskrit College, 144
- Sattara [Satara], deposition of Rajah of, 34-5
- Scotland, natives of, in EIC, 38
- Secret Committee. *See* East India Company
- Sikhs, 100

- Sind: customs duties in, 109; canals in, 129; roads in, 135; pacification of frontier in, 154-5
- Singapore, trade of, 6-9 *passim*
- Slavery, abolition of in India, 124
- Sudder Adawlut [Sadr Adalat], 14
- Sugar, duties on East and West Indian, 5-6
- Suttee [Sati], suppression of, 123
- TALOOKDARS [Talukdars] (of Oudh), 101, 224-5, 226
- Taxation: effects of, 6-7; requirements of just, 94; of commodities in India, 106-8, 160.
See also Customs duties, Revenue system
- Tea, cultivation of in India, 150
- Telegraph, electric, in India, 140-1
- Thugs [Thags], 27, 121
- Tobacco, 107-8
- Trade, flourishing of Indian, 111. *See also* Customs duties, Free trade
- Transit duties, 108
- Trinity House, Corporation of the, 177, 188
- ULWUR [Alwar], 152-3
- United States of America, 77, 149, 165
- Universities: competitive examinations in English, 60; establishment of colleges and, in India, 142, 144-5, 146
- VACCINATION, in India, 151
- Village communities: in India, 98-9, 101, 223, 226-7; ancient Teutonic, 216-19
- WEST INDIES, discriminating duties favouring, 3-6
- Witchcraft, 123
- Women, position of Indian, 123, 125, 148
- ZEMINDARS [Zamindars], 95